



TRANSPORTATION CABINET

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Steven L. Beshear
Governor

Michael W. Hancock, P.E.
Secretary

June 11, 2012

CALL NO. 105
CONTRACT ID NO. 121329
ADDENDUM # 2

Subject: Jefferson County, IM 0642 (178)
Letting June 15, 2012

(1) Revised - Plan Sheet - R58

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

Plan revisions are available at <http://www.lynnimaging.com/kytransportation/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Ryan Griffith".

Ryan Griffith
Director
Division of Construction Procurement

RG:ks
Enclosures



An Equal Opportunity Employer M/F/D

TRAFFIC MANAGEMENT PLAN - PHASE 1

COUNTY OF	ITEM NO.	SHEET NO.
JEFFERSON	5-52.00	R58

PREPARED BY _____ DATE _____
 CHECKED BY _____ DATE _____
 APPROVED BY _____ DATE _____

PHASE 1 TRAFFIC CONTROL - DAYTIME HOURS (6 a.m. to 9 p.m.)

During this phase, traffic will be maintained along existing roadways, approaches, and entrances as detailed below.

KY 1747 (Hurstbourne Parkway)

The Contractor shall maintain all existing lanes with existing lane widths in each direction at all times except as noted below for this phase. All approaches and entrances shall remain open at all times unless otherwise noted.

During daytime hours, the Contractor will be allowed to install shoulder closures on both sides of KY 1747 (Hurstbourne Parkway) in the proposed construction areas during this phase. Shoulder closures shall be installed according to Standard Drawing No. TTC-135-01. Contrary to Standard Drawing No. TTC-135-01, drums may be used in lieu of temporary traffic barrier. The shoulder closures will only be allowed in the proposed construction areas. See Maintenance of Traffic typical section on the sheet R61.

I-64

The Contractor shall maintain all existing lanes of traffic at their existing lane widths during this phase at all times.

Ramp 4

The Contractor shall maintain all existing lanes of traffic at their existing lane widths during this phase at all times.

Ramp 5

The Contractor shall maintain all existing lanes of traffic at their existing lane widths during this phase at all times.

Ramp 6

The Contractor shall maintain all existing lanes of traffic at their existing lane widths during this phase at all times.

Bluegrass Parkway

The Contractor shall maintain all existing lanes of traffic at their existing lane widths during this phase at all times.

PHASE 1 TRAFFIC CONTROL - NIGHTTIME HOURS (9 p.m. to 6 a.m.)

During this phase, traffic will be maintained along existing roadways, approaches, and entrances as detailed below.

KY 1747 (Hurstbourne Parkway)

The Contractor shall maintain all existing lanes with existing lane widths in each direction at all times except as noted below for this phase. All approaches and entrances shall remain open at all times unless otherwise noted.

During nighttime hours, the Contractor will be allowed to install lane closures on both sides of KY 1747 (Hurstbourne Parkway) in the proposed construction areas during this phase. Lane closures shall be installed according to Standard Drawing No. TTC-115-01. The lane closures will only be allowed in the proposed construction areas. See Maintenance of Traffic typical section on sheet R61.

A disincentive in the amount of \$8,000 for the first hour and \$20,000 for each hour thereafter shall be assessed the Contractor in quarter hour

intervals for any time after 6 a.m. that all lanes of traffic along KY 1747 (Hurstbourne Parkway) are not open to traffic. The full amount per quarter hour will be charged the Contractor for each full quarter hour and portion of an quarter hour after 6 a.m. that all existing lanes of KY 1747 (Hurstbourne Parkway) are not open to traffic.

I-64

The Contractor shall maintain all existing lanes of traffic at their existing lane widths during this phase at all times.

Ramp 4

The Contractor shall maintain all existing lanes of traffic at their existing lane widths during this phase at all times.

Ramp 5

The Contractor shall maintain all existing lanes of traffic at their existing lane widths during this phase at all times.

Ramp 6

The Contractor shall maintain all existing lanes of traffic at their existing lane widths during this phase at all times.

Bluegrass Parkway

The Contractor shall maintain all existing lanes of traffic at their existing lane widths during this phase at all times.

PHASE 1 CONSTRUCTION

KY 1747 (Hurstbourne Parkway)

1. Complete widening from Left Station 34+60.74 to Left Station 69+46.24.
2. Complete widening from Right Station 62+83.36 to Right Station 69+27.16.
3. Complete final asphalt surface course and overlay of the southbound lanes.

I-64

No construction to be completed during this phase.

Ramp 4

No construction to be completed during this phase.

Ramp 5

No construction to be completed during this phase.

Ramp 6

No construction to be completed during this phase.

Bluegrass Parkway

No construction to be completed during this phase.

USER: \$\$\$USER\$\$\$
 DATE: \$\$\$DATE\$\$\$
 FILE NAME: \$\$\$design\$file\$specification\$\$\$
 E-SHEET NAME:

TRAFFIC MANAGEMENT PLAN - PHASE 1

COUNTY OF	ITEM NO.	SHEET NO.
JEFFERSON	5-52.00	R58

 REVISED 06-07-2012

PREPARED BY _____ DATE _____
 CHECKED BY _____ DATE _____
 APPROVED BY _____ DATE _____

PHASE 1 TRAFFIC CONTROL - DAYTIME HOURS (6 a.m. to 9 p.m.)

During this phase, traffic will be maintained along existing roadways, approaches, and entrances as detailed below.

KY 1747 (Hurstbourne Parkway)

The Contractor shall maintain all existing lanes with existing lane widths in each direction at all times except as noted below for this phase. All approaches and entrances shall remain open at all times unless otherwise noted.

During daytime hours, the Contractor will be allowed to install shoulder closures on both sides of KY 1747 (Hurstbourne Parkway) in the proposed construction areas during this phase. Shoulder closures shall be installed according to Standard Drawing No. TTC-135-01. Contrary to Standard Drawing No. TTC-135-01, drums may be used in lieu of temporary traffic barrier. The shoulder closures will only be allowed in the proposed construction areas. See Maintenance of Traffic typical section on the sheet R61.

I-64

The Contractor shall maintain all existing lanes of traffic at their existing lane widths during this phase at all times.

Ramp 4

The Contractor shall maintain all existing lanes of traffic at their existing lane widths during this phase at all times.

Ramp 5

The Contractor shall maintain all existing lanes of traffic at their existing lane widths during this phase at all times.

Ramp 6

The Contractor shall maintain all existing lanes of traffic at their existing lane widths during this phase at all times.

Bluegrass Parkway

The Contractor shall maintain all existing lanes of traffic at their existing lane widths during this phase at all times.

PHASE 1 TRAFFIC CONTROL - NIGHTTIME HOURS (9 p.m. to 6 a.m.)

During this phase, traffic will be maintained along existing roadways, approaches, and entrances as detailed below.

KY 1747 (Hurstbourne Parkway)

The Contractor shall maintain all existing lanes with existing lane widths in each direction at all times except as noted below for this phase. All approaches and entrances shall remain open at all times unless otherwise noted.

During nighttime hours, the Contractor will be allowed to install lane closures on both sides of KY 1747 (Hurstbourne Parkway) in the proposed construction areas during this phase. Lane closures shall be installed according to Standard Drawing No. TTC-115-01. The lane closures will only be allowed in the proposed construction areas. See Maintenance of Traffic typical section on sheet R61.

A disincentive in the amount of \$8,000 for the first hour and \$20,000 for each hour thereafter shall be assessed the Contractor in quarter hour

intervals for any time after 6 a.m. that all lanes of traffic along KY 1747 (Hurstbourne Parkway) are not open to traffic. The full amount per quarter hour will be charged the Contractor for each full quarter hour and portion of a quarter hour after 6 a.m. that all existing lanes of KY 1747 (Hurstbourne Parkway) are not open to traffic.

I-64

The Contractor shall maintain all existing lanes of traffic at their existing lane widths during this phase at all times.

Ramp 4

The Contractor shall maintain all existing lanes of traffic at their existing lane widths during this phase at all times.

Ramp 5

The Contractor shall maintain all existing lanes of traffic at their existing lane widths during this phase at all times.

Ramp 6

The Contractor shall maintain all existing lanes of traffic at their existing lane widths during this phase at all times.

Bluegrass Parkway

The Contractor shall maintain all existing lanes of traffic at their existing lane widths during this phase at all times.

PHASE 1 CONSTRUCTION

KY 1747 (Hurstbourne Parkway)

1. Complete widening from Left Station 34+60.74 to Left Station 69+46.24.
2. Complete widening from Right Station 62+83.36 to Right Station 69+27.16.
3. Complete final asphalt surface course and overlay of the southbound lanes.

I-64

No construction to be completed during this phase.

Ramp 4

No construction to be completed during this phase.

Ramp 5


No construction to be completed during this phase.

Ramp 6

No construction to be completed during this phase.

Bluegrass Parkway

No construction to be completed during this phase.

USER: \$\$\$USER\$\$\$
 DATE: \$\$\$DATE\$\$\$
 FILE NAME: \$\$\$design\$file\$specification\$\$\$
 E-SHEET NAME: