



TRANSPORTATION CABINET

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Steven L. Beshear
Governor

Michael W. Hancock, P.E.
Secretary

April 22, 2015

CALL NO. 112
CONTRACT ID NO. 152197
ADDENDUM # 1

Subject: Lee County, ER 5262 (055)
Letting April 24, 2015

- (1) Revised - Completion Date - Page 4 of 105
- (2) Revised - Bid Items - Pages 104-105 of 105

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Robert C. Lewis".

Robert C. Lewis, P.E.
Acting Director
Division of Construction Procurement

RL:ks
Enclosures



An Equal Opportunity Employer M/F/D

ADMINISTRATIVE DISTRICT - 10

CONTRACT ID - 152197

ER 5262 (055)

COUNTY - LEE

PCN - MP06500521502

ER 5262 (055)

BEATTYVILLE-JACKSON ROAD (KY 52) (MP 17.147) FROM 0.184 MILES EAST OF KY 2016 EXTENDING EAST TO 0.326 MILES EAST OF KY 2016 (MP 17.289), A DISTANCE OF 0.14 MILES.ASPHALT SURFACE WITH BRIDGE SYP NO. 10-295.

GEOGRAPHIC COORDINATES LATITUDE 37:34:43.00 LONGITUDE 83:38:46.00

COMPLETION DATE(S):

COMPLETED BY 07/31/2015

APPLIES TO ENTIRE CONTRACT

49 CALENDAR DAYS

APPLIES TO ROAD CLOSURE

PROPOSAL BID ITEMS

152197

Page 1 of 2

Report Date 4/22/15

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00003		CRUSHED STONE BASE	471.00	TON		\$	
0020	00020		TRAFFIC BOUND BASE	87.00	TON		\$	
0030	00100		ASPHALT SEAL AGGREGATE	9.00	TON		\$	
0040	00103		ASPHALT SEAL COAT	1.02	TON		\$	
0050	00190		LEVELING & WEDGING PG64-22	150.00	TON		\$	
0060	00212		CL2 ASPH BASE 1.00D PG64-22	434.00	TON		\$	
0070	00301		CL2 ASPH SURF 0.38D PG64-22	120.00	TON		\$	

Section: 0002 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0080	00078		CRUSHED AGGREGATE SIZE NO 2	330.00	TON		\$	
0090	01000		PERFORATED PIPE-4 IN	200.00	LF		\$	
0100	01010		NON-PERFORATED PIPE-4 IN	100.00	LF		\$	
0110	01020		PERF PIPE HEADWALL TY 1-4 IN	4.00	EACH		\$	
0120	01691		FLUME INLET TYPE 2	1.00	EACH		\$	
0130	01891		ISLAND HEADER CURB TYPE 2	97.00	LF		\$	
0140	01987		DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	6.00	EACH		\$	
0150	02014		BARRICADE-TYPE III	2.00	EACH		\$	
0160	02200		ROADWAY EXCAVATION	6,006.90	CUYD		\$	
0170	02223		GRANULAR EMBANKMENT	6,035.30	CUYD		\$	
0180	02242		WATER	33.00	MGAL		\$	
0190	02351		GUARDRAIL-STEEL W BEAM-S FACE	650.00	LF		\$	
0200	02360		GUARDRAIL TERMINAL SECTION NO 1	3.00	EACH		\$	
0210	02363		GUARDRAIL CONNECTOR TO BRIDGE END TY A	4.00	EACH		\$	
0220	02367		GUARDRAIL END TREATMENT TYPE 1	3.00	EACH		\$	
0230	02381		REMOVE GUARDRAIL	587.50	LF		\$	
0240	02399		EXTRA LENGTH GUARDRAIL POST	105.00	EACH		\$	
0250	02429		RIGHT-OF-WAY MONUMENT TYPE 1	9.00	EACH		\$	
0260	02432		WITNESS POST	3.00	EACH		\$	
0270	02484		CHANNEL LINING CLASS III	357.00	TON		\$	
0280	02545		CLEARING AND GRUBBING	1.00	LS		\$	
0290	02562		TEMPORARY SIGNS	206.00	SQFT		\$	
0300	02585		EDGE KEY	44.00	LF		\$	
0310	02599		FABRIC-GEOTEXTILE TYPE IV	1,825.00	SQYD		\$	
0320	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0330	02671		PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH		\$	
0340	02701		TEMP SILT FENCE	1,100.00	LF		\$	
0350	02703		SILT TRAP TYPE A	3.00	EACH		\$	
0360	02704		SILT TRAP TYPE B	3.00	EACH		\$	
0370	02705		SILT TRAP TYPE C	3.00	EACH		\$	
0380	02706		CLEAN SILT TRAP TYPE A	9.00	EACH		\$	
0390	02707		CLEAN SILT TRAP TYPE B	9.00	EACH		\$	
0400	02708		CLEAN SILT TRAP TYPE C	9.00	EACH		\$	
0410	02709		CLEAN TEMP SILT FENCE	1,100.00	LF		\$	

PROPOSAL BID ITEMS

REVISED ADDENDUM #1: 4-22-15

152197

Page 2 of 2

Report Date 4/22/15

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0420	02726		STAKING	1.00	LS		\$	
0430	02731		REMOVE STRUCTURE	1.00	LS		\$	
0440	05950		EROSION CONTROL BLANKET	126.00	SQYD		\$	
0450	05952		TEMP MULCH	6,500.00	SQYD		\$	
0460	05953		TEMP SEEDING AND PROTECTION	6,500.00	SQYD		\$	
0470	05963		INITIAL FERTILIZER	.30	TON		\$	
0480	05964		20-10-10 FERTILIZER	.60	TON		\$	
0490	05985		SEEDING AND PROTECTION	6,500.00	SQYD		\$	
0500	05992		AGRICULTURAL LIMESTONE	3.60	TON		\$	
0510	06510		PAVE STRIPING-TEMP PAINT-4 IN	3,000.00	LF		\$	
0520	06514		PAVE STRIPING-PERM PAINT-4 IN	3,000.00	LF		\$	
0530	08019		CYCLOPEAN STONE RIP RAP	625.00	TON		\$	
0540	21289ED		LONGITUDINAL EDGE KEY	1,075.00	LF		\$	

Section: 0003 - DRAINAGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0550	00441		ENTRANCE PIPE-18 IN	47.00	LF		\$	
0560	00450		ENTRANCE PIPE-15 IN EQUIV	33.00	LF		\$	
0570	01204		PIPE CULVERT HEADWALL-18 IN	1.00	EACH		\$	
0580	01370		METAL END SECTION TY 1-15 IN	2.00	EACH		\$	
0590	01450		S & F BOX INLET-OUTLET-18 IN	1.00	EACH		\$	

Section: 0004 - BRIDGE - STA 103+06.85

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0600	02231		STRUCTURE GRANULAR BACKFILL	348.00	CUYD		\$	
0610	02998		MASONRY COATING	673.00	SQYD		\$	
0620	03299		ARMORED EDGE FOR CONCRETE	59.50	LF		\$	
0630	08001		STRUCTURE EXCAVATION-COMMON (REVISED: 4-22-15)	644.00	CUYD		\$	
0640	08019		CYCLOPEAN STONE RIP RAP	1,405.00	TON		\$	
0650	08033		TEST PILES	77.00	LF		\$	
0660	08046		PILES-STEEL HP12X53	405.00	LF		\$	
0670	08094		PILE POINTS-12 IN	14.00	EACH		\$	
0680	08100		CONCRETE-CLASS A	52.20	CUYD		\$	
0690	08104		CONCRETE-CLASS AA	199.70	CUYD		\$	
0700	08151		STEEL REINFORCEMENT-EPOXY COATED	38,379.00	LB		\$	
0710	08638		PRECAST PC I BEAM TYPE 8	538.00	LF		\$	
0720	21532ED		RAIL SYSTEM TYPE III	272.00	LF		\$	
0730	23813EC		DECK DRAIN	3.00	EACH		\$	

Section: 0005 - DEMOBILIZATION &/OR MOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0740	02569		DEMOBILIZATION	1.00	LS		\$	