

Matthew G. Bevin Governor

# COMMONWEALTH OF KENTUCKY TRANSPORTATION CABINET

Frankfort, Kentucky 40622 www.transportation.ky.gov/

**Greg Thomas** Secretary

September 28, 2016

CALL NO. 305

CONTRACT ID NO. 162904

ADDENDUM # 1

Subject: Harlan County, FE02 048 0119 B00126N

Letting September 30, 2016

(1) Revised - Note - Page 10 of 80

(2) Revised - Bid Items - Page 80 of 80

Proposal revisions are available at  $\frac{\text{http://transportation.ky.gov/Construction-Procurement/.}}{\text{Procurement/.}}$ 

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills, P.E.

Director

Division of Construction Procurement

Kachel Mille

RM:ks

Enclosures



All new structural steel shall receive shop surface preparation and shop applied prime coating in accordance with section 607. Intermediate and Finish coatings specified shall be field applied or shop applied in accordance with section 607. Necessary touch up/repair of the shop applied coatings on the new steel may be performed in the field. All items necessary to complete painting as specified in this note shall be considered to the unit price bid "Each" for Bearing Replacement.

- **G. Verifying Field Conditions.** The Contractor shall field verify all plate and shape dimensions, bolt patterns and locations before ordering any material. New material that is unsuitable due to variation in existing structure shall be replaced at the Contractors expense.
- **H. Damage to the structure.** The Contractor shall bear all responsibility and expense for any and all damage to the structure during the repair work, even to the removal and replacement of a fallen span, should the fallen span result from the Contractors actions.

#### IV MEASUREMENT.

**Bearing Replacement.** The Department will measure the quantity for "Each" repair.

**Jack and Support Bridge Span.** The Department will measure the quantity as "Lump Sum".

#### V. PAYMENT.

**Bearing Replacement (21969NN).** Payment at the contract unit price for "Each" is full compensation for furnishing and installing all material as specified.

**Jack & Support Bridge Span (08435):** Payment at the contract lump sum shall include all items and labor necessary to jack and support the bridge span as specified.

**Residual lead paint may still be on bridge.** The Contractor is advised to take all necessary protective measures including worker safety and environmental regulations when performing surface preparation and other work. The Department will not consider any claims based on residual lead paint.

## **PROPOSAL BID ITEMS**

REVISED ADDENDUM #1: 9-28-16 Contract ID: 162904 Page 80 of 80

Page 1 of 1

### Report Date 9/28/16

Section: 0001 - BRIDGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	<b>UNIT PRIC</b>	FP	AMOUNT
0010	02562		TEMPORARY SIGNS	149.00	SQFT		\$	
0020	02650		MAINTAIN & CONTROL TRAFFIC APPLIES TO 048B00126N	1.00	LS		\$	
0030	02653		LANE CLOSURE	4.00	EACH		\$	
0040	02775		ARROW PANEL	2.00	EACH		\$	
0050	03298		EXPAN JOINT REPLACE 4 IN	303.00	LF		\$	
0060	03299		ARMORED EDGE FOR CONCRETE	190.00	LF		\$	
0070	03304		BRIDGE OVERLAY APPROACH PAVEMENT	1,056.00	SQYD		\$	
0800	06514		PAVE STRIPING-PERM PAINT-4 IN	20.00	LF		\$	
0090	06549		PAVE STRIPING-TEMP REM TAPE-B	1,000.00	LF		\$	
0100	06550		PAVE STRIPING-TEMP REM TAPE-W	4,000.00	LF		\$	
0110	06551		PAVE STRIPING-TEMP REM TAPE-Y	4,000.00	LF		\$	
0120	08150		STEEL REINFORCEMENT	267.00	LB		\$	
0125	08435		JACK & SUPPORT BRIDGE SPAN (ADDED: 9-28-16)	1.00	LS		\$	
0130	08510		REM EPOXY BIT FOREIGN OVERLAY	327.00	SQYD		\$	
0140	08534		CONCRETE OVERLAY-LATEX	18.10	CUYD		\$	
0150	08540		JOINT SEALING	120.00	LF		\$	
0160	08549		BLAST CLEANING	327.00	SQYD		\$	
0170	21969NN		BEARING REPLACEMENT	3.00	EACH		\$	
0180	24094EC		PARTIAL DEPTH PATCHING	10.00	CUYD		\$	

Section: 0002 - DEMOBILIZATION

LINE	BID CODE	ALT DESCRIPTION	QUANTITY	UNIT	<b>UNIT PRIC</b>	FP AMOUNT
0190	02569	DEMOBILIZATION	1.00	LS		\$