



**TRANSPORTATION CABINET**

Frankfort, Kentucky 40622  
www.transportation.ky.gov/

**Steven L. Beshear**  
Governor

**Michael W. Hancock, P.E.**  
Secretary

September 24, 2014

CALL NO. 306  
CONTRACT ID NO. 141053  
ADDENDUM # 1

Subject: Whitley County, FD04 SPP 118 2386 000-001  
Letting September 26, 2014

(1) Revised - Bid Items - Pages 103-105 of 105

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Diana Castle Radcliffe".

Diana Castle Radcliffe  
Director  
Division of Construction Procurement

DR:ks  
Enclosures



An Equal Opportunity Employer M/F/D

**PROPOSAL BID ITEMS**

141053

Page 1 of 3

Report Date 9/24/14

**Section: 0001 - PAVING**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0010	00003		CRUSHED STONE BASE	3,879.00	TON		\$	
0020	00020		TRAFFIC BOUND BASE	489.00	TON		\$	
0030	00078		CRUSHED AGGREGATE SIZE NO 2	6,263.00	TON		\$	
0040	00190		LEVELING & WEDGING PG64-22	343.00	TON		\$	
0050	00212		CL2 ASPH BASE 1.00D PG64-22	3,175.00	TON		\$	
0060	00307		CL2 ASPH SURF 0.38B PG64-22	1,079.00	TON		\$	
0070	02101		CEM CONC ENT PAVEMENT-8 IN	135.00	SQYD		\$	
0080	02599		FABRIC-GEOTEXTILE TYPE IV	21,348.00	SQYD		\$	
0090	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0100	02677		ASPHALT PAVE MILLING & TEXTURING	452.00	TON		\$	

**Section: 0002 - ROADWAY**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0110	01000		PERFORATED PIPE-4 IN	3,244.00	LF		\$	
0120	01010		NON-PERFORATED PIPE-4 IN	180.00	LF		\$	
0130	01015		INSPECT & CERTIFY EDGE DRAIN SYSTEM	1.00	LS		\$	
0140	01310		REMOVE PIPE	603.00	LF		\$	
0150	01810		STANDARD CURB AND GUTTER	4,382.00	LF		\$	
0160	01875		STANDARD HEADER CURB	337.00	LF		\$	
0170	02014		BARRICADE-TYPE III	4.00	EACH		\$	
0180	02159		TEMP DITCH	1,750.00	LF		\$	
0190	02230		EMBANKMENT IN PLACE	35,411.00	CUYD		\$	
0200	02242		WATER	1,000.00	MGAL		\$	
0210	02429		RIGHT-OF-WAY MONUMENT TYPE 1	37.00	EACH		\$	
0220	02430		RIGHT-OF-WAY MONUMENT TYPE 1A	6.00	EACH		\$	
0230	02432		WITNESS POST	29.00	EACH		\$	
0240	02545		CLEARING AND GRUBBING 6.41 ACRES	1.00	LS		\$	
0250	02562		TEMPORARY SIGNS	277.00	SQFT		\$	
0260	02611		HANDRAIL-TYPE A-1	75.00	LF		\$	
0270	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0280	02671		PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH		\$	
0290	02690		SAFELoading	4.00	CUYD		\$	
0300	02701		TEMP SILT FENCE	1,750.00	LF		\$	
0310	02703		SILT TRAP TYPE A	10.00	EACH		\$	
0320	02704		SILT TRAP TYPE B	8.00	EACH		\$	
0330	02705		SILT TRAP TYPE C	14.00	EACH		\$	
0340	02706		CLEAN SILT TRAP TYPE A	20.00	EACH		\$	
0350	02707		CLEAN SILT TRAP TYPE B	16.00	EACH		\$	
0360	02708		CLEAN SILT TRAP TYPE C	28.00	EACH		\$	
0370	02709		CLEAN TEMP SILT FENCE	3,500.00	LF		\$	
0380	02720		SIDEWALK-4 IN CONCRETE	2,089.00	SQYD		\$	
0390	02726		STAKING	1.00	LS		\$	
0400	02731		REMOVE STRUCTURE	1.00	LS		\$	
0410	05950		EROSION CONTROL BLANKET	913.00	SQYD		\$	
0420	05952		TEMP MULCH	2,500.00	SQYD		\$	

**PROPOSAL BID ITEMS**

141053

Page 2 of 3

Report Date 9/24/14

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0430	05953		TEMP SEEDING AND PROTECTION	2,500.00	SQYD		\$	
0440	05963		INITIAL FERTILIZER	.80	TON		\$	
0450	05964		20-10-10 FERTILIZER	1.40	TON		\$	
0460	05985		SEEDING AND PROTECTION	24,290.00	SQYD		\$	
0470	05990		SODDING	1,859.00	SQYD		\$	
0480	05992		AGRICULTURAL LIMESTONE	16.20	TON		\$	
0490	06510		PAVE STRIPING-TEMP PAINT-4 IN	1,050.00	LF		\$	
0500	06514		PAVE STRIPING-PERM PAINT-4 IN	7,500.00	LF		\$	
0510	06550		PAVE STRIPING-TEMP REM TAPE-W	500.00	LF		\$	
0520	06551		PAVE STRIPING-TEMP REM TAPE-Y	500.00	LF		\$	
0530	06568		PAVE MARKING-THERMO STOP BAR-24IN	50.00	LF		\$	
0540	06570		PAVE MARKING-PAINT CROSS-HATCH	600.00	SQFT		\$	
0550	06572		PAVE MARKING-DOTTED LANE EXTEN	225.00	LF		\$	
0560	06573		PAVE MARKING-THERMO STR ARROW	4.00	EACH		\$	
0570	06574		PAVE MARKING-THERMO CURV ARROW	16.00	EACH		\$	
0580	06589		PAVEMENT MARKER TYPE V-MW	4.00	EACH		\$	
0590	06591		PAVEMENT MARKER TYPE V-BY	110.00	EACH		\$	
0600	10020NS		FUEL ADJUSTMENT	14,842.00	DOLL	\$1.00	\$	\$14,842.00
0610	10030NS		ASPHALT ADJUSTMENT	17,972.00	DOLL	\$1.00	\$	\$17,972.00
0620	20430ED		SAW CUT	2,233.00	LF		\$	
0630	23131ER701		PIPELINE VIDEO INSPECTION	949.00	LF		\$	
0640	23158ES505		DETECTABLE WARNINGS	305.00	SQFT		\$	

**Section: 0003 - DRAINAGE**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0650	00440		ENTRANCE PIPE-15 IN	82.00	LF		\$	
0660	00521		STORM SEWER PIPE-15 IN	331.00	LF		\$	
0670	00522		STORM SEWER PIPE-18 IN	599.00	LF		\$	
0680	00524		STORM SEWER PIPE-24 IN	153.00	LF		\$	
0690	00531		STORM SEWER PIPE-54 IN	803.00	LF		\$	
0700	00560		STORM SEWER PIPE-48 IN EQUIV	11.00	LF		\$	
0710	01202		PIPE CULVERT HEADWALL-15 IN	2.00	EACH		\$	
0720	01208		PIPE CULVERT HEADWALL-24 IN	1.00	EACH		\$	
0730	01217		PIPE CULVERT HEADWALL-48 IN EQUIV	1.00	EACH		\$	
0740	01456		CURB BOX INLET TYPE A	13.00	EACH		\$	
0750	01544		DROP BOX INLET TYPE 11	3.00	EACH		\$	
0760	01568		DROP BOX INLET TYPE 13S	3.00	EACH		\$	
0770	01634		CAP CURB BOX INLET	2.00	EACH		\$	
0780	01756		MANHOLE TYPE A	3.00	EACH		\$	
0790	01767		MANHOLE TYPE C	2.00	EACH		\$	
0800	02600		FABRIC GEOTEXTILE TY IV FOR PIPE REVISED: 9-24-14	9,510.00	SQYD	\$2.00	\$	\$19,020.00
0810	08100		CONCRETE-CLASS A	8.42	CUYD		\$	
0820	23274EN11F		TURF REINFORCEMENT MAT 1	1,033.00	SQYD		\$	
0830	24026EC		PIPE CULVERT HEADWALL-54 IN	1.00	EACH		\$	

**Section: 0004 - BRIDGE**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
------	----------	-----	-------------	----------	------	------------	----	--------

**PROPOSAL BID ITEMS**

141053

Page 3 of 3

Report Date 9/24/14

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0840	02231		STRUCTURE GRANULAR BACKFILL	955.00	CUYD		\$	
0850	02998		MASONRY COATING	460.00	SQYD		\$	
0860	03299		ARMORED EDGE FOR CONCRETE	81.00	LF		\$	
0870	08001		STRUCTURE EXCAVATION-COMMON	655.00	CUYD		\$	
0880	08002		STRUCTURE EXCAV-SOLID ROCK	250.00	CUYD		\$	
0890	08100		CONCRETE-CLASS A	689.30	CUYD		\$	
0900	08104		CONCRETE-CLASS AA	108.50	CUYD		\$	
0910	08150		STEEL REINFORCEMENT	106,140.00	LB		\$	
0920	08151		STEEL REINFORCEMENT-EPOXY COATED	22,675.00	LB		\$	
0930	08669		PRECAST PC BOX BEAM SB21	233.50	LF		\$	
0940	21119ED		CONCRETE FORM LINER	355.00	SQYD		\$	
0950	23168ED		CONCRETE STAINING	355.00	SQYD		\$	

**Section: 0005 - LIGHTING**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0960	04740		POLE BASE	20.00	EACH		\$	
0970	04793		CONDUIT-1 1/4 IN	4,620.00	LF		\$	
0980	04795		CONDUIT-2 IN	1,580.00	LF		\$	
0990	04820		TRENCHING AND BACKFILLING	3,790.00	LF		\$	
1000	20391NS835		ELECTRICAL JUNCTION BOX TYPE A	22.00	EACH		\$	
1010	21543EN		BORE AND JACK CONDUIT	450.00	LF		\$	
1020	24601EC		INSTALL TERMINATION BOX	20.00	EACH		\$	
1030	24601EC		INSTALL TRANSFORMER BASE	1.00	EACH		\$	

**Section: 0006 - MOBILIZATION/DEMOBILIZATION**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
1040	02568		MOBILIZATION	1.00	LS		\$	
1050	02569		DEMOBILIZATION	1.00	LS		\$	