



**TRANSPORTATION CABINET**

Frankfort, Kentucky 40622  
www.transportation.ky.gov/

**Steven L. Beshear**  
Governor

**Michael W. Hancock, P.E.**  
Secretary

December 5, 2014

CALL NO. 307  
CONTRACT ID NO. 141302  
ADDENDUM # 1

Subject: Calloway County, FD04 SPP 018 0121 014-016  
Letting December 12, 2014

- (1) Added - Special Note - Page 1 of 1
- (2) Revised - Bid Items - Pages 114-118 of 118

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Diana Castle Radcliffe".

Diana Castle Radcliffe  
Director  
Division of Construction Procurement

DR:ks  
Enclosures



An Equal Opportunity Employer M/F/D

### **Special Note for Reinforced Concrete Box Culvert Extension**

Extend existing 3'X3' reinforced concrete box culvert at Station 68+59. Construct the extension per Standard Drawing RDX-300-03 or as directed by the Engineer. Payment at the contract unit price linear feet shall be full compensation for removing existing headwalls, prep work to existing structure, Removing Concrete Masonry and Concrete Class D Modified.

Construct 2 - 3'X3' Precast Box Culvert Headwalls at 0 degree skew at Station 68+59 per drawing RDH-1000-02, RDH-1100-02 and RDH-1200-02 of the Standard Drawing Headwall Supplement. Payment for headwall construction will be made per cubic yard for Class A Concrete and per pound of Steel Reinforcement.

### PROPOSAL BID ITEMS

141302

Page 1 of 5

Report Date 12/5/14

#### Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00001		DGA BASE	13,364.00	TON		\$	
0020	00190		LEVELING & WEDGING PG64-22	743.00	TON		\$	
0030	00214		CL3 ASPH BASE 1.00D PG64-22	14,245.00	TON		\$	
0040	00216		CL3 ASPH BASE 1.00D PG76-22	6,382.00	TON		\$	
0050	00324		CL3 ASPH SURF 0.50B PG64-22	548.00	TON		\$	
0060	00326		CL3 ASPH SURF 0.50B PG76-22	4,499.00	TON		\$	
0070	02084		JPC PAVEMENT-8 IN	267.00	SQYD		\$	
0080	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0090	02677		ASPHALT PAVE MILLING & TEXTURING	1,659.00	TON		\$	

#### Section: 0002 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0100	01810		STANDARD CURB AND GUTTER	13,854.00	LF		\$	
0110	01811		STANDARD CURB AND GUTTER MOD	37.00	LF		\$	
0120	01830		STANDARD INTEGRAL CURB (FOR ENTRANCES)	67.00	LF		\$	
0130	01875		STANDARD HEADER CURB (FOR ENTRANCES)	151.00	LF		\$	
0140	01982		DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL WHITE	7.00	EACH		\$	
0150	02101		CEM CONC ENT PAVEMENT-8 IN	1,856.00	SQYD		\$	
0160	02230		EMBANKMENT IN PLACE	31,023.00	CUYD		\$	
0170	02351		GUARDRAIL-STEEL W BEAM-S FACE	237.50	LF		\$	
0180	02360		GUARDRAIL TERMINAL SECTION NO 1	5.00	EACH		\$	
0190	02367		GUARDRAIL END TREATMENT TYPE 1	3.00	EACH		\$	
0200	02381		REMOVE GUARDRAIL	1,329.00	LF		\$	
0210	02429		RIGHT-OF-WAY MONUMENT TYPE 1	83.00	EACH		\$	
0220	02432		WITNESS POST	83.00	EACH		\$	
0230	02483		CHANNEL LINING CLASS II	99.00	TON		\$	
0240	02484		CHANNEL LINING CLASS III	282.00	TON		\$	
0250	02545		CLEARING AND GRUBBING (APPROXIMATELY 7 ACRES)	1.00	LS		\$	
0260	02585		EDGE KEY	379.00	LF		\$	
0270	02600		FABRIC GEOTEXTILE TY IV FOR PIPE	9,471.00	SQYD	\$2.00	\$	\$18,942.00
0280	02611		HANDRAIL-TYPE A-1	178.00	LF		\$	
0290	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0300	02690		SAFELoading	16.00	CUYD		\$	
0310	02701		TEMP SILT FENCE	6,151.00	LF		\$	
0320	02704		SILT TRAP TYPE B	37.00	EACH		\$	
0330	02705		SILT TRAP TYPE C	18.00	EACH		\$	
0340	02707		CLEAN SILT TRAP TYPE B	111.00	EACH		\$	
0350	02708		CLEAN SILT TRAP TYPE C	54.00	EACH		\$	
0360	02709		CLEAN TEMP SILT FENCE	12,300.00	LF		\$	
0370	02710		SCARIFYING AND RESHAPING	45.00	SQYD		\$	
0380	02720		SIDEWALK-4 IN CONCRETE	5,773.00	SQYD		\$	
0390	02726		STAKING	1.00	LS		\$	

**PROPOSAL BID ITEMS**

141302

Page 2 of 5

Report Date 12/5/14

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0400	05950		EROSION CONTROL BLANKET	6,140.00	SQYD		\$	
0410	05952		TEMP MULCH	31,000.00	SQYD		\$	
0420	05953		TEMP SEEDING AND PROTECTION	4,000.00	SQYD		\$	
0430	05963		INITIAL FERTILIZER	1.10	TON		\$	
0440	05964		20-10-10 FERTILIZER	1.60	TON		\$	
0450	05985		SEEDING AND PROTECTION (METHOD 1)	31,000.00	SQYD		\$	
0460	05990		SODDING (FOR MEDIAN)	1,030.00	SQYD		\$	
0470	05992		AGRICULTURAL LIMESTONE	21.00	TON		\$	
0480	06510		PAVE STRIPING-TEMP PAINT-4 IN	3,000.00	LF		\$	
0490	06514		PAVE STRIPING-PERM PAINT-4 IN	41,806.00	LF		\$	
0500	06550		PAVE STRIPING-TEMP REM TAPE-W	1,000.00	LF		\$	
0510	06551		PAVE STRIPING-TEMP REM TAPE-Y	1,000.00	LF		\$	
0520	06565		PAVE MARKING-THERMO X-WALK-6 IN	1,549.00	LF		\$	
0530	06568		PAVE MARKING-THERMO STOP BAR-24IN	717.00	LF		\$	
0540	06570		PAVE MARKING-PAINT CROSS-HATCH	9,200.00	SQFT		\$	
0550	06573		PAVE MARKING-THERMO STR ARROW	19.00	EACH		\$	
0560	06574		PAVE MARKING-THERMO CURV ARROW	61.00	EACH		\$	
0570	06575		PAVE MARKING-THERMO COMB ARROW	28.00	EACH		\$	
0580	06589		PAVEMENT MARKER TYPE V-MW	185.00	EACH		\$	
0590	06591		PAVEMENT MARKER TYPE V-BY	297.00	EACH		\$	
0600	06600		REMOVE PAVEMENT MARKER TYPE V	155.00	EACH		\$	
0610	10020NS		FUEL ADJUSTMENT	54,561.00	DOLL	\$1.00	\$	\$54,561.00
0620	10030NS		ASPHALT ADJUSTMENT	103,280.00	DOLL	\$1.00	\$	\$103,280.00
0630	23131ER701		PIPELINE VIDEO INSPECTION	3,924.00	LF		\$	
0640	23158ES505		DETECTABLE WARNINGS	892.00	SQFT		\$	
0650	23274EN11F		TURF REINFORCEMENT MAT 1	713.00	SQYD		\$	

**Section: 0003 - DRAINAGE**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0660	00440		ENTRANCE PIPE-15 IN	60.00	LF		\$	
0670	00441		ENTRANCE PIPE-18 IN	463.00	LF		\$	
0680	00443		ENTRANCE PIPE-24 IN	37.00	LF		\$	
0690	00503		CULVERT PIPE-72 IN EQUIV	43.00	LF		\$	
0700	00505		CULVERT PIPE-78 IN EQUIV	84.00	LF		\$	
0710	00520		STORM SEWER PIPE-12 IN	184.00	LF		\$	
0720	00521		STORM SEWER PIPE-15 IN	5,177.00	LF		\$	
0730	00522		STORM SEWER PIPE-18 IN	1,109.00	LF		\$	
0740	00524		STORM SEWER PIPE-24 IN	557.00	LF		\$	
0750	00526		STORM SEWER PIPE-30 IN	75.00	LF		\$	
0760	00530		STORM SEWER PIPE-48 IN	55.00	LF		\$	
0770	00536		STORM SEWER PIPE-84 IN	117.00	LF		\$	
0780	00558		STORM SEWER PIPE-36 IN EQUIV	144.00	LF		\$	
0790	01200		PIPE CULVERT HEADWALL-12 IN	1.00	EACH		\$	
0800	01202		PIPE CULVERT HEADWALL-15 IN	3.00	EACH		\$	
0810	01204		PIPE CULVERT HEADWALL-18 IN	2.00	EACH		\$	
0820	01208		PIPE CULVERT HEADWALL-24 IN	3.00	EACH		\$	

**PROPOSAL BID ITEMS**

141302

Page 3 of 5

Report Date 12/5/14

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0830	01210		PIPE CULVERT HEADWALL-30 IN	1.00	EACH		\$	
0840	01216		PIPE CULVERT HEADWALL-48 IN	1.00	EACH		\$	
0850	01371		METAL END SECTION TY 1-18 IN	1.00	EACH		\$	
0860	01373		METAL END SECTION TY 1-24 IN	1.00	EACH		\$	
0870	01374		METAL END SECTION TY 1-30 IN	1.00	EACH		\$	
0880	01391		METAL END SECTION TY 3-18 IN	2.00	EACH		\$	
0890	01456		CURB BOX INLET TYPE A	52.00	EACH		\$	
0900	01496		DROP BOX INLET TYPE 3	16.00	EACH		\$	
0910	01499		DROP BOX INLET TYPE 4	1.00	EACH		\$	
0920	01550		DROP BOX INLET TYPE 12A	24.00	LF		\$	
0930	01559		DROP BOX INLET TYPE 13G	1.00	EACH		\$	
0940	01577		DROP BOX INLET TYPE 14	7.00	EACH		\$	
0950	01641		JUNCTION BOX-15 IN	1.00	EACH		\$	
0960	01642		JUNCTION BOX-18 IN	1.00	EACH		\$	
0970	01644		JUNCTION BOX-30 IN	4.00	EACH		\$	
0980	01647		JUNCTION BOX-48 IN	1.00	EACH		\$	
0990	01650		JUNCTION BOX (TYPE B1)	1.00	EACH		\$	
1000	01650		JUNCTION BOX (84 INCH)	3.00	EACH		\$	
1010	01650		JUNCTION BOX (18 INCH MODIFIED)	1.00	EACH		\$	
1020	01650		JUNCTION BOX (72 INCH)	1.00	EACH		\$	
1030	01691		FLUME INLET TYPE 2	1.00	EACH		\$	
1040	01756		MANHOLE TYPE A	1.00	EACH		\$	
1050	01767		MANHOLE TYPE C	1.00	EACH		\$	
1060	22045NN		FLUME INLET TY 2-MOD	1.00	EACH		\$	
1070	24025EC		PIPE CULVERT HEADWALL-72 IN	1.00	EACH		\$	
1080	24575ES610		HEADWALL (72 INCH EQUIV.)	2.00	EACH		\$	

**Section: 0004 - BRIDGE - CULVERT - STA 98+15 - DWG. 25699 (REVISED: 12-5-14)**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1090	02625		REMOVE HEADWALL	2.00	EACH		\$	
1100	08003		FOUNDATION PREPARATION	1.00	LS		\$	
1110	08100		CONCRETE-CLASS A	116.60	CUYD		\$	
1120	08150		STEEL REINFORCEMENT	9,531.00	LB		\$	

**Section: 0005 - BRIDGE - CULVERT - STA 115+88 - DWG. 25700 (REVISED: 12-5-14)**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1130	02403		REMOVE CONCRETE MASONRY	.80	CUYD		\$	
1140	08003		FOUNDATION PREPARATION	1.00	LS		\$	
1150	08100		CONCRETE-CLASS A	114.80	CUYD		\$	
1160	08150		STEEL REINFORCEMENT	14,299.00	LB		\$	

**PROPOSAL BID ITEMS**

141302

Page 4 of 5

Report Date 12/5/14

**Section: 0006 - BRIDGE - CULVERT - STA 68+59 (ADDED: 12-5-14)**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1170	08100		CONCRETE-CLASS A	4.39	CUYD		\$	
1180	08150		STEEL REINFORCEMENT	365.00	LB		\$	
1190	24234EC		PRECAST CONC BOX SECT-3 X 3	47.00	LF		\$	

**Section: 0007 - SIGNALIZATION**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1200	04792		CONDUIT-1 IN	490.00	LF		\$	
1210	04793		CONDUIT-1 1/4 IN	715.00	LF		\$	
1220	04795		CONDUIT-2 IN	3,475.00	LF		\$	
1230	04811		ELECTRICAL JUNCTION BOX TYPE B	21.00	EACH		\$	
1240	04820		TRENCHING AND BACKFILLING	3,480.00	LF		\$	
1250	04830		LOOP WIRE	14,410.00	LF		\$	
1260	04844		CABLE-NO. 14/5C	11,220.00	LF		\$	
1270	04850		CABLE-NO. 14/1 PAIR	10,850.00	LF		\$	
1280	04885		MESSENGER-10800 LB	525.00	LF		\$	
1290	04895		LOOP SAW SLOT AND FILL	3,710.00	LF		\$	
1300	04931		INSTALL CONTROLLER TYPE 170	4.00	EACH		\$	
1310	04932		INSTALL STEEL STRAIN POLE	4.00	EACH		\$	
1320	04950		REMOVE SIGNAL EQUIPMENT	4.00	EACH		\$	
1330	20093NS835		INSTALL PEDESTRIAN HEAD-LED	32.00	EACH		\$	
1340	20094ES835		TEMP RELOCATION OF SIGNAL HEAD	48.00	EACH		\$	
1350	20188NS835		INSTALL LED SIGNAL-3 SECTION	32.00	EACH		\$	
1360	20266ES835		INSTALL LED SIGNAL- 4 SECTION	10.00	EACH		\$	
1370	20391NS835		ELECTRICAL JUNCTION BOX TYPE A	14.00	EACH		\$	
1380	21543EN		BORE AND JACK CONDUIT	940.00	LF		\$	
1390	21743NN		INSTALL PEDESTRIAN DETECTOR	32.00	EACH		\$	
1400	22631NN		INSTALL MAST ARM POLE	8.00	EACH		\$	
1410	23068NN		REMOVE & REINSTALL COORDINATING UNIT	4.00	EACH		\$	
1420	23157EN		TRAFFIC SIGNAL POLE BASE	60.00	CUYD		\$	
1430	23222EC		INSTALL SIGNAL PEDESTAL	14.00	EACH		\$	

**Section: 0008 - LIGHTING**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1440	04740		POLE BASE	38.00	EACH		\$	
1450	04761		LIGHTING CONTROL EQUIPMENT	1.00	EACH		\$	
1460	04780		FUSED CONNECTOR KIT	76.00	EACH		\$	
1470	04791		CONDUIT-3/4 IN	450.00	LF		\$	
1480	04792		CONDUIT-1 IN	20.00	LF		\$	
1490	04795		CONDUIT-2 IN	5,200.00	LF		\$	
1500	04797		CONDUIT-3 IN	100.00	LF		\$	
1510	04820		TRENCHING AND BACKFILLING	4,400.00	LF		\$	
1520	04833		WIRE-NO. 8	12,084.00	LF		\$	
1530	04834		WIRE-NO. 6	2,920.00	LF		\$	

**PROPOSAL BID ITEMS**

141302

Page 5 of 5

Report Date 12/5/14

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1540	04835		WIRE-NO. 4	420.00	LF		\$	
1550	04836		WIRE-NO. 2	200.00	LF		\$	
1560	20391NS835		ELECTRICAL JUNCTION BOX TYPE A	38.00	EACH		\$	
1570	21543EN		BORE AND JACK CONDUIT	750.00	LF		\$	
1580	23778EC		WIRE-NO. 10	4,560.00	LF		\$	
1590	24122EC		TRANSFORMER PAD	.50	CUYD		\$	
1600	24601EC		INSTALL (LUMINAIRE LED TEARDROP)	50.00	EACH		\$	
1610	24601EC		INSTALL (DECORATIVE POLE 22-FT BREAK-AWAY SKIRT)	38.00	EACH		\$	
1620	24601EC		INSTALL (DECORATIVE BRACKET ARM 72 IN SINGLE)	26.00	EACH		\$	
1630	24601EC		INSTALL (DECORATIVE BRACKET ARM 72 IN DOUBLE)	12.00	EACH		\$	
1640	24601EC		INSTALL (TRANSFORMER BASE)	38.00	EACH		\$	

**Section: 0009 - DEMOBILIZATION &/OR MOBILIZATION**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1650	02568		MOBILIZATION	1.00	LS		\$	
1660	02569		DEMOBILIZATION	1.00	LS		\$	