

Frankfort, Kentucky 40622 www.transportation.ky.gov/

December 9, 2015

CALL NO. 307

CONTRACT ID NO. 152326

ADDENDUM # 1

Subject: Oldham County, FE01 093 0071 014-015

Letting December 11, 2015

(1) Revised - Special Note - Page 19 of 97

(2) Revised - Traffic Control Plan - Pages 29-38 of 97

Proposal revisions are available at $\frac{\text{http://transportation.ky.gov/Construction-Procurement/.}}$

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills, P.E.

Director

Division of Construction Procurement

Kachel Mille

RM:ks

Enclosures

Contract ID: 152326 Page 19 of 97

REVISED ADDENDUM #1: 12-9-15

SPECIAL NOTE FOR LIQUIDATED DAMAGES

Additional Liquidated damages in the amount specified in Section 108.09 will be assessed for each excavated area for each day or part of a day beyond 14 days (as specified in the Traffic Control Plan) an excavated PCC Pavement removal area remains open without the PCC Pavement being placed, excluding delays caused by inclement weather; the Engineer will measure the time beginning when the PCC Pavement excavation commences and ending when the concrete is placed to completely eliminate the hole or the asphalt base placed to eliminate the open trench. If the work is delayed by inclement weather, the work required to place the new PCC Pavement or asphalt base shall be resumed immediately as soon as weather permits.

Liquidated damages in the amount of \$1,000 per hour will be assessed for each hour or part of an hour a lane closure remains in place during times and dates prohibited by the Traffic Control Plan.

Contrary to section 108.09, liquidated damages will be assessed for the months of December, January, February, and March.

Contrary to section 108.09, liquidated damages will be assessed regardless of whether seasonal limitations prohibit the Contractor from performing work on the controlling operation.

All liquidated damages will be applied accumulatively.

All other applicable portions of Section 108 apply.

Contract ID: 152326 Page 29 of 97

REVISED ADDENDUM #1: 12-9-15

TRAFFIC CONTROL PLAN

FE01 093 0071 014-015

TRAFFIC CONTROL GENERAL

Except as provided herein, traffic shall be maintained in accordance with the 2012 Standard Specifications and the Standard Drawings, current editions. Except for the roadway and traffic control bid items listed, all items of work necessary to maintain and control traffic will be paid at the lump sum bid price to "Maintain and Control Traffic".

Contrary to Section 106.01, traffic control devices used on this project may be new, or used in like new condition, at the beginning of the work and maintained in like new condition until completion of the work.

PROJECT PHASING & CONSTRUCTION PROCEDURES

NO WORK SHALL BE PERMITTED DURING THE FOLLOWING DATES IN 2015

THANKSGIVING WEEKEND: THURSDAY, NOVEMBER 26^{TH} -SUNDAY NOVEMBER 29^{TH}

CHRISTMAS WEEKEND: THURSDAY, DECEMBER 24TH-SUNDAY, DECEMBER 27TH

NO WORK SHALL BE PERMITTED DURING THE FOLLOWING DATES IN 2016

EASTER WEEKEND: MARCH 26^{TH} AND 27^{TH} KY DERBY WEEKEND: MAY 6^{TH} AND 7^{TH}

MEMORIAL DAY WEEKEND: MAY 28^{TH} – MAY 30^{TH} INDEPENDENCE DAY WEEKEND: JULY 2^{ND} - 4^{TH} LABOR DAY WEEKEND: SEPTEMBER 3^{RD} - 5^{TH}

THANKSGIVING WEEKEND: NOVEMBER 23RD – 27TH

CHRISTMAS WEEKEND: DECEMBER 23RD – DECEMBER 26TH

WORKING HOURS ARE AS FOLLOWS: A ONE TIME RAMP CLOSURE WILL BE ALLOWED BEGINNING ON A FRIDAY AT 8:00 P.M. UNTIL TWO FRIDAYS LATER AT 8:00 P.M. FOR A TOTAL OF 14 DAYS. A LANE CLOSURE WILL BE ALLOWED ON KY 329 IN THE LANE MOST ADJACENT TO THE RAMP.

At the discretion of the Engineer, days and hours may be specified when lane closures will not be allowed.

The Department will sign and maintain detour routes during construction. No lane closures will be

Contract ID: 152326 Page 30 of 97

REVISED ADDENDUM #1: 12-9-15

allowed on Interstate 71 during construction; shoulder closures will be allowed. Maintain alternating one way traffic during construction on KY 329. The clear lane width shall be 10 feet. If traffic should be stopped due to construction operations, and a school bus on an official run arrives on the scene, the Contractor shall make provisions for the passage of the bus as quickly as possible.

PUBLIC INFORMATION PLAN

This project is considered a significant project according to Section 112.03.12. The Department will prepare a public information plan. Submit a proposed schedule of lane closures to the Engineer for approval 14 calendar days prior to beginning work. Notify the Engineer immediately and obtain the Engineer's approval of any proposed deviations from the approved work schedule.

LANE CLOSURES

Do not leave lane closures in place during non-working hours.

SIGNS

Contrary to section 112.04.02, only long term signs (signs intended to be continuously in place for more than 3 days) will be measured for payment; short term signs (signs intended to be left in place for 3 days or less) will not be measured for payment but will be incidental to Maintain and Control Traffic.

BARRICADES

Barricades used in lieu of barrels and cones for channelization or delineation will be incidental to Maintain and Control Traffic according to Section 112.04.01. Barricades used to protect pavement removal areas will be bid as each according to Section 112.04.04.

CHANGEABLE MESSAGE SIGNS

Provide changeable message signs in advance of and within the project at locations determined by the Engineer. If work is in progress concurrently in both directions or if more than one lane closure is in place in the same direction of travel, provide additional changeable message signs as directed by the Engineer. Place changeable message signs one mile in advance of the anticipated queue at each lane closure. As the actual queue lengthens and/or shortens, relocate or provide additional changeable message signs so that traffic has warning of slowed or stopped traffic at least one mile but not more than two miles before reaching the end of the actual queue. The Engineer may vary the designated locations as the work progresses. The Engineer will determine the messages to be displayed. In the event of damage or mechanical/electrical failure, repair or replace the Changeable Message Sign within 24 hours. The Department will measure for payment the maximum number

Contract ID: 152326 Page 31 of 97

REVISED ADDENDUM #1: 12-9-15

of Changeable Message Signs in concurrent use at the same time on a single day on all sections of the contract. The Department will measure individual Changeable Message Signs only once for payment, regardless of how many times they are set, reset, removed, and relocated during the duration of the project. The Department will not measure replacements for damaged Changeable Message Signs or for signs the Engineer directs be replaced due to poor condition or readability. Retain possession of the Changeable Message Signs upon completion of the work.

ARROW PANELS

Use arrow panels as shown on the Standard Drawings or as directed by the Engineer. The Department will measure for payment the maximum number of arrow panels in concurrent use at the same time on a single day on all sections of the contract. The Department will measure for payment the maximum number of Arrow Panels in concurrent use at the same time on a single day on all sections of the contract. The Department will measure individual Arrow Panels only once for payment, regardless of how many times they are set, reset, removed, and relocated during the duration of the project. The Department will not measure replacements for damaged Arrow Panels or for panels signs the Engineer directs be replaced due to poor condition or readability for payment. Retain possession of the Arrow Panels upon completion of the work.

THERMOPLASTIC INTERSECTION MARKINGS

Consider the locations listed on the summary as approximate only. Prior to milling and/or resurfacing, locate and document the locations of the existing markings. After resurfacing, replace the markings at their approximate existing locations or as directed by Engineer. Place markings not existing prior to resurfacing as directed by the Engineer.

PAVEMENT EDGE DROP-OFFS

Do not allow a pavement edge between opposing directions of traffic or lanes that traffic is expected to cross in a lane change situation with an elevation difference greater than 1½". Place Warning signs (MUTCD W8-11 or W8-9A) in advance of and at 1500' intervals throughout the drop-off area. Dual post the signs on both sides of the traveled way. Wedge all transverse transitions between resurfaced and unresurfaced areas which traffic may cross with asphalt mixture for leveling and wedging. Remove the wedges prior to placement of the final surface course.

Protect pavement edges that traffic is not expected to cross, except accidentally, as follows:

Less than 2" - No protection required.

2" to 4" - Place plastic drums, vertical panels, or barricades every 50 feet. During daylight working hours only, the Engineer will allow the Contractor to use cones in lieu of plastic drums, panels, and barricades. Wedge the drop-off with DGA or asphalt mixture for leveling and wedging with a 1:1 or flatter slope in daylight hours,

Contract ID: 152326 Page 32 of 97

REVISED ADDENDUM #1: 12-9-15

or 3:1 or flatter slope during nighttime hours, when work is not active in the drop-off area.

Greater than 4" - Protect drop-offs greater than 4 inches within 10 feet of traffic by placing drums, vertical panels, or barricades every 25 feet. On KY 329, if a lane closure adjacent to the drop-off is not utilized, install an asphalt wedge at the drop-off on KY 329. The Engineer will not allow the use of cones in lieu of drums, vertical panels, or barricades for drop-offs greater than 4". Place Type III Barricades directly in front of the drop-off facing on-coming traffic in both directions of travel. Provide warning signs as shown on the Standard Drawings or as directed by the Engineer

Contract ID: 152326 Page 33 of 97

REVISED ADDENDUM #1: 12-9-15

USE AND PLACEMENT OF CHANGEABLE MESSAGE SIGNS

The following policy is based upon current Changeable Message Signs (CMS) standards and practice from many sources, including the Federal Highway Administration (FHWA), other State Departments of Transportation, and Traffic Safety Associations. It is understood that each CMS installation or use requires individual consideration due to the specific location or purpose. However, there will be elements that are constant in nearly all applications. Accordingly these recommended guidelines bring a level of uniformity, while still being open to regional experience and engineering judgment.

Application

The primary purpose of CMS is to advise the driver of unexpected traffic and routing situations. Examples of applications where CMS can be effective include:

- Closures (road, lane, bridge, ramp, shoulder, interstate)
- Changes in alignment or surface conditions
- Significant delays, congestion
- Construction/maintenance activities (delays, future activities)
- Detours/alternative routes
- Special events with traffic and safety implications
- Crash/incidents
- Vehicle restrictions (width, height, weight, flammable)
- Advance notice of new traffic control devices
- Real-time traffic conditions (must be kept up to date)
- Weather /driving conditions, environmental conditions, Roadway Weather Information Systems
- Emergency Situations
- Referral to Highway Advisory Radio (if available)
- Messages as approved by the County Engineer's Office

CMS should not be used for:

- Replacement of static signs (e.g. road work ahead), regulatory signage (e.g. speed limits), pavement markings, standard traffic control devices, conventional warning or guide signs.
- Replacement of lighted arrow board
- Advertising (Don't advertise the event unless clarifying "action" to be taken by driver – e.g. Speedway traffic next exit)
- Generic messages
- Test messages (portable signs only)
- Describe recurrent congestion (e.g. rush hour)
- Public service announcements (not traffic related

Contract ID: 152326 Page 34 of 97

REVISED ADDENDUM #1: 12-9-15

Messages

Basic principles that are important to providing proper messages and insuring the proper operation of a CMS are:

- Visible for at least ½ mile under ideal daytime and nighttime conditions
- Legible from all lanes a minimum of 650 feet
- Entire message readable twice while traveling at the posted speed
- Nor more than two message panels should be used (three panels may be used on roadways where vehicles are traveling less than 45 mph). A panel is the message that fits on the face of the sign without flipping or scrolling.
- Each panel should convey a single thought; short and concise
- Do not use two unrelated panels on a sign
- Do not use the sign for two unrelated messages
- Should not scroll text horizontally or vertically
- Should not contain both the words left and right
- Use standardized abbreviations and messages
- Should be accurate and timely
- Avoid filler/unnecessary words and periods (hazardous, a, an, the)
- Avoid use of speed limits
- Use words (not numbers) for dates

Placement

Placement of the CMS is important to insure that the signs is visible to the driver and provides ample time to take any necessary action. Some of the following principles may only be applicable to controlled access roadways. The basic principles of placement for a CMS are:

- When 2 signs are needed, place on same side of roadway and at least 1,000 feet apart
- Place behind semi-rigid/rigid protection (guardrail, barrier) or outside of the clear zone
- Place 1,000 feet in advance of work zone; at least one mile ahead of decision point
- Normally place on right side of roadway; but should be placed closest to the affected lane so that either side is acceptable
- Signs should not be dual mounted (one on each side of roadway facing same direction)
- Point trailer hitch downstream
- Secure to immovable object to prevent thief (if necessary)
- Do not place in sags or just beyond crest
- Check for reflection of sun to prevent the blinding of motorist
- Should be turned ~3 degrees outward from perpendicular to the edge of pavement
- Bottom of sign should be 7 feet above the elevation of edge of roadway
- Should be removed when not in use

•

FE01 093 0071 014-015

Contract ID: 152326 Page 35 of 97 REVISED ADDENDUM #1: 12-9-15

Standard Abbreviations

The following is a list of standard abbreviations to be used on CMS.

Word	Abbrev.	Example
Access	ACCS	ACCIDENT AHEAD/USE ACCS RD
		NEXT RIGHT
Alternate	ALT	ACCIDENT AHEAD/USE ALT RTE NEXT RIGHT
Avenue	AVE	FIFTH AVE CLOSED/DETOUR
		NEXT LEFT
Blocked	BLKD	FIFTH AVE BLKD/MERGE LEFT
Boulevard	BLVD	MAIN BLVD CLOSED/USE ALT RTE
Bridge	BRDG	SMITH BRDG CLOSED/USE ALT RTE
Cardinal Directions	N, S, E, W	N I75 CLOSED/ DETOUR EXIT 30
Center	CNTR	CNTR LANE CLOSED/MERGE LEFT
Commercial	COMM	OVRSZ COMM VEH/USE I275
Condition	COND	ICY COND POSSIBLE
Congested	CONG	HVY CONG NEXT 3 MI
Construction	CONST	CONST WORK AHEAD/EXPECT
		DELAYS
Downtown	DWNTN	DWNTN TRAF USE EX 40
Eastbound	E-BND	E-BND I64 CLOSED/DETOUR
		EXIT 20
Emergency	EMER	EMER VEH AHEAD/PREPARE TO
		STOP
Entrance, Enter	EX, EXT	DWNTN TRAF USE EX 40
Expressway	EXPWY	WTRSN EXPWY CLOSED/DETOUR EXIT 10
Freeway	FRWY, FWY	GN SYNDR FWY CLOSED/DETOUR
Ticeway		EXIT 15
Hazardous Materials	HAZMAT	HAZMAT IN ROADWAY/ALL TRAF
		EXIT 25
Highway	HWY	ACCIDENT ON AA HWY/EXPECT
**	110	DELAYS
Hour	HR	ACCIDENT ON AA HWY/2 HR
T 0	N.E.O.	DELAY
Information	INFO	TRAF INFO TUNE TO 1240 AM
Interstate	I	E-BND I64 CLOSED/DETOUR EXIT 20
Lane	LN	LN CLOSED/MERGE LEFT
Left	LFT	LANE CLOSED/MERGE LFT
Local	LOC	LOC TRAF USE ALT RTE
Maintenance	MAINT	MAINT WRK ON BRDG/SLOW
Major	MAJ	MAJ DELWAYS I75/USE ALT RTE
Mile	MI	ACCIDENT 3 MI AHEAD/ USE
-		ALT RTE

Contract ID: 152326 Page 36 of 97

REVISED ADDENDUM #1: 12-9-15

Minor	MNR	ACCIDENT 3 MI MNR DELAY
Minutes	MIN	ACCIDENT 3 MI/30 MIN DELAY
Northbound	N-BND	N-BND I75 CLOSED/ DETOUR
		EXIT 50
Oversized	OVRSZ	OVRSZ COMM VEH/USE 1275
		NEXT RIGHT
Parking	PKING	EVENT PKING NEXT RGT
Parkway	PKWY	CUM PKWAY TRAF/DETOUR
•		EXIT 60
Prepare	PREP	ACCIDENT 3 MIL/PREP TO STOP
Right	RGT	EVENT PKING NEXT RGT
Road	RD	HAZMAT IN RD/ALL TRAF EXIT 25
Roadwork	RDWK	RDWK NEXT 4 MI/POSSIBLE
		DELAYS
Route	RTE	MAJ DELAYS 175/USE ALT RTE
Shoulder	SHLDR	SHLDR CLOSED NEXT 5 MI
Slippery	SLIP	SLIP COND POSSIBLE/ SLOW SPD
Southbound	S-BND	S-BND I75 CLOSED/DETOUR
		EXIT 50
Speed	SPD	SLIP COND POSSIBLE/ SLOW SPD
Street	ST	MAIN ST CLOSED/USE ALT RTE
Traffic	TRAF	CUM PKWAY TRAF/DETOUR
		EXIT 60
Vehicle	VEH	OVRSZ COMM VEH/USE 1275
		NEXT RIGHT
Westbound	W-BND	W-BND I64 CLOSED/DETOUR
		EXIT 50
Work	WRK	CONST WRK 2MI/POSSIBLE
		DELAYS

Certain abbreviations are prone to inviting confusion because another word is abbreviated or could be abbreviated in the same way. DO NO USE THESE ABBREVIATIONS.

Abbrev.	Intended Word	Word Erroneously Given
ACC	Accident	Access (Road)
CLRS	Clears	Colors
DLY	Delay	Daily
FDR	Feeder	Federal
L	Left	Lane (merge)
LOC	Local	Location
LT	Light (traffic)	Left
PARK	Parking	Park
POLL	Pollution (index)	Poll
RED	Reduce	Red
STAD	Stadium	Standard
TEMP	Temporary	Temperature
WRNG	Warning	Wrong

Page 37 of 97

REVISED ADDENDUM #1: 12-9-15

Contract ID: 152326

TYPICAL MESSAGES

The following is a list of typical messages used on CMS. The list consists of the reason or problem that you want the driver to be aware of and the action that you want the driver to take.

Reason/Problem

ACCIDENT

ACCIDENT/XX MILES XX ROAD CLOSED XX EXIT CLOSED BRIDGE CLOSED

BRIDGE/(SLIPPERY, ICE, ETC.) CENTER/LANE/CLOSED DELAY(S), MAJOR/DELAYS

DEBRIS AHEAD DENSE FOG

DISABLED/VEHICLE EMER/VEHICLES/ONLY EVENT PARKING

EXIT XX CLOSED FLAGGER XX MILES FOG XX MILES FREEWAY CLOSED

FRESH OIL HAZMAT SPILL

ICE

INCIDENT AHEAD

LANES (NARROW, SHIFT, MERGE, ETC.)

LEFT LANE CLOSED LEFT LANE NARROWS LEFT 2 LANES CLOSED LEFT SHOULDER CLOSED

LOOSE GRAVEL

MEDIAN WORK XX MILES

MOVING WORK ZONE, WORKERS IN ROADWAY

NEXT EXIT CLOSED NO OVERSIZED LOADS

NO PASSING NO SHOULDER ONE LANE BRIDGE PEOPLE CROSSING RAMP CLOSED

RAMP (SLIPPERY, ICE, ETC.)

RIGHT LANE CLOSED RIGHT LANE NARROWS RIGHT SHOULDER CLOSED

ROAD CLOSED

Action

ALL TRAFFIC EXIT RT AVOID DELAY USE XX CONSIDER ALT ROUTE

DETOUR

DETOUR XX MILES DO NOT PASS EXPECT DELAYS FOLLOW ALT ROUTE

KEEP LEFT
KEEP RIGHT
MERGE XX MILES
MERGE LEFT
MERGE RIGHT
ONE-WAY TRAFFIC
PASS TO LEFT
PASS TO RIGHT
PREPARE TO STOP

SLOW

SLOW DOWN
STAY IN LANE
STOP AHEAD
STOP XX MILES
TUNE RADIO 1610 AM
USE NN ROAD
USE CENTER LANE
USE DETOUR ROUTE

REDUCE SPEED

USE LEFT TURN LANE USE NEXT EXIT USE RIGHT LANE WATCH FOR FLAGGER

Contract ID: 152326 Page 38 of 97

REVISED ADDENDUM #1: 12-9-15

ROAD CLOSED XX MILES

ROAD (SLIPPERY, ICE, ETC.)

ROAD WORK

ROAD WORK (OR CONSTRUCTION) (TONIGHT, TODAY, TOMORROW, DATE)

ROAD WORK XX MILES

SHOULDER (SLIPPERY, ICE, SOFT, BLOCKED, ETC.)

NEW SIGNAL XX MILES

SLOW 1 (OR 2) - WAY TRAFFIC

SOFT SHOULDER

STALLED VEHICLES AHEAD

TRAFFIC BACKUP

TRAFFIC SLOWS

TRUCK CROSSING

TRUCKS ENTERING

TOW TRUCK AHEAD

UNEVEN LANES

WATER ON ROAD

WET PAINT

WORK ZONE XX MILES

WORKERS AHEAD