



TRANSPORTATION CABINET

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Steven L. Beshear
Governor

Michael W. Hancock, P.E.
Secretary

July 23, 2015

CALL NO. 311
CONTRACT ID NO. 153123
ADDENDUM # 1

Subject: Jefferson County, CB06 056 1819 000-003
Letting July 31, 2015

- (1) Added - Special Note - Page 11(a) of 62
- (2) Revised - Note - Page 15 of 62
- (3) Revised - Bid Items - Page 62 of 62

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Robert C. Lewis".

Robert C. Lewis, P.E.
Acting Director
Division of Construction Procurement

RL:ks
Enclosures



An Equal Opportunity Employer M/F/D

**SPECIAL NOTE FOR COORDINATION
WITH KYTC MAINTENANCE ACTIVITIES**

Be advised that during recent rain events, portions of the route to be resurfaced have suffered damage to the pavement and drainage facilities adjacent to the roadway. The Department is currently scheduling repairs of these items and plans to have all damages corrected prior to resurfacing activities beginning. The Contractor will coordinate their resurfacing work with the Engineer to ensure all Department repairs have been completed prior to starting work. It is anticipated that the Department's repairs will be completed by early September 2015.

SPECIAL NOTE FOR BASE FAILURE REPAIR

The Engineer will determine actual repair locations and dimensions at the time of construction. Prior to overall milling and/or leveling and wedging, excavate the designated base failure areas to a depth 12 inches below the existing asphalt pavement surface level. Dispose of the excavated materials at waste sites off the Right-of-Way obtained by the Contractor at no additional cost to the Department. See Special Note for Waste and Borrow.

Backfill the excavated areas with Class 2 Asphalt Base 1.00D PG64-22. Compact the asphalt base to the compaction required in Section 403.03.10 in 4 inch maximum courses. Perform all base failure repairs in such a manner that removal and replacement are completed during the same work shift. Do this work as one of the Contractor's first operations in order to allow further compaction by traffic. Do not mill or place new asphalt surface over repaired base failure areas until a minimum of 14 calendar days have elapsed after placement of the asphalt base. After a minimum of 14 calendar days and when the Engineer determines the base failure repair areas have sufficiently stabilized, milling and/or resurfacing operations can begin in this area. Prior to milling and/or constructing the new asphalt surface, level and wedge any settlement of the repair areas.

The bidder must draw conclusions as to the conditions encountered. The Department does not give any guarantee as to the accuracy of the data and will not consider any claim for additional compensation if the materials encountered that are not in accord with the classification shown.

Accept payment at the Contract unit prices per square yard for Base Failure repair as full compensation for all labor, materials, equipment, and incidentals for removing pavement and disposing of the materials, furnishing and placing asphalt base, leveling and wedging, and all other items necessary to complete the work according to these notes to the satisfaction of the Engineer.

1-3606basefailurerepairmillinlaypaybysy D-5
7/20/2015

PROPOSAL BID ITEMS

153123

Page 1 of 1

Report Date 7/23/15

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00190		LEVELING & WEDGING PG64-22 (REVISED: 7-23-15)	325.00	TON		\$	
0020	00301		CL2 ASPH SURF 0.38D PG64-22	1,527.00	TON		\$	
0030	02562		TEMPORARY SIGNS	250.00	SQFT		\$	
0040	02650		MAINTAIN & CONTROL TRAFFIC (KY 1819)	1.00	LS		\$	
0050	02676		MOBILIZATION FOR MILL & TEXT (KY 1819)	1.00	LS		\$	
0060	02677		ASPHALT PAVE MILLING & TEXTURING	12.00	TON		\$	
0070	03240		BASE FAILURE REPAIR (REVISED: 7-23-15)	150.00	SQYD		\$	
0080	06510		PAVE STRIPING-TEMP PAINT-4 IN	48,408.00	LF		\$	
0090	06514		PAVE STRIPING-PERM PAINT-4 IN	48,408.00	LF		\$	
0100	06568		PAVE MARKING-THERMO STOP BAR-24IN	20.00	LF		\$	

Section: 0002 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0110	02569		DEMOBILIZATION	1.00	LS		\$	