



TRANSPORTATION CABINET

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Steven L. Beshear
Governor

Michael W. Hancock, P.E.
Secretary

April 22, 2015

CALL NO. 345
CONTRACT ID NO. 152083
ADDENDUM # 2

Subject: Mason County, FD05 081 0068 005-011
Letting April 24, 2015

- (1) Revised - Joint Summary - Page 27 of 80
- (2) Revised - Bid Items - Page 80 of 80

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Robert C. Lewis".

Robert C. Lewis, P.E.
Acting Director
Division of Construction Procurement

RL:ks
Enclosures



An Equal Opportunity Employer M/F/D

FD05 081 0068 005-011 Concrete Base Section Joint Summary

Section	FULL DEPTH JOINT REPAIR			SAW CLEAN AND RESEAL		TOTAL LF
	Full-Depth 6'x24'	Full-Depth 6'x36'	Full-Depth LF	24'	36'	
5.851-7.000	10	0	240	72	0	2016
7.000-8.000	2	9	372	11	61	2748
8.000-9.000	6	5	324	34	41	2592
9.000-10.000	4	5	276	41	48	3068
10.000-10.245	3	0	72	20	0	560
Full-Depth Total:			1284	Existing Joints to Saw, Clean, and Seal LF		10984
Full-Depth Width:			6'	Saw Clean and Reseal Total LF:		10984
Crushed Stone Depth:			6"			
Asphalt Base Depth:			12"			
Crushed Stone (Tons):			300			
Asphalt Base (Tons):			600			
SAW CLEAN AND RESEAL						
Full Depth Joint Repair (Both Sides)			2744			
Random Transverse Cracks			1210			
Saw Clean and Reseal Total LF:			3954			

*Base: CL2 ASPH BASE 1.00D PG64-22

**Actual locations for the full depth joint repairs will be determined by the Engineer at the time of construction.

***For Saw, Clean, and Reseal details, see "Saw, Clean, and Reseal Transverse Joint Note."

PROPOSAL BID ITEMS

152083

Page 1 of 1

Report Date 4/22/15

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00001		DGA BASE	100.00	TON		\$	
0020	00003		CRUSHED STONE BASE	300.00	TON		\$	
0030	00078		CRUSHED AGGREGATE SIZE NO 2	45.00	TON		\$	
0040	00190		LEVELING & WEDGING PG64-22	929.00	TON		\$	
0050	00212		CL2 ASPH BASE 1.00D PG64-22 (JOINT REPAIR) (REVISED: 4-21-15)	600.00	TON		\$	
0051	00212		CL2 ASPH BASE 1.00D PG64-22 (EDGE REPAIR) (ADDED: 4-21-15)	587.00	TON		\$	
0060	00301		CL2 ASPH SURF 0.38D PG64-22	3,250.00	TON		\$	
0070	00307		CL2 ASPH SURF 0.38B PG64-22	5,645.00	TON		\$	
0080	01010		NON-PERFORATED PIPE-4 IN	572.00	LF		\$	
0090	01020		PERF PIPE HEADWALL TY 1-4 IN	42.00	EACH		\$	
0100	01024		PERF PIPE HEADWALL TY 2-4 IN	3.00	EACH		\$	
0110	02115		SAW-CLEAN-RESEAL TVERSE JOINT (REVISED: 4-22-15)	14,938.00	LF		\$	
0120	02562		TEMPORARY SIGNS	300.00	SQFT		\$	
0130	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0140	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0150	02677		ASPHALT PAVE MILLING & TEXTURING	684.00	TON		\$	
0160	02696		SHOULDER RUMBLE STRIPS-SAWED	46,500.00	LF		\$	
0170	02775		ARROW PANEL	2.00	EACH		\$	
0180	06510		PAVE STRIPING-TEMP PAINT-4 IN	73,300.00	LF		\$	
0190	06514		PAVE STRIPING-PERM PAINT-4 IN	84,500.00	LF		\$	
0200	06600		REMOVE PAVEMENT MARKER TYPE V	700.00	EACH		\$	
0210	10020NS		FUEL ADJUSTMENT	15,604.00	DOLL	\$1.00	\$	\$15,604.00
0220	10030NS		ASPHALT ADJUSTMENT	27,498.00	DOLL	\$1.00	\$	\$27,498.00
0230	20458ES403		CENTERLINE RUMBLE STRIPS	23,300.00	LF		\$	

Section: 0002 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0240	02569		DEMOBILIZATION	1.00	LS		\$	