

Steven L. Beshear Governor Frankfort, Kentucky 40622 www.transportation.ky.gov/

Michael W. Hancock, P.E. Secretary

June 23, 2015

CALL NO. 401

CONTRACT ID NO. 152242

ADDENDUM # 1

Subject: Jefferson County, 056GR15P041-FD05

Letting June 26, 2015

(1) Revised - Note - Page 19 of 99

(2) Revised - Material Summary - Pages 38-39 of 99

(3) Revised - Bid Items - Page 99 of 99

Proposal revisions are available at <a href="http://transportation.ky.gov/Construction-procurement/">http://transportation.ky.gov/Construction-procurement/</a>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Robert C. Lewis, P.E.

Acting Director

Division of Construction Procurement

RL:ks

Enclosures



## SPECIAL NOTE FOR PAVEMENT REPAIRS

Repair locations listed on the summary are approximate only. The Engineer will determine actual repair locations and dimensions at the time of construction. Prior to overall milling and/or leveling and wedging, excavate the designated pavement repair areas to a depth 6 inches below the existing asphalt pavement surface level. Dispose of the excavated materials at waste sites off the Right-of-Way obtained by the Contractor at no additional cost to the Department. See Special Note for Waste and Borrow.

Backfill the excavated areas with Class 3 Asphalt Base 1.50D PG64-22. Compact the asphalt base to the compaction required in Section 403.03.10 in a single 6 inch course. Perform all pavement repairs in such a manner that removal and replacement are completed during the same work shift. Do this work as one of the Contractor's first operations in order to allow further compaction by traffic. Do not mill or place new asphalt surface over repaired areas until a minimum of 14 calendar days have elapsed after placement of the asphalt base. After a minimum of 14 calendar days and when the Engineer determines the pavement repair areas have sufficiently stabilized, milling and/or resurfacing operations can begin in this area. Prior to milling and/or constructing the new asphalt surface, level and wedge any settlement of the repair areas.

The bidder must draw conclusions as to the conditions encountered. The Department does not give any guarantee as to the accuracy of the data and will not consider any claim for additional compensation if the materials encountered that are not in accord with the classification shown.

Accept payment at the Contract unit prices per SY for Pavement Repair as full compensation for all labor, materials, equipment, and incidentals for removing pavement and disposing of the materials, furnishing and placing asphalt base, leveling and wedging, and all other items necessary to complete the work according to these notes to the satisfaction of the Engineer.

REVISED ADDENDUM #1: 6-23-15 Contract ID: 152242

Page 38 of 99

## **MATERIAL SUMMARY**

| CONTRACT ID: 152242 | 056GR15P041-FD05 | MP056060A1502 |
|---------------------|------------------|---------------|
|---------------------|------------------|---------------|

EASTERN PARKWAY (US 60A) (OMIT MP 3.409-3.795) FROM KY 1020-SOUTH THIRD-WINKLER AVENUE EXTENDING EAST TO US 31E-BARDSTOWN ROAD ASPHALT RESURFACING, A DISTANCE OF 3.67 MILES.

| Project<br>Line No | Bid Code   | DESCRIPTION                                 | Quantity   | Unit |
|--------------------|------------|---|------------|------|
| 0005               | 00190      | LEVELING & WEDGING PG64-22                  | 645.00     | TON  |
| 0010               | 00336      | CL3 ASPH SURF 0.38A PG76-22                 | 9,400.00   | TON  |
| 0015               | 01811      | STANDARD CURB AND GUTTER MOD                | 1,090.00   | LF   |
| 0020               | 01876      | STANDARD HEADER CURB MOD                    | 486.00     | LF   |
| 0025               | 23839EC    | REMOVE CONCRETE MEDIAN - (REVISED: 6-23-15) | 30.00      | SQYD |
| 0030               | 02562      | TEMPORARY SIGNS                             | 1,130.00   | SQFT |
| 0035               | 02650      | MAINTAIN & CONTROL TRAFFIC                  | 1.00       | LS   |
| 0040               | 02676      | MOBILIZATION FOR MILL & TEXT                | 1.00       | LS   |
| 0045               | 02677      | ASPHALT PAVE MILLING & TEXTURING            | 9,400.00   | TON  |
| 0050               | 02720      | SIDEWALK-4 IN CONCRETE - (HISTORIC MIX)     | 877.00     | SQYD |
| 0055               | 02775      | ARROW PANEL                                 | 4.00       | EACH |
| 0060               | 04793      | CONDUIT-1 1/4 IN                            | 200.00     | LF   |
| 0065               | 04811      | ELECTRICAL JUNCTION BOX TYPE B              | 2.00       | EACH |
| 0070               | 04820      | TRENCHING AND BACKFILLING                   | 200.00     | LF   |
| 0075               | 04830      | LOOP WIRE                                   | 13,510.00  | LF   |
| 0800               | 04895      | LOOP SAW SLOT AND FILL                      | 5,880.00   | LF   |
| 0085               | 06510      | PAVE STRIPING-TEMP PAINT-4 IN               | 116,200.00 | LF   |
| 0090               | 06514      | PAVE STRIPING-PERM PAINT-4 IN               | 58,100.00  | LF   |
| 0095               | 06516      | PAVE STRIPING-PERM PAINT-8 IN               | 300.00     | LF   |
| 0100               | 06565      | PAVE MARKING-THERMO X-WALK-6 IN             | 4,203.00   | LF   |
| 0105               | 06568      | PAVE MARKING-THERMO STOP BAR-24IN           | 1,713.00   | LF   |
| 0110               | 06574      | PAVE MARKING-THERMO CURV ARROW              | 48.00      | EACH |
| 0115               | 06575      | PAVE MARKING-THERMO COMB ARROW              | 5.00       | EACH |
| 0120               | 06576      | PAVE MARKING-THERMO ONLY                    | 1.00       | EACH |
| 0125               | 10020NS    | FUEL ADJUSTMENT                             | 15,635.00  | DOLL |
| 0130               | 10030NS    | ASPHALT ADJUSTMENT                          | 39,271.00  | DOLL |
| 0135               | 20757ED    | PAVEMENT REPAIR                             | 7,781.00   | SQYD |
| 0140               | 22520EN    | PAVE MARKING-THERMO YIELD BAR-36 IN         | 38.00      | LF   |
| 0145               | 23158ES505 | DETECTABLE WARNINGS                         | 884.00     | SQFT |
| 0150               | 23607EC    | PAVE MARK THERMO-LANE REDUCTION ARROW       | 3.00       | EACH |
| 0155               | 23625EC    | PAVE MARK THERMO-6 IN W CAT TRAXX           | 208.00     | LF   |
| 0160               | 02569      | DEMOBILIZATION                              | 1.00       | LS   |

JEFFERSON COUNTY 056GR15P041-FD05 REVISED ADDENDUM #1: 6-23-15 Contract ID: 152242

Page 39 of 99

## **MATERIAL SUMMARY**

| CONTRACT ID: 152242 056GR15P041-FD05 MP056060A1503 | NTRACT ID: 152242 |
|--|-------------------|
|--|-------------------|

EASTERN PARKWAY (US 60A) (OMIT MP 3.409-3.795). FROM KY 1020-SOUTH THIRD-WINKLER AVENUE EXTENDING EAST TO US 31E-BARDSTOWN ROAD ASPHALT RESURFACING, A DISTANCE OF 3.67 MILES.

| Project<br>Line No | Bid Code | DESCRIPTION        | Quantity | Unit |
|--------------------|----------|--------------------|----------|------|
| 0005               | 01792    | ADJUST MANHOLE     | 4.00     | EACH |
| 0010               | 03425    | ADJUST WATER VALVE | 12.00    | EACH |
| 0015               | 02569    | DEMOBILIZATION     | 1.00     | LS   |

## **PROPOSAL BID ITEMS**

REVISED ADDENDUM #1: 6-23-15 Contract ID: 152242 Page 99 of 99

Page 1 of 1

Report Date 6/23/15

Section: 0001 - PAVING

| LINE | BID CODE   | ALT | DESCRIPTION                               | QUANTITY   | UNIT | UNIT PRIC | FP | AMOUNT      |
|------|------------|-----|---|------------|------|-----------|----|-------------|
| 0010 | 00190      |     | LEVELING & WEDGING PG64-22                | 645.00     | TON  |           | \$ |             |
| 0020 | 00336      |     | CL3 ASPH SURF 0.38A PG76-22               | 9,400.00   | TON  |           | \$ |             |
| 0030 | 01811      |     | STANDARD CURB AND GUTTER MOD              | 1,090.00   | LF   |           | \$ |             |
| 0040 | 01876      |     | STANDARD HEADER CURB MOD                  | 486.00     | LF   |           | \$ |             |
| 0050 | 23839EC    |     | REMOVE CONCRETE MEDIAN (REVISED: 6-23-15) | 30.00      | SQYD |           | \$ |             |
| 0060 | 02562      |     | TEMPORARY SIGNS                           | 1,130.00   | SQFT |           | \$ |             |
| 0070 | 02650      |     | MAINTAIN & CONTROL TRAFFIC                | 1.00       | LS   |           | \$ |             |
| 0800 | 02676      |     | MOBILIZATION FOR MILL & TEXT              | 1.00       | LS   |           | \$ |             |
| 0090 | 02677      |     | ASPHALT PAVE MILLING & TEXTURING          | 9,400.00   | TON  |           | \$ |             |
| 0100 | 02720      |     | SIDEWALK-4 IN CONCRETE<br>(HISTORIC MIX)  | 877.00     | SQYD |           | \$ |             |
| 0110 | 02775      |     | ARROW PANEL                               | 4.00       | EACH |           | \$ |             |
| 0120 | 04793      |     | CONDUIT-1 1/4 IN                          | 200.00     | LF   |           | \$ |             |
| 0130 | 04811      |     | ELECTRICAL JUNCTION BOX TYPE B            | 2.00       | EACH |           | \$ |             |
| 0140 | 04820      |     | TRENCHING AND BACKFILLING                 | 200.00     | LF   |           | \$ |             |
| 0150 | 04830      |     | LOOP WIRE                                 | 13,510.00  | LF   |           | \$ |             |
| 0160 | 04895      |     | LOOP SAW SLOT AND FILL                    | 5,880.00   | LF   |           | \$ |             |
| 0170 | 06510      |     | PAVE STRIPING-TEMP PAINT-4 IN             | 116,200.00 | LF   |           | \$ |             |
| 0180 | 06514      |     | PAVE STRIPING-PERM PAINT-4 IN             | 58,100.00  | LF   |           | \$ |             |
| 0190 | 06516      |     | PAVE STRIPING-PERM PAINT-8 IN             | 300.00     | LF   |           | \$ |             |
| 0200 | 06565      |     | PAVE MARKING-THERMO X-WALK-6 IN           | 4,203.00   | LF   |           | \$ |             |
| 0210 | 06568      |     | PAVE MARKING-THERMO STOP BAR-24IN         | 1,713.00   | LF   |           | \$ |             |
| 0220 | 06574      |     | PAVE MARKING-THERMO CURV ARROW            | 48.00      | EACH |           | \$ |             |
| 0230 | 06575      |     | PAVE MARKING-THERMO COMB ARROW            | 5.00       | EACH |           | \$ |             |
| 0240 | 06576      |     | PAVE MARKING-THERMO ONLY                  | 1.00       | EACH |           | \$ |             |
| 0250 | 10020NS    |     | FUEL ADJUSTMENT                           | 15,635.00  | DOLL | \$1.00    | \$ | \$15,635.00 |
| 0260 | 10030NS    |     | ASPHALT ADJUSTMENT                        | 39,271.00  | DOLL | \$1.00    | \$ | \$39,271.00 |
| 0270 | 20757ED    |     | PAVEMENT REPAIR                           | 7,781.00   | SQYD |           | \$ |             |
| 0280 | 22520EN    |     | PAVE MARKING-THERMO YIELD BAR-36 IN       | 38.00      | LF   |           | \$ |             |
| 0290 | 23158ES505 |     | DETECTABLE WARNINGS                       | 884.00     | SQFT |           | \$ |             |
| 0300 | 23607EC    |     | PAVE MARK THERMO-LANE REDUCTION ARROW     | 3.00       | EACH |           | \$ |             |
| 0310 | 23625EC    |     | PAVE MARK THERMO-6 IN W CAT TRAXX         | 208.00     | LF   |           | \$ |             |
|      |            |     |   |            |      |           |    |             |

Section: 0002 - MISCELLANEOUS

| LINE | BID CODE | ALT DESCRIPTION    | QUANTITY | UNIT | UNIT PRIC | FΡ | AMOUNT |
|------|----------|--------------------|----------|------|-----------|----|--------|
| 0320 | 01792    | ADJUST MANHOLE     | 4.00     | EACH |           | \$ |        |
| 0330 | 03425    | ADJUST WATER VALVE | 12.00    | EACH |           | \$ |        |

Section: 0003 - DEMOBILIZATION

| LINE | BID CODE | ALT DESCRIPTION | QUANTITY | UNIT | UNIT PRIC FP | AMOUNT |
|------|----------|-----------------|----------|------|--------------|--------|
| 0340 | 02569    | DEMOBILIZATION  | 1.00     | LS   | \$           |        |