



TRANSPORTATION CABINET

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Steven L. Beshear
Governor

Michael W. Hancock, P.E.
Secretary

December 8, 2014

CALL NO. 402
CONTRACT ID NO. 141070
ADDENDUM # 1

Subject: Nelson-Bullitt-Spencer Counties, 121GR14D070-FD04
Letting December 12, 2014

(1) Revised - Bid Items - Pages 99-103 of 103

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Diana Castle Radcliffe".

Diana Castle Radcliffe
Director
Division of Construction Procurement

DR:ks
Enclosures



An Equal Opportunity Employer M/F/D

PROPOSAL BID ITEMS

141070

Page 1 of 5

Report Date 12/8/14

Section: 0001 - PAVING-ASPHALT ALT REVISED: 12-8-14

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00003		CRUSHED STONE BASE	54,046.00	TON		\$	
0020	00008		CEMENT STABILIZED ROADBED	137,829.00	SQYD		\$	
0030	00020		TRAFFIC BOUND BASE	2,000.00	TON		\$	
0040	00100		ASPHALT SEAL AGGREGATE	30.00	TON		\$	
0050	00103		ASPHALT SEAL COAT	4.00	TON		\$	
0060	00190		LEVELING & WEDGING PG64-22	650.00	TON		\$	
0070	00214		CL3 ASPH BASE 1.00D PG64-22	72,291.00	TON		\$	
0080	00358		ASPHALT CURING SEAL	138.00	TON		\$	
0090	00388		CL3 ASPH SURF 0.38B PG64-22	14,513.00	TON		\$	
0100	02101		CEM CONC ENT PAVEMENT-8 IN	129.00	SQYD		\$	
0110	02542		CEMENT	2,556.00	TON		\$	
0120	02677		ASPHALT PAVE MILLING & TEXTURING	20.00	TON		\$	
0130	02702		SAND FOR BLOTTER	344.00	TON		\$	
0140	10203ND		PAVEMENT ADJUSTMENT ASPHALT	1.00	LS	730,810.00	\$	\$730,810.00

Section: 0002 - PAVING-CONCRETE ALT REVISED: 12-8-14

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0150	00003		CRUSHED STONE BASE	55,200.00	TON		\$	
0160	00008		CEMENT STABILIZED ROADBED	137,358.00	SQYD		\$	
0170	00020		TRAFFIC BOUND BASE	2,000.00	TON		\$	
0180	00100		ASPHALT SEAL AGGREGATE	30.00	TON		\$	
0190	00103		ASPHALT SEAL COAT	4.00	TON		\$	
0200	00190		LEVELING & WEDGING PG64-22	650.00	TON		\$	
0210	00214		CL3 ASPH BASE 1.00D PG64-22	22,851.00	TON		\$	
0220	00358		ASPHALT CURING SEAL	137.00	TON		\$	
0230	00388		CL3 ASPH SURF 0.38B PG64-22	7,848.00	TON		\$	
0240	02073		JPC PAVEMENT-9 IN	96,939.00	SQYD		\$	
0250	02101		CEM CONC ENT PAVEMENT-8 IN	129.00	SQYD		\$	
0260	02542		CEMENT	2,547.00	TON		\$	
0270	02702		SAND FOR BLOTTER	343.00	TON		\$	
0280	10203ND		PAVEMENT ADJUSTMENT CONCRETE	1.00	LS	461,334.00	\$	\$461,334.00

Section: 0003 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0290	01825		ISLAND CURB AND GUTTER	200.00	LF		\$	
0300	01987		DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	475.00	EACH		\$	
0310	02014		BARRICADE-TYPE III	20.00	EACH		\$	
0320	02091		REMOVE PAVEMENT	5,824.00	SQYD		\$	
0330	02159		TEMP DITCH	44,152.00	LF		\$	
0340	02200		ROADWAY EXCAVATION	1,516,824.00	CUYD		\$	
0350	02223		GRANULAR EMBANKMENT	16,923.00	CUYD		\$	

PROPOSAL BID ITEMS

141070

Page 2 of 5

Report Date 12/8/14

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0360	02230		EMBANKMENT IN PLACE	1,627,907.00	CUYD		\$	
0370	02242		WATER	1,334.00	MGAL		\$	
0380	02262		FENCE-WOVEN WIRE TYPE 1	69,605.00	LF		\$	
0390	02351		GUARDRAIL-STEEL W BEAM-S FACE	30,475.00	LF		\$	
0400	02360		GUARDRAIL TERMINAL SECTION NO 1	27.00	EACH		\$	
0410	02363		GUARDRAIL CONNECTOR TO BRIDGE END TY A	8.00	EACH		\$	
0420	02369		GUARDRAIL END TREATMENT TYPE 2A	1.00	EACH		\$	
0430	02381		REMOVE GUARDRAIL	2,787.50	LF		\$	
0440	02391		GUARDRAIL END TREATMENT TYPE 4A	48.00	EACH		\$	
0450	02429		RIGHT-OF-WAY MONUMENT TYPE 1	341.00	EACH		\$	
0460	02430		RIGHT-OF-WAY MONUMENT TYPE 1A	1.00	EACH		\$	
0470	02431		WITNESS R/W MONUMENT TYPE 2	1.00	EACH		\$	
0480	02483		CHANNEL LINING CLASS II	13,826.00	TON		\$	
0490	02484		CHANNEL LINING CLASS III	8,126.00	TON		\$	
0500	02545		CLEARING AND GRUBBING 174 ACRES	1.00	LS		\$	
0510	02545		CLEARING AND GRUBBING 11 ACRES	1.00	LS		\$	
0520	02545		CLEARING AND GRUBBING 71 ACRES	1.00	LS		\$	
0530	02562		TEMPORARY SIGNS	1,202.00	SQFT		\$	
0540	02585		EDGE KEY	237.00	LF		\$	
0550	02598		FABRIC-GEOTEXTILE TYPE III	64,139.00	SQYD		\$	
0560	02599		FABRIC-GEOTEXTILE TYPE IV	27,866.00	SQYD		\$	
0570	02600		FABRIC GEOTEXTILE TY IV FOR PIPE	29,765.00	SQYD	\$2.00	\$	\$59,530.00
0580	02650		MAINTAIN & CONTROL TRAFFIC (NELSON COUNTY)	1.00	LS		\$	
0590	02650		MAINTAIN & CONTROL TRAFFIC (BULLITT COUNTY)	1.00	LS		\$	
0600	02650		MAINTAIN & CONTROL TRAFFIC (SPENCER COUNTY)	1.00	LS		\$	
0610	02651		DIVERSIONS (BY-PASS DETOURS)	1.00	LS		\$	
0620	02671		PORTABLE CHANGEABLE MESSAGE SIGN	6.00	EACH		\$	
0630	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0640	02690		SAFELOADING	4.00	CUYD		\$	
0650	02696		SHOULDER RUMBLE STRIPS-SAWED	67,552.00	LF		\$	
0660	02701		TEMP SILT FENCE	44,152.00	LF		\$	
0670	02703		SILT TRAP TYPE A	275.00	EACH		\$	
0680	02704		SILT TRAP TYPE B	275.00	EACH		\$	
0690	02705		SILT TRAP TYPE C	275.00	EACH		\$	
0700	02706		CLEAN SILT TRAP TYPE A	825.00	EACH		\$	
0710	02707		CLEAN SILT TRAP TYPE B	825.00	EACH		\$	
0720	02708		CLEAN SILT TRAP TYPE C	825.00	EACH		\$	
0730	02709		CLEAN TEMP SILT FENCE	44,152.00	LF		\$	
0740	02726		STAKING (NELSON COUNTY)	1.00	LS		\$	
0750	02726		STAKING (BULLITT COUNTY)	1.00	LS		\$	
0760	02726		STAKING (SPENCER COUNTY)	1.00	LS		\$	
0770	02775		ARROW PANEL	2.00	EACH		\$	
0780	05950		EROSION CONTROL BLANKET	28,288.00	SQYD		\$	

PROPOSAL BID ITEMS

141070

Page 3 of 5

Report Date 12/8/14

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0790	05952		TEMP MULCH	952,585.00	SQYD		\$	
0800	05953		TEMP SEEDING AND PROTECTION	952,585.00	SQYD		\$	
0810	05963		INITIAL FERTILIZER	23.98	TON		\$	
0820	05964		20-10-10 FERTILIZER	40.02	TON		\$	
0830	05985		SEEDING AND PROTECTION	773,629.00	SQYD		\$	
0840	05989		SPECIAL SEEDING CROWN VETCH	199,767.00	SQYD		\$	
0850	05992		AGRICULTURAL LIMESTONE	479.51	TON		\$	
0860	06510		PAVE STRIPING-TEMP PAINT-4 IN	211,130.00	LF		\$	
0870	06514		PAVE STRIPING-PERM PAINT-4 IN	218,533.00	LF		\$	
0880	06574		PAVE MARKING-THERMO CURV ARROW	4.00	EACH		\$	
0890	06576		PAVE MARKING-THERMO ONLY	4.00	EACH		\$	
0900	20209EP69		GRANULAR PILE CORE	3,720.00	CUYD		\$	
0910	20458ES403		CENTERLINE RUMBLE STRIPS	46,754.00	LF		\$	
0920	24540		R/W MONUMENT TYPE 3	29.00	EACH		\$	
0930	24721EC		CHEMICAL TESTING EQUIPMENT X-RAY	1.00	LS	450,000.00	\$	\$450,000.00

Section: 0004 - DRAINAGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0940	00078		CRUSHED AGGREGATE SIZE NO 2	54.00	TON		\$	
0950	00440		ENTRANCE PIPE-15 IN	334.00	LF		\$	
0960	00441		ENTRANCE PIPE-18 IN	415.00	LF		\$	
0970	00443		ENTRANCE PIPE-24 IN	352.00	LF		\$	
0980	00445		ENTRANCE PIPE-30 IN	132.00	LF		\$	
0990	00462		CULVERT PIPE-18 IN	1,942.00	LF		\$	
1000	00464		CULVERT PIPE-24 IN	2,466.00	LF		\$	
1010	00466		CULVERT PIPE-30 IN	1,219.00	LF		\$	
1020	00468		CULVERT PIPE-36 IN	736.00	LF		\$	
1030	00471		CULVERT PIPE-54 IN	380.00	LF		\$	
1040	00472		CULVERT PIPE-60 IN	357.00	LF		\$	
1050	00473		CULVERT PIPE-66 IN	166.00	LF		\$	
1060	01000		PERFORATED PIPE-4 IN	6,571.00	LF		\$	
1070	01010		NON-PERFORATED PIPE-4 IN	530.00	LF		\$	
1080	01020		PERF PIPE HEADWALL TY 1-4 IN	6.00	EACH		\$	
1090	01024		PERF PIPE HEADWALL TY 2-4 IN	8.00	EACH		\$	
1100	01028		PERF PIPE HEADWALL TY 3-4 IN	34.00	EACH		\$	
1110	01032		PERF PIPE HEADWALL TY 4-4 IN	6.00	EACH		\$	
1120	01204		PIPE CULVERT HEADWALL-18 IN	15.00	EACH		\$	
1130	01204		PIPE CULVERT HEADWALL-18 IN	4.00	EACH		\$	
1140	01208		PIPE CULVERT HEADWALL-24 IN	17.00	EACH		\$	
1150	01208		PIPE CULVERT HEADWALL-24 IN	8.00	EACH		\$	
1160	01210		PIPE CULVERT HEADWALL-30 IN	12.00	EACH		\$	
1170	01210		PIPE CULVERT HEADWALL-30 IN	1.00	EACH		\$	
1180	01212		PIPE CULVERT HEADWALL-36 IN	6.00	EACH		\$	
1190	01220		PIPE CULVERT HEADWALL-60 IN	3.00	EACH		\$	
1200	01222		PIPE CULVERT HEADWALL-66 IN	2.00	EACH		\$	
1210	01450		S & F BOX INLET-OUTLET-18 IN	17.00	EACH		\$	
1220	01451		S & F BOX INLET-OUTLET-24 IN	5.00	EACH		\$	

PROPOSAL BID ITEMS

141070

Page 4 of 5

Report Date 12/8/14

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1230	01490		DROP BOX INLET TYPE 1	1.00	EACH		\$	
1240	01493		DROP BOX INLET TYPE 2	1.00	EACH		\$	
1250	01497		DROP BOX INLET TYPE 3 MOD	1.00	EACH		\$	
1260	01545		DROP BOX INLET TYPE 11 MOD	1.00	EACH		\$	
1270	01691		FLUME INLET TYPE 2	4.00	EACH		\$	
1280	02597		FABRIC-GEOTEXTILE TYPE II	3,944.00	SQYD		\$	
1290	23131ER701		PIPELINE VIDEO INSPECTION	7,241.00	LF		\$	
1300	24026EC		PIPE CULVERT HEADWALL-54 IN	2.00	EACH		\$	

Section: 0005 - BRIDGE-27146

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1310	02231		STRUCTURE GRANULAR BACKFILL	305.00	CUYD		\$	
1320	02998		MASONRY COATING	908.00	SQYD		\$	
1330	03299		ARMORED EDGE FOR CONCRETE	116.80	LF		\$	
1340	08001		STRUCTURE EXCAVATION-COMMON	245.00	CUYD		\$	
1350	08002		STRUCTURE EXCAV-SOLID ROCK	37.00	CUYD		\$	
1360	08020		CRUSHED AGGREGATE SLOPE PROT	319.00	TON		\$	
1370	08033		TEST PILES	33.00	LF		\$	
1380	08039		PRE-DRILLING FOR PILES	110.00	LF		\$	
1390	08046		PILES-STEEL HP12X53	320.00	LF		\$	
1400	08094		PILE POINTS-12 IN	22.00	EACH		\$	
1410	08100		CONCRETE-CLASS A	249.20	CUYD		\$	
1420	08104		CONCRETE-CLASS AA	307.20	CUYD		\$	
1430	08150		STEEL REINFORCEMENT	28,256.00	LB		\$	
1440	08151		STEEL REINFORCEMENT-EPOXY COATED	94,894.00	LB		\$	
1450	08633		PRECAST PC I BEAM TYPE 3	739.20	LF		\$	
1460	21532ED		RAIL SYSTEM TYPE III	303.80	LF		\$	

Section: 0006 - BRIDGE-27147

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1470	02231		STRUCTURE GRANULAR BACKFILL	681.40	CUYD		\$	
1480	02998		MASONRY COATING	1,347.00	SQYD		\$	
1490	03299		ARMORED EDGE FOR CONCRETE	88.00	LF		\$	
1500	08001		STRUCTURE EXCAVATION-COMMON	678.70	CUYD		\$	
1510	08002		STRUCTURE EXCAV-SOLID ROCK	237.20	CUYD		\$	
1520	08020		CRUSHED AGGREGATE SLOPE PROT	1,140.00	TON		\$	
1530	08033		TEST PILES	106.00	LF		\$	
1540	08046		PILES-STEEL HP12X53	893.00	LF		\$	
1550	08094		PILE POINTS-12 IN	20.00	EACH		\$	
1560	08100		CONCRETE-CLASS A	1,327.10	CUYD		\$	
1570	08104		CONCRETE-CLASS AA	1,318.10	CUYD		\$	
1580	08150		STEEL REINFORCEMENT	179,584.00	LB		\$	
1590	08151		STEEL REINFORCEMENT-EPOXY COATED	378,512.00	LB		\$	
1600	21532ED		RAIL SYSTEM TYPE III	1,436.00	LF		\$	
1610	23813EC		DECK DRAIN	54.00	EACH		\$	
1620	24627ED		PPC I-BEAM BT96-49	3,565.80	LF		\$	

141070

PROPOSAL BID ITEMS

Page 5 of 5

Report Date 12/8/14

Section: 0007 - BRIDGE-27148

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1630	02231		STRUCTURE GRANULAR BACKFILL	416.00	CUYD		\$	
1640	08001		STRUCTURE EXCAVATION-COMMON	526.00	CUYD		\$	
1650	08003		FOUNDATION PREPARATION	1.00	LS		\$	
1660	08100		CONCRETE-CLASS A	153.50	CUYD		\$	
1670	08150		STEEL REINFORCEMENT	26,855.00	LB		\$	

Section: 0008 - DEMOBILIZATION & OR MOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1680	02568		MOBILIZATION	1.00	LS		\$	
1690	02569		DEMOBILIZATION	1.00	LS		\$	