



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

April 21, 2023

CALL NO. 408
CONTRACT ID NO. 232976
ADDENDUM # 1

Subject: Adair County, 001GR23M038
Letting April 27, 2023

- (1) Revised - Omit Proposal Pages 12-14 of 177
- (2) Revised - Material Summary - Pages 158-159 of 177
- (3) Revised - Proposal Bid Items - Pages 175-177 of 177

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

MATERIAL SUMMARY

CONTRACT ID: 232976

001GR23M038

MB00105512301

KNIFLEY ROAD (KY 551) 001B00036N REPLACE CULVERT OVER BUTLER BRANCH AT MP 01.10 BRIDGE WITH GRADE, DRAIN & SURFACE, A DISTANCE OF .5 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	00001	DGA BASE	357.00	TON
0010	00020	TRAFFIC BOUND BASE	50.00	TON
0015	00100	ASPHALT SEAL AGGREGATE	3.20	TON
0020	00103	ASPHALT SEAL COAT	.40	TON
0025	00221	CL2 ASPH BASE 0.75D PG64-22	166.00	TON
0030	00301	CL2 ASPH SURF 0.38D PG64-22	79.00	TON
0035	02677	ASPHALT PAVE MILLING & TEXTURING	30.00	TON
0045	24970EC	ASPHALT MATERIAL FOR TACK NON-TRACKING	.70	TON
0050	01990	DELINEATOR FOR BARRIER WALL-B/W	24.00	EACH
0055	02200	ROADWAY EXCAVATION	167.00	CUYD
0060	02483	CHANNEL LINING CLASS II	27.00	TON
0065	02484	CHANNEL LINING CLASS III	160.00	TON
0070	02545	CLEARING AND GRUBBING - (LESS THAN 1 ACRE)	1.00	LS
0075	02562	TEMPORARY SIGNS	150.00	SQFT
0080	02602	FABRIC-GEOTEXTILE CLASS 1	470.00	SQYD
0085	02650	MAINTAIN & CONTROL TRAFFIC	1.00	LS
0090	02676	MOBILIZATION FOR MILL & TEXT	1.00	LS
0095	02701	TEMP SILT FENCE	480.00	LF
0100	02703	SILT TRAP TYPE A	2.00	EACH
0105	02705	SILT TRAP TYPE C	2.00	EACH
0110	02706	CLEAN SILT TRAP TYPE A	2.00	EACH
0115	02708	CLEAN SILT TRAP TYPE C	2.00	EACH
0120	02726	STAKING	1.00	LS
0125	02731	REMOVE STRUCTURE	1.00	LS
0130	02898	RELOCATE CRASH CUSHION	4.00	EACH
0135	03171	CONCRETE BARRIER WALL TYPE 9T	440.00	LF
0140	04933	TEMP SIGNAL 2 PHASE	1.00	EACH
0145	05963	INITIAL FERTILIZER	.10	TON
0150	05964	MAINTENANCE FERTILIZER	.10	TON
0155	05985	SEEDING AND PROTECTION	500.00	SQYD
0160	06511	PAVE STRIPING-TEMP PAINT-6 IN	1,960.00	LF
0165	06515	PAVE STRIPING-PERM PAINT-6 IN	1,800.00	LF
0170	08901	CRASH CUSHION TY VI CLASS BT TL2	4.00	EACH
0175	20318ES508	RELOCATE CONC BARRIER WALL	440.00	LF
0180	23010EN	PAVE MARK TEMP PAINT STOP BAR-24 IN	42.00	LF
0185	03250	WATERPROOFING MEMBRANE	134.00	SQYD
0190	08002	STRUCTURE EXCAV-SOLID ROCK	79.00	CUYD
0195	08003	FOUNDATION PREPARATION	1.00	LS
0200	08100	CONCRETE-CLASS A	142.00	CUYD
0205	08150	STEEL REINFORCEMENT	19,988.00	LB
0210	02568	MOBILIZATION	1.00	LS
0215	02569	DEMOBILIZATION	1.00	LS

MATERIAL SUMMARY

CONTRACT ID: 232976

001GR23M038

MB00105512302

KNIFLEY ROAD (KY 551) 001B00037N REPLACE CULVERT OVER BUTLER BRANCH AT MP 01.83 BRIDGE WITH GRADE, DRAIN & SURFACE, A DISTANCE OF .05 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	00001	DGA BASE	400.00	TON
0010	00020	TRAFFIC BOUND BASE	50.00	TON
0015	00100	ASPHALT SEAL AGGREGATE	4.80	TON
0020	00103	ASPHALT SEAL COAT	.60	TON
0025	00221	CL2 ASPH BASE 0.75D PG64-22	201.00	TON
0030	00301	CL2 ASPH SURF 0.38D PG64-22	84.00	TON
0035	02677	ASPHALT PAVE MILLING & TEXTURING	35.00	TON
0045	24970EC	ASPHALT MATERIAL FOR TACK NON-TRACKING	.80	TON
0050	01990	DELINEATOR FOR BARRIER WALL-B/W	29.00	EACH
0055	02230	EMBANKMENT IN PLACE	245.00	CUYD
0060	02483	CHANNEL LINING CLASS II	20.00	TON
0065	02484	CHANNEL LINING CLASS III	331.00	TON
0070	02545	CLEARING AND GRUBBING - (LESS THAN 1 ACRE)	1.00	LS
0075	02562	TEMPORARY SIGNS	150.00	SQFT
0080	02602	FABRIC-GEOTEXTILE CLASS 1	470.00	SQYD
0085	02650	MAINTAIN & CONTROL TRAFFIC	1.00	LS
0090	02676	MOBILIZATION FOR MILL & TEXT	1.00	LS
0095	02701	TEMP SILT FENCE	480.00	LF
0100	02703	SILT TRAP TYPE A	2.00	EACH
0105	02705	SILT TRAP TYPE C	2.00	EACH
0110	02706	CLEAN SILT TRAP TYPE A	2.00	EACH
0115	02708	CLEAN SILT TRAP TYPE C	2.00	EACH
0120	02726	STAKING	1.00	LS
0125	02731	REMOVE STRUCTURE	1.00	LS
0130	02898	RELOCATE CRASH CUSHION	4.00	EACH
0135	03171	CONCRETE BARRIER WALL TYPE 9T	540.00	LF
0140	04933	TEMP SIGNAL 2 PHASE	1.00	EACH
0145	05963	INITIAL FERTILIZER	.10	TON
0150	05964	MAINTENANCE FERTILIZER	.10	TON
0155	05985	SEEDING AND PROTECTION	500.00	SQYD
0160	06511	PAVE STRIPING-TEMP PAINT-6 IN	2,160.00	LF
0165	06515	PAVE STRIPING-PERM PAINT-6 IN	2,210.00	LF
0170	08901	CRASH CUSHION TY VI CLASS BT TL2	4.00	EACH
0175	20318ES508	RELOCATE CONC BARRIER WALL	540.00	LF
0180	23010EN	PAVE MARK TEMP PAINT STOP BAR-24 IN	42.00	LF
0185	03250	WATERPROOFING MEMBRANE	134.00	SQYD
0190	08002	STRUCTURE EXCAV-SOLID ROCK	77.00	CUYD
0195	08003	FOUNDATION PREPARATION	1.00	LS
0200	08100	CONCRETE-CLASS A	139.70	CUYD
0205	08150	STEEL REINFORCEMENT	19,789.00	LB
0210	02568	MOBILIZATION	1.00	LS
0215	02569	DEMOBILIZATION	1.00	LS

PROPOSAL BID ITEMS

232976

Page 1 of 3

Report Date 4/21/23

Section: 0001 - PAVING (001B00036N)

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00001		DGA BASE	357.00	TON		\$	
0020	00020		TRAFFIC BOUND BASE	50.00	TON		\$	
0030	00100		ASPHALT SEAL AGGREGATE	3.20	TON		\$	
0040	00103		ASPHALT SEAL COAT	.40	TON		\$	
0050	00221		CL2 ASPH BASE 0.75D PG64-22	166.00	TON		\$	
0060	00301		CL2 ASPH SURF 0.38D PG64-22	79.00	TON		\$	
0070	02677		ASPHALT PAVE MILLING & TEXTURING	30.00	TON		\$	
0090	24970EC		ASPHALT MATERIAL FOR TACK NON-TRACKING	.70	TON		\$	

Section: 0002 - PAVING (001B00037N)

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0100	00001		DGA BASE	400.00	TON		\$	
0110	00020		TRAFFIC BOUND BASE	50.00	TON		\$	
0120	00100		ASPHALT SEAL AGGREGATE	4.80	TON		\$	
0130	00103		ASPHALT SEAL COAT	.60	TON		\$	
0140	00221		CL2 ASPH BASE 0.75D PG64-22	201.00	TON		\$	
0150	00301		CL2 ASPH SURF 0.38D PG64-22	84.00	TON		\$	
0160	02677		ASPHALT PAVE MILLING & TEXTURING	35.00	TON		\$	
0180	24970EC		ASPHALT MATERIAL FOR TACK NON-TRACKING	.80	TON		\$	

Section: 0003 - ROADWAY (001B00036N)

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0190	01990		DELINEATOR FOR BARRIER WALL-B/W	24.00	EACH		\$	
0200	02200		ROADWAY EXCAVATION	167.00	CUYD		\$	
0210	02483		CHANNEL LINING CLASS II	27.00	TON		\$	
0220	02484		CHANNEL LINING CLASS III	160.00	TON		\$	
0230	02545		CLEARING AND GRUBBING (LESS THAN 1 ACRE)	1.00	LS		\$	
0240	02562		TEMPORARY SIGNS	150.00	SQFT		\$	
0250	02602		FABRIC-GEOTEXTILE CLASS 1	470.00	SQYD		\$	
0260	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0270	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0280	02701		TEMP SILT FENCE	480.00	LF		\$	
0290	02703		SILT TRAP TYPE A	2.00	EACH		\$	
0300	02705		SILT TRAP TYPE C	2.00	EACH		\$	
0310	02706		CLEAN SILT TRAP TYPE A	2.00	EACH		\$	
0320	02708		CLEAN SILT TRAP TYPE C	2.00	EACH		\$	
0330	02726		STAKING	1.00	LS		\$	
0340	02731		REMOVE STRUCTURE	1.00	LS		\$	
0350	02898		RELOCATE CRASH CUSHION	4.00	EACH		\$	
0360	03171		CONCRETE BARRIER WALL TYPE 9T	440.00	LF		\$	

PROPOSAL BID ITEMS

232976

Page 2 of 3

Report Date 4/21/23

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0370	04933		TEMP SIGNAL 2 PHASE	1.00	EACH		\$	
0380	05963		INITIAL FERTILIZER	.10	TON		\$	
0390	05964		MAINTENANCE FERTILIZER	.10	TON		\$	
0400	05985		SEEDING AND PROTECTION	500.00	SQYD		\$	
0410	06511		PAVE STRIPING-TEMP PAINT-6 IN	1,960.00	LF		\$	
0420	06515		PAVE STRIPING-PERM PAINT-6 IN	1,800.00	LF		\$	
0430	08901		CRASH CUSHION TY VI CLASS BT TL2	4.00	EACH		\$	
0440	20318ES508		RELOCATE CONC BARRIER WALL	440.00	LF		\$	
0450	23010EN		PAVE MARK TEMP PAINT STOP BAR-24 IN	42.00	LF		\$	

Section: 0004 - ROADWAY(001B00037N)

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0460	01990		DELINEATOR FOR BARRIER WALL-B/W	29.00	EACH		\$	
0470	02230		EMBANKMENT IN PLACE	245.00	CUYD		\$	
0480	02483		CHANNEL LINING CLASS II	20.00	TON		\$	
0490	02484		CHANNEL LINING CLASS III	331.00	TON		\$	
0500	02545		CLEARING AND GRUBBING (LESS THAN 1 ACRE)	1.00	LS		\$	
0510	02562		TEMPORARY SIGNS	150.00	SQFT		\$	
0520	02602		FABRIC-GEOTEXTILE CLASS 1	470.00	SQYD		\$	
0530	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0540	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0550	02701		TEMP SILT FENCE	480.00	LF		\$	
0560	02703		SILT TRAP TYPE A	2.00	EACH		\$	
0570	02705		SILT TRAP TYPE C	2.00	EACH		\$	
0580	02706		CLEAN SILT TRAP TYPE A	2.00	EACH		\$	
0590	02708		CLEAN SILT TRAP TYPE C	2.00	EACH		\$	
0600	02726		STAKING	1.00	LS		\$	
0610	02731		REMOVE STRUCTURE	1.00	LS		\$	
0620	02898		RELOCATE CRASH CUSHION	4.00	EACH		\$	
0630	03171		CONCRETE BARRIER WALL TYPE 9T	540.00	LF		\$	
0640	04933		TEMP SIGNAL 2 PHASE	1.00	EACH		\$	
0650	05963		INITIAL FERTILIZER	.10	TON		\$	
0660	05964		MAINTENANCE FERTILIZER	.10	TON		\$	
0670	05985		SEEDING AND PROTECTION	500.00	SQYD		\$	
0680	06511		PAVE STRIPING-TEMP PAINT-6 IN	2,160.00	LF		\$	
0690	06515		PAVE STRIPING-PERM PAINT-6 IN	2,210.00	LF		\$	
0700	08901		CRASH CUSHION TY VI CLASS BT TL2	4.00	EACH		\$	
0710	20318ES508		RELOCATE CONC BARRIER WALL	540.00	LF		\$	
0720	23010EN		PAVE MARK TEMP PAINT STOP BAR-24 IN	42.00	LF		\$	

Section: 0005 - BRIDGE (001B00036N)

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0730	03250		WATERPROOFING MEMBRANE	134.00	SQYD		\$	
0740	08002		STRUCTURE EXCAV-SOLID ROCK	79.00	CUYD		\$	

PROPOSAL BID ITEMS

232976

Page 3 of 3

Report Date 4/21/23

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0750	08003		FOUNDATION PREPARATION	1.00	LS		\$	
0760	08100		CONCRETE-CLASS A	142.00	CUYD		\$	
0770	08150		STEEL REINFORCEMENT	19,988.00	LB		\$	

Section: 0006 - BRIDGE(001B00037N)

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0780	03250		WATERPROOFING MEMBRANE	134.00	SQYD		\$	
0790	08002		STRUCTURE EXCAV-SOLID ROCK	77.00	CUYD		\$	
0800	08003		FOUNDATION PREPARATION	1.00	LS		\$	
0810	08100		CONCRETE-CLASS A	139.70	CUYD		\$	
0820	08150		STEEL REINFORCEMENT	19,789.00	LB		\$	

Section: 0007 - DEMOBILIZATION &/OR MOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0830	02568		MOBILIZATION	1.00	LS		\$	
0840	02569		DEMOBILIZATION	1.00	LS		\$	