



TRANSPORTATION CABINET

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Steven L. Beshear
Governor

Michael W. Hancock, P.E.
Secretary

March 12, 2012

CALL NO. 410
CONTRACT ID NO. 122086
ADDENDUM # 1

Subject: McCracken County, 073GR12P044-FD05
Letting March 23, 2012

- (1) Revised - Table of Contents - Page 2 of 81
- (2) Deleted - Fuel & Asphalt Pay Adjustment - Page 11 of 81
- (3) Deleted - Page 12 of 81
- (4) Revised - Material Summary - Page 23 of 81
- (5) Revised - Bid Items - Page 81 of 81

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Ryan Griffith".

Ryan Griffith
Director
Division of Construction Procurement

RG:ks
Enclosures



An Equal Opportunity Employer M/F/D

TABLE OF CONTENTS

PART I	SCOPE OF WORK <ul style="list-style-type: none">• PROJECT(S), COMPLETION DATE(S), & LIQUIDATED DAMAGES• CONTRACT NOTES• STATE CONTRACT NOTES• 2012 DEFERRED PAY• SURFACING AREAS• ASPHALT MIXTURE• DGA BASE FOR SHOULDERS• INCIDENTAL SURFACING• COMPACTION OPTION B• SPECIAL NOTE(S) APPLICABLE TO PROJECT• AWARD OF CONTRACT• EDGE KEY• ASPHALT MILLING AND TEXTURING• TYPICAL SECTION DIMENSIONS• TRAFFIC CONTROL PLAN• SKETCH MAP(S)• MATERIAL SUMMARY• SUMMARY SHEET(S)• TYPICAL SECTION(S)
PART II	SPECIFICATIONS AND STANDARD DRAWINGS <ul style="list-style-type: none">• SPECIFICATIONS REFERENCE• SUPPLEMENTAL SPECIFICATIONS• 2008 STANDARD DRAWINGS THAT APPLY
PART III	EMPLOYMENT, WAGE AND RECORD REQUIREMENTS <ul style="list-style-type: none">• LABOR AND WAGE REQUIREMENTS• EXECUTIVE BRANCH CODE OF ETHICS• KENTUCKY EQUAL EMPLOYMENT OPPORTUNITY ACT OF 1978• PROJECT WAGE RATES
PART IV	INSURANCE
PART V	BID ITEMS

DEFERRED PAYMENT: The successful bidder on this project may request a work order with an effective date prior to June 15, 2012. The successful bidder must make the request in writing to the Department. The Department will issue a work order at the request of the contractor with the distinct understanding that payment for any Work Performed Estimates may be delayed until July 15, 2012. Unless the successful bidder requests an earlier work order date, the Department will issue a work order on June 15, 2012 for this project.

SURFACING AREAS

KY 787

The Department estimates the mainline surfacing width to be 19 feet.

The Department estimates the total mainline area to be surfaced to be 20,740 square yards.

The Department estimates the shoulder width to be 1 foot on each side.

The Department estimates the total shoulder area to be DGA to be 1,898 square yards.

KY 1201

The Department estimates the mainline surfacing width to be 20 feet.

The Department estimates the total mainline area to be surfaced to be 18,328 square yards.

The Department estimates the shoulder width to be 1.5 feet on each side.

The Department estimates the total shoulder area to be DGA to be 2,499 square yards.

ASPHALT MIXTURE

Unless otherwise noted, the Department estimates the rate of application for all asphalt mixtures to be 110 lbs/sy per inch of depth.

DGA BASE FOR SHOULDERS

Unless otherwise noted, the Department estimates the rate of application for DGA Base for Shoulders to be 115 lbs/sy per inch of depth. The Department will not measure necessary grading and/or shaping of existing shoulders prior to placing of DGA Base, but shall be incidental to the Contract unit price per ton for DGA Base.

Accept payment at the Contract unit price per ton as full compensation for all labor, materials, equipment, and incidentals for grading and/or shaping of existing shoulders and furnishing, placing, and compacting the DGA Base.

INCIDENTAL SURFACING

The Department has included in the quantities of asphalt mixtures established in the proposal estimated quantities required for resurfacing or surfacing mailbox turnouts, farm field entrances, residential and commercial entrances, curve widening, ramp gores and tapers, and road and street approaches, as applicable. Pave these areas to the limits as shown on Standard Drawing RPM-110-05 or as directed by the Engineer. In the event signal detectors are present in the intersecting streets or roads, pave the crossroads to the right of way limit or back of the signal detector, whichever is the farthest back of the mainline. Surface or resurface these areas as directed by the Engineer. The Department will not measure placing and compacting for separate payment but shall be incidental to the Contract unit price for the asphalt mixtures.

OPTION B

Be advised that the Department will control and accept compaction of asphalt mixtures furnished on this project under OPTION B in accordance with Sections 402 and 403.

MATERIAL SUMMARY

CONTRACT ID: 122086

FD05 073 0787 001-004 PES NO: MP07307871101
BRYANT FORD ROAD (KY 787) FROM NORTH END OF CLARKS RIVER EAST FORK BRIDGE (MP 1.596)
EXTENDING NORTH TO US 68 (MP 3.214), A DISTANCE OF 1.620000 MILES.

LINE NO	BID CODE	DESCRIPTION	QUANTITY	UNIT
0010	00001	DGA BASE	385.00	TON
0020	00190	LEVELING & WEDGING PG64-22	412.00	TON
0030	00301	CL2 ASPH SURF 0.38D PG64-22	1,145.00	TON
0040	02562	SIGNS	270.00	SQFT
0050	02650	MAINTAIN & CONTROL TRAFFIC KY 787 MP 1.596-3.214	1.00	LS
0060	02676	MOBILIZATION FOR MILL & TEXT KY 787 MP 1.596-3.214	1.00	LS
0070	02677	ASPHALT PAVE MILLING & TEXTURING	17.00	TON
0080	06510	PAVE STRIPING-TEMP PAINT-4 IN	12,000.00	LF
0090	06514	PAVE STRIPING-PERM PAINT-4 IN	12,000.00	LF
0100	06568	PAVE MARKING-THERMO STOP BAR-24IN	10.00	LF
0130	02569	DEMOBILIZATION	1.00	LS

FD05 073 1201 000-002 PES NO: MP07312011101
CULP ROAD (KY 1201) FROM KY 787 (MP 0.000) EXTENDING NORTH TO ENTRANCE GATE TO
SYNTECHNICS (MP 1.420), A DISTANCE OF 1.420000 MILES.

LINE NO	BID CODE	DESCRIPTION	QUANTITY	UNIT
0010	00001	DGA BASE	220.00	TON
0020	00190	LEVELING & WEDGING PG64-22	277.00	TON
0030	00301	CL2 ASPH SURF 0.38D PG64-22	1,010.00	TON
0040	02562	SIGNS	390.00	SQFT
0050	02650	MAINTAIN & CONTROL TRAFFIC KY 1201 MP 0.000-1.420	1.00	LS
0060	02676	MOBILIZATION FOR MILL & TEXT KY 1201 MP 0.000-1.420	1.00	LS
0070	02677	ASPHALT PAVE MILLING & TEXTURING	20.00	TON
0080	06510	PAVE STRIPING-TEMP PAINT-4 IN	10,000.00	LF
0090	06514	PAVE STRIPING-PERM PAINT-4 IN	13,500.00	LF
0100	06542	PAVE STRIPING-THERMO-6 IN W	27.00	LF
0110	06562	PAVE MARKING-THERMO R 6 FT	2.00	EACH
0120	06563	PAVE MARKING-R/R XBUCKS 16 IN	44.00	LF
0130	06568	PAVE MARKING-THERMO STOP BAR-24IN	63.00	LF
0160	02569	DEMOBILIZATION	1.00	LS

CONTRACT ID: 122086
COUNTY: MCCRACKEN
PROPOSAL: 073GR12P044-FD05PAGE: 1
LETTING: 03/23/12
CALL NO: 410

LINE NO	ITEM	DESCRIPTION	APPROXIMATE UNIT QUANTITY	UNIT PRICE	AMOUNT
SECTION 0001 ROADWAY					
0010	00001	DGA BASE	605.000 TON		
0020	00190	LEVELING & WEDGING PG64-22	689.000 TON		
0030	00301	CL2 ASPH SURF 0.38D PG64-22	2,155.000 TON		
0040	02562	SIGNS	660.000 SQFT		
0050	02650	MAINTAIN & CONTROL TRAFFIC KY 1201 MP 0.000-1.420	(1.00) LS		
0060	02650	MAINTAIN & CONTROL TRAFFIC KY 787 MP 1.596-3.214	(1.00) LS		
0070	02676	MOBILIZATION FOR MILL & TEXT KY 1201 MP 0.000-1.420	(1.00) LS		
0080	02676	MOBILIZATION FOR MILL & TEXT KY 787 MP 1.596-3.214	(1.00) LS		
0090	02677	ASPHALT PAVE MILLING & TEXTURING	37.000 TON		
0100	06510	PAVE STRIPING-TEMP PAINT-4 IN	22,000.000 LF		
0110	06514	PAVE STRIPING-PERM PAINT-4 IN	25,500.000 LF		
0120	06542	PAVE STRIPING-THERMO-6 IN W	27.000 LF		
0130	06562	PAVE MARKING-THERMO R 6 FT	2.000 EACH		
0140	06563	PAVE MARKING-R/R XBUCKS 16 IN	44.000 LF		
0150	06568	PAVE MARKING-THERMO STOP BAR-24IN	73.000 LF		
SECTION 0002 DEMOBILIZATION					
0180	02569	DEMOBILIZATION (AT LEAST 1.5%)	LUMP		
		TOTAL BID			