



Commonwealth of Kentucky  
**Transportation Cabinet**  
Frankfort, Kentucky 40622

James C. Codell, III  
Secretary of Transportation

Paul E. Patton  
Governor

Clifford C. Linkes, P.E.  
Deputy Secretary

May 15, 2003

PCN 030342  
Change # 1

Subject: Logan County, BRZ 0303 (179)  
Letting May 23, 2003

Enclosed is a set of revised bid items on the subject project.

If you obtained bid items from our Website, it is imperative that you download a new set of bid items before submitting them for bidding.

Your bid, to be considered, must be based upon the above-mentioned bid items, and these bid items are to be made a part of the bid proposal, which you submit to the Kentucky Department of Highways.

Specimen proposals may not be used for bidding purposes.

If you have any questions, please contact us at (502) 564-3500.

Sincerely,

Rick Stansel  
Director  
Division of Contract Procurement

Enclosure  
RS:ks



KENTUCKY TRANSPORTATION CABINET  
"PROVIDE A SAFE, EFFICIENT, ENVIRONMENTALLY SOUND, AND FISCALLY RESPONSIBLE TRANSPORTATION SYSTEM  
WHICH PROMOTES ECONOMIC GROWTH AND ENHANCES THE QUALITY OF LIFE IN KENTUCKY."  
"AN EQUAL OPPORTUNITY EMPLOYER M/F/D"

**TRANSPORTATION CABINET**

Department of Highways

FRANKFORT, KY 40622

Sheet No: 1

LOGAN COUNTY

BRZ 0303 (179)

PCN: 03-0342

Letting: 5/23/2003

THE BIDDER MUST MAKE THE EXTENSIONS AND ADDITIONS  
SHOWING TOTAL AMOUNT BID USING FIGURES ONLY

Item No.	Code No.	Item	Approximate Quantity	Unit	Unit Price Dollars	Amount Dollars
		BRIDGE AND CULVERT QUANTITIES			.	.
1	2231	STRUCTURE GRANULAR BACKFILL	59.30	CU YD	.	.
2	8002	STRUCTURE EXCAV-SOLID ROCK	158.00	CU YD	.	.
3	2998	MASONRY COATING	666.00	SQ YD	.	.
4	8100	CONCRETE-CLASS A	134.10	CU YD	.	.
5	8104	CONCRETE-CLASS AA	177.10	CU YD	.	.
6	8019	CYCLOPEAN STONE RIP RAP	313.00	TON	.	.
7	8046	PILES-STEEL HP12X53	114.80	LIN FT	.	.
8	8094	PILE POINTS-12 INCH	8.00	EACH	.	.
9	8033	TEST PILES	16.40	LIN FT	.	.
10	8151	STEEL REINF-EPOXY COATED	50,764.00	LB	.	.
11	8150	STEEL REINFORCEMENT	15,485.00	LB	.	.
12	8636	PRECAST PC I BEAM TYPE 5 (60" MOD)	492.40	LIN FT	.	.
13	2596	FABRIC-GEOTEXTILE TYPE I	313.00	SQ YD	.	.
		STRUCTURAL STEEL (APPROX. 885 LBS.) (DELETED: 5-15-03)			.	.
14	3299	ARMORED EDGE FOR CONCRETE (ADDED: 5-15-03)	44.00	LIN FT	.	.
15	8003	FOUNDATION PREPARATION	1.00	LP SUM	.	.
		ROADWAY QUANTITIES			.	.
16	2200	ROADWAY EXCAVATION	5,007.00	CU YD	.	.
17	2562	SIGNS	52.00	SQ FT	.	.
18	2351	GUARDRAIL-STEEL W BEAM-S FACE	175.00	LIN FT	.	.
19	2371	GUARDRAIL END TREATMENT TYPE 7	4.00	EACH	.	.
20	2363	GUARDRAIL CON TO BR END TYPE A	4.00	EACH	.	.
21	2091	REMOVE PAVEMENT	1,869.00	SQ YD	.	.

**TRANSPORTATION CABINET**

Department of Highways

FRANKFORT, KY 40622

Sheet No: 2

LOGAN COUNTY

BRZ 0303 (179)

**PCN: 03-0342**

Letting: 5/23/2003

THE BIDDER MUST MAKE THE EXTENSIONS AND ADDITIONS  
SHOWING TOTAL AMOUNT BID USING FIGURES ONLY

Item No.	Code No.	Item	Approximate Quantity	Unit	Unit Price Dollars	Amount Dollars
22	0440	ENTRANCE PIPE-15 INCH	88.00	LIN FT	.	.
23	1000	PERFORATED PIPE-4 INCH	22.00	LIN FT	.	.
24	1010	NON-PERFORATED PIPE-4 INCH	14.00	LIN FT	.	.
25	1020	PERF PIPE HEADWALL TY 1-4 INCH	1.00	EACH	.	.
26	5985	SEEDING AND PROTECTION	9,634.00	SQ YD	.	.
27	5953	TEMP SEEDING AND PROTECTION	963.00	SQ YD	.	.
28	5989	SPECIAL SEEDING CROWN VETCH	2,740.00	SQ YD	.	.
29	5966	TOPDRESSING FERTILIZER	1.00	TON	.	.
30	5950	EROSION CONTROL BLANKET	1,536.00	SQ YD	.	.
31	2705	SILT CHECK	11.00	EACH	.	.
32	2708	CLEAN SILT CHECK	44.00	EACH	.	.
33	2701	TEMPORARY SILT FENCE	165.00	LIN FT	.	.
34	2709	CLEAN TEMPORARY SILT FENCE	330.00	LIN FT	.	.
35	2483	CHANNEL LINING CLASS II	604.00	TON	.	.
36	2434	R/W MARKER RURAL TYPE 1	14.00	EACH	.	.
37	2677	ASPH PAVE MILLING & TEXTURING	25.00	TON	.	.
38	0001	D G A BASE	871.00	TON	.	.
39	0020	TRAFFIC BOUND BASE	31.00	TON	.	.
40	0291	EMULSIFIED ASPHALT RS-2	0.50	TON	.	.
41	0100	ASPHALT SEAL AGGREGATE	3.50	TON	.	.
42	0220	CL1 ASPH BASE 0.75D PG64-22	1,135.00	TON	.	.
43	0300	CL1 ASPH SURF 0.38D PG64-22	231.00	TON	.	.
44	2545	CLEARING AND GRUBBING (2.7 ACRES)	1.00	LP SUM	.	.
45	2726	STAKING	1.00	LP SUM	.	.
46	2650	MAINTAIN AND CONTROL TRAFFIC	1.00	LP SUM	.	.
47	2731	REMOVE EXISTING STRUCTURE	1.00	LP SUM	.	.

**TRANSPORTATION CABINET**

Department of Highways

FRANKFORT, KY 40622

Sheet No: 3

LOGAN COUNTY

BRZ 0303 (179)

PCN: 03-0342

Letting: 5/23/2003

THE BIDDER MUST MAKE THE EXTENSIONS AND ADDITIONS  
SHOWING TOTAL AMOUNT BID USING FIGURES ONLY

Item No.	Code No.	Item	Approximate Quantity	Unit	Unit Price Dollars	Amount Dollars
48	2676	MOBILIZATION FOR MILL & TEXT	1.00	LP SUM	.	.
49	2569	DEMOBILIZATION	1.00	LP SUM	.	.
50		TOTAL BID			\$	.