



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

April 22, 2024

CALL NO. 107
CONTRACT ID NO. 245343
ADDENDUM #1

Subject: Harlan County, STP BRZ 9030 (458)
Letting April 25, 2024

Revised - Proposal Bid Items Pg.146-147 of 147.

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:ce
Enclosures

PROPOSAL BID ITEMS

245343

Page 1 of 2

Report Date 4/22/24

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00001		DGA BASE	161.00	TON		\$	
0020	00221		CL2 ASPH BASE 0.75D PG64-22	150.00	TON		\$	
0030	00301		CL2 ASPH SURF 0.38D PG64-22	35.00	TON		\$	
0040	24970EC		ASPHALT MATERIAL FOR TACK NON-TRACKING	.35	TON		\$	

Section: 0002 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0050	00522		STORM SEWER PIPE-18 IN	115.00	LF		\$	
0060	01204		PIPE CULVERT HEADWALL-18 IN	1.00	EACH		\$	
0070	01559		DROP BOX INLET TYPE 13G	1.00	EACH		\$	
0080	01810		STANDARD CURB AND GUTTER	67.00	LF		\$	
0090	01987		DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	4.00	EACH		\$	
0100	02101		CEM CONC ENT PAVEMENT-8 IN	13.30	SQYD		\$	
0110	02355		GUARDRAIL-STEEL W BEAM-S FACE A	130.00	LF		\$	
0120	02360		GUARDRAIL TERMINAL SECTION NO 1	4.00	EACH		\$	
0130	02585		EDGE KEY	52.00	LF		\$	
0140	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0150	02671		PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH		\$	
0160	02720		SIDEWALK-4 IN CONCRETE	39.00	SQYD		\$	
0170	02726		STAKING	1.00	LS		\$	
0180	06514		PAVE STRIPING-PERM PAINT-4 IN	780.00	LF		\$	
0190	14003		W CAP EXISTING MAIN	1.00	EACH		\$	
0200	14030		W METER RELOCATE	1.00	EACH		\$	
0210	14088		W STRUCTURE REMOVAL EX Water Vault Removal	1.00	EACH		\$	
0220	14163		W LINE STOP SIZE 1	1.00	EACH		\$	
0230	20418ED		REMOVE & RELOCATE SIGNS	4.00	EACH		\$	
0240	21373ND		REMOVE SIGN	2.00	EACH		\$	
0250	21415ND		EROSION CONTROL	1.00	LS		\$	
0260	23158ES505		DETECTABLE WARNINGS	10.00	SQFT		\$	

Section: 0003 - BRIDGE - 048B00091N

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0270	02273		FENCE-4 FT CHAIN LINK	242.20	LF		\$	
0280	02403		REMOVE CONCRETE MASONRY	12.90	CUYD		\$	
0290	02731		REMOVE STRUCTURE	1.00	LS		\$	
0300	03299		ARMORED EDGE FOR CONCRETE	53.20	LF		\$	
0310	08002		STRUCTURE EXCAV-SOLID ROCK	189.00	CUYD		\$	
0320	08003		FOUNDATION PREPARATION	1.00	LS		\$	
0330	08019		CYCLOPEAN STONE RIP RAP	1,147.00	TON		\$	
0340	08033		TEST PILES (REVISED 4-22-24)	48.00	LF		\$	

PROPOSAL BID ITEMS

245343

Page 2 of 2

Report Date 4/22/24

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0350	08039		PRE-DRILLING FOR PILES	108.00	LF		\$	
0360	08046		PILES-STEEL HP12X53 (REVISED 4-22-24)	190.00	LF		\$	
0370	08094		PILE POINTS-12 IN	12.00	EACH		\$	
0380	08100		CONCRETE-CLASS A	276.90	CUYD		\$	
0390	08104		CONCRETE-CLASS AA	279.70	CUYD		\$	
0400	08150		STEEL REINFORCEMENT	20,812.00	LB		\$	
0410	08151		STEEL REINFORCEMENT-EPOXY COATED	84,752.00	LB		\$	
0420	23378EC		CONCRETE SEALING	15,995.00	SQFT		\$	
0430	23813EC		DECK DRAIN	5.00	EACH		\$	
0440	23963EC		PPC I-BEAM TYPE HN 36-49	953.40	LF		\$	
0450	24896ED		RAIL SYSTEM TYPE T631	484.40	LF		\$	

Section: 0004 - DEMOBILIZATION & MOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0460	02568		MOBILIZATION	1.00	LS		\$	
0470	02569		DEMOBILIZATION	1.00	LS		\$	