



**TRANSPORTATION CABINET**

Frankfort, Kentucky 40622  
www.transportation.ky.gov/

**Steven L. Beshear**  
Governor

**Michael W. Hancock, P.E.**  
Secretary

May 6, 2015

CALL NO. 100  
CONTRACT ID NO. 151222  
ADDENDUM # 2

Subject: Jefferson County, ER 8714 (012)  
Letting May 8, 2015

- (1) Revised - Notes - Pages 21-22 of 94
- (2) Revised - Special Notes - Pages 29-31 of 94
- (3) Revised - Bid Items - Pages 93-94 of 94

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Robert C. Lewis".

Robert C. Lewis, P.E.  
Acting Director  
Division of Construction Procurement

RL:ks  
Enclosures



An Equal Opportunity Employer M/F/D

GENERAL SUMMARY

PAVING SUMMARY

COURTY OF JEFFERSON  
ITEM NO. 371.12  
SHEET NO. 2

ITEM	DESCRIPTION	UNIT	KY 22	ITEM	UNIT	KY 22	ITEM CODE	TOTAL PROJECT
00069	CRUSHED AGGREGATE NO. 3	TON	3073					
02231	STRUCTURAL GRANULAR BACKFILL	CU.YD.	700					
02599	GEOTEXTILE FABRIC TYPE IV	SQ.YD.	596					
02091	REMOVE PAVEMENT	SQ.YD.	181					
02731	REMOVE STRUCTURE	LS	1					
08003	FOUNDATION PREP	LS	1					
21804EN	3-SIDED CULVERT	LF	60					
03171	CONCRETE BARRIER WALL TYPE B1	LF	200					
02381	REMOVE GUARDRAIL	LF	275					
06514	PAVE STRIPING-PERW PAINT - 4 IN	LF	1000					
02363	G/R CONNECTOR TO BRIDGE END TY A	EACH	4					
02364	GUARDRAIL TERMINAL SECTION NO. 2	EACH	4					
02545	CLEARING AND GRUBBING	LS	1					
08019	CYCLOPER STONE RIP RAP	EA	200					
02671	PORTABLE CHANGEABLE MESSAGE SIGNS	SF	192					
02662	TEMPORARY SIGNS	EA	12					
02614	TYPE III BARRICADES	EA	12					
02701	TEMPORARY SILT FENCE	LF	1000					
02703	SILT TRAP TYPE A	EACH	1					
02704	SILT TRAP TYPE B	EACH	1					
02705	SILT TRAP TYPE C	EACH	1					
02706	CLEAN SILT TRAP TYPE A	EACH	2					
02707	CLEAN SILT TRAP TYPE B	EACH	2					
02708	CLEAN SILT TRAP TYPE C	EACH	2					
02200	ROADWAY EXCAVATION	CU.YD.	2200					
02569	DEMOBILIZATION	LS	1					
24786EN	HDPE PIPE-12 INCH	LF	100					
20166ES810	TEMPORARY PIPE	LF	515					

ITEM CODE	ITEM	UNIT	KY 22	ITEM	UNIT	KY 22	TOTAL PROJECT
00214	CL3 ASPH BASE 1.00 D P664-22	TON	168				
Z906ES403	CL3 ASPH SURF 0.380 P664-22	TON	20				
00100	ASPHALT SEAL AGGREGATE	TON	2				
00103	ASPHALT SEAL COAT	TON	15				
00003	CRUSHED STONE BASE	TON	140				

PAVING AREAS

ITEM	UNIT	KY 22	S	Q	U	A	R	E	A	R	D	S
CL3 ASPH BASE 1.00 D P664-22	TON	288										
CL3 ASPH SURF 0.380 P664-22	TON	272										
ASPHALT SEAL AGGREGATE	TON	98										
ASPHALT SEAL COAT	TON	98										
CRUSHED STONE BASE	TON	311										

NOTES  
ALL ASPHALT MIXTURES SHALL BE ESTIMATED AT 110 LBS. PER SQ. YD. PER INCH OF DEPTH, UNLESS NOTED OTHERWISE.  
① ESTIMATED AT 115 LBS. PER SQ. YD. PER INCH OF DEPTH.  
② ESTIMATED AT 110 LBS. PER SQ. YD. PER INCH OF DEPTH.  
③ ESTIMATED AT 2.4 LBS. PER SQ. YD.  
④ ESTIMATED AT 20 LBS PER SQ. YD.  
⑤ CLEARING AND GRUBBING APPROXIMATELY 0.20 ACRES  
⑥ FOR USE IN GEOTEXTILE FABRIC WRAPPED BACKFILL  
⑦ ITEM IS FOR REMOVAL OF PAVEMENT OUTSIDE THE EXCAVATION LIMITS OF THE PROJECT. PAVEMENT SHALL BE REMOVED IN THE DIRECTION OF THE ENGINEER.  
⑧ ITEM IS FOR BANK AND SLOPE PROTECTION AT THE DESCRIPTION OF THE ENGINEER

GENERAL, & PAVING SUMMARY SHEET



## SPECIAL NOTES FOR UTILITY CLEARANCE IMPACT ON CONSTRUCTION

**JEFFERSON COUNTY, FD 52 056 671985**  
**STP 8714 010**  
**5-371.12**  
**KY 22 Culvert Replacement**

**GENERAL PROJECT NOTE ON UTILITY PROTECTION**

Prior to any work taking place the Contractor will notify the Engineer and Louisville Water Company 5 days in advance. Any damage to the water transmission line and any further damage caused by construction to adjacent facilities will be the responsibility of the Contractor. All other utilities identified below will not be disturbed. The Contractor is responsible for the immediate repair and replacement of any utility listed below as "DO NOT DISTURB".

**NOTE: DO NOT DISTURB THE FOLLOWING UTILITIES LOCATED WITHIN THE PROJECT DISTURB LIMITS**

LG&E (Electric) – has existing overhead lines running approximately 17 feet north of, and parallel to, KY 22 and to remain in place and are not to be disturbed.

LG&E (Gas) – has an existing 8" gas main which crosses Goose Creek at KY-22 Sta. 164+62 approximately 65 feet south of the roadway centerline, then turns at Sta. 165+00 approximately 60 from the centerline and runs perpendicular to the roadway for 45 feet. The gas main then runs under the shoulder approximately 15 feet from the centerline and parallel with the roadway for 81 feet to Sta. 165+81 before crossing KY 22 at Springcrest Drive and following the shoulder to the east.

Time Warner Cable – has overhead lines running on LG&E poles approximately 17 feet north of, and parallel to, KY 22 and to remain in place and are not to be disturbed.

**\*The Contractor is fully responsible for protection of all utilities listed above\***

**THE FOLLOWING COMPANIES ARE RELOCATING/ADJUSTING THEIR UTILITIES WITHIN THE PROJECT LIMITS AND WILL BE COMPLETE PRIOR TO CONSTRUCTION**

N/A

**THE FOLLOWING COMPANIES HAVE FACILITIES TO BE RELOCATED/ADJUSTED BY THE COMPANY OR THE COMPANY'S SUBCONTRACTOR AND IS TO BE COORDINATED WITH THE ROAD CONTRACT**

AT&T – has an existing overhead line running approximately 20 feet south of, and parallel to, KY 22. An AT&T pole located in the immediate vicinity of the culvert collapse is to be relocated during construction and is to be coordinated with the roadway Contractor. **This work is anticipated to be completed by June 26, 2015.**

**(NOTE: Use the following Text Only If Applicable)**The Department will consider submission of a bid as the Contractor's agreement to not make any claims for additional compensation due to delays or other

## **SPECIAL NOTES FOR UTILITY CLEARANCE**

### **IMPACT ON CONSTRUCTION**

**JEFFERSON COUNTY, FD 52 056 671985**  
**STP 8714 010**  
**5-371.12**  
**KY 22 Culvert Replacement**

conditions created by the operations of (Utility Company(s) Name). Working days will not be charged for those days on which work on (Utility Company(s) Name) facilities is delayed, as provided in the current edition of the KY Standard Specifications for Road and Bridge Construction. Should a difference of opinion arise as to the rights of the Contractor and others working within the limits of, or adjacent to the project, the KYTC Resident Engineer will decide as to the respective rights of the various parties involved in order to assure the completion of the Department's work in general harmony and in a satisfactory manner, and his decision shall be final and binding upon the Contractor. .

**THE FOLLOWING COMPANIES HAVE FACILITIES TO BE RELOCATED/ADJUSTED BY THE ROAD CONTRACTOR AS INCLUDED IN THIS CONTRACT**

Louisville Water Company – has an existing 12-in HDPE that runs under the KY 22 south edge of pavement. A temporary water line will tie into the HDPE main near the MSD pump station west of the project, and near the residential entrance approximately 150 feet east of the proposed culvert. The temporary line will be laid down the embankment south of KY-22, then crossing Goose Creek before running back up the embankment and tying into the HDPE water main.

Prior to any work taking place the Contractor will notify the Engineer and Louisville Water Company 5 days in advance. Any damage to the water transmission line and any further damage caused by construction to adjacent facilities will be the responsibility of the Contractor.

#### **SPECIAL CAUTION NOTE – PROTECTION OF UTILITIES**

The contractor will be responsible for contacting all utility facility owners on the subject project to coordinate his activities. The contractor will coordinate his activities to minimize and, where possible, avoid conflicts with utility facilities. Due to the nature of the work proposed, it is unlikely to conflict with the existing utilities beyond minor facility adjustments. Where conflicts with utility facilities are unavoidable, the contractor will coordinate any necessary relocation work with the facility owner and Resident Engineer. The Kentucky Transportation Cabinet maintains the right to remove or alter portions of this contract if a utility conflict occurs.

The utility facilities as noted in the previous section(s) have been determined using data garnered by varied means and with varying degrees of accuracy: from the facility owners, a result of S.U.E., field inspections, and/or reviews of record drawings. The facilities defined may not be inclusive of all utilities in the project scope and are not Level A quality, unless specified as such. It is the contractor's responsibility to verify all utilities and their respective locations before excavating.

**SPECIAL NOTES FOR UTILITY CLEARANCE**  
**IMPACT ON CONSTRUCTION**

**JEFFERSON COUNTY, FD 52 056 671985**  
**STP 8714 010**  
**5-371.12**  
**KY 22 Culvert Replacement**

**BEFORE YOU DIG**

The contractor is instructed to call 1-800-752-6007 to reach KY 811, the one-call system for information on the location of existing underground utilities. The call is to be placed a minimum of two (2) and no more than ten (10) business days prior to excavation. The contractor should be aware that owners of underground facilities are not required to be members of the KY 811 one-call Before-U-Dig (BUD) service. The contractor must coordinate excavation with the utility owners, including those whom do not subscribe to KY 811. It may be necessary for the contractor to contact the County Court Clerk to determine what utility companies have facilities in the area.

*Please Note: The information presented in this Utility Note is informational in nature and the information contained herein is not guaranteed.*

**AREA UTILITIES CONTACT LIST**

- |   |  |
|---|--|
| <p><b>1.</b> LG&amp;E KU (Electric)<br/>820 West Broadway<br/>Louisville, KY 40202<br/><b>LG&amp;E Emergency Number (502) 589-1444</b><br/><b>LG&amp;E and KU Emergency Number 1-800-331-7370</b></p> | <p><b>Greg Geiser</b><br/><b>work: (502) 627-3708</b><br/><b><u>Greg.Geiser@LGE-KU.com</u></b></p> |
| <p><b>2.</b> Louisville Water Company<br/>550 South Third Street<br/>Louisville, KY 40202</p>   | <p><b>Daniel Tegene, PE</b><br/><b>(502) 569-3649</b><br/><b><u>DTegene@LWCky.com</u></b></p>      |
| <p><b>3.</b> AT&amp;T KY<br/>3719 Bardstown Road - 2nd Floor<br/>Louisville, KY 40218</p>   | <p><b>Morgan Herndon</b><br/><b><u>Morgan.Herndon@att.com</u></b><br/><b>(502) 458-7312</b></p>    |
| <p><b>4.</b> Time Warner Communications<br/>4701 Commerce Crossings Dr.<br/>Louisville, KY40229</p>   | <p><b>Deno Barbour</b><br/><b>Cell: (502) 664-7395</b><br/><b>Office(502) 357-4376</b></p>         |



**PROPOSAL BID ITEMS**

151222

Page 1 of 2

Report Date 5/6/15

**Section: 0001 - PAVING**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00003		CRUSHED STONE BASE	140.00	TON		\$	
0020	00100		ASPHALT SEAL AGGREGATE	2.00	TON		\$	
0030	00103		ASPHALT SEAL COAT	.15	TON		\$	
0040	00214		CL3 ASPH BASE 1.00D PG64-22 (REVISED: 5-6-15)	168.00	TON		\$	
0050	22906ES403		CL3 ASPH SURF 0.38A PG64-22 (REVISED: 5-6-15)	20.00	TON		\$	

**Section: 0002 - ROADWAY**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0060	00069		CRUSHED AGGREGATE SIZE NO 3	3,073.00	TON		\$	
0070	02014		BARRICADE-TYPE III	12.00	EACH		\$	
0080	02091		REMOVE PAVEMENT	181.00	SQYD		\$	
0090	02200		ROADWAY EXCAVATION	2,200.00	CUYD		\$	
0100	02363		GUARDRAIL CONNECTOR TO BRIDGE END TY A	4.00	EACH		\$	
0110	02364		GUARDRAIL TERMINAL SECTION NO 2	4.00	EACH		\$	
0120	02381		REMOVE GUARDRAIL	275.00	LF		\$	
0130	02545		CLEARING AND GRUBBING (APPROXIMATELY 0.20 ACRES)	1.00	LS		\$	
0140	02562		TEMPORARY SIGNS	192.00	SQFT		\$	
0150	02599		FABRIC-GEOTEXTILE TYPE IV	6,916.00	SQYD		\$	
0160	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0170	02671		PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH		\$	
0180	02731		REMOVE STRUCTURE	1.00	LS		\$	
0190	03171		CONCRETE BARRIER WALL TYPE 9T	200.00	LF		\$	
0200	06514		PAVE STRIPING-PERM PAINT-4 IN	1,000.00	LF		\$	
0210	08019		CYCLOPEAN STONE RIP RAP	200.00	TON		\$	
0211	20166ES810		TEMPORARY PIPE (ADDED: 5-6-15)	515.00	LF		\$	
0220	24786EN		HDPE PIPE (12 INCH)	100.00	LF		\$	

**Section: 0003 - DRAINAGE**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0230	02701		TEMP SILT FENCE	1,000.00	LF		\$	
0240	02703		SILT TRAP TYPE A	1.00	EACH		\$	
0250	02704		SILT TRAP TYPE B	1.00	EACH		\$	
0260	02705		SILT TRAP TYPE C	1.00	EACH		\$	
0270	02706		CLEAN SILT TRAP TYPE A	2.00	EACH		\$	
0280	02707		CLEAN SILT TRAP TYPE B	2.00	EACH		\$	
0290	02708		CLEAN SILT TRAP TYPE C	2.00	EACH		\$	

**PROPOSAL BID ITEMS**

151222

Page 2 of 2

Report Date 5/6/15

**Section: 0004 - BRIDGE**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0300	02231		STRUCTURE GRANULAR BACKFILL	700.00	CUYD		\$	
0310	08003		FOUNDATION PREPARATION	1.00	LS		\$	
0320	21804EN		3-SIDED CULVERT	60.00	LF		\$	

**Section: 0005 - DEMOBILIZATION &/OR MOBILIZATION**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0330	02569		DEMOBILIZATION	1.00	LS		\$	