

**US 150 Washington County
Fredericktown Road to Mayfield Lane
April 9 & April 23, 2019**

	Alternative #1	Alternative #2
Length (ft.)	11,976	11,968
Maximum Grade %	3.91%	3.91%
Earthwork	\$10/CY	\$10/CY
Cut (cu yd.)	173,801	119,937
Fill (cu yd.)	24,783	25,576
Net (cu yd.)	149,018	94,360
Disturb Limits (acres)	31.34	31.11
Blueline Stream Crossings	3	3
Impact to Parker Run (LF)	0	0
Crop Land Impacts	LOW	LOW
Number of Parcels	23	23
Right of Way Acquisition (AC)	9.64	9.55
Easements (SF)	0	0
Residential Takings	0	0
Garage/Barns Takings	0	0
Maintenance of Traffic Impacts	HIGH	HIGH
Utility Impacts	MODERATE	MODERATE
Costs		
Right of Way	\$350,000	\$350,000
Utilities	\$1,000,000	\$1,000,000
Construction	\$8,340,000	\$7,810,000
Contingency 25%	\$2,090,000	\$1,960,000
Total	\$11,780,000	\$11,120,000