

## KY 418 FAYETTE COUNTY 7-9012.51 EARTHWORK

1 of 3

STATION	AREA Common SQ FT	Distance	VOLUME Common CU YD	SHEET TOTALS CU YD	STATION	AREA Embankment SQ FT	Distance	VOLUME Embankment CU YD	SHEET TOTALS CU YD
10241	49.1				10241				
10250	49.1	9	16		10250				
10300	49.1	50	91		10300				
10350	49.1	50	91		10350				
10400	49.1	50	91		10400				
10450	49.1	50	91		10450				
10500	49.1	50	91		10500				
10550	49.1	50	91		10550				
10600	49.1	50	90		10600		50	0	
10650	48.2	50	132		10650		50	5	
10700	93.9	50	167		10700	5.8	50	15	
10750	86.2	50	127		10750	10.8	50	14	
10800	51.4	50	95		10800	3.9	50	5	
10850	51.0	50	95		10850	1.3	50	2	
10900	51.6	50	96		10900	0.6	50	1	
10950	51.7	50	92		10950	0.3	50	2	
11000	47.5	50	89		11000	2.2	50	3	
11050	49.0	50	68		11050	1.0	50	1	
11100	24.5	50	46		11100		50	0	
11150	25.5	50	141		11150		50	13	
11200	126.6				11200	14.4			

## KY 418 FAYETTE COUNTY 7-9012.51 EARTHWORK

STATION	AREA Common SQ FT	Distance	VOLUME Common CU YD	SHEET TOTALS CU YD	STATION	AREA Embankment SQ FT	Distance	VOLUME Embankment CU YD	SHEET TOTALS CU YD
		50	160				50	28	
<b>11250</b>	46.6				<b>11250</b>	16.2			
		50	100				50	28	
<b>11300</b>	61.2				<b>11300</b>	14.1			
		50	111				50	26	
<b>11350</b>	58.4				<b>11350</b>	14.2			
		50	106				50	25	
<b>11400</b>	56.4				<b>11400</b>	13.2			
		50	517				50	25	
<b>11450</b>	502.0				<b>11450</b>	13.5			
		50	509				50	27	
<b>11500</b>	47.7				<b>11500</b>	15.9			
		50	84				50	27	
<b>11550</b>	42.9				<b>11550</b>	13.2			
		50	82				50	28	
<b>11600</b>	45.7				<b>11600</b>	16.6			
		50	96				50	31	
<b>11650</b>	57.8				<b>11650</b>	16.6			
		50	151				50	29	
<b>11700</b>	104.8				<b>11700</b>	14.4			
		50	268				50	23	
<b>11750</b>	184.7				<b>11750</b>	10.5			
		50	377				50	24	
<b>11800</b>	222.0				<b>11800</b>	15.8			
		50	382				50	33	
<b>11850</b>	190.9				<b>11850</b>	19.8			
		50	207				50	109	
<b>11900</b>	32.6				<b>11900</b>	97.6			
		50	51				50	95	
<b>11950</b>	22.9				<b>11950</b>	4.8			
		50	41				50	12	
<b>12000</b>	21.4				<b>12000</b>	8.2			
		50	45				50	11	
<b>12050</b>	27.5				<b>12050</b>	4.1			
		50	49				50	4	
<b>12100</b>	25.5				<b>12100</b>				
		50	49				50	0	
<b>12150</b>	27.4				<b>12150</b>				
		50	25				50	0	
<b>12200</b>					<b>12200</b>				
		50	29				50	2	
<b>12250</b>	31.1				<b>12250</b>	2.7			
		50	56				50	3	

## KY 418 FAYETTE COUNTY 7-9012.51 EARTHWORK

STATION	AREA Common SQ FT	Distance	VOLUME Common CU YD	SHEET TOTALS CU YD	STATION	AREA Embankment SQ FT	Distance	VOLUME Embankment CU YD	SHEET TOTALS CU YD
12300	29.8				12300	0.7			
		50	55				50	2	
12350	30.1				12350	1.1			
		50	52				50	6	
12400	26.0				12400	5.6			
		50	48				50	13	
12450	25.5				12450	8.9			
		50	47				50	15	
12500	25.2				12500	6.9			
		50	46				50	9	
12550	24.4				12550	3.0			
		50	47				50	3	
12600	26.2				12600				
		50	47				50	0	
12650	24.4				12650				
		50	46				50	0	
12700	24.8				12700				699
		50	46						
12750	24.6								
		50	45						
12800	23.8								
		50	43						
12850	23.0								
		50	21						
12900									
		50	0						
12950				5929					
		<b>PROJECT TOTALS</b>		<b>5929</b>					<b>699</b>