



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

November 14, 2025

CALL NO. 100
CONTRACT ID NO. 251122
ADDENDUM # 1 REVISED

Subject: Bullitt County, FD06 015 0245 004-007
Letting November 20, 2025

- (1) Revised - Proposal Bid Items - Pages 161-166 of 166
 - Removed Line Item 1890 - 14089 W TAPPING SLEEVE AND VALVE SIZE 1
- (2) Revised Plan Sheet U02

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

251122

PROPOSAL BID ITEMS

Report Date 11/14/25

Page 1 of 6

251122

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00003		CRUSHED STONE BASE	59,485.00	TON		\$	
0020	00013		LIME STABILIZED ROADBED	100,178.00	SQYD		\$	
0030	00014		LIME	1,828.00	TON		\$	
0040	00020		TRAFFIC BOUND BASE	500.00	TON		\$	
0050	00100		ASPHALT SEAL AGGREGATE	173.00	TON		\$	
0060	00103		ASPHALT SEAL COAT	20.00	TON		\$	
0070	00212		CL2 ASPH BASE 1.00D PG64-22	9,295.00	TON		\$	
0080	00214		CL3 ASPH BASE 1.00D PG64-22	24,819.00	TON		\$	
0090	00301		CL2 ASPH SURF 0.38D PG64-22	2,554.00	TON		\$	
0100	00356		ASPHALT MATERIAL FOR TACK	80.40	TON		\$	
0110	00358		ASPHALT CURING SEAL	100.00	TON		\$	
0120	02071		JPC PAVEMENT-11 IN	1,171.00	SQYD		\$	
0130	02084		JPC PAVEMENT-8 IN	319.00	SQYD		\$	
0140	02091		REMOVE PAVEMENT	42,036.00	SQYD		\$	
0150	02585		EDGE KEY	234.60	LF		\$	
0160	02702		SAND FOR BLOTTER	250.00	TON		\$	
0170	20071EC		JOINT ADHESIVE	56,250.00	LF		\$	
0180	22906ES403		CL3 ASPH SURF 0.38A PG64-22	5,682.00	TON		\$	
0190	24891EC		PAVE MOUNT INFRARED TEMP EQUIPMENT	619,839.00	SF		\$	

Section: 0002 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0200	00078		CRUSHED AGGREGATE SIZE NO 2	6,670.00	TON		\$	
0210	00078		CRUSHED AGGREGATE SIZE NO 2 FOR PERFORATED PIPE HEADWALLS	4.00	TON		\$	
0220	01001		PERFORATED PIPE-6 IN	243.00	LF		\$	
0230	01011		NON-PERFORATED PIPE-6 IN	48.00	LF		\$	
0240	01021		PERF PIPE HEADWALL TY 1-6 IN	1.00	EACH		\$	
0250	01025		PERF PIPE HEADWALL TY 2-6 IN	1.00	EACH		\$	
0260	01029		PERF PIPE HEADWALL TY 3-6 IN	2.00	EACH		\$	
0270	01825		ISLAND CURB AND GUTTER	11,959.70	LF		\$	
0280	01845		ISLAND INTEGRAL CURB	199.00	LF		\$	
0290	01982		DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL WHITE	62.00	EACH		\$	
0300	02014		BARRICADE-TYPE III	20.00	EACH		\$	
0310	02015		CEMENT CONCRETE ISLAND	6,797.00	SQYD		\$	
0320	02157		PAVED DITCH TYPE 1	52.00	SQYD		\$	
0330	02159		TEMP DITCH	10,000.00	LF		\$	
0340	02160		CLEAN TEMP DITCH	5,000.00	LF		\$	
0350	02203		STRUCTURE EXCAV-UNCLASSIFIED	651.00	CUYD		\$	
0360	02230		EMBANKMENT IN PLACE	126,385.00	CUYD		\$	
0370	02242		WATER	100.00	MGAL		\$	
0380	02275		FENCE-8 FT CHAIN LINK	2,309.00	LF		\$	

251122

PROPOSAL BID ITEMS

Page 2 of 6

Report Date 11/14/25

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0390	02281		PEDESTRIAN GATE-CHAIN LINK	2.00	EACH		\$	
0400	02287		DOUBLE VEHICULAR CHAIN LINK GATE	1.00	EACH		\$	
0410	02360		GUARDRAIL TERMINAL SECTION NO 1	4.00	EACH		\$	
0420	02367		GUARDRAIL END TREATMENT TYPE 1	6.00	EACH		\$	
0430	02370		GUARDRAIL END TREATMENT TYPE 2M	4.00	EACH		\$	
0440	02381		REMOVE GUARDRAIL	3,355.00	LF		\$	
0450	02397		TEMP GUARDRAIL	500.00	LF		\$	
0460	02429		RIGHT-OF-WAY MONUMENT TYPE 1	25.00	EACH		\$	
0470	02432		WITNESS POST	25.00	EACH		\$	
0480	02471		FILL AND CAP SINKHOLE	2.00	EACH		\$	
0490	02545		CLEARING AND GRUBBING 57.5 ACRES	1.00	LS		\$	
0500	02555		CONCRETE-CLASS B	308.50	CUYD		\$	
0510	02562		TEMPORARY SIGNS	700.00	SQFT		\$	
0520	02602		FABRIC-GEOTEXTILE CLASS 1	18,450.00	SQYD		\$	
0530	02611		HANDRAIL-TYPE A-1	328.00	LF		\$	
0540	02650		MAINTAIN & CONTROL TRAFFIC DIVERSIONS (BY-PASS DETOURS) NO. 1	1.00	LS		\$	
0550	02651		DIVERSIONS (BY-PASS DETOURS) NO. 2	1.00	LS		\$	
0560	02651		DIVERSIONS (BY-PASS DETOURS) NO. 3	1.00	LS		\$	
0570	02651		DIVERSIONS (BY-PASS DETOURS) NO. 4	1.00	LS		\$	
0580	02651		DIVERSIONS (BY-PASS DETOURS) NO. 5	1.00	LS		\$	
0590	02651		TRUCK MOUNTED ATTENUATOR	1.00	EACH		\$	
0600	02654		PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH		\$	
0610	02671		EDGE LINE RUMBLE STRIPS (REVISED 11-14-25)	18,923.00	LF		\$	
0620	02697		TEMP SILT FENCE	10,000.00	LF		\$	
0630	02701		SILT TRAP TYPE A	65.00	EACH		\$	
0640	02703		SILT TRAP TYPE B	65.00	EACH		\$	
0650	02704		SILT TRAP TYPE C	65.00	EACH		\$	
0660	02705		CLEAN SILT TRAP TYPE A	65.00	EACH		\$	
0670	02706		CLEAN SILT TRAP TYPE B	65.00	EACH		\$	
0680	02707		CLEAN SILT TRAP TYPE C	65.00	EACH		\$	
0690	02708		STAKING	1.00	LS		\$	
0700	02726		REMOVE LIGHTING	1.00	LS		\$	
0710	04940		EROSION CONTROL BLANKET	8,808.00	SQYD		\$	
0720	05950		TEMP MULCH	208,188.00	SQYD		\$	
0730	05952		TEMP SEEDING AND PROTECTION	155,364.00	SQYD		\$	
0740	05953		INITIAL FERTILIZER	11.00	TON		\$	
0750	05963		MAINTENANCE FERTILIZER	7.00	TON		\$	
0760	05964		SEEDING AND PROTECTION	193,600.00	SQYD		\$	
0770	05985		SODDING	627.00	SQYD		\$	
0780	05990		AGRICULTURAL LIMESTONE	110.00	TON		\$	
0790	05992		PAVE STRIPING-TEMP PAINT-6 IN	95,382.00	LF		\$	
0800	06511		PAVE STRIPING-THERMO-6 IN W	28,823.00	LF		\$	
0810	06542		PAVE STRIPING-THERMO-6 IN Y	19,731.00	LF		\$	
0820	06543							

251122

PROPOSAL BID ITEMS

Page 3 of 6

Report Date 11/14/25

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0830	06546		PAVE STRIPING-THERMO-12 IN W	1,131.00	LF		\$	
0840	06547		PAVE STRIPING-THERMO-12 IN Y	348.00	LF		\$	
0850	06549		PAVE STRIPING-TEMP REM TAPE-B	5,000.00	LF		\$	
0860	06550		PAVE STRIPING-TEMP REM TAPE-W	5,000.00	LF		\$	
0870	06551		PAVE STRIPING-TEMP REM TAPE-Y	5,000.00	LF		\$	
0880	06568		PAVE MARKING-THERMO STOP BAR-24IN	80.00	LF		\$	
0890	06569		PAVE MARKING-THERMO CROSS-HATCH	524.00	SQFT		\$	
0900	06574		PAVE MARKING-THERMO CURV ARROW	64.00	EACH		\$	
0910	06576		PAVE MARKING-THERMO ONLY	3.00	EACH		\$	
0920	06588		PAVEMENT MARKER TY IVA-BY TEMP	1,013.00	EACH		\$	
0930	06610		INLAID PAVEMENT MARKER-MW	340.00	EACH		\$	
0940	06611		INLAID PAVEMENT MARKER-MY	160.00	EACH		\$	
0950	06612		INLAID PAVEMENT MARKER-BY	125.00	EACH		\$	
0960	06614		INLAID PAVEMENT MARKER-B Y/R	4.00	EACH		\$	
0970	10020NS		FUEL ADJUSTMENT	118,671.00	DOLL	\$1.00	\$	\$118,671.00
0980	10030NS		ASPHALT ADJUSTMENT	165,572.00	DOLL	\$1.00	\$	\$165,572.00
0990	20191ED		OBJECT MARKER TY 3	4.00	EACH		\$	
1000	21417ES717		PAVE MARK THERMO CONE CAP-SOLID YELLOW	101.00	SQFT		\$	
1010	21802EN		G/R STEEL W BEAM-S FACE (7 FT POST)	3,050.00	LF		\$	
1020	22520EN		PAVE MARKING-THERMO YIELD BAR-36 IN	19.00	LF		\$	
1030	22664EN		WATER BLASTING EXISTING STRIPE	9,460.00	LF		\$	
1040	23274EN11F		TURF REINFORCEMENT MAT 1	7,979.00	SQYD		\$	
1050	23607EC		PAVE MARK THERMO-LANE REDUCTION ARROW	4.00	EACH		\$	
1060	23791EC		PAVE STRIPING-CHEVRON MARKINGS	302.00	SQFT		\$	
1070	24814EC		PIPELINE INSPECTION	755.00	LF		\$	
1080	24845EC		UTILITY COORDINATION	1.00	LS		\$	
1090	26153EC		PAVE MARK-THERMO POLYMER MOD COMBO ARROW	4.00	EACH		\$	
1100	26248EC		ELECTRONIC DELIVERY MGMT SYSTEM - AGG	1.00	LS		\$	

Section: 0003 - DRAINAGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1110	00439		ENTRANCE PIPE-12 IN	43.00	LF		\$	
1120	00440		ENTRANCE PIPE-15 IN	262.00	LF		\$	
1130	00441		ENTRANCE PIPE-18 IN	151.00	LF		\$	
1140	00443		ENTRANCE PIPE-24 IN	138.00	LF		\$	
1150	00461		CULVERT PIPE-15 IN	100.00	LF		\$	
1160	00462		CULVERT PIPE-18 IN	282.00	LF		\$	
1170	00464		CULVERT PIPE-24 IN	97.00	LF		\$	
1180	00466		CULVERT PIPE-30 IN	69.00	LF		\$	
1190	00473		CULVERT PIPE-66 IN	104.00	LF		\$	
1200	00521		STORM SEWER PIPE-15 IN	919.00	LF		\$	
1210	00522		STORM SEWER PIPE-18 IN	49.00	LF		\$	
1220	01202		PIPE CULVERT HEADWALL-15 IN	1.00	EACH		\$	
1230	01204		PIPE CULVERT HEADWALL-18 IN	1.00	EACH		\$	

Report Date 11/14/25

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1240	01222		PIPE CULVERT HEADWALL-66 IN	2.00	EACH		\$	
1250	01433		SLOPED BOX OUTLET TYPE 1-18 IN	3.00	EACH		\$	
1260	01434		SLOPED BOX OUTLET TYPE 1-24 IN	1.00	EACH		\$	
1270	01450		S & F BOX INLET-OUTLET-18 IN	2.00	EACH		\$	
1280	01451		S & F BOX INLET-OUTLET-24 IN	1.00	EACH		\$	
1290	01452		S & F BOX INLET-OUTLET-30 IN	3.00	EACH		\$	
1300	01456		CURB BOX INLET TYPE A	11.00	EACH		\$	
1310	01490		DROP BOX INLET TYPE 1	5.00	EACH		\$	
1320	01550		DROP BOX INLET TYPE 12A	6.00	LF		\$	
1330	01584		CAP DROP BOX INLET	2.00	EACH		\$	
1340	01644		JUNCTION BOX-30 IN	1.00	EACH		\$	
1350	02483		CHANNEL LINING CLASS II	8.00	TON		\$	
1360	02484		CHANNEL LINING CLASS III	126.00	TON		\$	
1370	02607		FABRIC-GEOTEXTILE CLASS 2 FOR PIPE	2,492.00	SQYD	\$2.00	\$	\$4,984.00
1380	21541NN		CORED HOLE DRAINAGE BOX CON- 18 IN	2.00	EACH		\$	
1390	23822EC		CORED HOLE DRAINAGE BOX CON-15 IN	2.00	EACH		\$	
1400	24252EC		JUNCTION BOX-66 IN	2.00	EACH		\$	

Section: 0004 - DWG NO 27525 - 12' X 6' RCBC EXTENSION - KY 245 STA. 38+46.71

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1410	02403		REMOVE CONCRETE MASONRY	25.90	CUYD		\$	
1420	08003		FOUNDATION PREPARATION	1.00	LS		\$	
1430	08100		CONCRETE-CLASS A	96.50	CUYD		\$	
1440	08150		STEEL REINFORCEMENT	14,606.00	LB		\$	

Section: 0005 - DWG NO 27526 - 6' X 5' RCBC EXTENSION - KY 245 STA. 89+79.29

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1450	02403		REMOVE CONCRETE MASONRY	38.70	CUYD		\$	
1460	08003		FOUNDATION PREPARATION	1.00	LS		\$	
1470	08100		CONCRETE-CLASS A	50.10	CUYD		\$	
1480	08150		STEEL REINFORCEMENT	5,719.00	LB		\$	

Section: 0006 - DWG NO 27527 - 14' X 14' RCBC - KY 245 STA. 112+17.00

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1490	08003		FOUNDATION PREPARATION	1.00	LS		\$	
1500	08100		CONCRETE-CLASS A	615.10	CUYD		\$	
1510	08150		STEEL REINFORCEMENT	108,608.00	LB		\$	

Section: 0007 - SIGNING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1520	06406		SBM ALUM SHEET SIGNS .080 IN	361.00	SQFT		\$	

251122

PROPOSAL BID ITEMS

Page 5 of 6

Report Date 11/14/25

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1530	06407		SBM ALUM SHEET SIGNS .125 IN	118.00	SQFT		\$	
1540	06410		STEEL POST TYPE 1	780.00	LF		\$	
1550	06412		STEEL POST MILE MARKERS	4.00	EACH		\$	
1560	06490		CLASS A CONCRETE FOR SIGNS	0.23	CUYD		\$	
1570	20418ED		REMOVE & RELOCATE SIGNS	6.00	EACH		\$	
1580	21596ND		GMSS TYPE D	11.00	EACH		\$	
1590	24631EC		BARCODE SIGN INVENTORY	88.00	EACH		\$	

Section: 0008 - SIGNALIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1600	04844		CABLE-NO. 14/5C	185.00	LF		\$	
1610	04885		MESSENGER-10800 LB	275.00	LF		\$	
1620	04932		INSTALL STEEL STRAIN POLE	4.00	EACH		\$	
1630	23157EN		TRAFFIC SIGNAL POLE BASE	17.00	CUYD		\$	
1640	24528ED		TETHER WIRE	275.00	LF		\$	
1650	24601EC		INSTALL -SOLAR SCHOOL FLASHER	2.00	EACH		\$	
1660	24955ED		REMOVE SIGNAL EQUIPMENT	1.00	EACH		\$	

Section: 0009 - LIGHTING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1670	04701		POLE 40 FT MTG HT	5.00	EACH		\$	
1680	04725		BRACKET 15 FT	5.00	EACH		\$	
1690	04740		POLE BASE	5.00	EACH		\$	
1700	04750		TRANSFORMER BASE	5.00	EACH		\$	
1710	04780		FUSED CONNECTOR KIT	16.00	EACH		\$	
1720	04820		TRENCHING AND BACKFILLING	950.00	LF		\$	
1730	04832		WIRE-NO. 12	900.00	LF		\$	
1740	04834		WIRE-NO. 6	3,825.00	LF		\$	
1750	04940		REMOVE LIGHTING	1.00	LS		\$	
1760	20391NS835		ELECTRICAL JUNCTION BOX TYPE A	2.00	EACH		\$	
1770	21543EN		BORE AND JACK CONDUIT	100.00	LF		\$	
1780	24589ED		LED LUMINAIRE	5.00	EACH		\$	
1790	24900EC		PVC CONDUIT-1 1/4 IN-SCHEDULE 80	950.00	LF		\$	
1800	24901EC		PVC CONDUIT-2 IN-SCHEDULE 80	100.00	LF		\$	

Section: 0010 - WATERLINE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1810	14009		W ENCASEMENT STEEL BORED RANGE 4	85.00	LF		\$	
1820	14019		W FIRE HYDRANT ASSEMBLY	1.00	EACH		\$	
1830	14021		W FIRE HYDRANT REMOVE	1.00	EACH		\$	
1840	14047		W PIPE DCTL IRON RSTRND JOINT 06 IN	150.00	LF		\$	

251122

PROPOSAL BID ITEMS

Page 6 of 6




Report Date 11/14/25

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1850	14066		W PIPE PVC SPECIAL -08 INCH RSTRND JOINT	1,520.00	LF		\$	
1860	14074		W PLUG EXISTING MAIN	3.00	EACH		\$	
1870	14077		W SERV PE/PLST LONG SIDE 1 IN	2.00	EACH		\$	
1880	14082		W SERV PE/PLST SHORT SIDE 1 IN	1.00	EACH		\$	
1900	14094		W TIE-IN 06 INCH	1.00	EACH		\$	
1910	14095		W TIE-IN 08 INCH	2.00	EACH		\$	
1920	14105		W VALVE 06 INCH	2.00	EACH		\$	
1930	14106		W VALVE 08 INCH	5.00	EACH		\$	












Section: 0011 - DEMOBILIZATION &/OR MOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1940	02568		MOBILIZATION	1.00	LS		\$	
1950	02569		DEMOBILIZATION	1.00	LS		\$	

SYMBOLGY

	EXISTING GATE VALVE (LWC STD. - OPENS CLOCKWISE)
	PROPOSED GATE VALVE (LWC STD. - OPENS CLOCKWISE)
	EXISTING BUTTERFLY VALVE (LWC STD. - OPENS CLOCKWISE)
	PROPOSED BUTTERFLY VALVE (LWC STD. - OPENS CLOCKWISE)
	GATE VALVE (AWWA STD. - CLOSSES CLOCKWISE)
	EZ VALVE
	BYPASS GATE VALVE OR LEAK DETECTION METER GATE VALVE WITH BYPASS ASSEMBLY
	CHECK VALVE
	PRESSURE REGULATING VALVE
	ALTITUDE VALVE
	SAMPLE STATION
	TAPPING SLEEVE AND GATE VALVE
	AIR VALVE, LABEL AS AUTOMATIC OR MANUAL
	PITOMETER W/ACCESS MANHOLE
	DRAIN ASSEMBLY
	FIRE HYDRANT
	FIRE / DOMESTIC SERVICE
	PRESSURE PLANE BOUNDARY VALVE
	REDUCER
	ABANDONED VALVE
	BEND (HORIZONTAL)
	BEND (VERTICAL)
	OFFSET (HORIZONTAL)
	OFFSET (VERTICAL)
	TEE (HORIZONTAL)
	TEE (VERTICAL)
	CROSS
	PLUG
	WYE
	OUTLET
	PRESSURE REDUCING STATION
	PUMP STATION



UTILITY LINE TYPES

	940 PRESSURE PLANE
	840 PRESSURE PLANE
	60" SEWER
	ELECTRIC
	OVERHEAD ELECTRIC
	UNDERGROUND ELECTRIC
	ELECTRIC GUY WIRE
	FIBER OPTIC
	SILT FENCE
	GAS
	OVERHEAD UTILITY
	SANITARY SEWER
	STORM SEWER
	FORCE MAIN SEWER
	COMBINED STORM & SANITARY SEWERS OR UNKNOWN SEWER TYPE
	CABLE TV
	EXISTING WATER
	PROPOSED WATER
	TRANSMISSION WATER MAIN
	TELEPHONE
	UNDERGROUND TELEPHONE
	OVERHEAD TELEPHONE


PIPE TYPES

AC	ASBESTOS CEMENT
CCL	CLEAN AND CEMENT LINED CAST IRON
CI	CAST IRON UNLINED
CL	CEMENT LINED CAST IRON
CLD	CEMENT LINED DELAUAUD CAST IRON
CONC	REINFORCED OR PRE-STRESSED CONCRETE
COP	COPPER
CPS	CATHODIC PROTECTED WITH SACRIFICIAL ANODES
DI	CEMENT LINED DUCTILE IRON
DIW	CEMENT LINED DUCTILE POLYWRAPPED
DPW	DUCTILE IRON PRESSURE WRAPPED
GAL	GALVANIZED STEEL
HDP	HDPE (HIGH DENSITY POLYETHYLENE)
PCP	PRE-STRESSED CONCRETE PIPE
PVC	POLYVINYL CHLORIDE
SCI	UNLINED SAND CAST IRON
UCI	UNDERSIGNATED CAST IRON
SWS	SPIRAL WELD STEEL

RESTORATION

	PAVEMENT RESTORATION AREA MILL & PAVE
	SIDEWALK RESTORATION AREA
	DRIVEWAY RESTORATION AREA

ROCK SOUNDINGS

	-NO ROCK @ 6.0'
	-ROCK @ X.X'
	NO ROCK
	ROCK

ITEM NUMBER	ITEM DESCRIPTION	UNITS	QUANTITY
14047	W PIPE DCTL IRON RSTRND JOINT 06 IN	LF	150
14066	W PIPE PVC SPECIAL (08 INCH RSTRND JOINT)	LF	1520
14105	W VALVE 06 INCH	EACH	2
14106	W VALVE 08 INCH	EACH	5
14094	W TIE-IN 06 INCH	EACH	1
14095	W TIE-IN 08 INCH	EACH	2
14009	W ENCASEMENT STEEL BORED RANGE 4	LF	85
14074	W PLUG EXISTING MAIN	EACH	3
14021	W FIRE HYDRANT REMOVE	EACH	1
14019	W FIRE HYDRANT ASSEMBLY	EACH	1
14082	W SERV PE/PLST SHORT SIDE 1 IN	EACH	1
14077	W SERV PE/PLST LONG SIDE 1 IN	EACH	2

** NOT ALL NOTES AND DESIGNATIONS ARE APPLICABLE **

GENERAL NOTES

- THESE DRAWINGS ARE FOR L.W.C. WORK ONLY – UTILITIES LOCATIONS ARE SHOWN FROM AVAILABLE INFORMATION AND ARE APPROXIMATE. CONTRACTORS ARE URGED TO MAKE THEIR OWN DETERMINATION OF EXACT LOCATIONS.
- THIS PROJECT HAS BEEN APPROVED IN ACCORDANCE WITH KDOV AGREED ORDER NO. DOW-WLO9001 OR IT HAS BEEN SUBMITTED TO KDOV FOR APPROVAL AND IS VALID FOR 2-YEARS FROM DATE OF THE DESIGNATED PLAN REVIEWER CERTIFICATION, DURING WHICH TIME PROJECT CONSTRUCTION SHALL BEGIN.
- BASE MAP INFORMATION DERIVED FROM PLANIMETRIC AND TOPOGRAPHIC DATA FROM LOUISVILLE/ JEFFERSON COUNTY INFORMATION CONSORTIUM. (LOJIC)
- JEFFERSON COUNTY PROPERTY DATA SHOWN ON THIS MAP WAS DIGITIZED FROM PVA BLOCK MAPS, ADJUSTED TO LOJIC PLANIMETRIC MAP DATA AND HAS BEEN UPDATED FROM PVA RECORDS. THE PROPERTY DATA DOES NOT SUPERSEDE DEED RECORDS AND SHOULD NOT BE USED FOR PURPOSES OTHER THAN GENERAL PROPERTY REFERENCE AND IDENTIFICATION.
- CONTRACTOR TO ABANDON ALL GATE VALVES ALONG EXISTING WATER MAIN THAT IS BEING ABANDONED. CONTRACTOR TO REMOVE OPERATOR NUT, KEYTUBE, ROUND TOP & LID AND BACKFILL WITH EITHER CONCRETE OR ASPHALT.
- MAINTAIN 18” VERTICAL CLEARANCE BETWEEN WATER MAIN AND DRAINAGE / SEWER LINES.
- CONTRACTOR WILL BE RESPONSIBLE TO BRACE OR PROTECT ANY UTILITY POLES IN ORDER TO COMPLETE CONSTRUCTION OF WATER MAIN AT ITS DESIGNED LOCATION AT THE CONTRACTORS EXPENSE. ALL NECESSARY WORK TO COMPLETE THIS TASK IN A SAFE MANNER SHALL BE INCLUDED IN THE CONTRACTORS ORIGINAL BID.
- ALL MATERIAL, EXCEPT METERS, SHALL BE SUPPLIED AND INSTALLED BY CONTRACTOR.
- RENEW ALL SERVICES, UNLESS OTHERWISE NOTED, ALONG ENTIRE PROJECT EXCEPT DOUBLE SETTERS OR SINGLE VAULTS IN DRIVEWAYS OR SIDEWALKS. ANY VAULT IN A DRIVEWAY OR SIDEWALK SHALL BE RELOCATED TO DIRT.
- RELOCATE ALL DOUBLE SETTERS WITH TWO NEW VAULTS. NO VAULTS SHALL BE INSTALLED IN DRIVEWAYS OR SIDEWALKS.
- NEW VAULTS SHALL FRONT THE PROPERTY IT SERVES WHICH MAY REQUIRE PRIVATE SERVICE LINE WORK. ALL PRIVATE SERVICE LINE WORK SHALL BE COMPLETED BY A LICENSED PLUMBER AS PART OF THIS BID.
- DRIVEWAY REPAIR:
 - ASPHALT – REPAVE FROM STREET TO EDGE OF EASEMENT.
 - CONCRETE – POUR FROM STREET TO 1st EXPANSION JOINT BEYOND TRENCH CUT.








For Buried Line/Cable Locations
** Contact Two Business Days Before **

LOUISVILLE WATER COMPANY
550 S. 3RD STREET • LOUISVILLE, KENTUCKY 40202 • (502) 569-3600
SPENCER W. BRUCE, PE – PRESIDENT
LARRY D. BRYANT, PE – VICE PRESIDENT/CHIEF ENGINEER









CLERMONT ROAD (KY. HIGHWAY #245)
WATER MAIN RELOCATION
LEGEND & GENERAL NOTES

DATE	09-23-25	SCALE	NONE	MAP NO.	NONE
DRAWN BY	E. SCHMIDT	CHECKED BY	P. HOWARD	ENGR.	M. MEYER
PROJECT NUMBER	17197	SHEET	1	OF	3
TASK NUMBER	04				

SYMBOLGY

	EXISTING GATE VALVE (LWC STD. - OPENS CLOCKWISE)
	PROPOSED GATE VALVE (LWC STD. - OPENS CLOCKWISE)
	EXISTING BUTTERFLY VALVE (LWC STD. - OPENS CLOCKWISE)
	PROPOSED BUTTERFLY VALVE (LWC STD. - OPENS CLOCKWISE)
	GATE VALVE (AWWA STD. - CLOSSES CLOCKWISE)
	EZ VALVE
	BYPASS GATE VALVE OR LEAK DETECTION METER GATE VALVE WITH BYPASS ASSEMBLY
	CHECK VALVE
	PRESSURE REGULATING VALVE
	ALTITUDE VALVE
	SAMPLE STATION
	TAPPING SLEEVE AND GATE VALVE
	AIR VALVE, LABEL AS AUTOMATIC OR MANUAL
	PITOMETER W/ACCESS MANHOLE
	DRAIN ASSEMBLY
	FIRE HYDRANT
	FIRE / DOMESTIC SERVICE
	PRESSURE PLANE BOUNDARY VALVE
	REDUCER
	ABANDONED VALVE
	BEND (HORIZONTAL)
	BEND (VERTICAL)
	OFFSET (HORIZONTAL)
	OFFSET (VERTICAL)
	TEE (HORIZONTAL)
	TEE (VERTICAL)
	CROSS
	PLUG
	WYE
	OUTLET
	PRESSURE REDUCING STATION
	PUMP STATION

UTILITY LINE TYPES

	940 PRESSURE PLANE
	840 PRESSURE PLANE
	60" SEWER
	ELECTRIC
	OVERHEAD ELECTRIC
	UNDERGROUND ELECTRIC
	ELECTRIC GUY WIRE
	FIBER OPTIC
	SILT FENCE
	GAS
	OVERHEAD UTILITY
	SANITARY SEWER
	STORM SEWER
	FORCE MAIN SEWER
	COMBINED STORM & SANITARY SEWERS OR UNKNOWN SEWER TYPE
	CABLE TV
	EXISTING WATER
	PROPOSED WATER
	TRANSMISSION WATER MAIN
	TELEPHONE
	UNDERGROUND TELEPHONE
	OVERHEAD TELEPHONE

PIPE TYPES

AC	ASBESTOS CEMENT
CCL	CLEAN AND CEMENT LINED CAST IRON
CI	CAST IRON UNLINED
CL	CEMENT LINED CAST IRON
CLD	CEMENT LINED DELAUAUD CAST IRON
CONC	REINFORCED OR PRE-STRESSED CONCRETE
COP	COPPER
CPS	CATHODIC PROTECTED WITH SACRIFICIAL ANODES
DI	CEMENT LINED DUCTILE IRON
DIW	CEMENT LINED DUCTILE POLYWRAPPED
DPW	DUCTILE IRON PRESSURE WRAPPED
GAL	GALVANIZED STEEL
HDP	HDPE (HIGH DENSITY POLYETHYLENE)
PCP	PRE-STRESSED CONCRETE PIPE
PVC	POLYVINYL CHLORIDE
SCI	UNLINED SAND CAST IRON
UCI	UNDERSIGNATED CAST IRON
SWS	SPIRAL WELD STEEL

RESTORATION

	PAVEMENT RESTORATION AREA MILL & PAVE
	SIDEWALK RESTORATION AREA
	DRIVEWAY RESTORATION AREA

ROCK SOUNDINGS

	-NO ROCK @ 6.0'
	-ROCK @ X.X'
	NO ROCK

Rock

ITEM NUMBER	ITEM DESCRIPTION	UNITS	QUANTITY
14047	W PIPE DCTL IRON RSTRND JOINT 06 IN	LF	150
14066	W PIPE PVC SPECIAL (08 INCH RSTRND JOINT)	LF	1520
14105	W VALVE 06 INCH	EACH	2
14106	W VALVE 08 INCH	EACH	5
14094	W TIE-IN 06 INCH	EACH	1
14095	W TIE-IN 08 INCH	EACH	2
14009	W ENCASEMENT STEEL BORED RANGE 4	LF	85
14074	W PLUG EXISTING MAIN	EACH	3
14021	W FIRE HYDRANT REMOVE	EACH	1
14019	W FIRE HYDRANT ASSEMBLY	EACH	1
14082	W SERV PE/PLST SHORT SIDE 1 IN	EACH	1
14077	W SERV PE/PLST LONG SIDE 1 IN	EACH	2

** NOT ALL NOTES AND DESIGNATIONS ARE APPLICABLE **

GENERAL NOTES

- THESE DRAWINGS ARE FOR L.W.C. WORK ONLY – UTILITIES LOCATIONS ARE SHOWN FROM AVAILABLE INFORMATION AND ARE APPROXIMATE. CONTRACTORS ARE URGED TO MAKE THEIR OWN DETERMINATION OF EXACT LOCATIONS.
- THIS PROJECT HAS BEEN APPROVED IN ACCORDANCE WITH KDOV AGREED ORDER NO. DOW-WLO9001 OR IT HAS BEEN SUBMITTED TO KDOV FOR APPROVAL AND IS VALID FOR 2-YEARS FROM DATE OF THE DESIGNATED PLAN REVIEWER CERTIFICATION, DURING WHICH TIME PROJECT CONSTRUCTION SHALL BEGIN.
- BASE MAP INFORMATION DERIVED FROM PLANIMETRIC AND TOPOGRAPHIC DATA FROM LOUISVILLE/ JEFFERSON COUNTY INFORMATION CONSORTIUM. (LOJIC)
- JEFFERSON COUNTY PROPERTY DATA SHOWN ON THIS MAP WAS DIGITIZED FROM PVA BLOCK MAPS, ADJUSTED TO LOJIC PLANIMETRIC MAP DATA AND HAS BEEN UPDATED FROM PVA RECORDS. THE PROPERTY DATA DOES NOT SUPERSEDE DEED RECORDS AND SHOULD NOT BE USED FOR PURPOSES OTHER THAN GENERAL PROPERTY REFERENCE AND IDENTIFICATION.
- CONTRACTOR TO ABANDON ALL GATE VALVES ALONG EXISTING WATER MAIN THAT IS BEING ABANDONED. CONTRACTOR TO REMOVE OPERATOR NUT, KEYTUBE, ROUND TOP & LID AND BACKFILL WITH EITHER CONCRETE OR ASPHALT.
- MAINTAIN 18” VERTICAL CLEARANCE BETWEEN WATER MAIN AND DRAINAGE / SEWER LINES.
- CONTRACTOR WILL BE RESPONSIBLE TO BRACE OR PROTECT ANY UTILITY POLES IN ORDER TO COMPLETE CONSTRUCTION OF WATER MAIN AT ITS DESIGNED LOCATION AT THE CONTRACTORS EXPENSE. ALL NECESSARY WORK TO COMPLETE THIS TASK IN A SAFE MANNER SHALL BE INCLUDED IN THE CONTRACTORS ORIGINAL BID.
- ALL MATERIAL, EXCEPT METERS, SHALL BE SUPPLIED AND INSTALLED BY CONTRACTOR.
- RENEW ALL SERVICES, UNLESS OTHERWISE NOTED, ALONG ENTIRE PROJECT EXCEPT DOUBLE SETTERS OR SINGLE VAULTS IN DRIVEWAYS OR SIDEWALKS. ANY VAULT IN A DRIVEWAY OR SIDEWALK SHALL BE RELOCATED TO DIRT.
- RELOCATE ALL DOUBLE SETTERS WITH TWO NEW VAULTS. NO VAULTS SHALL BE INSTALLED IN DRIVEWAYS OR SIDEWALKS.
- NEW VAULTS SHALL FRONT THE PROPERTY IT SERVES WHICH MAY REQUIRE PRIVATE SERVICE LINE WORK. ALL PRIVATE SERVICE LINE WORK SHALL BE COMPLETED BY A LICENSED PLUMBER AS PART OF THIS BID.
- DRIVEWAY REPAIR:
 - ASPHALT – REPAVE FROM STREET TO EDGE OF EASEMENT.
 - CONCRETE – POUR FROM STREET TO 1st EXPANSION JOINT BEYOND TRENCH CUT.

Item Number 14089 W TAPPING SLEEVE
AND VALVE SIZE 1 removed from Utility
Summary

For Buried Line/Cable Locations
** Contact Two Business Days Before **



LOUISVILLE WATER COMPANY
550 S. 3RD STREET • LOUISVILLE, KENTUCKY 40202 • (502) 569-3600
SPENCER W. BRUCE, PE – PRESIDENT
LARRY D. BRYANT, PE – VICE PRESIDENT/CHIEF ENGINEER

CLERMONT ROAD (KY. HIGHWAY #245)
WATER MAIN RELOCATION
LEGEND & GENERAL NOTES

DATE	09-23-25	SCALE	NONE	MAP NO.	NONE
DRAWN BY	E. SCHMIDT	CHECKED BY	P. HOWARD	ENGR.	M. MEYER
PROJECT NUMBER	17197	SHEET	1	OF	3
TASK NUMBER	04				