



**COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET**

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Matthew G. Bevin
Governor

Greg Thomas
Secretary

March 21, 2018

CALL NO. 100
CONTRACT ID NO. 181201
ADDENDUM # 2

Subject: FAYETTE COUNTY, NHPP 2681 (033)
Letting March 23, 2018

(1) Revised - Utility and Rail Certification - Pages 108-119 of 281

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures



An Equal Opportunity Employer M/F/D

UTILITIES AND RAIL CERTIFICATION NOTE

**Fayette County
ONHPP2681031
FD52 034 7664201U
Mile point: 8.731 TO 10.015
WIDEN NEW CIRCLE ROAD IN LEXINGTON FROM GEORGETOWN ROAD TO BOARDWALK AVENUE
INCLUDING INTERCHANGE RECONSTRUCTION AT NEWTOWN
PIKE.(2002BOPC)(2004BOPP)(10CCR)(12CCR)(14CCR)
ITEM NUMBER: 07-366.00**

PROJECT NOTES ON UTILITIES

Please Note: The information presented in this Utility Note is informational in nature and the information contained herein is not guaranteed.

The contractor will be responsible for contacting all utility facility owners on the subject project to coordinate his activities. The contractor will coordinate his activities to minimize and, where possible, avoid conflicts with utility facilities. Where conflicts with utility facilities are unavoidable, the contractor will coordinate any necessary relocation work with the facility owner and Resident Engineer. The Kentucky Transportation Cabinet maintains the right to remove or alter portions of this contract if a utility conflict occurs. The utility facilities as noted in the previous section(s) have been determined using data garnered by varied means and with varying degrees of accuracy: from the facility owners, a result of S.U.E., field inspections, and/or reviews of record drawings. The facilities defined may not be inclusive of all utilities in the project scope and are not Level A quality, unless specified as such. It is the contractor's responsibility to verify all utilities and their respective locations before excavating.

The contractor shall make every effort to protect underground facilities from damage as prescribed in the Underground Facility Damage Protection Act of 1994, Kentucky Revised Statute KRS 367.4901 to 367.4917. It is the contractor's responsibility to determine and take steps necessary to be in compliance with federal and state damage prevention directives. The contractor is instructed to contact KY 811 for the location of existing underground utilities. Contact shall be made a minimum of two (2) and no more than ten (10) business days prior to excavation. The contractor shall submit Excavation Locate Requests to the Kentucky Contact Center (KY 811) via web ticket entry. The submission of this request does not relieve the contractor from the responsibility of contacting non-member facility owners, whom are to be contacted through their individual Protection Notification Center. It may be necessary for the contractor to contact the County Court Clerk to determine what utility companies have facilities in the area. Non-compliance with these directives can result in the enforcement of penalties.

UTILITIES AND RAIL CERTIFICATION NOTE

Fayette County
0NHPP2681031
FD52 034 7664201U
Mile point: 8.731 TO 10.015
WIDEN NEW CIRCLE ROAD IN LEXINGTON FROM GEORGETOWN ROAD TO BOARDWALK AVENUE
INCLUDING INTERCHANGE RECONSTRUCTION AT NEWTOWN
PIKE.(2002BOPC)(2004BOPP)(10CCR)(12CCR)(14CCR)
ITEM NUMBER: 07-366.00

NOTE: DO NOT DISTURB THE FOLLOWING FACILITIES LOCATED WITHIN THE PROJECT DISTURB LIMITS

Columbia Gas of Kentucky – Gas Distribution

The company has yet to provide final relocation plans for their facilities; consequently, we are unable to identify all current, or proposed, locations of the company's facilities; however, the following locations are approximated within the roadway plans:

Beginning at Station 100+00, the company has a gas main located on the north side of New Circle Road. The gas main follows along New Circle Road, heading east, and enters the disturbance limits near Station 106+50. From there, the gas main continues to Station 124+00 then makes a quick turn south then east and crosses under the New Circle Road/Georgetown Road Ramp D. The gas main then continues travelling east on the north side of New Circle Road. Starting near Station 137+00, a second gas main begins running parallel to the aforementioned gas main. Farther down, near Station 138+50, a gas main approaches the south side of New Circle Road and turns east. There are now two gas mains on the north side of New Circle Road and one gas main on the south side. Near Station 141+00, the gas main located along the south side of New Circle Road turns north, crosses under New Circle Road, and meets near the other two gas mains. From this intersection, only two gas mains depart. One gas main goes north under New Circle Road/Georgetown Road Ramp C and continues along the and the other continues east along New Circle Road and crosses under New Circle Road/Georgetown Road Ramp C. The latter gas main continues east and splits near station 146+00. One gas main turns south and crosses under New Circle Road then turns east to follow along the south side of New Circle Road. The other gas main remains on the north side of New Circle Road, continues east, and crossed under New Circle Road/Newtown Pike Ramp B before turning north near Station 162+00 and turned east while crossing New Circle Road/Newtown Pike Loop B. The gas main then crosses under Newtown Pike and New Circle Road/Newtown Pike Ramp C near Station 172+00 and splits near Station 174+00. One gas main heads north and the other gas main continues east along New Circle Road. The gas main along the south side of New Circle Road keeps going east and crosses under both New Circle Road/Newtown Pike Ramp A, Loop D, and Ramp D near Stations 159+00, 168+00, and 174+00 then ends. The gas main on the north side of New Circle Road continues along east and crosses under Colesbury Circle near Station 203+00. Another gas main joins on the north side of New Circle Road at Colebury Circle as well. One of the gas main continues east until the end of construction near Station 211+00. The other gas main turn south and crosses under New Circle Road near

UTILITIES AND RAIL CERTIFICATION NOTE

Fayette County
ONHPP2681031
FD52 034 7664201U
Mile point: 8.731 TO 10.015
WIDEN NEW CIRCLE ROAD IN LEXINGTON FROM GEORGETOWN ROAD TO BOARDWALK AVENUE
INCLUDING INTERCHANGE RECONSTRUCTION AT NEWTOWN
PIKE.(2002BOPC)(2004BOPP)(10CCR)(12CCR)(14CCR)
ITEM NUMBER: 07-366.00

Station 204+50. This gas main then turns east and follows the south side of New Circle Road before turning south near Station 209+00.

Additionally, there are gas mains along and under Georgetown Road and Newtown Pike that may also cross loops and ramps near the New Circle Road intersections.

Kentucky American Water – Drinking Water Distribution

Beginning at Station 100+00, the company has a water line that follows along the south side of New Circle Road. The water line remains outside the disturbance limits until it splits and crosses under New Circle Road near Station 108+50. The water line crossing New Circle Road heads north, while the other water line continues east along the south side of New Circle Road and around New Circle Road/Georgetown Road Ramp A. The water line then crosses under Georgetown Road. In addition to this water line, two other water lines approach Finney Drive from Georgetown Road. Two of these waterlines intersect near Finney Drive, and from there, two water lines cross under Frontage Road and follow along the south side of Frontage Road. One water line then cross under New Circle Road/Georgetown Road Ramp B, New Circle Road, and New Circle Road/Georgetown Road Ramp C near Station 142+00 and heads northwest along New Circle Road/Georgetown Road Ramp C, before crossing under Georgetown Road and heading north. The other water line continues along and under Frontage Road. This water line continues on the south side of New Circle Road and then splits near Station 154+50. One line heads south and the other heads north under New Circle Road. After crossing, this water line heads east along the north side of New Circle Road, before travelling along the north side of New Circle Road/Newtown Pike Ramp B. This water line then crosses under Newtown Pike and exits the disturbance limits. Later, a different water line crosses New Circle Road near Station 183+00 and two water lines enter the disturbance limits near Station 193+00. The two water lines follow along the north side of New Circle Road. One of the water lines heads south and crosses under New Circle Road near Station 202+50.

Additionally, there are water lines along and under Georgetown Road and Newtown Pike that may also cross loops and ramps near the New Circle Road intersections.

UTILITIES AND RAIL CERTIFICATION NOTE

Fayette County
ONHPP2681031
FD52 034 7664201U
Mile point: 8.731 TO 10.015
WIDEN NEW CIRCLE ROAD IN LEXINGTON FROM GEORGETOWN ROAD TO BOARDWALK AVENUE
INCLUDING INTERCHANGE RECONSTRUCTION AT NEWTOWN
PIKE.(2002BOPC)(2004BOPP)(10CCR)(12CCR)(14CCR)
ITEM NUMBER: 07-366.00

Lexington Fayette Urban County Government – Sewer Collection

The company has facilities along Georgetown Road from Stations 104+00 to 108+00 and 115+00 to 118+00, with Georgetown Road crossings near Stations 104+50, 107+50, and 117+50. The company has facilities on both the north side of New Circle Road/Georgetown Road Ramp C and the south side of New Circle Road/Georgetown Road Ramp B. From there, the company has facilities along the north side of New Circle Road between Stations 144+00 and 152+00. The company has facilities crossing New Circle Road near Station 158+50. Lastly, the company has numerous facilities along the north and south side of New Circle Road from Stations 196+00 to 211+00, with a crossing under Boardwalk.

Kentucky Utilities Company - Electric Distribution

The company has electric distribution facilities along both the north and south sides of New Circle Road throughout the project and along Georgetown Road, Newtown Pike, and Boardwalk as well. There are many roadway crossings throughout the project, especially near the intersections of Georgetown Road, Newtown Pike, and Boardwalk. Additionally, there are numerous service lines and a substation near Station 139+00.

Kentucky Utilities Company - Electric Transmission

The company has two electric transmission lines along New Circle Road. One is a 138 kV line and the other is a 69 kV line. The 138kV line begins on the north side of New Circle Road and crosses diagonally near Station 102+00. The 138 kV line then runs along the south side of New Circle Road from Stations 103+00 to 122+50, before crossing New Circle Road diagonally near Station 124+00. The 138kV line then follows along the north side of New Circle Road through the end of the project near Station 211+00. The 69 kV line is attached to the 138 kV line from Stations 100+00 to 122+50. While the 138 kV line crosses New Circle Road near Station 124+00, the 69 kV line separates and continues along the south side of New Circle Road through Station 158+00, before turning southeast. The 69kV line then crosses Newtown Pike and leaves the project area.

UTILITIES AND RAIL CERTIFICATION NOTE

Fayette County
ONHPP2681031
FD52 034 7664201U
Mile point: 8.731 TO 10.015
WIDEN NEW CIRCLE ROAD IN LEXINGTON FROM GEORGETOWN ROAD TO BOARDWALK AVENUE
INCLUDING INTERCHANGE RECONSTRUCTION AT NEWTOWN
PIKE.(2002BOPC)(2004BOPP)(10CCR)(12CCR)(14CCR)
ITEM NUMBER: 07-366.00

AT&T KY – Phone, Communication

Beginning at Station 172+50, the company has aerial fiber cable attached to Kentucky Utilities' facilities that cross New Circle Road/Newtown Pike Ramp D and New Circle Road diagonally. The company then has aerial fiber cables which travel along the north side of New Circle Road from Stations 175+00 to 205+00 which then turn south and cross New Circle Road near Station 205+00. The company also has buried fiber cables along the north side of New Circle Road from Stations 182+75 to 186+75 and along the south side of New Circle Road from Stations 203+00 to 205+00.

Beginning at Station 100+00 and ending at near Station 123+00, the company has aerial fiber cable attached to Kentucky Utilities' facilities along the west side of Georgetown Road. Additionally, the company has buried fiber cable along the west side of Georgetown Road from Stations 100+00 to 103+00.

Windstream - Communication

The company has yet to provide a proposed relocation plan for their facilities; consequently, we are unable to identify the current, or proposed, location of the company's facilities. It is anticipated that the company may have facilities located along New Circle Road, Georgetown Road, Newtown Pike, and Boardwalk. It is also possible that the company will have facilities located at other locations throughout the project.

KDL Windstream - Communication

The company has yet to provide a proposed relocation plan for their facilities; consequently, we are unable to identify the current, or proposed, location of the company's facilities. It is anticipated that the company may have facilities located along New Circle Road, Georgetown Road, Newtown Pike, and Boardwalk. It is also possible that the company will have facilities located at other locations throughout the project.

Spectrum – CATV, Communication

The company has yet to provide a proposed relocation plan for their facilities; consequently, we are unable to identify the current, or proposed, location of the company's facilities. It is anticipated that the company may have facilities located along New Circle Road, Georgetown Road,

UTILITIES AND RAIL CERTIFICATION NOTE

Fayette County
ONHPP2681031
FD52 034 7664201U
Mile point: 8.731 TO 10.015
WIDEN NEW CIRCLE ROAD IN LEXINGTON FROM GEORGETOWN ROAD TO BOARDWALK AVENUE
INCLUDING INTERCHANGE RECONSTRUCTION AT NEWTOWN
PIKE.(2002BOPC)(2004BOPP)(10CCR)(12CCR)(14CCR)
ITEM NUMBER: 07-366.00

Newtown Pike, and Boardwalk. It is also possible that the company will have facilities located at other locations throughout the project.

THE FOLLOWING FACILITY OWNERS ARE RELOCATING/ADJUSTING THEIR FACILITIES WITHIN THE PROJECT LIMITS AND WILL BE COMPLETE PRIOR TO CONSTRUCTION

Not Applicable

THE FOLLOWING FACILITY OWNERS HAVE FACILITIES TO BE RELOCATED/ADJUSTED BY THE OWNER OR THEIR SUBCONTRACTOR AND IS TO BE COORDINATED WITH THE ROAD CONTRACT

Columbia Gas of Kentucky – Gas Distribution

Though the company has worked closely with KYTC District 7 and provided preliminary relocation plans, the company has yet to provide a final proposed relocation plan for their facilities; consequently, we are unable to identify all current, or proposed, locations of the company's facilities. It is anticipated that the company may have facilities located along New Circle Road, Georgetown Road, Newtown Pike, and Boardwalk. It is also possible that the company will have facilities located at other locations throughout the project.

The company is estimated to submit relocations plans and execute an agreement with KYTC by April 15, 2018. The company is then estimated to begin relocation work on July 1, 2018 with an estimated completion date of January 1, 2020. The company plans to relocate the utilities in three phases. Phase 1 will focus on relocating the infrastructure around the Newtown Pike / New Circle interchange. It is estimated that Phase 1 will be complete by November 30, 2018. Phase 2 will focus on relocating the infrastructure from the Newtown Pike / New Circle interchange to Boardwalk. It is estimated that Phase 2 will be complete by April 1, 2019.

Kentucky American Water – Drinking Water Distribution

The company will relocate the water line crossing New Circle Road near Station 142+00 to approximate Station 142+75. The company will also relocate water line on the north side of Ramp C and south side of Ramp B.

UTILITIES AND RAIL CERTIFICATION NOTE

Fayette County
ONHPP2681031
FD52 034 7664201U
Mile point: 8.731 TO 10.015
WIDEN NEW CIRCLE ROAD IN LEXINGTON FROM GEORGETOWN ROAD TO BOARDWALK AVENUE
INCLUDING INTERCHANGE RECONSTRUCTION AT NEWTOWN
PIKE.(2002BOPC)(2004BOPP)(10CCR)(12CCR)(14CCR)
ITEM NUMBER: 07-366.00

The company will relocate the water line on the south side of New Circle Road from Stations 143+00 to 155+00.

The company will relocate the water line on the north side of New Circle Road from Stations 196+00 to 203+00. This includes the relocation of a meter vault near Station 196+00. The company also has a small water line relocation segment on the south side of New Circle Road near Station 203+00.

The company has some small water line relocation segments along Georgetown Road near Stations 104+00, 106+00, 120+00, and 122+00. The company will also relocate water line on the east side of Georgetown Road from Stations 115+00 to 119+00. This include a crossing under Georgetown Road near Station 117+50.

The company is estimated to begin relocation work on April 1, 2018 with an estimated completion date of October 1, 2018.

Kentucky Utilities Company - Electric Distribution

The company will install fours new poles from Stations 134+00 to 139+00 along the south side of New Circle Road. This will relocate the electric lines crossing New Circle Road near Station 134+50 to approximate Station 134+25. It will also adjust the electric line clearance over Georgetown Road.

The company will install three poles from Stations 139+00 to 145+00 along the south side of New Circle Road. This will allow the electric line to cross over Ramp B rather than pass through Ramp B.

The company will install three poles from Stations 145+00 to 151+00, two along the south side of New Circle Road and one along the north side. This will shift the electric lines on the south side of New Circle Road approximately fifty feet further south and the New Circle Road crossing near Station 149+00 to approximate Station 149+25.

The company will install three poles from Stations 151+00 to 158+00, along the south side of New Circle Road. This will shift the electric lines on the south side of New Circle Road further south.

UTILITIES AND RAIL CERTIFICATION NOTE

Fayette County
ONHPP2681031
FD52 034 7664201U
Mile point: 8.731 TO 10.015
WIDEN NEW CIRCLE ROAD IN LEXINGTON FROM GEORGETOWN ROAD TO BOARDWALK AVENUE
INCLUDING INTERCHANGE RECONSTRUCTION AT NEWTOWN
PIKE.(2002BOPC)(2004BOPP)(10CCR)(12CCR)(14CCR)
ITEM NUMBER: 07-366.00

The company will install one pole on the north side of New Circle Road near Station 174+25. This will adjust a pole outside of the disturbance limits. The company will also install one pole on each side of New Circle Road near Stations 194+50 and 196+00.

The company will install two poles along the west side of Georgetown Road from Stations 107+00 to 110+00. This will shift the electric lines further west. The company will also install three poles along Georgetown Road from Stations 113+00 to 118+00.

The company is estimated to begin relocation work on January 1, 2019 with an estimated completion date of March 1, 2019.

Kentucky Utilities Company - Electric Transmission

The company is relocating portions of both their 138kV line and 69 kV line.

The 138 kV line's relocation begins near Station 143+00 and ends near Station 202+00. This segment of the 138 kV line follows along the north side of New Circle Road. To complete the relocation, the company is relocating poles near Stations 146+50, 150+00, 153+25, 158+25, 163+25, 167+75, 172+25, 175+75, 180+00, 184+50, 189+00, 192+75, 196+50, 199+75, and 202+25. An additional pole will be relocated along the Lexmark Overpass, north of New Circle Road.

The 138 kV line's relocation begins near Station 122+50 and ends near Station 158+50. This segment of the 138 kV line follows along the north side of New Circle Road. To complete the relocation, the company is relocating poles near Stations 134+25, 136+75, 139+00, 141+25, 144+75, 147+00, 149+25, 152+75, 155+50, 156+75, and 158+25. Two additional poles will be relocated along New Circle Road/Georgetown Road Ramp A near Stations 18+00 and 21+75.

The company is estimated to begin relocation work on October 1, 2018 with an estimated completion date of January 1, 2019.

UTILITIES AND RAIL CERTIFICATION NOTE

Fayette County
ONHPP2681031
FD52 034 7664201U
Mile point: 8.731 TO 10.015
WIDEN NEW CIRCLE ROAD IN LEXINGTON FROM GEORGETOWN ROAD TO BOARDWALK AVENUE
INCLUDING INTERCHANGE RECONSTRUCTION AT NEWTOWN
PIKE.(2002BOPC)(2004BOPP)(10CCR)(12CCR)(14CCR)
ITEM NUMBER: 07-366.00

AT&T KY – Phone, Communication

The company is relocating their aerial cables along the north side of New Circle Road from Stations 174+00 to 205+00. This includes installing poles near Stations 176+00, 178+00, 180+00, 182+50, 187+00, 189+00, 192+75, and 193+50.

The company is relocating buried fiber cable along the south side of New Circle Road from Stations 192+50 to 194+50.

The company is relocating their aerial fiber cable along the west side of Georgetown Road from Stations 100+00 to 103+00 and 107+00 to 116+00.

The company is estimated to begin relocation work on May 1, 2019 with an estimated completion date of September 1, 2019.

Windstream - Communication

The company has yet to provide a proposed relocation plan for their facilities; consequently, we are unable to identify the current, or proposed, location of the company's facilities. It is anticipated that the company may have facilities located along New Circle Road, Georgetown Road, Newtown Pike, and Boardwalk. It is also possible that the company will have facilities located at other locations throughout the project.

The company is estimated to begin relocation work, upon AT&T's relocation completion, on September 1, 2019 with an estimated completion date of January 1, 2020.

KDL Windstream - Communication

The company has yet to provide a proposed relocation plan for their facilities; consequently, we are unable to identify the current, or proposed, location of the company's facilities. It is anticipated that the company may have facilities located along New Circle Road, Georgetown Road, Newtown Pike, and Boardwalk. It is also possible that the company will have facilities located at other locations throughout the project.

UTILITIES AND RAIL CERTIFICATION NOTE

Fayette County
ONHPP2681031
FD52 034 7664201U
Mile point: 8.731 TO 10.015
WIDEN NEW CIRCLE ROAD IN LEXINGTON FROM GEORGETOWN ROAD TO BOARDWALK AVENUE
INCLUDING INTERCHANGE RECONSTRUCTION AT NEWTOWN
PIKE.(2002BOPC)(2004BOPP)(10CCR)(12CCR)(14CCR)
ITEM NUMBER: 07-366.00

The company is estimated to begin relocation work, upon AT&T's relocation completion, on September 1, 2019 with an estimated completion date of January 1, 2020.

Spectrum – CATV, Communication

The company has yet to provide a proposed relocation plan for their facilities; consequently, we are unable to identify the current, or proposed, location of the company's facilities. It is anticipated that the company may have facilities located along New Circle Road, Georgetown Road, Newtown Pike, and Boardwalk. It is also possible that the company will have facilities located at other locations throughout the project.

The company is estimated to begin relocation work, upon KU Distribution's relocation completion, on March 1, 2019 with an estimated completion date of May 1, 2019.

**THE FOLLOWING FACILITY OWNERS HAVE FACILITIES TO BE RELOCATED/ADJUSTED BY THE ROAD
CONTRACTOR AS INCLUDED IN THIS CONTRACT**

Lexington Fayette Urban County Government – Sewer Collection

The company is relocating a sanitary sewer line which crosses New Circle Road diagonally near Station 104+50.

The company is relocating a segment of the sanitary sewer line which crosses New Circle Road diagonally near Station 107+25. The relocated segment is on the south side of New Circle Road near New Circle Road/Georgetown Road Ramp D.

The company is relocating a sanitary sewer line along the north side of New Circle Road from Stations 141+00 (New Circle Road/Georgetown Road Ramp C Station 33+50) to 155+00. This includes sanitary sewer manhole installations near Stations 141+00, 143+50, 147+00, 150+00, 152+25, and 155+00.

The company is relocating sanitary sewer lines which cross Georgetown Road near Station 116+75 and Frontage Road near Station 117+25.

UTILITIES AND RAIL CERTIFICATION NOTE

<p>Fayette County ONHPP2681031 FD52 034 7664201U Mile point: 8.731 TO 10.015 WIDEN NEW CIRCLE ROAD IN LEXINGTON FROM GEORGETOWN ROAD TO BOARDWALK AVENUE INCLUDING INTERCHANGE RECONSTRUCTION AT NEWTOWN PIKE.(2002BOPC)(2004BOPP)(10CCR)(12CCR)(14CCR) ITEM NUMBER: 07-366.00</p>

The company is relocating a sanitary sewer line which follows along the north side of Frontage Road and crosses under Frontage Road near the intersection of Frontage Road and Finney Drive. This is located just south of New Circle Road/Georgetown Road Ramp B.

The company is relocating a sanitary sewer line which crosses New Circle Road near Station 197+00. The company is also replacing sanitary sewer lines located along the north and south side of New Circle Road from Stations 196+50 to 199+50. The sanitary sewer line relocation continues along the south side of New Circle Road from Stations 199+50 to 212+50 and includes a crossing under Boardwalk. Sanitary sewer manholes will be placed along the north side of New Circle Road near Stations 196+50, 197+00, and 199+50. Sanitary sewer manholes will be placed along the south side of New Circle Road near Stations 197+00, 199+00, 201+00, 203+50, 204+25, 206+00, 208+00, 210+25, and 212+50.

<p>RAIL COMPANIES HAVE FACILITIES IN CONJUNCTION WITH THIS PROJECT AS NOTED</p>
--

No Rail Involvement Rail Involved Rail Adjacent

The Contractor is fully responsible for protection of all utilities listed above

UTILITIES AND RAIL CERTIFICATION NOTE

Fayette County
ONHPP2681031
FD52 034 7664201U
Mile point: 8.731 TO 10.015
WIDEN NEW CIRCLE ROAD IN LEXINGTON FROM GEORGETOWN ROAD TO BOARDWALK AVENUE
INCLUDING INTERCHANGE RECONSTRUCTION AT NEWTOWN
PIKE.(2002BOPC)(2004BOPP)(10CCR)(12CCR)(14CCR)
ITEM NUMBER: 07-366.00

AREA FACILITY OWNER CONTACT LIST

Facility Owner	Address	Contact Name	Phone	Email
AT&T KY – Phone, Communication	894 East Main Street Ext Georgetown, KY 40324	Frank Ambrose	502-867-8240	fa2207@att.com
Columbia Gas of Kentucky - Natural Gas	PO Box 14241 Lexington, KY 40512	Bryan Slone	859-288-0253	bkslone@nisource.com
Kentucky Utilities Company - Electric Distribution	500 Stone Road Lexington, KY 40503	Chris Cobbler	502-627-3708	chris.cobbler@LGE-KU.com
Kentucky Utilities Company - Electric Transmission	820 West Broadway Louisville, KY 40232	Greg Geiser	502-627-3708	greg.geiser@LGE-KU.com
Kentucky-American Water Company – Drinking Water	2300 Richmond Road Lexington, KY 40502	Cole Mitcham	859-335-3415	cole.mitcam@amwater.com
Lexington Fayette Urban County Government - Sewer	301 Lisle Industrial Avenue Lexington, KY 40511	Rod Chervus	859-425-2408	rchervus@lexingtonky.gov
Spectrum – CATV, Communication	2544 Palumbo Dive Lexington, KY 40509	Ralph McDonie	859-514-2417	ralph.mcdonie@twcable.com
Windstream KDL - Communication	130 West New Circle Road Lexington, KY 40505	Larry Brashear	859-357-6255	larry.l.brashear@windstream.com
Windstream - Communication	130 West New Circle Road Lexington, KY 40505	Steve Johnson	859-357-6209	steve.johnson@windstream.com