



Andy Beshear  
GOVERNOR

## TRANSPORTATION CABINET

200 Mero Street  
Frankfort, Kentucky 40601

Jim Gray  
SECRETARY

December 4, 2024

CALL NO. 101  
CONTRACT ID NO. 245369  
ADDENDUM # 2

Subject: Daviess County, STP BRZ 9030 (487)  
Letting December 12, 2024

(1) Revised - Proposal Bid Items - Pages 134-135 of 135

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.  
Director  
Division of Construction Procurement

RM:mr  
Enclosures

**PROPOSAL BID ITEMS**

Report Date 12/4/24

**Section: 0001 - PAVING**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00003		CRUSHED STONE BASE	655.00	TON		\$	
0020	00100		ASPHALT SEAL AGGREGATE	11.00	TON		\$	
0030	00103		ASPHALT SEAL COAT	2.00	TON		\$	
0040	00212		CL2 ASPH BASE 1.00D PG64-22	679.00	TON		\$	
0050	00301		CL2 ASPH SURF 0.38D PG64-22	134.00	TON		\$	
0060	00356		ASPHALT MATERIAL FOR TACK	2.00	TON		\$	

**Section: 0002 - ROADWAY**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0070	01987		DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	19.00	EACH		\$	
0080	02230		EMBANKMENT IN PLACE	593.00	CUYD		\$	
0090	02351		GUARDRAIL-STEEL W BEAM-S FACE	525.00	LF		\$	
0100	02367		GUARDRAIL END TREATMENT TYPE 1	4.00	EACH		\$	
0110	02381		REMOVE GUARDRAIL	721.30	LF		\$	
0120	02545		CLEARING AND GRUBBING APPROX LESS THAN 1 ACRE	1.00	LS		\$	
0130	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0140	02671		PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH		\$	
0150	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0160	02677		ASPHALT PAVE MILLING & TEXTURING	42.00	TON		\$	
0170	02726		STAKING	1.00	LS		\$	
0180	02731		REMOVE STRUCTURE	1.00	LS		\$	
0190	03171		CONCRETE BARRIER WALL TYPE 9T	900.00	LF		\$	
0200	06542		PAVE STRIPING-THERMO-6 IN W	1,170.00	LF		\$	
0210	06543		PAVE STRIPING-THERMO-6 IN Y	1,170.00	LF		\$	
0220	06556		PAVE STRIPING-DUR TY 1-6 IN W	348.00	LF		\$	
0230	06557		PAVE STRIPING-DUR TY 1-6 IN Y	348.00	LF		\$	
0240	08901		CRASH CUSHION TY VI CLASS BT TL2	2.00	EACH		\$	
0250	20191ED		OBJECT MARKER TY 3	4.00	EACH		\$	
0260	21415ND		EROSION CONTROL	1.00	LS		\$	
0270	25078ED		THRIE BEAM GUARDRAIL TRANSITION TL-3	4.00	EACH		\$	

**Section: 0003 - BRIDGE - 030B00096N**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0280	02231		STRUCTURE GRANULAR BACKFILL	215.00	CUYD		\$	
0290	03299		ARMORED EDGE FOR CONCRETE	92.00	LF		\$	
0300	08003		FOUNDATION PREPARATION	1.00	LS		\$	
0310	08019		CYCLOPEAN STONE RIP RAP	818.00	TON		\$	
0320	08033		TEST PILES	310.00	LF		\$	
0330	08051		PILES-STEEL HP14X89 (REVISED 12/4/2024)	3,150.00	LF		\$	
0340	08100		CONCRETE-CLASS A	292.00	CUYD		\$	

**PROPOSAL BID ITEMS**

Report Date 12/4/24

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0350	08104		CONCRETE-CLASS AA	213.00	CUYD		\$	
0360	08130		MECHANICAL REINF COUPLER #5	172.00	EACH		\$	
0370	08140		MECHANICAL REINF COUPLER #5 EPOXY COATED	294.00	EACH		\$	
0380	08141		MECHANICAL REINF COUPLER #6 EPOXY COATED	416.00	EACH		\$	
0390	08150		STEEL REINFORCEMENT	26,602.00	LB		\$	
0400	08151		STEEL REINFORCEMENT-EPOXY COATED	71,081.00	LB		\$	
0410	08670		PRECAST PC BOX BEAM SB27	850.00	LF		\$	
0420	23378EC		CONCRETE SEALING	13,915.00	SQFT		\$	
0430	24405EC		MECHANICAL REINF COUPLER-#8 EPOXY COATED	18.00	EACH		\$	
0440	26231ED		RAIL SYSTEM TYPE C412	349.00	LF		\$	
0450	26233EC		MOBILIZATION FOR CONCRETE SURF TREATMENT	1.00	LS		\$	

**Section: 0004 - DEMOBILIZATION &/OR MOBILIZATION**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0460	02568		MOBILIZATION	1.00	LS		\$	
0470	02569		DEMOBILIZATION	1.00	LS		\$	