



Andy Beshear  
GOVERNOR

## TRANSPORTATION CABINET

200 Mero Street  
Frankfort, Kentucky 40601

Jim Gray  
SECRETARY

October 17, 2023

CALL NO. 101  
CONTRACT ID NO. 231340  
ADDENDUM # 1

Subject: Fayette County, NHPP 1602(003)  
Letting October 26, 2023

(1) Revised - Revised Utility Notes - Pages 80-84 of 239

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.  
Director  
Division of Construction Procurement

RM:mr  
Enclosures

## UTILITIES AND RAIL CERTIFICATION NOTE

Fayette County  
ONHPP1602003  
FD52 034 7996301U  
Mile point: 1.470 TO 3.220  
**IMPROVE NEWTOWN PIKE FROM KY-4 TO I-75. (16CCR)(18CCR)(2020CCR) (2022CCR)**  
ITEM NUMBER: 07-252.00

**PROJECT NOTES ON UTILITIES**

The contractor should be aware that there is UTILITY WORK INCLUDED IN THIS ROAD CONSTRUCTION CONTRACT. The Contractor shall review the GENERAL UTILITY NOTES AND INSTRUCTIONS which may include KYTC Utility Bid Item Descriptions, utility owner supplied specifications, plans, list of utility owner preapproved subcontractors, and other instructions. Utility contractors may be added via addendum if KYTC is instructed to do so by the utility owner. Potential contractors must seek prequalification from the utility owner. Any revisions must be sent from the utility owner to KYTC a minimum of one week prior to bid opening.

**NOTE: DO NOT DISTURB THE FOLLOWING FACILITIES LOCATED WITHIN THE PROJECT DISTURB LIMITS**

- AT&T Kentucky - Communication
- Charter DBA Spectrum - CATV
- Columbia Gas of Kentucky - Natural Gas
- Kentucky-American Water Company - Drinking Water Distribution
- Kentucky Utilities - Electric Distribution
- Ledcor / Kentucky Wired - Communication
- Lumen / Level 3 / CenturyLink Communication, LLC - Communication
- Lexington Fayette Urban County Government - Sewer
- Metro Net - Communication
- Windstream dba Windstream Holdings II, LLC – Communication
- Windstream KDL dba Windstream Holdings II, LLC - Communication

**\*The Contractor is fully responsible for protection of all utilities listed above\***

**THE FOLLOWING FACILITY OWNERS ARE RELOCATING/ADJUSTING THEIR FACILITIES WITHIN THE PROJECT LIMITS AND WILL BE COMPLETE PRIOR TO CONSTRUCTION**

Not Applicable

## UTILITIES AND RAIL CERTIFICATION NOTE

**Fayette County**  
**ONHPP1602003**  
**FD52 034 7996301U**  
**Mile point: 1.470 TO 3.220**  
**IMPROVE NEWTOWN PIKE FROM KY-4 TO I-75. (16CCR)(18CCR)(2020CCR) (2022CCR)**  
**ITEM NUMBER: 07-252.00**

**THE FOLLOWING FACILITY OWNERS HAVE FACILITIES TO BE RELOCATED/ADJUSTED BY THE OWNER OR THEIR SUBCONTRACTOR AND IS TO BE COORDINATED WITH THE ROAD CONTRACT**

### **AT&T - KY – Communication**

The company has submitted relocation plans and estimates. Their agreement has been routed for signatures and is anticipated being executed by September 18, 2023. AT&T Kentucky has aerial facilities attached to existing Kentucky Utilities poles within a limited area of relocation along the west side of Newtown Pike approximately from Station 107+00 to Station 118+13. AT&T Kentucky will transfer its existing fiber optic cable from existing Kentucky Utilities poles to proposed KU poles beginning at Newtown Court Station 51+53.5 and remaining along the existing KU pole line attaching to proposed KU poles along the west side of Newtown Pike at approximately Station 113+25.5, 114+85, 116+10, and 118+13 before turning perpendicular to west side of Newtown Pike and leaving the construction limits following the existing pole line behind the building on KYTC plan set Parcel 4 running west behind the buildings along Nandino Boulevard. AT&T’s anticipated completion date is July 31, 2024.

### **Charter dba Spectrum – CATV, Communications**

The company has yet to provide a proposed relocation plan for their facilities; consequently, we are unable to identify the current, or proposed, location of the company’s facilities. It is anticipated that the company will have facilities along Newtown Pike. The company’s aerial facilities will likely attach to the new KU poles throughout the project. It is also possible that the company will have facilities located at other locations throughout the project. Charter dba Spectrum’s anticipated completion date is July 31, 2024.

### **Columbia Gas – Natural Gas Distribution**

The company has yet to provide a proposed relocation plan for their facilities; consequently, we are unable to identify the current, or proposed, location of the company’s facilities. It is anticipated that the company will have facilities along Newtown Pike. It is also possible that the company will have facilities located at other locations throughout the project. The company is estimated to begin relocation work on April 1, 2024 with an estimated completion date of November 1, 2024.

### **Kentucky-American Water Company – Drinking Water Distribution**

The company has yet to provide a proposed relocation plan for their facilities; consequently, we are unable to identify the current, or proposed, location of the company’s facilities. It is anticipated that the company will have facilities along Newtown Pike. The company’s relocation work along Newtown will not be one continuous waterline relocation but will instead leave sections of the existing waterline intact. Kentucky American will relocate individual sections of waterline throughout the project. It is also

## UTILITIES AND RAIL CERTIFICATION NOTE

**Fayette County**  
**ONHPP1602003**  
**FD52 034 7996301U**  
**Mile point: 1.470 TO 3.220**  
**IMPROVE NEWTOWN PIKE FROM KY-4 TO I-75. (16CCR)(18CCR)(2020CCR) (2022CCR)**  
**ITEM NUMBER: 07-252.00**

possible that the company will have facilities located at other locations throughout the project. Kentucky American Water’s anticipated completion date is April 30, 2024.

### **Kentucky Utilities - Electric Distribution**

The company has submitted its relocation plans and KYTC is waiting for estimates in order to draft an agreement. The agreement between KU and KYTC is expected to be executed by September 30, 2023. The company will install new poles at various locations from Station 107+25 to Station 167+97 and the majority of these new poles will be installed along the west side of Newtown Pike near KU’s existing pole line. These pole relocations will include poles near Station 107+25, 113+25, 114+85, 116+10, 118+13, 118+90, 120+53, 131+45, 136+81, 137+87, with a new wire crossing at 137+10, poles near 140+50, 144+25, 148+18, 149+44, 150+17, and 164+97. The anticipated completion date is February 28, 2024.

### **Ledcor / Kentucky Wired – Communication**

The company has yet to provide a proposed relocation plan for their facilities; consequently, we are unable to identify the current, or proposed, location of the company’s facilities. It is anticipated that the company will have facilities along Newtown Pike. The company has stated that the majority of its facilities are currently attached to the existing KU poles and the company will likely transfer its facilities to the new KU poles when they are installed. It is also possible that the company will have facilities located at other locations throughout the project. The anticipated completion date is July 31, 2024

### **Lumen / Level 3 / CenturyLink Communication, LLC – Communication**

Lumen / Level 3 / CenturyLink Communication, LLC has a fiber optic duct to be installed at approximately Sta 130+00. The roadway contractor will be required to notify Lumen 21 days prior to installing the CBI and storm sewer pipe located at LT Sta 129+75 and shall coordinate with Lumen to ensure fiber optic line is installed at an appropriate depth to avoid the storm sewer and the existing stone wall along the western side of Newtown Pike. Additionally, Lumen is attached to the KU poles along the western right of way of Newtown Pike from Newtown Court to Aristides Boulevard and will attach to the new KU poles once KU has completed their relocation work. No relocation plans have been submitted from Lumen at this time. Contact Richard Compton with Lumen for coordination – 859-413-8254 or 859-550-2208 – [Richard.compton@lumen.com](mailto:Richard.compton@lumen.com)

### **Metro Net – Communication**

The company has yet to provide a proposed relocation plan for their facilities; consequently, we are unable to identify the current, or proposed, location of the company’s facilities. It is anticipated that the company will have facilities along Newtown Pike. It is also possible that the company will have facilities located at other locations throughout the project. The anticipated completion date is July 31, 2024

## UTILITIES AND RAIL CERTIFICATION NOTE

**Fayette County**  
**ONHPP1602003**  
**FD52 034 7996301U**  
**Mile point: 1.470 TO 3.220**  
**IMPROVE NEWTOWN PIKE FROM KY-4 TO I-75. (16CCR)(18CCR)(2020CCR) (2022CCR)**  
**ITEM NUMBER: 07-252.00**

**Windstream dba Windstream Holdings II, LLC – Communication**

The company has yet to provide a proposed relocation plan for their facilities; consequently, we are unable to identify the current, or proposed, location of the company’s facilities. It is anticipated that the company will have facilities along Newtown Pike. Preliminary Windstream facilities maps indicate both aerial and buried fiber conflicts on both sides of Newtown Pike approximately from Station 107+00 through Station 154+00. The majority of Windstream’s aerial fiber is currently attached to existing KU poles. It is also possible that the company will have facilities located at other locations throughout the project. The anticipated completion date is July 31, 2024.

**Windstream KDL dba Windstream Holdings II, LLC – Communication**

The company has yet to provide a proposed relocation plan for their facilities; consequently, we are unable to identify the current, or proposed, location of the company’s facilities. It is anticipated that the company will have facilities along Newtown Pike. It is also possible that the company will have facilities located at other locations throughout the project. The anticipated completion date is July 31, 2024

**THE FOLLOWING FACILITY OWNERS HAVE FACILITIES TO BE RELOCATED/ADJUSTED BY THE ROAD CONTRACTOR AS INCLUDED IN THIS CONTRACT**

**Lexington Fayette Urban County Government – Sewer Collection**

The city is relocating a single segment of sanitary sewer along the west side of Newtown Pike beginning approximately at Station 118+40 and crossing Cane Run Creek at Station 118+95 to its juncture with an existing 30” sanitary sewer line approximately at 119+75.

**RAIL COMPANIES HAVE FACILITIES IN CONJUNCTION WITH THIS PROJECT AS NOTED**

**No Rail Involvement**    **Rail Involved**    **Rail Adjacent**

## UTILITIES AND RAIL CERTIFICATION NOTE

**Fayette County**  
**ONHPP1602003**  
**FD52 034 7996301U**  
**Mile point: 1.470 TO 3.220**  
**IMPROVE NEWTOWN PIKE FROM KY-4 TO I-75. (16CCR)(18CCR)(2020CCR) (2022CCR)**  
**ITEM NUMBER: 07-252.00**

### AREA FACILITY OWNER CONTACT LIST

Facility Owner	Address	Contact Name	Phone	Email
AT&T - KY - Communication	894 E. Main St. Ext. Georgetown KY 40324	Frank Ambrose	859-753-8377	fa2207@att.com
Charter DBA Spectrum - CATV	1575 Winchester Road Lexington KY 40505	John Oram	859-519-3434	john.oram@charter.com
Columbia Gas of Kentucky - Natural Gas	PO Box 14241 Lexington KY 40512	Andrew Weber	859-288-0253	aweber@nisource.com
Kentucky Utilities - Electric Distribution	820 W. Broadway Louisville KY 40202	Caroline Justice	502-627-3708	Caroline.Justice@lge-ku.com
Kentucky-American Water Company - Water	2300 Richmond Road Lexington KY 40502	John Magner	859-268-6349	John.magner@amwater.com
Ledcor - Communication	2008 Mercer Road Lexington Ky 40511	Jonathon Young	442-236-2533	Jonathon.Young@ledcor.com
Lumen/Level 3 / CenturyLink Communication, LLC - Communication	565 W. Main St. Lexington KY 40507	Richard Compton	859-550-2208 859-413-8254	Richard.Compton@Lumen.com
Lexington Fayette Urban County Government – Sanitary Sewer	301 Lisle Industrial Avenue Lexington KY 40511	Chris Dent	859-258-3472	cdent@lexingtonky.gov
Metro Net - Communication	904 N Broadway Lexington KY 40507	Doug Haney	606-336-1853	doug.haney@metronet.com
Windstream Holdings II, LLC - Communication	130 West New Circle Road Lexington KY 40505	Mark Ware  Steve Johnson	606-329-6195  859-357-6209	<a href="mailto:Mark.Ware@windstream.com">Mark.Ware@windstream.com</a> <a href="mailto:Steve.Johnson@windstream.com">Steve.Johnson@windstream.com</a>