Andy Beshear
GOVERNOR

TRANSPORTATION CABINET
200 Mero Street
Frankfort, Kentucky 40601

Rebecca Goodman
SECRETARY

November 16, 2026

CALL NO. 101
CONTRACT ID NO. 261521
ADDENDUM # 1

Subject: Fayette County, STP 3003 (337)
Letting November 19, 2026

(1) Added – Special Notes – Pages 35A-35K of 163
(2) Revised – Proposal Bid Items – Pages 159-163 of 163
(3) Revised Plan Sheets – R2L, R2N

Proposal revisions are available at http://transportation.ky.gov/Construction-Procurement/.

If you have any questions, please contact us at 502-564-3500.

Sincerely,



Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

Kentucky Transportation Cabinet
Division of Highway Design

TRAFFIC MANAGEMENT PLAN

County: Fayette Item No.: 7-8902

Federal Project No.: STP 3003 (337) - FD52 034 1927 000-002

Project Description:

Reconstruction of KY 1927 corridor from Grafton's Mill Lane to KY 4 (New Circle Road) with urban typical section, intersection improvements, and addition of sidewalk and separated bike and pedestrian path.

Roadway Classification: ☒ Urban ☐ Rural

☐ Local ☐ Collector ☒ Arterial ☐ Interstate

ADT (current) 16,384 AM Peak Current _____ PM Peak Current _____ % Trucks 10.7%

Project Designation: ☒ Significant ☐ Other: _____

Traffic Control Plan Design:

Taper and Diversion Design Speeds 35 MPH

Minimum Lane Width 10 FT Minimum Shoulder Width 1 FT

Minimum Bridge Width N/A

Minimum Radius Existing Maximum Grade Existing

Minimum Taper Length Per MUTCD Minimum Intersection Level of Service N/A

Existing Traffic Queue Lengths N/A Projected Traffic Queue Lengths N/A

Comments:

See Maintenance of Traffic drawings R66-R86 for maintenance of traffic phasing.

Kentucky Transportation Cabinet
Division of Highway Design
TRAFFIC MANAGEMENT PLAN

Item No. 7-8902

Discussion:

1) Public Information Plan	
a) Prepare with assistance from ☒ KYTC or ☐ _____	
b) Identify Trip Generators Referenced	f) Railroad Involvement Referenced
c) Identify Types of Road Users Referenced	g) Address Pedestrians, Bikes Mass Transit Referenced
d) Public Information Message Referenced	h) Address Timing, Frequency, Updates, Effectiveness of Plan Referenced
e) Public Information Strategies to be used Referenced	i) Police & Other Emergency Services Referenced

Kentucky Transportation Cabinet
Division of Highway Design
TRAFFIC MANAGEMENT PLAN

Item No. 7-8902

2) Temporary Traffic Control Plan (For Each Phase of Construction) Phase I

Exposure Control Measures		**Positive Protection Measures**	
a) Is Road Closure Allowed Type:	Referenced	a) Address Drop Off Protection Criteria	Referenced
b) Detour Conditions	Referenced	b) Temporary Barrier Requirements	Referenced
c) Working Hour Restrictions	Referenced	c) Evaluation of Existing Guardrail Conditions	Referenced
d) Holiday or Special Event Work Restrictions	Referenced	d) Address Temporary Drainage	Referenced
e) Evaluation of Intersection LOS	Referenced	**Uniformed Law Enforcement Officers**	N/A
f) Evaluation of Queue Lengths	Referenced	**Payment for Traffic Control***	
g) Evaluation of User Costs and Incentives/Disincentives	Referenced	a) Method of Project Bidding	Referenced
h) Address Pedestrians, Bikes, Mass Transit	Referenced	b) Special Notes	Referenced
Work Vehicles and Equipment	Referenced	*Payment for traffic control items shall be in accordance with the Kentucky Department of Highways Standard Specifications for Road and Bridge Construction	

Comments:

Kentucky Transportation Cabinet
Division of Highway Design
TRAFFIC MANAGEMENT PLAN

Item No. 7-8902

2) Temporary Traffic Control Plan (For Each Phase of Construction) Phase 2

Exposure Control Measures		**Positive Protection Measures**	
a) Is Road Closure Allowed Type:	Referenced	a) Address Drop Off Protection Criteria	Referenced
b) Detour Conditions	Referenced	b) Temporary Barrier Requirements	Referenced
c) Working Hour Restrictions	Referenced	c) Evaluation of Existing Guardrail Conditions	Referenced
d) Holiday or Special Event Work Restrictions	Referenced	d) Address Temporary Drainage	Referenced
e) Evaluation of Intersection LOS	Referenced	**Uniformed Law Enforcement Officers**	N/A
f) Evaluation of Queue Lengths	Referenced	**Payment for Traffic Control***	
g) Evaluation of User Costs and Incentives/Disincentives	Referenced	a) Method of Project Bidding	Referenced
h) Address Pedestrians, Bikes, Mass Transit	Referenced	b) Special Notes	Referenced
Work Vehicles and Equipment	Referenced	*Payment for traffic control items shall be in accordance with the Kentucky Department of Highways Standard Specifications for Road and Bridge Construction	

Comments:

Kentucky Transportation Cabinet
Division of Highway Design
TRAFFIC MANAGEMENT PLAN

Item No. 7-8902

2) Temporary Traffic Control Plan (For Each Phase of Construction) Phase 3

Exposure Control Measures		**Positive Protection Measures**	
a) Is Road Closure Allowed Type:	Referenced	a) Address Drop Off Protection Criteria	Referenced
b) Detour Conditions	Referenced	b) Temporary Barrier Requirements	Referenced
c) Working Hour Restrictions	Referenced	c) Evaluation of Existing Guardrail Conditions	Referenced
d) Holiday or Special Event Work Restrictions	Referenced	d) Address Temporary Drainage	Referenced
e) Evaluation of Intersection LOS	Referenced	**Uniformed Law Enforcement Officers**	N/A
f) Evaluation of Queue Lengths	Referenced	**Payment for Traffic Control***	
g) Evaluation of User Costs and Incentives/Disincentives	Referenced	a) Method of Project Bidding	Referenced
h) Address Pedestrians, Bikes, Mass Transit	Referenced	b) Special Notes	Referenced
Work Vehicles and Equipment	Referenced	*Payment for traffic control items shall be in accordance with the Kentucky Department of Highways Standard Specifications for Road and Bridge Construction	

Comments:

Kentucky Transportation Cabinet
Division of Highway Design
TRAFFIC MANAGEMENT PLAN

Item No. 7-8902

2) Temporary Traffic Control Plan (For Each Phase of Construction) Phase 3

Exposure Control Measures		**Positive Protection Measures**	
a) Is Road Closure Allowed Type:	Referenced	a) Address Drop Off Protection Criteria	Referenced
b) Detour Conditions	Referenced	b) Temporary Barrier Requirements	Referenced
c) Working Hour Restrictions	Referenced	c) Evaluation of Existing Guardrail Conditions	Referenced
d) Holiday or Special Event Work Restrictions	Referenced	d) Address Temporary Drainage	Referenced
e) Evaluation of Intersection LOS	Referenced	**Uniformed Law Enforcement Officers**	N/A
f) Evaluation of Queue Lengths	Referenced	**Payment for Traffic Control***	
g) Evaluation of User Costs and Incentives/Disincentives	Referenced	a) Method of Project Bidding	Referenced
h) Address Pedestrians, Bikes, Mass Transit	Referenced	b) Special Notes	Referenced
Work Vehicles and Equipment	Referenced	*Payment for traffic control items shall be in accordance with the Kentucky Department of Highways Standard Specifications for Road and Bridge Construction	

Comments:

Kentucky Transportation Cabinet
Division of Highway Design
TRAFFIC MANAGEMENT PLAN

Item No. 7-8902

1) Public Information Plan

The primary goal of the Public Information Plan (PIP) is to inform the public and area stakeholders of project information including Temporary Traffic Control Plan (TTCP). KYTC will coordinate and disseminate to stakeholders and the media appropriate information regarding construction activities.

Project Impacts
The project is along an urban residential corridor. Fayette County Public Schools (FCPS) Liberty Elementary School and Bus Garage are both located along the corridor and generate a considerable number of daily bus trips throughout much of the year. While limited pedestrian facilities exist, pedestrians should be anticipated traveling between Fortune Drive and existing public transit stops. These transit stops will need to be maintained during construction. Contractor will coordinate with LexTran on temporary transit stop relocations.

Local Stakeholders
The following stakeholders will be contacted at the beginning of the construction and at key transition points during construction activities.

- City Council Members
- Kentucky Transportation Cabinet, District 7
- Fayette County Public Schools
- LFUCG Emergency Services
- LexTran
- Local Businesses
- Utility Companies
- Neighborhood Associations

Media Strategies
The following media will be contacted at the beginning of the construction project at key construction transitions points during construction and at the end of construction:

Points of Media Contact
- Newspapers
- Radio
- Television / Cable

Milestones to Contact Media
Media will be contacted immediately prior to construction and updated throughout construction, and at significant transitions of construction phases.

Public Information Message
Notifications of the closures and detours will be provided a minimum of one-week advance notice. Further, variable message boards will be used throughout the community for notice.

Kentucky Transportation Cabinet
Division of Highway Design
TRAFFIC MANAGEMENT PLAN

Item No. 7-8902

2) Temporary Traffic Control Plan (TTCP)

The Contractor shall maintain and control traffic according the requirements of the contract documents. Contractor shall furnish and erect suitable barricades, signs and other necessary devices to control, guide, and safeguard traffic passing through or around the construction project. All such devices shall conform in all respects to the requirements of the MUTCD. Contractor, before erecting any barricades or changing the location of one already placed, shall notify the Engineer at least three days prior to such contemplated erection or change, except in case of an emergency. In case of an emergency, the Engineer may direct the Contractor to immediately provide safety and warning devices to safeguard traffic. All night-time control devices requiring illumination shall be lighted every night during the entire period from sunset to sunrise. The Contractor will be held responsible for all damage to Work due to failure to provide barricades, signs, lights, and watchmen to protect it; and whenever evidence of such damage is found prior to acceptance, the Engineer may order the damaged portion removed and replaced by the Contractor at the Contractor's expense. The responsibility remains the Contractor's until the project is accepted.

Allowable Traffic Control Restrictions and Closures

Auxiliary Turn Lane Closures
Contractor may temporarily close auxiliary turn lanes within active construction areas within the corridor with the following limitations: KY 1927 dedicated left turn lane onto KY 4 may be closed for up to 2 weeks and KY 1927 dedicated left turn lane onto Fortune Drive for up to 2 weeks when Fayette County Public Schools is not is session (https://www.fcps.net/news-calendars/calendar). Contractor shall notify LFUCG Traffic Engineering at least 2 weeks prior to closing auxiliary turn lanes along KY 1927. Contractor to provide closure signage in accordance with the MUTCD and modify existing signage and adjust existing traffic signal heads as required.

Property Impacts
Reasonable means of ingress and egress shall be maintained to all properties within the project limits.

Travel Lane Closures
Contractor may temporarily close one lane of travel in accordance with Standard Drawing TTC-100-05 for single-lane closures on two-lane, two-direction roadways and TTC-115-04 for single lane closures on multi-lane roadways. Lane closures shall not be permitted during peak travel periods (Monday-Friday 6 AM to 9 AM and from 2 PM to 6 PM), when Fayette County Public Schools is in session (https://www.fcps.net/news-calendars/calendar), or on state holidays (https://extranet.personnel.ky.gov/pages/leave.aspx) unless otherwise approved by the Engineer.

Sidewalk Closures
Pedestrian access shall remain available at all times, either by reasonable detour or diversion. The temporary facility must replicate the existing facility as nearly as practical, including ADA compliance where necessary. Contractor shall provide signed detour route and sidewalk closure signage in accordance with the MUTCD. Contractor shall utilize appropriate temporary barriers and/or temporary fence on the sidewalk to separate and protect the pedestrians from the adjacent work areas.

Kentucky Transportation Cabinet
Division of Highway Design
TRAFFIC MANAGEMENT PLAN

Item No. 7-8902

Road Closures
Contractor may temporarily close the below roadway segments in accordance with the requirements in this section. Contractor shall provide signed detour routes and road closure signage in accordance with the drawings and MUTCD. The temporary closures shall not be completed concurrently.

Gerardi Road Access and Stonewood Lane Access

1. Closure Coordination Requirements:
    a. Contractor may close Stonewood Lane for up to one week during Phase 1 and restrict access to right-in/right-out while crossings are being constructed. Access points at both Fortune Drive and Burkewood Drive shall be maintained while access is restricted.
    b. Contractor to close KY 1927 access to Gerardi Road and Stonewood Lane permanently. Contractor shall complete construction and have Old Rosebud Road and Kingsbury Road open to traffic prior to closing Gerardi Road and Stonewood Lane.

Burkewood Drive Access and Fortune Drive Access

1. Closure Coordination Requirements:
    a. Contractor may close Burkewood Drive for up to 4 weeks.
    b. Contractor may close Fortune Drive and KY 1927 eastbound left turn lane for up to 2 weeks.
    c. Contractor shall maintain KY 1927 access to either Burkewood Drive or Fortune Drive at all times.

FCPS Bus Garage Access

1. Closure Coordination Requirements:
    a. Contractor may close each access point of FCPS Bus Garage for up to 4 weeks each.
    b. Contractor shall maintain at least one access point to FCPS Bus Garage at all times.
2. School Access Requirements
    a. Contractor shall maintain both access points to the FCPS Bus Garage when school is in session and during employee and bus arrival/departure times.
    b. Contractor may close one site access point at a time during FCPS period breaks. See FCPS calendar https://www.fcps.net/news-calendars/calendar for break period dates.
    c. Contractor shall maintain two-lanes of traffic on KY 1927 (Liberty Road) from Liberty Hill Drive to Fortune Drive during AM and PM peak periods when school is in session.
    d. Contractor will assist with traffic control on this parcel from 1;45-2:30 pm during the construction of the project.

Contractor Restrictions

Work Hour Restrictions
This project is located near a residential area. No work shall be conducted between 9:00 pm and 6:00 am unless otherwise approved by the Engineer.

Liquidated Damages

Kentucky Transportation Cabinet
Division of Highway Design

TRAFFIC MANAGEMENT PLAN

Liquidated Damages will be assessed in accordance with the subsection 112.03.15 of the Standard Specifications for non-compliance of Maintain and Control Traffic.

Item No. 7-8902

APPROVAL:

Lauren Meighan — 9/3/2026

Project Manager — Date

9/3/26

Project Delivery and Preservation Manager — Date

Kelly Baker — 9/3/2026

Engineering Support Manager — Date

FHWA Representative — Date

Revisions to the TMP require review/approval by the signatories.

Special Note for Utility Coordination Bid Item

The Contractor shall communicate, cooperate, and coordinate with the Department, the utility owners, and potentially affected third parties, as necessary for the utility relocation work. The Contractor shall be responsible for all coordination needed to ensure that the road construction and utility relocation work may concurrently and effectively take place. No delay claims will be considered due to utility relocations.

This item shall include assignment of a utility coordinator for the project to coordinate plans, work, and schedules directly with the utility companies and KYTC personnel. This item includes responsibility to ensure the project progresses efficiently and in accordance with the proposed contract documents. The Department may consult the utility coordinator on matters of utility work construction, cost and/or schedule. Any changes in the proposed scope, design, construction, cost, and/or schedule for the utility work shall be approved by the Department. If necessary, this item includes conducting utility coordination meetings with involved utility companies and as needed on project site visits to manage utility relocation activity, resolve conflicts with the road activity, and minimize impact to the project. The Department shall be invited to utility coordination meetings.

The Department will consider payment as full compensation for all work required under this note.

See utility and rail certification for impacted utilities.

Code	Item Description	Unit
24845EC	Utility Coordination	Lump Sum

261521

PROPOSAL BID ITEMS

Report Date 11/16/26

261521

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00001		DGA BASE	26,977.00	TON		$	
0015	00020		TRAFFIC BOUND BASE (ADDED 11-16-26)	800.00	TON		$	
0020	00078		CRUSHED AGGREGATE SIZE NO 2	37,749.00	TON		$	
0030	00190		LEVELING & WEDGING PG64-22	810.00	TON		$	
0040	00212		CL2 ASPH BASE 1.00D PG64-22	1,269.00	TON		$	
0050	00214		CL3 ASPH BASE 1.00D PG64-22	15,753.00	TON		$	
0060	00301		CL2 ASPH SURF 0.38D PG64-22	620.00	TON		$	
0070	02071		JPC PAVEMENT-11 IN	368.00	SQYD		$	
0080	02677		ASPHALT PAVE MILLING & TEXTURING	1,840.00	TON		$	
0090	22906ES403		CL3 ASPH SURF 0.38A PG64-22	3,996.00	TON		$	
0100	24970EC		ASPHALT MATERIAL FOR TACK NON-TRACKING	36.11	TON		$	

Section: 0002 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0110	00005		GEOGRID REINFORCEMENT FOR SUBGRADE	3,600.00	SQYD		$	
0120	01718		REMOVE INLET	25.00	EACH		$	
0130	01810		STANDARD CURB AND GUTTER	16,131.00	LF		$	
0140	01820		LIP CURB AND GUTTER	415.00	LF		$	
0150	01875		STANDARD HEADER CURB	803.00	LF		$	
0160	01917		STANDARD BARRIER MEDIAN TYPE 2	589.00	SQYD		$	
0170	01921		STANDARD BARRIER MEDIAN TYPE 4	123.00	SQYD		$	
0180	01992		INSTALL TEMP CONC MED BARR	816.00	LF		$	
0190	02003		RELOCATE TEMP CONC BARRIER	472.00	LF		$	
0200	02015		CEMENT CONCRETE ISLAND	67.00	SQYD		$	
0210	02101		CEM CONC ENT PAVEMENT-8 IN	2,191.00	SQYD		$	
0220	02159		TEMP DITCH	4,100.00	LF		$	
0230	02160		CLEAN TEMP DITCH	2,050.00	LF		$	
0240	02200		ROADWAY EXCAVATION	54,254.00	CUYD		$	
0250	02223		GRANULAR EMBANKMENT	135.00	CUYD		$	
0260	02242		WATER	600.00	MGAL		$	
0270	02351		G/R-W BEAM-S FACE TL-3	37.50	LF		$	
0280	02360		G/R TERMINAL SECTION NO 1	2.00	EACH		$	
0290	02429		RIGHT-OF-WAY MONUMENT TYPE 1	72.00	EACH		$	
0300	02432		WITNESS POST	16.00	EACH		$	
0310	02469		CLEAN SINKHOLE	1.00	EACH		$	
0320	02545		CLEARING AND GRUBBING APPROXIMATELY 22 ACRES	1.00	LS		$	
0330	02562		TEMPORARY SIGNS	1,320.00	SQFT		$	
0340	02585		EDGE KEY	193.00	LF		$	
0350	02602		FABRIC-GEOTEXTILE CLASS 1	115,700.00	SQYD		$	

261521

PROPOSAL BID ITEMS

Report Date 11/16/26

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0360	02603		FABRIC-GEOTEXTILE CLASS 2	2,538.00	SQYD		$	
0370	02612		HANDRAIL-TYPE A-2	645.00	LF		$	
0380	02625		REMOVE HEADWALL	18.00	EACH		$	
0390	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		$	
0400	02671		PORTABLE CHANGEABLE MESSAGE SIGN	6.00	EACH		$	
0410	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		$	
0420	02701		TEMP SILT FENCE	3,545.00	LF		$	
0430	02704		SILT TRAP TYPE B	61.00	EACH		$	
0440	02705		SILT TRAP TYPE C	132.00	EACH		$	
0450	02707		CLEAN SILT TRAP TYPE B	122.00	EACH		$	
0460	02708		CLEAN SILT TRAP TYPE C	264.00	EACH		$	
0470	02720		SIDEWALK-4 IN CONCRETE	4,568.00	SQYD		$	
0480	02726		STAKING	1.00	LS		$	
0490	05952		TEMP MULCH	70,987.00	SQYD		$	
0500	05953		TEMP SEEDING AND PROTECTION	53,240.00	SQYD		$	
0510	05963		INITIAL FERTILIZER	2.00	TON		$	
0520	05964		MAINTENANCE FERTILIZER	1.00	TON		$	
0530	05985		SEEDING AND PROTECTION	27,000.00	SQYD		$	
0540	05990		SODDING	11,690.00	SQYD		$	
0550	05992		AGRICULTURAL LIMESTONE	17.00	TON		$	
0560	06406		SBM ALUM SHEET SIGNS .080 IN	344.00	SQFT		$	
0570	06407		SBM ALUM SHEET SIGNS .125 IN	176.00	SQFT		$	
0580	06410		STEEL POST TYPE 1	680.00	LF		$	
0590	06490		CLASS A CONCRETE FOR SIGNS	4.00	CUYD		$	
0600	06511		PAVE STRIPING-TEMP PAINT-6 IN	65,300.00	LF		$	
0610	06546		PAVE STRIPING-THERMO-12 IN W	332.00	LF		$	
0620	06568		PAVE MARKING-THERMO STOP BAR-24IN	573.00	LF		$	
0630	06569		PAVE MARKING-THERMO CROSS-HATCH	449.00	SQFT		$	
0640	06572		PAVE MARKING-DOTTED LANE EXTEN	636.00	LF		$	
0650	06573		PAVE MARKING-THERMO STR ARROW	5.00	EACH		$	
0660	06574		PAVE MARKING-THERMO CURV ARROW	35.00	EACH		$	
0670	06575		PAVE MARKING-THERMO COMB ARROW	6.00	EACH		$	
0680	06576		PAVE MARKING-THERMO ONLY	3.00	EACH		$	
0690	06600		REMOVE PAVEMENT MARKER TYPE V	70.00	EACH		$	
0700	06610		INLAID PAVEMENT MARKER-MW	183.00	EACH		$	
0710	06612		INLAID PAVEMENT MARKER-BY	231.00	EACH		$	
0720	08018		RETAINING WALL	4,060.00	SQFT		$	
0730	10020NS		FUEL ADJUSTMENT	44,805.00	DOLL	$1.00	$	$44,805.00
0740	10030NS		ASPHALT ADJUSTMENT	90,854.00	DOLL	$1.00	$	$90,854.00
0750	20631ND		INSTALL POLE MOUNTED SIGN	4.00	EACH		$	
0760	21417ES717		PAVE MARK THERMO CONE CAP-SOLID YELLOW	71.00	SQFT		$	
0770	21596ND		GMSS TYPE D	16.00	EACH		$	
0780	22000ED		WOOD PLANK FENCE	915.00	LF		$	
0790	22520EN		PAVE MARKING-THERMO YIELD BAR-36 IN	78.00	LF		$	
0800	23158ES505		DETECTABLE WARNINGS	746.00	SQFT		$	
0810	23261EC		PAVE MARK-THERMO-X-WALK-24 IN	1,380.00	LF		$	
0820	23875NC		REMOVE THERMOPLASTIC ARROWS	8.00	EACH		$	
0830	24540		R/W MONUMENT TYPE 3	26.00	EACH		$	
0840	24631EC		BARCODE SIGN INVENTORY	93.00	EACH		$	

261521

PROPOSAL BID ITEMS

Report Date 11/16/26

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0850	24995EC		PAVE STRIPING-SPRAY THERMO-6 IN W	17,843.00	LF		$	
0860	24996EC		PAVE STRIPING-SPRAY THERMO-6 IN Y	12,688.00	LF		$	

Section: 0003 - DRAINAGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0870	00520		STORM SEWER PIPE-12 IN	39.00	LF		$	
0880	00521		STORM SEWER PIPE-15 IN	2,013.00	LF		$	
0890	00522		STORM SEWER PIPE-18 IN	3,518.00	LF		$	
0900	00524		STORM SEWER PIPE-24 IN	1,184.00	LF		$	
0910	00526		STORM SEWER PIPE-30 IN	974.00	LF		$	
0920	00528		STORM SEWER PIPE-36 IN	50.00	LF		$	
0930	00530		STORM SEWER PIPE-48 IN	215.00	LF		$	
0940	00531		STORM SEWER PIPE-54 IN	114.00	LF		$	
0950	01000		PERFORATED PIPE-4 IN	684.00	LF		$	
0960	01202		PIPE CULVERT HEADWALL-15 IN	1.00	EACH		$	
0970	01204		PIPE CULVERT HEADWALL-18 IN	5.00	EACH		$	
0980	01208		PIPE CULVERT HEADWALL-24 IN	2.00	EACH		$	
0990	01210		PIPE CULVERT HEADWALL-30 IN	1.00	EACH		$	
1000	01212		PIPE CULVERT HEADWALL-36 IN	1.00	EACH		$	
1010	01219		PIPE CULVERT HEADWALL-54 IN EQUIV	2.00	EACH		$	
1020	01310		REMOVE PIPE	2,531.00	LF		$	
1030	01314		PLUG PIPE	12.00	EACH		$	
1040	01456		CURB BOX INLET TYPE A	59.00	EACH		$	
1050	01459		CURB BOX INLET TYPE A MOD	3.00	EACH		$	
1060	01480		CURB BOX INLET TYPE B	1.00	EACH		$	
1070	01487		CURB BOX INLET TYPE F	4.00	EACH		$	
1080	01490		DROP BOX INLET TYPE 1	6.00	EACH		$	
1090	01496		DROP BOX INLET TYPE 3	18.00	EACH		$	
1100	01511		DROP BOX INLET TYPE 5D	1.00	EACH		$	
1110	01538		DROP BOX INLET TYPE 7	1.00	EACH		$	
1120	01559		DROP BOX INLET TYPE 13G	8.00	EACH		$	
1130	01568		DROP BOX INLET TYPE 13S	2.00	EACH		$	
1140	01577		DROP BOX INLET TYPE 14	3.00	EACH		$	
1150	01653		JUNCTION BOX-SPECIAL	3.00	EACH		$	
1160	01719		ADJUST INLET	1.00	EACH		$	
1170	01756		MANHOLE TYPE A	5.00	EACH		$	
1180	01767		MANHOLE TYPE C	12.00	EACH		$	
1190	01770		MANHOLE TYPE C SPECIAL	1.00	EACH		$	
1200	02483		CHANNEL LINING CLASS II	571.00	TON		$	
1210	02607		FABRIC-GEOTEXTILE CLASS 2 FOR PIPE	11,538.00	SQYD	$2.00	$	$23,076.00
1220	05950		EROSION CONTROL BLANKET	10,200.00	SQYD		$	
1230	23274EN11F		TURF REINFORCEMENT MAT 1	964.00	SQYD		$	
1240	23609ED		HYDRAULIC CONTROL STRUCTURE STA 144+58.88	1.00	LS		$	
1250	23609ED		HYDRAULIC CONTROL STRUCTURE STA. 138+97.15	1.00	LS		$	

261521

PROPOSAL BID ITEMS

Report Date 11/16/26

Section: 0004 - UTILITY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1260	15000		S BYPASS PUMPING	5.00	EACH		$	
1270	15012		S ENCASEMENT CONCRETE	20.00	LF		$	
1280	15086		S LATERAL CLEANOUT	5.00	EACH		$	
1290	15088		S LATERAL LONG SIDE 06 INCH	4.00	EACH		$	
1300	15090		S LATERAL SHORT SIDE 06 INCH	1.00	EACH		$	
1310	15092		S MANHOLE	10.00	EACH		$	
1320	15093		S MANHOLE ABANDON/REMOVE	6.00	EACH		$	
1330	15094		S MANHOLE ADJUST TO GRADE	9.00	EACH		$	
1340	15099		S MANHOLE TAP EXISTING	1.00	EACH		$	
1350	15101		S MANHOLE WITH DROP	1.00	EACH		$	
1360	15112		S PIPE PVC 08 INCH	1,275.00	LF		$	
1370	24845EC		UTILITY COORDINATION	1.00	LS		$	

Section: 0005 - SIGNALIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1380	04740		POLE BASE	84.00	EACH		$	
1390	04780		FUSED CONNECTOR KIT	28.00	EACH		$	
1400	04795		CONDUIT-2 IN	41.00	LF		$	
1410	04811		ELECTRICAL JUNCTION BOX TYPE B	1.00	EACH		$	
1420	04820		TRENCHING AND BACKFILLING	20,244.00	LF		$	
1430	04821		OPEN CUT ROADWAY	695.00	LF		$	
1440	04841		CABLE-NO. 14/2C	3,085.00	LF		$	
1450	04844		CABLE-NO. 14/5C	75.00	LF		$	
1460	04845		CABLE-NO. 14/7C	6,655.00	LF		$	
1470	04885		MESSENGER-10800 LB	190.00	LF		$	
1480	04886		MESSENGER-15400 LB	970.00	LF		$	
1490	04932		INSTALL STEEL STRAIN POLE	10.00	EACH		$	
1500	04941		REMOVE POLE BASE	13.00	EACH		$	
1510	06472		INSTALL SPAN MOUNTED SIGN	4.00	EACH		$	
1520	20093NS835		INSTALL PEDESTRIAN HEAD-LED	14.00	EACH		$	
1530	20188NS835		INSTALL LED SIGNAL-3 SECTION	23.00	EACH		$	
1540	20266ES835		INSTALL LED SIGNAL- 4 SECTION	4.00	EACH		$	
1550	20391NS835		ELECTRICAL JUNCTION BOX TYPE A	15.00	EACH		$	
1560	20392NS835		ELECTRICAL JUNCTION BOX TYPE C	16.00	EACH		$	
1570	20457NS835		INSTALL PED DETECTOR-AUDIBLE	14.00	EACH		$	
1580	21077ED		FIBER OPTIC CABLE	8,100.00	LF		$	
1590	23157EN		TRAFFIC SIGNAL POLE BASE	41.00	CUYD		$	
1600	23222EC		INSTALL SIGNAL PEDESTAL	8.00	EACH		$	
1610	24121EC		HDPE CONDUIT-2 IN-SCHEDULE 80	6,940.00	LF		$	
1620	24528ED		TETHER WIRE	500.00	LF		$	
1630	24900EC		PVC CONDUIT-1 1/4 IN-SCHEDULE 80	145.00	LF		$	
1640	24901EC		PVC CONDUIT-2 IN-SCHEDULE 80	14,643.00	LF		$	
1650	24908EC		INSTALL SIGNAL CONTROLLER-TY ATC	2.00	EACH		$	
1660	24922EC		FIBER OPTIC SPLICE ENCLOSURE	2.00	EACH		$	
1670	24923EC		CABINET FIBER TERMINATION PANEL	2.00	EACH		$	
1680	24955ED		REMOVE SIGNAL EQUIPMENT	3.00	EACH		$	

261521

PROPOSAL BID ITEMS

Report Date 11/16/26

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1690	26119EC		INSTALL RADAR PRESENCE DETECTOR TYPE A	8.00	EACH		$	
1700	26171EC		RECTANGULAR RAPID FLASHING BEACON	8.00	EACH		$	
1710	26246EC		INSTALL SOLAR SCHOOL FLASHER ASSEMBLY	1.00	EACH		$	

Section: 0006 - MOBILIZATION/DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1720	02568		MOBILIZATION	1.00	LS		$	
1730	02569		DEMOBILIZATION	1.00	LS		$	

COUNTY OF	ITEM NO.	SHEET NO.
FAYETTE	07-8902.00	R2L

PAVING AREAS

ITEM	7-8902											
	KY 1927 BG. TO STA. 112+50	KY 1927 STA. 112+50 TO END	OLD ROSEBUD/ KINGSBURY	FORTUNE DRIVE	KY 4	DRIVEWAYS	MULTI-USE PATH	MAINTENANCE OF TRAFFIC		ALLOWANCE		7-8902 TOTAL
	SQUARE YARDS											
1.50'' CL3 ASPH SURF 0.38A PG 64-22	6,076	36,119	4,139	408	1,662							48,404
1.50'' CL2 ASPH SURF 0.38D PG 64-22						1,192	6,306					7,498
3.25'' CL3 ASPH BASE 1.00D PG 64-22	1,745	35,358	4,139	408	57			2,138				43,845
3.25'' CL3 ASPH BASE 1.00D PG 64-22	1,588	35,952	4,139	408	48			2,138				44,273
3.00'' CL2 ASPH BASE 1.00D PG64-22						1,222	6,464					7,686
LEVELING & WEDGING PG64-22 (4)	2,505				650	17		280				3,452
ASPHALT MATERIAL FOR TACK NON-TRACKING	10,326	71,477	8,278	816	2,369	1,222	6,464	2,138				103,090
11.00'' JPC PAVEMENT		368										368
4.00'' DGA BASE						2,191						2,191
6.00'' DGA BASE	4,254 (9)	42,236	4,957	480	48			2,138				54,113
6.00'' DGA BASE FOR SUBGRADE STABILIZATION		507	992	480	48			1,069 (6)		203 (7)		3,299
8.00'' DGA BASE						1,282	6,779					8,061
12.00'' CRUSHED AGGREGATE SIZE NO 2	4,037	41,729	3,965							4,974 (5)		54,705
1.50'' ASPHALT PAVE MILLING AND TEXTURING	4,488	811			1,614							6,913
3.25'' ASPHALT PAVE MILLING AND TEXTURING	1,238	5,853										7,091

NOTES:

1. ESTIMATED AT 110 POUNDS PER SQUARE YARD PER INCH OF DEPTH.
2. ESTIMATED AT 115 POUNDS PER SQUARE YARD PER INCH OF DEPTH.
3. ESTIMATED AT 0.70 POUNDS PER SQUARE YARD.
4. AS SHOWN ON THE CROSS SECTIONS AND DETAIL SHEETS.
5. ALLOWANCE QUANTITY PER GEOTECHNICAL RECOMMENDATION NO. 11 ON SHEET R134. ESTIMATED AS 10% OF THE SUBGRADE AREA.
6. INCLUDES 1,600 TONS FOR DGA WEDGE AND TEMPORARY SHOULDER FOR MAINTENANCE OF TRAFFIC.
7. ALLOWANCE QUANTITY FOR SUBGRADE STABLIZATION OF TEMPORARY PAVEMENT. ESTIMATED AS 50% OF THE TEMPORARY WIDENING.
8. TO BE DYED AND STAMPED AS DESCRIBED ON SHEET R2C NOTE 3
9. QUANTITY DOUBLED FOR TWO 6-INCH LIFTS
10. INCLUDES 800 TONS TO MAINTAIN ACCESS TO DRIVEWAYS AND ENTRANCES DURING CONSTRUCTION.

PAVING SUMMARY

ITEM	DESCRIPTION	UNIT	7-8902											
			KY 1927 BG. TO STA. 112+50	KY 1927 STA. 112+50 TO END	OLD ROSEBUD/ KINGSBURY	FORTUNE DRIVE	KY 4	DRIVEWAYS	MULTI-USE PATH	MAINTENANCE OF TRAFFIC		ALLOWANCE		7-8902 TOTAL
00001	DGA BASE (2)	TON	1,468	16,099	2,053	332	34	1,094	3,119	2,707 (6)		71 (7)		26,977
00078	CRUSHED AGGREGATE SIZE NO 2 (2)	TON	2,786	28,794	2,736							3,433 (5)		37,749
00190	LEVELING & WEDGING PG64-22 (1)	TON	700				67	3		40				810
00212	CL2 ASPH BASE 1.00D PG64-22 (1)	TON						202	1,067					1,269
00214	CL3 ASPH BASE 1.00D PG64-22 (1)	TON	596	12,747	1,480	146	19			765				15,753
00301	CL2 ASPH SURF 0.38D PG64-22 (1)	TON						99	521					620
02071	JPC PAVEMENT-11 IN (8)	SQYD		368										368
02677	ASPHALT PAVE MILLING & TEXTURING (1)	TON	592	1,114			134							1,840
22906ES4	CL3 ASPH SURF 0.38A PG64-22 (1)	TON	502	2,980	342	34	138							3,996
24970EC	ASPHALT MATERIAL FOR TACK NON-TRACKING (3)	TON	3.62	25.02	2.90	0.29	0.83	0.43	2.27	0.75				36.11
00020	TRAFFIC BOUND BASE	TON								800 (10)				800

FILE NAME: 07_8902_00_SUMMARY_TABLES.DGN
USER: ChelseaB
DATE PLOTTED: March 20, 2026
OpenRoads Designer v23.00.01.11

PAVING SUMMARY

COUNTY OF	ITEM NO.	SHEET NO.
FAYETTE	07-8902.00	R2L

REVISED 11-12-26

PAVING AREAS

ITEM	7-8902											
	KY 1927 BG. TO STA. 112+50	KY 1927 STA. 112+50 TO END	OLD ROSEBUD/ KINGSBURY	FORTUNE DRIVE	KY 4	DRIVEWAYS	MULTI-USE PATH	MAINTENANCE OF TRAFFIC		ALLOWANCE		7-8902 TOTAL
	SQUARE YARDS											
1.50'' CL3 ASPH SURF 0.38A PG 64-22	6,076	36,119	4,139	408	1,662							48,404
1.50'' CL2 ASPH SURF 0.38D PG 64-22						1,192	6,306					7,498
3.25'' CL3 ASPH BASE 1.00D PG 64-22	1,745	35,358	4,139	408	57			2,138				43,845
3.25'' CL3 ASPH BASE 1.00D PG 64-22	1,588	35,952	4,139	408	48			2,138				44,273
3.00'' CL2 ASPH BASE 1.00D PG64-22						1,222	6,464					7,686
LEVELING & WEDGING PG64-22 (4)	2,505				650	17		280				3,452
ASPHALT MATERIAL FOR TACK NON-TRACKING	10,326	71,477	8,278	816	2,369	1,222	6,464	2,138				103,090
11.00'' JPC PAVEMENT		368										368
4.00'' DGA BASE						2,191						2,191
6.00'' DGA BASE	4,254 (9)	42,236	4,957	480	48			2,138				54,113
6.00'' DGA BASE FOR SUBGRADE STABILIZATION		507	992	480	48			1,069 (6)		203 (7)		3,299
8.00'' DGA BASE						1,282	6,779					8,061
12.00'' CRUSHED AGGREGATE SIZE NO 2	4,037	41,729	3,965							4,974 (5)		54,705
1.50'' ASPHALT PAVE MILLING AND TEXTURING	4,488	811			1,614							6,913
3.25'' ASPHALT PAVE MILLING AND TEXTURING	1,238	5,853										7,091

NOTES:

1. ESTIMATED AT 110 POUNDS PER SQUARE YARD PER INCH OF DEPTH.
2. ESTIMATED AT 115 POUNDS PER SQUARE YARD PER INCH OF DEPTH.
3. ESTIMATED AT 0.70 POUNDS PER SQUARE YARD.
4. AS SHOWN ON THE CROSS SECTIONS AND DETAIL SHEETS.
5. ALLOWANCE QUANTITY PER GEOTECHNICAL RECOMMENDATION NO. 11 ON SHEET R134. ESTIMATED AS 10% OF THE SUBGRADE AREA.
6. INCLUDES 1,600 TONS FOR DGA WEDGE AND TEMPORARY SHOULDER FOR MAINTENANCE OF TRAFFIC.
7. ALLOWANCE QUANTITY FOR SUBGRADE STABLIZATION OF TEMPORARY PAVEMENT. ESTIMATED AS 50% OF THE TEMPORARY WIDENING.
8. TO BE DYED AND STAMPED AS DESCRIBED ON SHEET R2C NOTE 3
9. QUANTITY DOUBLED FOR TWO 6-INCH LIFTS
10. INCLUDES 800 TONS TO MAINTAIN ACCESS TO DRIVEWAYS AND ENTRANCES DURING CONSTRUCTION.

PAVING SUMMARY

ITEM	DESCRIPTION	UNIT	7-8902											
			KY 1927 BG. TO STA. 112+50	KY 1927 STA. 112+50 TO END	OLD ROSEBUD/ KINGSBURY	FORTUNE DRIVE	KY 4	DRIVEWAYS	MULTI-USE PATH	MAINTENANCE OF TRAFFIC		ALLOWANCE		7-8902 TOTAL
00001	DGA BASE (2)	TON	1,468	16,099	2,053	332	34	1,094	3,119	2,707 (6)		71 (7)		26,977
00078	CRUSHED AGGREGATE SIZE NO 2 (2)	TON	2,786	28,794	2,736							3,433 (5)		37,749
00190	LEVELING & WEDGING PG64-22 (1)	TON	700				67	3		40				810
00212	CL2 ASPH BASE 1.00D PG64-22 (1)	TON						202	1,067					1,269
00214	CL3 ASPH BASE 1.00D PG64-22 (1)	TON	596	12,747	1,480	146	19			765				15,753
00301	CL2 ASPH SURF 0.38D PG64-22 (1)	TON						99	521					620
02071	JPC PAVEMENT-11 IN (8)	SQYD		368										368
02677	ASPHALT PAVE MILLING & TEXTURING (1)	TON	592	1,114			134							1,840
22906ES4	CL3 ASPH SURF 0.38A PG64-22 (1)	TON	502	2,980	342	34	138							3,996
24970EC	ASPHALT MATERIAL FOR TACK NON-TRACKING (3)	TON	3.62	25.02	2.90	0.29	0.83	0.43	2.27	0.75				36.11
00020	TRAFFIC BOUND BASE	TON								800 (10)				800

FILE NAME: 07_8902_00_SUMMARY_TABLES.DGN
USER: ChelseaB
DATE PLOTTED: March 20, 2026
OpenRoads Designer v23.00.01.11

PAVING SUMMARY

COUNTY OF	ITEM NO.	SHEET NO.
FAYETTE	07-8902.00	R2N

GENERAL NOTES

UNLESS NOTED OTHERWISE, ALL WORK SHALL BE IN ACCORDANCE WITH THE CURRENT EDITION OF THE KENTUCKY DEPARTMENT OF HIGHWAYS STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, INCLUDING SUPPLEMENTAL SPECIFICATIONS.

SEE BID PROPOSAL FOR SPECIAL PROVISIONS RELATED TO MODIFICATIONS TO STANDARD PAY ITEMS AND NON-STANDARD PAY ITEMS.

BEFORE YOU DIG

THE CONTRACTOR IS INSTRUCTED TO CALL 1-800-752-6007 TO REACH KY 811, THE ONE-CALL SYSTEM FOR INFORMATION ON THE LOCATION OF EXISTING UNDERGROUND UTILITIES. THE CALL IS TO BE PLACED A MINIMUM OF TWO (2) AND NO MORE THAN TEN (10) BUSINESS DAYS PRIOR TO EXCAVATION. THE CONTRACTOR SHOULD BE AWARE THAT OWNERS OF UNDERGROUND FACILITIES ARE NOT REQUIRED TO BE MEMBERS OF THE KY 811 ONE-CALL BEFORE-U-DIG (BUD) SERVICE. THE CONTRACTOR MUST COORDINATE EXCAVATION WITH THE UTILITY OWNERS, INCLUDING THOSE WHOM DO NOT SUBSCRIBE TO KY 811. IT MAY BE NECESSARY FOR THE CONTRACTOR TO CONTACT THE COUNTY COURT CLERK TO DETERMINE WHAT UTILITY COMPANIES HAVE FACILITIES IN THE AREA.

STANDARD DRAWINGS

STANDARD DRAWINGS ARE NOT ATTACHED TO THESE PLANS. A STANDARD DRAWING BOOK AND THE HEADWALL SUPPLEMENTAL BOOK MAY BE OBTAINED FROM THE POLICY SUPPORT BRANCH OF THE DEPARTMENT OF ADMINISTRATIVE SERVICES IN FRANKFORT, KY. AT (502) 564-4610.

NOTICE - CAUTION - CLASSIFICATION

WITHOUT REGARDS TO THE MATERIALS ENCOUNTERED, ALL ROADWAY AND DRAINAGE EXCAVATION SHALL BE UNCLASSIFIED AND SHALL BE DESIGNATED AS 'ROADWAY EXCAVATION'. IT SHALL BE DISTINCTLY UNDERSTOOD THAT ANY REFERENCE TO ROCK, EARTH, OR ANY OTHER MATERIAL ON THE PLANS OR CROSS SECTIONS, WHETHER IN NUMBERS, WORDS, LETTERS, OR LINES, IS SOLELY FOR THE DEPARTMENT'S INFORMATION AND IS NOT TO BE TAKEN AS AN INDICATION OF CLASSIFIED EXCAVATION OR THE QUANTITY OF EITHER ROCK, EARTH, OR ANY OTHER MATERIAL INVOLVED. THE BIDDER MUST DRAW HIS OWN CONCLUSION AS TO THE CONDITIONS TO BE ENCOUNTERED. THE DEPARTMENT DOES NOT GIVE ANY GUARANTEE AS TO THE ACCURACY OF THE DATA AND NO CLAIM WILL BE CONSIDERED FOR ADDITIONAL COMPENSATION IF THE MATERIALS ENCOUNTERED ARE NOT IN ACCORD WITH THE CLASSIFICATION SHOWN.

ASPHALT PAVEMENT RIDE QUALITY

PAVEMENT RIDEABILITY REQUIREMENTS, IN ACCORDANCE WITH SECTION 410 OF THE STANDARD SPECIFICATIONS SHALL APPLY ON THIS PROJECT. CATEGORY A SHALL APPLY.

COMPACTION OF ASPHALT MIXTURES

WILL ACCEPT THE COMPACTION OF ASPHALT MIXTURES FURNISHED FOR DRIVING LANES AND RAMPS AT ONE INCH OR GREATER ON THIS PROJECT BY OPTION A ACCORDING TO SUBSECTIONS 402 AND 403 OF THE CURRENT STANDARD SPECIFICATIONS. USE JOINT CORES AS DESCRIBED IN SUBSECTION 402.03.02 FOR SURFACE MIXTURES ONLY. WILL ACCEPT THE COMPACTION OF ALL OTHER ASPHALT MIXTURES BY OPTION B.

EDGE KEY

THIS WORK INCLUDES CUTTING OUT THE EXISTING ASPHALT SURFACE TO A MINIMUM DEPTH AND WIDTH AS DETAILED ELSEWHERE IN THE PLANS SO THAT THE NEW SURFACE MAY HEEL INTO THE EXISTING SURFACE. THE CONTRACT UNIT PRICE BID LINEAR FOOT (PER METER) FOR "EDGE KEY" INCLUDES ALL NECESSARY MATERIALS, LABOR AND EQUIPMENT NECESSARY TO PERFORM THE WORK AND DISPOSE OF THE REMOVED ASPHALT MATERIAL.

DEPARTMENT OF THE ARMY PERMIT AND WATER QUALITY CERTIFICATION APPROVALS

A DEPARTMENT OF THE ARMY (DA) PERMIT, WHICH MAY REQUIRE APPROVAL OF A STATE WATER QUALITY CERTIFICATION FROM THE KENTUCKY DIVISION OF WATER, REGULATES THIS PROJECT AT ONE OR MORE LOCATIONS. PERFORM ALL APPLICABLE WORK IN COMPLIANCE WITH THE CONDITIONS STATED IN THE DA PERMIT AND THE APPROVED WATER QUALITY CERTIFICATION. POST A COPY OF THE DA PERMIT AND THE WATER QUALITY CERTIFICATION IN A CONSPICUOUS PLACE AT THE PROJECT SITE. IF A DA PERMIT OR WATER QUALITY CERTIFICATION APPROVAL IS PENDING, DO NOT WORK IN OR DISTURB THE DESIGNATED AREA(S) UNTIL OBTAINING THE APPROPRIATE APPROVAL(S). REFER TO NOTICE(S) CONTAINED IN THE CONTRACT BID PROPOSAL FOR DESIGNATED AREA(S) WHERE WORK IS PROHIBITED BY THE ABSENCE OF APPROVAL.

SPECIAL NOTES

11F FOR TURF REINFORCING MAT
FOR INLAID PAVEMENT MARKERS
FOR TREE REMOVAL
FOR UTILITY COORDINATION

GENERAL NOTES

OpenRoads Designer v23.00.01.11
USER: ChaseW
DATE PLOTTED: September 3, 2026
FILE NAME: 07_8902_00_GENERAL NOTES.DGN

COUNTY OF	ITEM NO.	SHEET NO.
FAYETTE	07-8902.00	R2N

REVISED 11-12-26

GENERAL NOTES

UNLESS NOTED OTHERWISE, ALL WORK SHALL BE IN ACCORDANCE WITH THE CURRENT EDITION OF THE KENTUCKY DEPARTMENT OF HIGHWAYS STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, INCLUDING SUPPLEMENTAL SPECIFICATIONS.

SEE BID PROPOSAL FOR SPECIAL PROVISIONS RELATED TO MODIFICATIONS TO STANDARD PAY ITEMS AND NON-STANDARD PAY ITEMS.

BEFORE YOU DIG

THE CONTRACTOR IS INSTRUCTED TO CALL 1-800-752-6007 TO REACH KY 811, THE ONE-CALL SYSTEM FOR INFORMATION ON THE LOCATION OF EXISTING UNDERGROUND UTILITIES. THE CALL IS TO BE PLACED A MINIMUM OF TWO (2) AND NO MORE THAN TEN (10) BUSINESS DAYS PRIOR TO EXCAVATION. THE CONTRACTOR SHOULD BE AWARE THAT OWNERS OF UNDERGROUND FACILITIES ARE NOT REQUIRED TO BE MEMBERS OF THE KY 811 ONE-CALL BEFORE-U-DIG (BUD) SERVICE. THE CONTRACTOR MUST COORDINATE EXCAVATION WITH THE UTILITY OWNERS, INCLUDING THOSE WHOM DO NOT SUBSCRIBE TO KY 811. IT MAY BE NECESSARY FOR THE CONTRACTOR TO CONTACT THE COUNTY COURT CLERK TO DETERMINE WHAT UTILITY COMPANIES HAVE FACILITIES IN THE AREA.

STANDARD DRAWINGS

STANDARD DRAWINGS ARE NOT ATTACHED TO THESE PLANS. A STANDARD DRAWING BOOK AND THE HEADWALL SUPPLEMENTAL BOOK MAY BE OBTAINED FROM THE POLICY SUPPORT BRANCH OF THE DEPARTMENT OF ADMINISTRATIVE SERVICES IN FRANKFORT, KY. AT (502) 564-4610.

NOTICE - CAUTION - CLASSIFICATION

WITHOUT REGARDS TO THE MATERIALS ENCOUNTERED, ALL ROADWAY AND DRAINAGE EXCAVATION SHALL BE UNCLASSIFIED AND SHALL BE DESIGNATED AS 'ROADWAY EXCAVATION'. IT SHALL BE DISTINCTLY UNDERSTOOD THAT ANY REFERENCE TO ROCK, EARTH, OR ANY OTHER MATERIAL ON THE PLANS OR CROSS SECTIONS, WHETHER IN NUMBERS, WORDS, LETTERS, OR LINES, IS SOLELY FOR THE DEPARTMENT'S INFORMATION AND IS NOT TO BE TAKEN AS AN INDICATION OF CLASSIFIED EXCAVATION OR THE QUANTITY OF EITHER ROCK, EARTH, OR ANY OTHER MATERIAL INVOLVED. THE BIDDER MUST DRAW HIS OWN CONCLUSION AS TO THE CONDITIONS TO BE ENCOUNTERED. THE DEPARTMENT DOES NOT GIVE ANY GUARANTEE AS TO THE ACCURACY OF THE DATA AND NO CLAIM WILL BE CONSIDERED FOR ADDITIONAL COMPENSATION IF THE MATERIALS ENCOUNTERED ARE NOT IN ACCORD WITH THE CLASSIFICATION SHOWN.

ASPHALT PAVEMENT RIDE QUALITY

PAVEMENT RIDEABILITY REQUIREMENTS, IN ACCORDANCE WITH SECTION 410 OF THE STANDARD SPECIFICATIONS SHALL APPLY ON THIS PROJECT. CATEGORY A SHALL APPLY.

COMPACTION OF ASPHALT MIXTURES

WILL ACCEPT THE COMPACTION OF ASPHALT MIXTURES FURNISHED FOR DRIVING LANES AND RAMPS AT ONE INCH OR GREATER ON THIS PROJECT BY OPTION A ACCORDING TO SUBSECTIONS 402 AND 403 OF THE CURRENT STANDARD SPECIFICATIONS. USE JOINT CORES AS DESCRIBED IN SUBSECTION 402.03.02 FOR SURFACE MIXTURES ONLY. WILL ACCEPT THE COMPACTION OF ALL OTHER ASPHALT MIXTURES BY OPTION B.

EDGE KEY

THIS WORK INCLUDES CUTTING OUT THE EXISTING ASPHALT SURFACE TO A MINIMUM DEPTH AND WIDTH AS DETAILED ELSEWHERE IN THE PLANS SO THAT THE NEW SURFACE MAY HEEL INTO THE EXISTING SURFACE. THE CONTRACT UNIT PRICE BID LINEAR FOOT (PER METER) FOR "EDGE KEY" INCLUDES ALL NECESSARY MATERIALS, LABOR AND EQUIPMENT NECESSARY TO PERFORM THE WORK AND DISPOSE OF THE REMOVED ASPHALT MATERIAL.

DEPARTMENT OF THE ARMY PERMIT AND WATER QUALITY CERTIFICATION APPROVALS

A DEPARTMENT OF THE ARMY (DA) PERMIT, WHICH MAY REQUIRE APPROVAL OF A STATE WATER QUALITY CERTIFICATION FROM THE KENTUCKY DIVISION OF WATER, REGULATES THIS PROJECT AT ONE OR MORE LOCATIONS. PERFORM ALL APPLICABLE WORK IN COMPLIANCE WITH THE CONDITIONS STATED IN THE DA PERMIT AND THE APPROVED WATER QUALITY CERTIFICATION. POST A COPY OF THE DA PERMIT AND THE WATER QUALITY CERTIFICATION IN A CONSPICUOUS PLACE AT THE PROJECT SITE. IF A DA PERMIT OR WATER QUALITY CERTIFICATION APPROVAL IS PENDING, DO NOT WORK IN OR DISTURB THE DESIGNATED AREA(S) UNTIL OBTAINING THE APPROPRIATE APPROVAL(S). REFER TO NOTICE(S) CONTAINED IN THE CONTRACT BID PROPOSAL FOR DESIGNATED AREA(S) WHERE WORK IS PROHIBITED BY THE ABSENCE OF APPROVAL.

SPECIAL NOTES

11F FOR TURF REINFORCING MAT
FOR INLAID PAVEMENT MARKERS
FOR TREE REMOVAL
FOR UTILITY COORDINATION

GENERAL NOTES

FILE NAME: 07_8902_00_GENERAL NOTES.DGN
USER: ChaseW
DATE PLOTTED: September 3, 2026
OpenRoads Designer v23.00.01.11