



COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET
www.transportation.ky.gov/

Andy Beshear
GOVERNOR

Jim Gray
SECRETARY

May 19, 2022

CALL NO. 102
CONTRACT ID NO. 221324
ADDENDUM # 1

Subject: Campbell County, STPM 0272 (114)
Letting May 26, 2022

- (1) Revised - Proposal Bid Items - Pages 106-107 of 107
- (2) Revised - Plan Sheet - R2a

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

PROPOSAL BID ITEMS

221324

Page 1 of 2

Report Date 5/19/22

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00001		DGA BASE	167.00	TON		\$	
0020	00022		JPC PAVEMENT DRAINAGE BLANKET	111.00	TON		\$	
0030	00078		CRUSHED AGGREGATE SIZE NO 2	334.00	TON		\$	
0040	02069		JPC PAVEMENT-10 IN	582.00	SQYD		\$	

Section: 0002 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0050	01310		REMOVE PIPE	11.00	LF		\$	
0060	01830		STANDARD INTEGRAL CURB	436.00	LF		\$	
0070	02200		ROADWAY EXCAVATION	760.00	CUYD		\$	
0080	02429		RIGHT-OF-WAY MONUMENT TYPE 1	13.00	EACH		\$	
0090	02432		WITNESS POST	13.00	EACH		\$	
0100	02562		TEMPORARY SIGNS	222.00	SQFT		\$	
0110	02603		FABRIC-GEOTEXTILE CLASS 2	1,200.00	SQYD		\$	
0120	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0130	02671		PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH		\$	
0140	02701		TEMP SILT FENCE	500.00	LF		\$	
0150	02705		SILT TRAP TYPE C	7.00	EACH		\$	
0160	02708		CLEAN SILT TRAP TYPE C	7.00	EACH		\$	
0170	02720		SIDEWALK-4 IN CONCRETE	231.00	SQYD		\$	
0180	02726		STAKING	1.00	LS		\$	
0190	05963		INITIAL FERTILIZER	.01	TON		\$	
0200	05964		MAINTENANCE FERTILIZER	.02	TON		\$	
0210	05990		SODDING	466.00	SQYD		\$	
0220	05992		AGRICULTURAL LIMESTONE	.29	TON		\$	
0230	06406		SBM ALUM SHEET SIGNS .080 IN	186.00	SQFT		\$	
0240	06410		STEEL POST TYPE 1	45.00	LF		\$	
0250	06511		PAVE STRIPING-TEMP PAINT-6 IN	1,530.00	LF		\$	
0260	06515		PAVE STRIPING-PERM PAINT-6 IN	6,183.00	LF		\$	
0270	06517		PAVE STRIPING-PERM PAINT-12 IN	645.00	LF		\$	
0280	06568		PAVE MARKING-THERMO STOP BAR-24IN	141.00	LF		\$	
0290	06574		PAVE MARKING-THERMO CURV ARROW	9.00	EACH		\$	
0300	06575		PAVE MARKING-THERMO COMB ARROW	4.00	EACH		\$	
0310	06576		PAVE MARKING-THERMO ONLY	2.00	EACH		\$	
0320	15094		S MANHOLE ADJUST TO GRADE	1.00	EACH		\$	
0330	20430ED		SAW CUT	481.00	LF		\$	
0340	22664EN		WATER BLASTING EXISTING STRIPE	250.00	LF		\$	
0350	23875NC		REMOVE THERMOPLASTIC ARROWS	4.00	EACH		\$	
0360	24631EC		BARCODE SIGN INVENTORY	25.00	EACH		\$	

Section: 0003 - DRAINAGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0370	00462		CULVERT PIPE-18 IN	19.00	LF		\$	

PROPOSAL BID ITEMS

221324

Page 2 of 2

Report Date 5/19/22

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0380	00468		CULVERT PIPE-36 IN	11.00	LF		\$	
0390	01000		PERFORATED PIPE-4 IN	491.00	LF		\$	
0400	01015		INSPECT & CERTIFY EDGE DRAIN SYSTEM	1.00	LS		\$	
0410	01456		CURB BOX INLET TYPE A	3.00	EACH		\$	
0420	01642		JUNCTION BOX-18 IN	2.00	EACH		\$	
0430	01645		JUNCTION BOX-36 IN	1.00	EACH		\$	
0440	01705		REMOVE CURB & GUTTER BOX INLET	3.00	EACH		\$	
0450	01740		CORED HOLE DRAINAGE BOX CON-4 IN	6.00	EACH		\$	
0460	02607		FABRIC-GEOTEXTILE CLASS 2 FOR PIPE (REVISED 5-19-22)	57.00	SQYD	\$2.00	\$	\$114.00

Section: 0004 - SIGNALIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0480	04845		CABLE-NO. 14/7C	1,432.00	LF		\$	
0490	06472		INSTALL SPAN MOUNTED SIGN	3.00	EACH		\$	
0500	20188NS835		INSTALL LED SIGNAL-3 SECTION	15.00	EACH		\$	
0510	24955ED		REMOVE SIGNAL EQUIPMENT	2.00	EACH		\$	

Section: 0005 - DEMOBILIZATION &/OR MOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0520	02569		DEMOBILIZATION	1.00	LS		\$	

GENERAL SUMMARY

ITEM	DESCRIPTION	UNIT	TOTAL PROJECT
01310	REMOVE PIPE	LF	11
01705	REMOVE CURB AND GUTTER BOX INLET	EACH	3
01830	STANDARD INTEGRAL CURB	LF	436
02200	ROADWAY EXCAVATION	CUYD	760
02429	RIGHT-OF-WAY MONUMENT TYPE 1	EACH	13
02432	WITNESS POST	EACH	13
02562	TEMPORARY SIGNS	SOFT	222
02569	DEMobilIZATION	LS	1
02603	FABRIC-GEOTEXTILE CLASS 2	SOYD	1200
02650	MAINTAIN & CONTROL TRAFFIC	LS	1
02671	PORTABLE CHANGEABLE MESSAGE SIGN	EACH	2
02701	TEMP SILT FENCE	LF	500
02705	SILT TRAP TYPE C	EACH	7
02708	CLEAN SILT TRAP TYPE C	EACH	7
02720	SIDEWALK-4 IN CONCRETE	SOYD	231
02726	STAKING	LS	1
05963	INITIAL FERTILIZER	TON	0.01
05964	MAINTENANCE FERTILIZER	TON	0.02
05990	SODDING	SOYD	466
05992	AGRICULTURAL LIMESTONE	TON	0.29
06406	SBM ALUM SHEET SIGNS .080 IN	SOFT	186
06410	STEEL POST TYPE 1	LF	45
06511	PAVE STRIPING-TEMP PAINT-6 IN	LF	1530
06515	PAVE STRIPING-PERM PAINT-6 IN	LF	6183
06517	PAVE STRIPING-PERM PAINT-12 IN	LF	645
06568	PAVE MARKING-THERMO STOP BAR-24IN	LF	141
06574	PAVE MARKING-THERMO CURV ARROW	EACH	9
06575	PAVE MARKING-THERMO COMB ARROW	EACH	4
06576	PAVE MARKING-THERMO ONLY	EACH	2
15094	S MANHOLE ADJUST TO GRADE	EACH	1
20430ED	SAW CUT	LF	481
22664EN	WATER BLASTING EXISTING STRIPE	LF	250
23875NC	REMOVE THERMOPLASTIC ARROWS	EACH	4
24631EC	BARCODE SIGN INVENTORY	EACH	25

PAVING SUMMARY

ITEM CODE	ITEM	UNIT	TOTAL PROJECT
00001	DGA BASE	TON	167
00022	JPC PAVEMENT DRAINAGE BLANKET	TON	111
00078	CRUSHED AGGREGATE SIZE NO 2	TON	334
02069	JPC PAVEMENT-10 IN	SOYD	582

PAVING AREAS

DEPTH INCHES	ITEM	S Q U A R E Y A R D S										TOTAL PROJECT
		4	8	10	4	4	9	4	2	1	481	
4	DGA BASE											727
8	CRUSHED AGGREGATE SIZE NO 2											727
10	JPC PAVEMENT-10 IN											582
4	JPC PAVEMENT DRAINAGE BLANKET											582

COUNTY OF	ITEM NO.	SHEET NO.
CAMPBELL	06-443.00	R2a

NOTES

ALL ASPHALT MIXTURES SHALL BE ESTIMATED AT 110 LBS. PER SQ. YD. PER INCH OF DEPTH, UNLESS NOTED OTHERWISE.

- ① ESTIMATED AT 115 LBS. PER SQ. YD. PER INCH OF DEPTH.
- ② ESTIMATED AT 95 LBS. PER SQ. YD. PER INCH OF DEPTH.
- ③ FOR MOT. ALL PERMANENT SIGN QUANTITIES ARE INCLUDED IN THE TRAFFIC PLANS.
- ④ FOR MOT. ALL PERMANENT PAVEMENT STRIPING AND MARKING QUANTITIES ARE INCLUDED IN THE TRAFFIC PLANS.
- ⑤ APPROX. STA 24+64 - 47.00' LT
- ⑦ QTY. INCLUDES:
1573 LF JOHNS HILL RD.,
1925 LF MARSHALL LN
1925 LF NUNN DR.
- ⑧ QTY. INCLUDES:
645 LF JOHNS HILL RD.
- ⑨ QTY. INCLUDES:
47 LF JOHNS HILL RD.,
47 LF MARSHALL LN
47 LF NUNN DR.
- ⑩ QTY. INCLUDES:
5 EA. JOHNS HILL RD.,
2 EA. MARSHALL LN
2 EA. NUNN DR.
- ⑪ QTY. INCLUDES:
2 EA. MARSHALL LN
2 EA. NUNN DR.
- ⑫ QTY. INCLUDES:
2 EA. JOHNS HILL RD.

SHEET NO.	ITEM CODE	UNIT TO BID	COVER DEPTH MINIMUM	DESIGN PH LEVEL	CURB BOX INLET TYPE A	JUNCTION BOX 18 - IN	JUNCTION BOX 36 - IN	CULVERT PIPE 18 - IN	CULVERT PIPE 24 - IN	CULVERT PIPE 36 - IN	FABRIC GEOTEXT CL 2 FOR PIPE	CORED HOLE DRAINAGE BOX CON - 4 - IN	PERFORATED PIPE 4 IN	INSPECT & CERTIFY EDGE DRAIN
R5	24+51.45 - 39.69' LT (CBI - 1)			M	1									
R5	24+51.45 - (PIPE - 18')		4.9	M				9						
R5	24+56.02 - 30.37' LT - (JBX - 1)			M		1								
R5	25+09.93 - 39.76' LT - (CBI - 2)			M	1									
R5	25+09.93 - (PIPE - 36')		7.29	M						11	25			
R5	25+15.23 - 27.57' LT - (JBX - 2)			M		1								
R5	26+80.38 - 39.75' LT (CBI - 3)			M	1									
R5	26+80.38 (PIPE - 18')		3	M				10			17			
R5	26+80.38 - 27.65' LT (JBX - 3)			M		1								
	PERFORATED PIPE QUANTITIES													
R3-5	23+43.90 LT to 28+34.78 LT				3	2	1	19		11	57	6	491	1
	TOTAL PROJECT													

PIPE DRAINAGE SUMMARY

PERFORATED PIPE SUMMARY

<i>Earthwork Quantities</i>	
Emb Bench = 0	
Com Emb = 760	
Emb = 1	

GENERAL, PAVING, PIPE AND PERFORATED PIPE SUMMARY

GENERAL SUMMARY

ITEM	DESCRIPTION	UNIT	TOTAL PROJECT
01310	REMOVE PIPE	LF	11
01705	REMOVE CURB AND GUTTER BOX INLET	EACH	3
01830	STANDARD INTEGRAL CURB	LF	436
02200	ROADWAY EXCAVATION	CUYD	760
02429	RIGHT-OF-WAY MONUMENT TYPE 1	EACH	13
02432	WITNESS POST	EACH	13
02562	TEMPORARY SIGNS	SOFT	222
02569	DEMobilIZATION	LS	1
02603	FABRIC-GEOTEXTILE CLASS 2	SOYD	1200
02650	MAINTAIN & CONTROL TRAFFIC	LS	1
02671	PORTABLE CHANGEABLE MESSAGE SIGN	EACH	2
02701	TEMP SILT FENCE	LF	500
02705	SILT TRAP TYPE C	EACH	7
02708	CLEAN SILT TRAP TYPE C	EACH	7
02720	SIDEWALK-4 IN CONCRETE	SOYD	231
02726	STAKING	LS	1
05963	INITIAL FERTILIZER	TON	0.01
05964	MAINTENANCE FERTILIZER	TON	0.02
05990	SODDING	SOYD	466
05992	AGRICULTURAL LIMESTONE	TON	0.29
06406	SBM ALUM SHEET SIGNS .080 IN	SOFT	186
06410	STEEL POST TYPE 1	LF	45
06511	PAVE STRIPING-TEMP PAINT-6 IN	LF	1530
06515	PAVE STRIPING-PERM PAINT-6 IN	LF	6183
06517	PAVE STRIPING-PERM PAINT-12 IN	LF	645
06568	PAVE MARKING-THERMO STOP BAR-24IN	LF	141
06574	PAVE MARKING-THERMO CURV ARROW	EACH	9
06575	PAVE MARKING-THERMO COMB ARROW	EACH	4
06576	PAVE MARKING-THERMO ONLY	EACH	2
15094	S MANHOLE ADJUST TO GRADE	EACH	1
20430ED	SAW CUT	LF	481
22664EN	WATER BLASTING EXISTING STRIPE	LF	250
23875NC	REMOVE THERMOPLASTIC ARROWS	EACH	4
24631EC	BARCODE SIGN INVENTORY	EACH	25

PAVING SUMMARY

ITEM CODE	ITEM	UNIT	TOTAL PROJECT
00001	DCA BASE	TON	167
00022	JPC PAVEMENT DRAINAGE BLANKET	TON	111
00078	CRUSHED AGGREGATE SIZE NO 2	TON	334
02069	JPC PAVEMENT-10 IN	SOYD	582

PAVING AREAS

DEPTH INCHES	ITEM	S Q U A R E Y A R D S					TOTAL PROJECT
4	DCA BASE						727
8	CRUSHED AGGREGATE SIZE NO 2						727
10	JPC PAVEMENT-10 IN						582
4	JPC PAVEMENT DRAINAGE BLANKET						582

COUNTY OF	ITEM NO.	SHEET NO.
CAMPBELL	06-443.00	R2a

NOTES

ALL ASPHALT MIXTURES SHALL BE ESTIMATED AT 110 LBS. PER SQ. YD. PER INCH OF DEPTH, UNLESS NOTED OTHERWISE.

① ESTIMATED AT 115 LBS. PER SQ. YD. PER INCH OF DEPTH.

② ESTIMATED AT 95 LBS. PER SQ. YD. PER INCH OF DEPTH.

③ FOR MOT. ALL PERMANENT SIGN QUANTITIES ARE INCLUDED IN THE TRAFFIC PLANS.

④ FOR MOT. ALL PERMANENT PAVEMENT STRIPING AND MARKING QUANTITIES ARE INCLUDED IN THE TRAFFIC PLANS.

⑤ APPROX. STA 24+64 - 47.00' LT

⑦ QTY. INCLUDES:
1573 LF JOHNS HILL RD.,
1925 LF MARSHALL LN
1925 LF NUNN DR.

⑧ QTY. INCLUDES:
645 LF JOHNS HILL RD.

⑨ QTY. INCLUDES:
47 LF JOHNS HILL RD.,
47 LF MARSHALL LN
47 LF NUNN DR.

⑩ QTY. INCLUDES:
5 EA. JOHNS HILL RD.,
2 EA. MARSHALL LN
2 EA. NUNN DR.

⑪ QTY. INCLUDES:
2 EA. MARSHALL LN
2 EA. NUNN DR.

⑫ QTY. INCLUDES:
2 EA. JOHNS HILL RD.

Earthwork Quantities
Emb Bench = 0
Com = 760
Emb = 1

PERFORATED PIPE SUMMARY

SHEET NO.	ITEM CODE	UNIT TO BID	COVER DEPTH MINIMUM	DESIGN PH LEVEL	CURB BOX INLET TYPE A	JUNCTION BOX 18 - IN	JUNCTION BOX 36 - IN	CULVERT PIPE 18 - IN	CULVERT PIPE 24 - IN	CULVERT PIPE 36 - IN	FABRIC GEOTEXT CL 2 FOR PIPE	CORED HOLE DRAINAGE BOX CON - 4 - IN	PERFORATED PIPE 4 IN	INSPECT & CERTIFY EDGE DRAIN
R5	24+51.45 - 39.69' LT (CBI - 1)			M	1									
R5	24+51.45 - (PIPE - 18')		4.9	M				9			15			
R5	24+56.02 - 30.37' LT - (JBX - 1)			M		1								
R5	25+09.93 - 39.76' LT - (CBI - 2)			M	1									
R5	25+09.93 - (PIPE - 36')		7.29	M						11	25			
R5	25+15.23 - 27.57' LT - (JBX - 2)			M		1								
R5	26+80.38 - 39.75' LT (CBI - 3)			M	1									
R5	26+80.38 (PIPE - 18')		3	M				10			17			
R5	26+80.38 - 27.65' LT (JBX - 3)			M		1								
	PERFORATED PIPE QUANTITIES													
R3-5	23+43.90 LT to 28+34.78 LT				3	2	1	19		11	57	6	491	1
	TOTAL PROJECT													

PIPE DRAINAGE SUMMARY

GENERAL, PAVING, PIPE AND PERFORATED PIPE SUMMARY