



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

July 22, 2025

CALL NO. 102
CONTRACT ID NO. 251017
ADDENDUM # 2

Subject: Campbell County, STP 8177(004)
Letting July 24, 2025

- (1) Revised - General Summary - Page 27 of 210
- (2) Revised - Proposal Bid Items - Pages 208-210 of 210

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:so
Enclosures

GENERAL SUMMARY

ITEM	DESCRIPTION	UNIT	TOTAL PROJECT
0078	CRUSHED AGGREGATE SIZE NO.2 ①	TON	1000
1791	ADJUST MANHOLE FRAME TO GRADE	EACH	5
1792	ADJUST MANHOLE	EACH	1
1811	STANDARD CURB AND GUTTER MOD	LF	10,198
2014	BARRICADE TYPE III	EACH	9
2159	TEMP DITCH	LF	300
2160	CLEAN TEMP DITCH	LF	150
2200	ROADWAY EXCAVATION	CUYD	6,315
2237	DITCHING	LF	272
2242	WATER ⑤	MGAL	139
2562	TEMPORARY SIGNS ①	SQFT	750
2568	MOBILIZATION	LS	1
2569	DEMOBILIZATION	LS	1
2585	EDGE KEY	LF	226
2604	FABRIC-GEOTEXTILE CLASS 1A ⑫	SQYD	1,449
2650	MAINTAIN & CONTROL TRAFFIC	LS	1
2671	PORTABLE CHANGEABLE MESSAGE SIGN ⑥	EACH	3
2701	TEMP SILT FENCE	LF	300
2704	SILT TRAP TYPE B	EACH	1
2705	SILT TRAP TYPE C	EACH	17
2707	CLEAN SILT TRAP TYPE B	EACH	1
2708	CLEAN SILT TRAP TYPE C	EACH	17
2720	SIDEWALK-4 IN CONCRETE ③	SQYD	512
2721	REMOVE CONCRETE SIDEWALK	SQYD	235
2726	STAKING ⑦	LS	1
3225	TUBULAR MARKERS	EACH	99
5950	EROSION CONTROL BLANKET	SQYD	242
5952	TEMP MULCH	SQYD	1,557
5953	TEMP SEEDING AND PROTECTION	SQYD	1,162
5963	INITIAL FERTILIZER ⑧	TON	0.1
5964	MAINTENANCE FERTILIZER ⑨	TON	1.4
5985	SEEDING AND PROTECTION	SQYD	2,323
5992	AGRICULTURAL LIMESTONE ⑪	TON	1.4
5997	TOPSOIL FURNISHED AND PLACED ④	CUYD	378
6510	PAVE STRIPING-TEMP PAINT-4 IN	LF	16,106
6511	PAVE STRIPING-TEMP PAINT-6 IN	LF	224
6542	PAVE STRIPING-THERMO-6 IN W	LF	9,061
6543	PAVE STRIPING-THERMO-6 IN Y	LF	7,045
6546	PAVE STRIPING-THERMO-12 IN W	LF	224
6550	PAVE STRIPING-TEMP REM TAPE-W	LF	6,753
6551	PAVE STRIPING-TEMP REM TAPE-Y	LF	11,471
6568	PAVE MARKING-THERMO STOP BAR-24IN	LF	242
6574	PAVE MARKING-THERMO CURV ARROW	EACH	9
6613	INLAID PAVEMENT MARKER-B W/R	EACH	92
6614	INLAID PAVEMENT MARKER-B Y/R	EACH	85
10020NS	FUEL ADJUSTMENT	DOLL	24,956
10030NS	ASPHALT ADJUSTMENT	DOLL	52,510
20099ES842	PAVE MARK TEMP PAINT STOP BAR	LF	242
20100ES842	PAVE MARK TEMP PAINT LINE ARROW	EACH	9
20512NS724	RED MAPLE	EACH	3
20550ND	SAWCUT PAVEMENT	LF	180
21289ED	LONGITUDINAL EDGE KEY	LF	1,554
21659NN	RELOCATE SIGNAL HEADS	EACH	20
23158ES505	DETECTABLE WARNINGS	SQFT	90
23319EC	HARDWOOD MULCH ②	SQYD	720
23835EC	STANDARD BARRIER MEDIAN TY 5-MOD	SQYD	402
23839EC	REMOVE CONCRETE MEDIAN	SQYD	423

- NOTES:
- ① TEMPORARY SIGNING SHALL FOLLOW KYTC STANDARD DRAWINGS AND/OR MUTCD AS REQUIRED
 - ② HARDWOOD MULCH COLOR WILL BE MATCHED IN KIND WITH EXISTING
 - ③ 177 SY TO BE USED FOR REPLACEMENT OF COLORED CONCRETE MEDIANS. BAJA RED COLORING WILL BE INCIDENTAL TO BID ITEM.

250 SY QUANTITY TO BE USED AS DIRECTED BY ENGINEER FOR SIDEWALK REPLACEMENT.
 - ④ TO REPLACE MATERIAL EXCAVATED BEHIND CURB
 - ⑤ FOR CONTROLLING DUST CAUSED BY MAINTAINING TRAFFIC ONLY (200 MGAL/MILE)
 - ⑥ PORTABLE CHANGEABLE MESSAGE SIGNS WILL REMAIN THE PROPERTY OF THE CONTRACTOR UPON COMPLETION OF THE PROJECT
 - ⑦ STAKING WILL ALSO INCLUDE ALL WORK ASSOCIATED WITH "NOTES APPLICABLE TO PROJECT" NOTE 11.
 - ⑧ ESTIMATED AT 300 LBS PER ACRE DISTURBED AND CONTAINS A MINIMUM OF 100 LBS OF NITROGEN, 100 LBS OF PHOSPHATE, AND 100 LBS OF POTASH PER ACRE.
 - ⑨ ESTIMATED AT 11.5 LBS PER 1000 SQFT DISTURBED
 - ⑩ ESTIMATED AT 3 TONS PER ACRE DISTURBED
 - ⑪ 1,000 TONS OF CRUSHED STONE AGGREGATE NO.2 ADDED FOR UNDERCUTTING AS DIRECTED BY THE ENGINEER.
 - ⑫ 1,449 SQYD OF FABRIC GEOTEXTILE CLASS 1 ADDED FOR UNDERCUTTING AS DIRECTED BY THE ENGINEER.

251017

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00003		CRUSHED STONE BASE	10,257.00	TON		\$	
0020	00005		GEOGRID REINFORCEMENT FOR SUBGRADE	25,484.00	SQYD		\$	
0030	00190		LEVELING & WEDGING PG64-22	10.00	TON		\$	
0040	00214		CL3 ASPH BASE 1.00D PG64-22	5,692.00	TON		\$	
0050	00216		CL3 ASPH BASE 1.00D PG76-22	5,612.00	TON		\$	
0060	00387		CL3 ASPH SURF 0.38B PG76-22	2,127.00	TON		\$	
0070	02091		REMOVE PAVEMENT	26,843.00	SQYD		\$	
0080	02602		FABRIC-GEOTEXTILE CLASS 1	25,484.00	SQYD		\$	
0090	20071EC		JOINT ADHESIVE	9,476.00	LF		\$	
0100	24891EC		PAVE MOUNT INFRARED TEMP EQUIPMENT	651,339.00	SF		\$	
0110	24970EC		ASPHALT MATERIAL FOR TACK NON-TRACKING	17.00	TON		\$	

Section: 0002 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0120	00078		CRUSHED AGGREGATE SIZE NO 2	1,000.00	TON		\$	
0130	01791		ADJUST MANHOLE FRAME TO GRADE	5.00	EACH		\$	
0140	01792		ADJUST MANHOLE	1.00	EACH		\$	
0150	01811		STANDARD CURB AND GUTTER MOD	10,198.00	LF		\$	
0170	02014		BARRICADE-TYPE III	9.00	EACH		\$	
0180	02159		TEMP DITCH	300.00	LF		\$	
0190	02160		CLEAN TEMP DITCH	150.00	LF		\$	
0200	02200		ROADWAY EXCAVATION	6,315.00	CUYD		\$	
0210	02237		DITCHING	272.00	LF		\$	
0220	02242		WATER	139.00	MGAL		\$	
0230	02562		TEMPORARY SIGNS	750.00	SQFT		\$	
0240	02585		EDGE KEY	226.00	LF		\$	
0250	02604		FABRIC-GEOTEXTILE CLASS 1A	1,449.00	SQYD		\$	
0260	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0270	02671		PORTABLE CHANGEABLE MESSAGE SIGN	3.00	EACH		\$	
0280	02701		TEMP SILT FENCE	300.00	LF		\$	
0290	02704		SILT TRAP TYPE B	1.00	EACH		\$	
0300	02705		SILT TRAP TYPE C	17.00	EACH		\$	
0310	02707		CLEAN SILT TRAP TYPE B	1.00	EACH		\$	
0320	02708		CLEAN SILT TRAP TYPE C	17.00	EACH		\$	
0330	02720		SIDEWALK-4 IN CONCRETE	512.00	SQYD		\$	
0340	02721		REMOVE CONCRETE SIDEWALK	235.00	SQYD		\$	
0350	02726		STAKING	1.00	LS		\$	
0360	03225		TUBULAR MARKERS	99.00	EACH		\$	
0370	05950		EROSION CONTROL BLANKET	242.00	SQYD		\$	
0380	05952		TEMP MULCH	1,557.00	SQYD		\$	
0390	05953		TEMP SEEDING AND PROTECTION	1,162.00	SQYD		\$	

251017

PROPOSAL BID ITEMS

Report Date 7/22/25

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0400	05963		INITIAL FERTILIZER	0.10	TON		\$	
0410	05964		MAINTENANCE FERTILIZER	1.40	TON		\$	
0420	05985		SEEDING AND PROTECTION	2,323.00	SQYD		\$	
0430	05992		AGRICULTURAL LIMESTONE	1.40	TON		\$	
0440	05997		TOPSOIL FURNISHED AND PLACED	378.00	CUYD		\$	
0450	06510		PAVE STRIPING-TEMP PAINT-4 IN	16,106.00	LF		\$	
0460	06511		PAVE STRIPING-TEMP PAINT-6 IN	224.00	LF		\$	
0470	06542		PAVE STRIPING-THERMO-6 IN W	9,061.00	LF		\$	
0480	06543		PAVE STRIPING-THERMO-6 IN Y	7,045.00	LF		\$	
0490	06546		PAVE STRIPING-THERMO-12 IN W	224.00	LF		\$	
0500	06550		PAVE STRIPING-TEMP REM TAPE-W	6,753.00	LF		\$	
0510	06551		PAVE STRIPING-TEMP REM TAPE-Y	11,471.00	LF		\$	
0520	06568		PAVE MARKING-THERMO STOP BAR-24IN	242.00	LF		\$	
0530	06574		PAVE MARKING-THERMO CURV ARROW	9.00	EACH		\$	
0540	06613		INLAID PAVEMENT MARKER-B W/R	92.00	EACH		\$	
0550	06614		INLAID PAVEMENT MARKER-B Y/R	85.00	EACH		\$	
0560	10020NS		FUEL ADJUSTMENT	24,956.00	DOLL	\$1.00	\$	\$24,956.00
0570	10030NS		ASPHALT ADJUSTMENT	52,510.00	DOLL	\$1.00	\$	\$52,510.00
0580	20099ES842		PAVE MARK TEMP PAINT STOP BAR	242.00	LF		\$	
0590	20100ES842		PAVE MARK TEMP PAINT LINE ARROW	9.00	EACH		\$	
0600	20512NS724		RED MAPLE	3.00	EACH		\$	
0610	20550ND		SAWCUT PAVEMENT	180.00	LF		\$	
0620	21289ED		LONGITUDINAL EDGE KEY	1,554.00	LF		\$	
0630	21659NN		RELOCATE SIGNAL HEAD	20.00	EACH		\$	
0640	23158ES505		DETECTABLE WARNINGS	90.00	SQFT		\$	
0650	23319EC		HARDWOOD MULCH	720.00	SQYD		\$	
0660	23835EC		STANDARD BARRIER MEDIAN TY 5-MOD	402.00	SQYD		\$	
0670	23839EC		REMOVE CONCRETE MEDIAN	423.00	SQYD		\$	
0680	24631EC		BARCODE SIGN INVENTORY	1.00	EACH		\$	
0700	26237EC		CONNECTED ARROW PANEL	3.00	MONT		\$	
0710	26248EC		ELECTRONIC DELIVERY MGMT SYSTEM - AGG	1.00	LS		\$	

Section: 0003 - DRAINAGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0720	01000		PERFORATED PIPE-4 IN	5,550.00	LF		\$	
0730	01001		PERFORATED PIPE-6 IN	2,159.00	LF		\$	
0740	01010		NON-PERFORATED PIPE-4 IN	160.00	LF		\$	
0750	01011		NON-PERFORATED PIPE-6 IN	30.00	LF		\$	
0760	01456		CURB BOX INLET TYPE A	4.00	EACH		\$	
0770	01740		CORED HOLE DRAINAGE BOX CON-4 IN	16.00	EACH		\$	
0780	01741		CORED HOLE DRAINAGE BOX CON-6 IN	3.00	EACH		\$	

Section: 0004 - BRIDGE- WEB WALLS

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
------	----------	-----	-------------	----------	------	-----------	----	--------

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0790	08100		CONCRETE-CLASS A	179.40	CUYD		\$	
0800	08150		STEEL REINFORCEMENT	7,896.00	LB		\$	
0810	23378EC		CONCRETE SEALING	3,088.00	SQFT		\$	

Section: 0005 - SIGNING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0820	06407		SBM ALUM SHEET SIGNS .125 IN	20.00	SQFT		\$	
0830	06410		STEEL POST TYPE 1	17.00	LF		\$	

Section: 0006 - TRAFFIC LOOPS

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0840	04793		CONDUIT-1 1/4 IN	40.00	LF		\$	
0850	04820		TRENCHING AND BACKFILLING	32.00	LF		\$	
0860	04830		LOOP WIRE	1,490.00	LF		\$	
0870	04895		LOOP SAW SLOT AND FILL	320.00	LF		\$	
0880	20360ES818		WOOD POST	2.00	EACH		\$	
0890	20468EC		ELECTRICAL JUNCTION BOX-10 X 8 X 4	2.00	EACH		\$	

Section: 0007 - TRAFFIC SIGNAL (ADDED 7-15-25)

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0891	04700		POLE 30 FT MTG HT	2.00	EACH		\$	
0892	04740		POLE BASE	2.00	EACH		\$	
0893	04750		TRANSFORMER BASE	2.00	EACH		\$	
0894	04780		FUSED CONNECTOR KIT	6.00	EACH		\$	
0895	04811		ELECTRICAL JUNCTION BOX TYPE B	4.00	EACH		\$	
0896	04820		TRENCHING AND BACKFILLING	100.00	LF		\$	
0897	04821		OPEN CUT ROADWAY	100.00	LF		\$	
0898	04845		CABLE-NO. 14/7C	700.00	LF		\$	
0899	20188NS835		INSTALL LED SIGNAL-3 SECTION	2.00	EACH		\$	
0901	21543EN		BORE AND JACK CONDUIT	100.00	LF		\$	
0902	24901EC		PVC CONDUIT-2 IN-SCHEDULE 80	175.00	LF		\$	
0903	26119EC		INSTALL RADAR PRESENCE DETECTOR TYPE A	11.00	EACH		\$	

Section: 0008 - MOBILIZATION AND/OR DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0900	02568		MOBILIZATION	1.00	LS		\$	
0910	02569		DEMOBILIZATION	1.00	LS		\$	