



**COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET**
Frankfort, Kentucky 40622
www.transportation.ky.gov/

Matthew G. Bevin
Governor

Greg Thomas
Secretary

November 29, 2017

CALL NO. 103
CONTRACT ID NO. 171052
ADDENDUM # 1

Subject: Jefferson County, NHPP IM 2651 (020)
Letting December 8, 2017

- (1) Revised - Front Sheet
- (2) Revised - Completion Date - Page 4 of 329
- (3) Revised - Note - Page 105 of 329
- (4) Revised - Special Note - Page 136 of 329

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:ks
Enclosures



An Equal Opportunity Employer M/F/D



CALL NO. 103

CONTRACT ID. 171052

JEFFERSON COUNTY

FED/STATE PROJECT NUMBER NHPP IM 2651 (020)

DESCRIPTION I-265

WORK TYPE JPC PAVEMENT REPAIRS - DIAMOND GRINDING

PRIMARY COMPLETION DATE 11/1/2018

LETTING DATE: December 08,2017

Sealed Bids will be received electronically through the Bid Express bidding service until 10:00 AM EASTERN STANDARD TIME December 08,2017. Bids will be publicly announced at 10:00 AM EASTERN STANDARD TIME.

NO PLANS ASSOCIATED WITH THIS PROJECT.

DBE CERTIFICATION REQUIRED - 6.50%

REQUIRED BID PROPOSAL GUARANTY: Not less than 5% of the total bid.

ADMINISTRATIVE DISTRICT - 05

CONTRACT ID - 171052

NHPP IM 2651 (020)

COUNTY - JEFFERSON

PCN - DE05602651752

NHPP IM 2651 (020)

I-265 REPAIR AND GRIND CONCRETE PAVEMENT ON I-265 FROM I-65(MP 10.250) EXTENDING EAST AND ENDING 0.476 MILE EAST OF KY-864 UNDERPASS(MP 15.660)., A DISTANCE OF 05.41 MILES.JPC PAVEMENT REPAIRS - DIAMOND GRINDING SYP NO. 05-02087.00.

GEOGRAPHIC COORDINATES LATITUDE 38:07:00.00 LONGITUDE 85:39:00.00

COMPLETION DATE(S):

COMPLETED BY 11/01/2018

APPLIES TO ENTIRE CONTRACT

PROJECT PHASING & CONSTRUCTION PROCEDURES

No lane closures will be allowed during the following days:

December 23-26, 2017	Christmas Weekend
December 29, 2017-January 1, 2018	New Years Weekend
March 30, 2018-April 1, 2018	Easter Weekend
April 20-22, 2018	Thunder Over Louisville
April 27, 2018-May 6, 2018	Kentucky Derby Week
May 25-28, 2018	Memorial Day Weekend
July 4-8, 2018	Independence Day Weekend
August 2-5, 2018	Street Rod Nationals
August 16-26, 2018	Kentucky State Fair
August 31, 2018-September 3, 2018	Labor Day Weekend
5:00 a.m. to 9:00 p.m.	Monday - Friday

In the event construction extends past the specified contract completion date, additional dates restricting lane closures may apply; the Department will determine these dates.

Traffic may be reduced to one lane in each direction during the following times:

- Weeknights from 9 PM until 5 AM the following morning
- Weekends from 9 PM Friday night until 5 AM the following Monday morning

The normal two lane traffic configuration must be maintained at all other times unless otherwise directed by the Engineer.

Use only one lane closure in each direction of travel at the same time during the hours specified. Lane closures may only be in the active work area. The minimum allowable clear lane width will be 11 feet; however, make provisions for the passage of wide loads up to 16 feet in width, with approval of the Engineer. Use a lane closure all times work is being performed in the lane or adjacent shoulder. Remove existing striping by water blasting. Remove edge lines throughout the project as directed and/or approved by the Engineer. Paint temporary edge lines through the lane closure. Payment for water blasting existing striping will be considered incidental to the bid item "Maintain and Control Traffic".

Approximate full depth pavement repair locations are listed in the proposal. The Engineer will determine the exact location at the time of construction. Once removal of pavement at a particular repair location has begun, work continuously within the parameters outlined above to complete the work and eliminate the "hole". Place Type III Barricades immediately in front of each pavement removal area, if not protected from traffic behind temporary concrete barrier wall, until the new JPC Pavement achieves 3000PSI compressive strength. Payment for Type III Barricades will be considered incidental to the bid item "Maintain and Control Traffic".

**Special Note for Fixed Completion Date and
Liquidated Damages
I-265
Jefferson County
Item No. 5-2087.00**

Contrary to Section 108.09, Liquidated Damages of \$5,000 per calendar day will be assessed for each day or fraction thereof work remains uncompleted beyond the Specified Project Completion Date. This project has a Fixed Project Completion Date of **November 1, 2018**.

In addition to the Liquidated Damages specified above, Liquidated Damages in the following amounts will be charged when a lane closure remains in place during the prohibited period outlined in the Traffic Control Plan:

Mainline & Ramps:	\$10,000 for the first hour or fraction thereof
	\$30,000 for any additional hour or fraction thereof

These hourly disincentives will still be in effect after the Fixed Completion Date and will be charged in addition to the \$5,000 per calendar day if warranted. The Contractor is expected to make every effort to complete the work in order to open the mainline lane closure within a specified timeframe.

Contrary to Section 108.09 of the Standard Specifications, **the disincentive fee will be charged during those periods when seasonal limitations of the Contract prohibit the Contractor from working on a controlling item or operation. This includes the months from December through March.**

All liquidated damages will be applied cumulatively.

All other applicable portions of Section 108 apply.