



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Rebecca Goodman
SECRETARY

September 1, 2026

CALL NO. 104
CONTRACT ID NO. 262055
ADDENDUM # 2

Subject: Daviess County, STP 6000(374)
Letting September 3, 2026

(1) Revised - Special Notes - Page 17 of 89

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

FD05 030 3143 000 003 Project Notes

Contractor is to pave asphalt shoulders separately from mainline.

At the intersection with KY298 at MM0.926, KYTC is planning on installing a round-a-bout. Contractor should contact the cabinet 30 days prior to paving operations to determine the boundary locations for paving. Should the round-a-bout construction not be started at the time of paving operations, the contractor is to mill an edge key starting at the joint with the intersection and taper to zero 150ft from the intersection on each side.

At the intersection with KY3335/Settles Rd. the contractor is to place an edge key 150ft into KY3155/Settles Rd. to be able to place 1.5 inches of asphalt through the intersection.

Beginning at MM 2.8 curb and gutter begins. The curb and gutter section is divided by a concrete median that varies from 4ft to 15ft in width. The typical section for this area (Typical 5) only shows the cross section for one direction at a time.