



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

October 7, 2025

CALL NO. 104
CONTRACT ID NO. 251015
ADDENDUM # 1

Subject: Marion County, STP 7480007
Letting October 23, 2025

- (1) Revised - DBE Goal - Cover Page
- (2) Revised - Proposal Bid Items - Pages 117-120 of 120
- (3) Revised - Plan Sheets - R2H, R2J

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures



CALL NO. 104

CONTRACT ID. 251015

MARION COUNTY

FED/STATE PROJECT NUMBER STP 7480007

DESCRIPTION EAST MAIN STREET(US-68)

WORK TYPE GRADE & DRAIN WITH ASPHALT SURFACE

PRIMARY COMPLETION DATE 11/1/2026

LETTING DATE: October 23,2025

Sealed Bids will be received electronically through the Bid Express bidding service until 10:00 AM EASTERN DAYLIGHT TIME October 23,2025. Bids will be publicly announced at 10:00 AM EASTERN DAYLIGHT TIME.

PLANS AVAILABLE FOR THIS PROJECT.

DBE CERTIFICATION REQUIRED - 0%

REQUIRED BID PROPOSAL GUARANTY: Not less than 5% of the total bid.

PROPOSAL BID ITEMS

Report Date 10/7/25

Page 1 of 4

251015

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00003		CRUSHED STONE BASE	12,532.00	TON		\$	
0020	00100		ASPHALT SEAL AGGREGATE	135.00	TON		\$	
0030	00103		ASPHALT SEAL COAT	19.00	TON		\$	
0040	00190		LEVELING & WEDGING PG64-22	2,689.00	TON		\$	
0050	00214		CL3 ASPH BASE 1.00D PG64-22	6,291.00	TON		\$	
0060	00356		ASPHALT MATERIAL FOR TACK	19.90	TON		\$	
0070	00387		CL3 ASPH SURF 0.38B PG76-22	244.00	TON		\$	
0080	00388		CL3 ASPH SURF 0.38B PG64-22	2,718.00	TON		\$	
0090	02677		ASPHALT PAVE MILLING & TEXTURING	1,408.00	TON		\$	
0100	20071EC		JOINT ADHESIVE	11,701.00	LF		\$	

Section: 0002 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0110	00078		CRUSHED AGGREGATE SIZE NO 2	9,805.00	TON		\$	
0120	01000		PERFORATED PIPE-4 IN	5,332.00	LF		\$	
0130	01010		NON-PERFORATED PIPE-4 IN	138.00	LF		\$	
0140	01015		INSPECT & CERTIFY EDGE DRAIN SYSTEM	1.00	LS		\$	
0150	01020		PERF PIPE HEADWALL TY 1-4 IN	2.00	EACH		\$	
0160	01024		PERF PIPE HEADWALL TY 2-4 IN	4.00	EACH		\$	
0170	01740		CORED HOLE DRAINAGE BOX CON-4 IN	20.00	EACH		\$	
0180	01810		STANDARD CURB AND GUTTER	4,660.00	LF		\$	
0190	01825		ISLAND CURB AND GUTTER	517.00	LF		\$	
0200	02014		BARRICADE-TYPE III	4.00	EACH		\$	
0210	02157		PAVED DITCH TYPE 1	25.00	SQYD		\$	
0220	02159		TEMP DITCH	3,330.00	LF		\$	
0230	02160		CLEAN TEMP DITCH	1,665.00	LF		\$	
0240	02200		ROADWAY EXCAVATION	18,508.00	CUYD		\$	
0250	02230		EMBANKMENT IN PLACE	16,436.00	CUYD		\$	
0260	02237		DITCHING	435.00	LF		\$	
0270	02242		WATER	5.00	MGAL		\$	
0280	02351		GUARDRAIL-STEEL W BEAM-S FACE	200.00	LF		\$	
0290	02360		GUARDRAIL TERMINAL SECTION NO 1	2.00	EACH		\$	
0300	02367		GUARDRAIL END TREATMENT TYPE 1	4.00	EACH		\$	
0310	02383		REMOVE & RESET GUARDRAIL	475.00	LF		\$	
0320	02429		RIGHT-OF-WAY MONUMENT TYPE 1	28.00	EACH		\$	
0330	02432		WITNESS POST	17.00	EACH		\$	
0340	02483		CHANNEL LINING CLASS II	643.00	TON		\$	
0350	02484		CHANNEL LINING CLASS III	31.00	TON		\$	
0360	02545		CLEARING AND GRUBBING 14 ACRES	1.00	LS		\$	
0370	02562		TEMPORARY SIGNS	600.00	SQFT		\$	
0380	02602		FABRIC-GEOTEXTILE CLASS 1	17,675.00	SQYD		\$	
0390	02604		FABRIC-GEOTEXTILE CLASS 1A	17,000.00	SQYD		\$	

MARION COUNTY
STP 7480007
251015

PROPOSAL BID ITEMS

Page 2 of 4

Report Date 10/7/25

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0400	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0410	02671		PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH		\$	
0420	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0430	02690		SAFELOADING	14.00	CUYD		\$	
0440	02701		TEMP SILT FENCE	3,330.00	LF		\$	
0450	02703		SILT TRAP TYPE A	16.00	EACH		\$	
0460	02704		SILT TRAP TYPE B	16.00	EACH		\$	
0470	02705		SILT TRAP TYPE C	16.00	EACH		\$	
0480	02706		CLEAN SILT TRAP TYPE A	16.00	EACH		\$	
0490	02707		CLEAN SILT TRAP TYPE B	16.00	EACH		\$	
0500	02708		CLEAN SILT TRAP TYPE C	16.00	EACH		\$	
0510	02720		SIDEWALK-4 IN CONCRETE	1,673.00	SQYD		\$	
0520	02726		STAKING	1.00	LS		\$	
0530	04953		TEMP RELOCATION OF SIGNAL HEAD	7.00	EACH		\$	
0540	05950		EROSION CONTROL BLANKET	9,601.00	SQYD		\$	
0550	05952		TEMP MULCH	49,800.00	SQYD		\$	
0560	05953		TEMP SEEDING AND PROTECTION	37,350.00	SQYD		\$	
0570	05963		INITIAL FERTILIZER	2.40	TON		\$	
0580	05964		MAINTENANCE FERTILIZER	3.90	TON		\$	
0590	05985		SEEDING AND PROTECTION	74,700.00	SQYD		\$	
0600	05989		SPECIAL SEEDING CROWN VETCH	8,975.00	SQYD		\$	
0610	05990		SODDING	1,988.00	SQYD		\$	
0620	05992		AGRICULTURAL LIMESTONE	46.40	TON		\$	
0630	05997		TOPSOIL FURNISHED AND PLACED	175.00	CUYD		\$	
0640	06511		PAVE STRIPING-TEMP PAINT-6 IN	17,050.00	LF		\$	
0650	06542		PAVE STRIPING-THERMO-6 IN W	14,043.00	LF		\$	
0660	06543		PAVE STRIPING-THERMO-6 IN Y	16,796.00	LF		\$	
0670	06546		PAVE STRIPING-THERMO-12 IN W	156.00	LF		\$	
0680	06547		PAVE STRIPING-THERMO-12 IN Y	1,342.00	LF		\$	
0690	06568		PAVE MARKING-THERMO STOP BAR-24IN	93.00	LF		\$	
0700	06569		PAVE MARKING-THERMO CROSS-HATCH	1,031.00	SQFT		\$	
0710	06574		PAVE MARKING-THERMO CURV ARROW	36.00	EACH		\$	
0720	06575		PAVE MARKING-THERMO COMB ARROW	4.00	EACH		\$	
0730	06610		INLAID PAVEMENT MARKER-MW	3.00	EACH		\$	
0740	06612		INLAID PAVEMENT MARKER-BY	314.00	EACH		\$	
0760	10020NS		FUEL ADJUSTMENT	18,588.00	DOLL	\$1.00	\$	\$18,588.00
0770	10030NS		ASPHALT ADJUSTMENT	46,688.00	DOLL	\$1.00	\$	\$46,688.00
0780	20000ES724		TREE REDBUD 7' HEIGHT/2" CALIPER B&B	3.00	EACH		\$	
0790	20001ES724		SHRUB GOLD COAST JUNIPER 2'-3' B&B	24.00	EACH		\$	
0800	20001ES724		SHRUB HONEY MAIN HOLLY 6'-8' B&B	3.00	EACH		\$	
0810	20001ES724		SHRUB SHORE JUNIPER #2	70.00	EACH		\$	
0820	20191ED		OBJECT MARKER TY 3	4.00	EACH		\$	
0830	22520EN		PAVE MARKING-THERMO YIELD BAR-36 IN	74.00	LF		\$	
0840	23158ES505		DETECTABLE WARNINGS	178.00	SQFT		\$	
0850	23261EC		PAVE MARK-THERMO-X-WALK-24 IN	32.00	LF		\$	
0860	23379EC		STAMPED CONCRETE	1,297.00	SQYD		\$	
0870	23385EC		CONCRETE MEDIAN	647.00	SQYD		\$	

MARION COUNTY
STP 7480007
251015

PROPOSAL BID ITEMS

Page 3 of 4

Report Date 10/7/25

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0880	23646EC		CONTAINER PLANTS CATMINT #3	37.00	EACH		\$	
0890	24814EC		PIPELINE INSPECTION	3,987.00	LF		\$	
0910	26248EC		ELECTRONIC DELIVERY MGMT SYSTEM - AGG	1.00	LS		\$	
0920	26257EC		DECORATIVE ROCK	1,450.00	SQFT		\$	

Section: 0003 - DRAINAGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0930	00440		ENTRANCE PIPE-15 IN	241.00	LF		\$	
0940	00441		ENTRANCE PIPE-18 IN	244.00	LF		\$	
0950	00443		ENTRANCE PIPE-24 IN	68.00	LF		\$	
0960	00462		CULVERT PIPE-18 IN	100.00	LF		\$	
0970	00466		CULVERT PIPE-30 IN	298.00	LF		\$	
0980	00468		CULVERT PIPE-36 IN	42.00	LF		\$	
0990	00470		CULVERT PIPE-48 IN	4.00	LF		\$	
1000	00521		STORM SEWER PIPE-15 IN	102.00	LF		\$	
1010	00522		STORM SEWER PIPE-18 IN	2,396.00	LF		\$	
1020	00524		STORM SEWER PIPE-24 IN	290.00	LF		\$	
1030	00526		STORM SEWER PIPE-30 IN	192.00	LF		\$	
1040	00528		STORM SEWER PIPE-36 IN	10.00	LF		\$	
1050	01204		PIPE CULVERT HEADWALL-18 IN	1.00	EACH		\$	
1060	01208		PIPE CULVERT HEADWALL-24 IN	1.00	EACH		\$	
1070	01210		PIPE CULVERT HEADWALL-30 IN	2.00	EACH		\$	
1080	01212		PIPE CULVERT HEADWALL-36 IN	2.00	EACH		\$	
1090	01432		SLOPED BOX OUTLET TYPE 1-15 IN	5.00	EACH		\$	
1100	01433		SLOPED BOX OUTLET TYPE 1-18 IN	8.00	EACH		\$	
1110	01450		S & F BOX INLET-OUTLET-18 IN	3.00	EACH		\$	
1120	01451		S & F BOX INLET-OUTLET-24 IN	4.00	EACH		\$	
1130	01452		S & F BOX INLET-OUTLET-30 IN	3.00	EACH		\$	
1140	01456		CURB BOX INLET TYPE A	16.00	EACH		\$	
1150	01544		DROP BOX INLET TYPE 11	3.00	EACH		\$	
1160	01568		DROP BOX INLET TYPE 13S	1.00	EACH		\$	
1170	01767		MANHOLE TYPE C	2.00	EACH		\$	
1180	02607		FABRIC-GEOTEXTILE CLASS 2 FOR PIPE	5,588.00	SQYD	\$2.00	\$	\$11,176.00
1190	08100		CONCRETE-CLASS A	13.26	CUYD		\$	
1200	20570ES710		DROP BOX INLET TY 13S(MOD)	1.00	EACH		\$	
1210	21583NN		MODIFY EXISTING DRAINAGE BOX	1.00	EACH		\$	

Section: 0004 - LIGHTING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1220	04701		POLE 40 FT MTG HT	12.00	EACH		\$	
1230	04722		BRACKET 8 FT	9.00	EACH		\$	
1240	04723		BRACKET 10 FT	3.00	EACH		\$	
1250	04740		POLE BASE	12.00	EACH		\$	
1260	04750		TRANSFORMER BASE	12.00	EACH		\$	

PROPOSAL BID ITEMS

Page 4 of 4

Report Date 10/7/25

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1270	04761		LIGHTING CONTROL EQUIPMENT	1.00	EACH		\$	
1280	04780		FUSED CONNECTOR KIT	24.00	EACH		\$	
1290	04820		TRENCHING AND BACKFILLING	1,475.00	LF		\$	
1300	04832		WIRE-NO. 12	1,985.00	LF		\$	
1310	04873		POLE 45 FT WOODEN	1.00	EACH		\$	
1320	20391NS835		ELECTRICAL JUNCTION BOX TYPE A	4.00	EACH		\$	
1330	21543EN		BORE AND JACK CONDUIT	255.00	LF		\$	
1340	23778EC		WIRE-NO. 10	6,200.00	LF		\$	
1350	24589ED		LED LUMINAIRE	12.00	EACH		\$	
1360	24900EC		PVC CONDUIT-1 1/4 IN-SCHEDULE 80	1,125.00	LF		\$	
1370	24901EC		PVC CONDUIT-2 IN-SCHEDULE 80	600.00	LF		\$	
1380	24955ED		REMOVE SIGNAL EQUIPMENT	1.00	EACH		\$	

Section: 0005 - DEMOBILIZATION &/OR MOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1390	02568		MOBILIZATION	1.00	LS		\$	
1400	02569		DEMOBILIZATION	1.00	LS		\$	

GENERAL SUMMARY

NOTES

- ① FOR SUBGRADE STABILIZATION. INCLUDES AND ADDITIONAL 675 SQ.YD. OF CLASS 1 FOR CONSTRUCTION ENTRANCES.
- ② INCLUDES 6 TONS FOR PERFORATED PIPE HEADWALLS, 345 TONS FOR CONSTRUCTION ENTRANCES, AND AN ADDITIONAL 500 TONS TO BE USED AT THE DISCRETION OF THE ENGINEER
- ③ FOR DUST CONTROL WHILE MAINTAINING TRAFFIC
- ④ CARRIED OVER FROM PIPE DRAINAGE SUMMARY
- ⑤ APPROXIMATELY 14 ACRES
- ⑥ ASPHALT PAVE MILLING AND TEXTURING CARRIED ON PAVING SUMMARY
- ⑦ REMOVAL OF PIPES WITHIN THE DISTURB LIMITS SHALL BE INCIDENTAL TO EARTHWORK CONSTRUCTION
- ⑧ INCLUDES ADDITIONAL 5,000 SQ. YD. ON US 68 AND 500 SQ. YD. ON CORPORATE DRIVE FOR 2:1 SIDE SLOPES.
- ⑨ FOR THE TRUCK APRONS & ROUNDABOUT LEG MEDIANS: DYED TO BAJA RED, 2-BAG (PG-28272R, INTERSTAR) AND STAMPED IN A STONE PATTERN. CONCRETE SHALL BE 24-HOUR CURING, 3500 PSI COMPRESSION STRENGTH CONCRETE.
- ⑩ INCLUDES AN ADDITIONAL 30 CY FOR SAW-CUTTING EXISTING PAVEMENT FOR PLACEMENT OF PROPOSED CURB & GUTTER. INCLUDES AN ADDITIONAL 115 CY FOR REMOVAL OF EXISTING PAVEMENT IN CENTER ISLAND.
- ⑪ INCLUDES AN ADDITIONAL 115 CY FOR REFILLING THE EXCAVATED EXISTING PAVEMENT IN CENTER ISLAND.

EARTHWORK QUANTITIES

EXCAVATION	CU YD
COMMON	12,604
DITCH LT	3,252
DITCH RT	591
EMBANKMENT BENCHING	1,916

EMBANKMENT	CU YD
EMBANKMENT	8,390
REFILL	47
SUBGRADE STABILIZATION	5,968
EMBANKMENT BENCHING	1,916

EXCESS

2,042

ESTIMATE FOR EARTHWORK CALCULATIONS IS FOR DESIGN ONLY. THE CONTRACTOR IS ADVISED THAT THE EARTHWORK CALCULATIONS SHOWN ARE FOR INFORMATION ONLY. ASSUMPTIONS FOR SHRINKAGE AND SWELL FACTORS ARE THE CONTRACTOR'S RESPONSIBILITY.

[illegible]

GENERAL SUMMARY

NOTES

REVISÉ: 10-7-25

- ① FOR SUBGRADE STABILIZATION. INCLUDES AND ADDITIONAL 675 SQ.YD. OF CLASS 1 FOR CONSTRUCTION ENTRANCES.
- ② INCLUDES 6 TONS FOR PERFORATED PIPE HEADWALLS, 345 TONS FOR CONSTRUCTION ENTRANCES, AND AN ADDITIONAL 500 TONS TO BE USED AT THE DISCRETION OF THE ENGINEER.
- ③ FOR DUST CONTROL WHILE MAINTAINING TRAFFIC
- ④ CARRIED OVER FROM PIPE DRAINAGE SUMMARY
- ⑤ APPROXIMATELY 14 ACRES
- ⑥ ASPHALT PAVE MILLING AND TEXTURING CARRIED ON PAVING SUMMARY
- ⑦ REMOVAL OF PIPES WITHIN THE DISTURB LIMITS SHALL BE INCIDENTAL TO EARTHWORK CONSTRUCTION
- ⑧ INCLUDES ADDITIONAL 5,000 SQ. YD. ON US 68 AND 500 SQ. YD. ON CORPORATE DRIVE FOR 2:1 SIDE SLOPES.
- ⑨ FOR THE TRUCK APRONS & ROUNDABOUT LEG MEDIANS: DYED TO BAJA RED, 2-BAG (RG-28272R INTERSTAR) AND STAMPED IN A STONE PATTERN. CONCRETE SHALL BE 24-HOUR CURING, 3500 PSI COMPRESSION STRENGTH CONCRETE.
- ⑩ INCLUDES AN ADDITIONAL 30 CY FOR SAW-CUTTING EXISTING PAVEMENT FOR PLACEMENT OF PROPOSED CURB & GUTTER. INCLUDES AN ADDITIONAL 115 CY FOR REMOVAL OF EXISTING PAVEMENT IN CENTER ISLAND.
- ⑪ INCLUDES AN ADDITIONAL 115 CY FOR REFILLING THE EXCAVATED EXISTING PAVEMENT IN CENTER ISLAND.
- ⑫ FOR THE CENTER ISLAND CONCRETE: DYED TO SikaColor 120G C34 DARK GRAY, AND STAMPED IN A STONE PATTERN. CONCRETE SHALL BE 24-HOUR CURING, 3500 PSI COMPRESSION STRENGTH CONCRETE.

EARTHWORK QUANTITIES

EXCAVATION	CU YD
COMMON	12,604
DITCH LT	3,252
DITCH RT	591
EMBANKMENT BENCHING	1,916
	18,363
EMBANKMENT	CU YD
EMBANKMENT	8,390
REFILL	47
SUBGRADE STABILIZATION	5,968
EMBANKMENT BENCHING	1,916
	16,321
EXCESS	2,042

ESTIMATE FOR EARTHWORK CALCULATIONS IS FOR DESIGN ONLY. THE CONTRACTOR IS ADVISED THAT THE EARTHWORK CALCULATIONS SHOWN ARE FOR INFORMATION ONLY. ASSUMPTIONS FOR SHRINKAGE AND SWELL FACTORS ARE THE CONTRACTOR'S RESPONSIBILITY.

[illegible]

