



TRANSPORTATION CABINET

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Steven L. Beshear
Governor

Michael W. Hancock, P.E.
Secretary

March 16, 2011

CALL NO. 104
CONTRACT ID NO. 111012
ADDENDUM # 3

Subject: Various Counties, STP 0031 (007)
Letting March 18, 2011

(1) Revised - Bid Items - Pages 202-208 of 208

Proposal revisions are available at <http://transportation.ky.gov/contract/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Ryan Griffith".

Ryan Griffith
Director
Division of Construction Procurement

RG:ks
Enclosures



An Equal Opportunity Employer M/F/D

CONTRACT ID: 111012
COUNTY: WARREN, DAVIESS, BUTLER, OHIO
PROPOSAL: STP 0031(007)

PAGE: 1
LETTING: 03/18/11
CALL NO: 104

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
ALT GROUPIAA10001 PAVING-CONC WITH CONC SHOULDER						
0010	00001	DGA BASE	67,936.000	TON		
0020	00008	CEMENT STABILIZED ROADBED	130,578.000	SQYD		
0030	00022	JPC PAVEMENT DRAINAGE BLANKET	38,909.000	TON		
0040	00100	ASPHALT SEAL AGGREGATE	681.000	TON		
0050	00291	EMULSIFIED ASPHALT RS-2	85.000	TON		
0060	00358	ASPHALT CURING SEAL	132.000	TON		
0070	02069	JPC PAVEMENT-10 IN	84,295.000	SQYD		
0080	02075	JPC PAVEMENT-6 IN	46,282.000	SQYD		
0090	02542	CEMENT	2,562.000	TON		
0100	02695	RUMBLE STRIPS TYPE 3	38,751.000	LF		
0110	02702	SAND FOR BLOTTER	327.000	TON		
0120	10203ND	PAVEMENT ADJUSTMENT CONC WITH CONC SHOULDER	(1.00)	LS	322,501.00	322,501.00
ALT GROUPIAA20002 PAVING-CONC WITH ASPH SHOULDER						
0130	00001	DGA BASE	67,865.000	TON		
0140	00008	CEMENT STABILIZED ROADBED	130,578.000	SQYD		
0150	00022	JPC PAVEMENT DRAINAGE BLANKET	41,716.000	TON		
0160	00100	ASPHALT SEAL AGGREGATE	681.000	TON		
0170	00212	CL2 ASPH BASE 1.00D PG64-22	10,378.000	TON		
0180	00291	EMULSIFIED ASPHALT RS-2	85.000	TON		
0190	00309	CL2 ASPH SURF 0.50D PG64-22	3,818.000	TON		
0200	00358	ASPHALT CURING SEAL	135.000	TON		

CONTRACT ID: 111012
COUNTY: WARREN, DAVIESS, BUTLER, OHIO
PROPOSAL: STP 0031(007)

PAGE: 2
LETTING: 03/18/11
CALL NO: 104

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
0210	02069	JPC PAVEMENT-10 IN	84,295.000	SQYD		
0220	02542	CEMENT	2,562.000	TON		
0230	02696	SHOULDER RUMBLE STRIPS-SAWED	38,751.000	LF		
0240	02702	SAND FOR BLOTTER	327.000	TON		
0250	10203ND	PAVEMENT ADJUSTMENT CONC WITH ASPH SHOULDER	(1.00)	LS	322,501.00	322,501.00
ALT GROUPIAA30003 PAVING-ASPH WITH ASPH SHOULDER						
0260	00001	DGA BASE	64,791.000	TON		
0270	00008	CEMENT STABILIZED ROADBED	130,578.000	SQYD		
0280	00018	DRAINAGE BLANKET-TYPE II-ASPH	40,104.000	TON		
0290	00100	ASPHALT SEAL AGGREGATE	681.000	TON		
0300	00212	CL2 ASPH BASE 1.00D PG64-22	10,182.000	TON		
0310	00214	CL3 ASPH BASE 1.00D PG64-22	30,961.000	TON		
0320	00216	CL3 ASPH BASE 1.00D PG76-22	7,048.000	TON		
0330	00291	EMULSIFIED ASPHALT RS-2	85.000	TON		
0340	00309	CL2 ASPH SURF 0.50D PG64-22	3,817.000	TON		
0350	00330	CL3 ASPH SURF 0.50A PG64-22	5,674.000	TON		
0360	00332	CL3 ASPH SURF 0.50A PG76-22	1,280.000	TON		
0370	00358	ASPHALT CURING SEAL	131.000	TON		
0380	02542	CEMENT	2,562.000	TON		
0390	02696	SHOULDER RUMBLE STRIPS-SAWED	38,751.000	LF		
0400	02702	SAND FOR BLOTTER	327.000	TON		
0410	10203ND	PAVEMENT ADJUSTMENT ASPHALT	(1.00)	LS	692,394.00	692,394.00

SECTION 0004 ROADWAY

CONTRACT ID: 111012
COUNTY: WARREN, DAVIESS, BUTLER, OHIO
PROPOSAL: STP 0031(007)

PAGE: 3
LETTING: 03/18/11
CALL NO: 104

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
0420	00078	CRUSHED AGGREGATE SIZE NO 2	97.000	TON		
0430	01000	PERFORATED PIPE-4 IN	31,507.000	LF		
0440	01010	NON-PERFORATED PIPE-4 IN	1,147.000	LF		
0450	01015	INSPECT & CERTIFY EDGE DRAIN SYSTEM	(1.00)	LS		
0460	01020	PERF PIPE HEADWALL TY 1-4 IN	9.000	EACH		
0470	01028	PERF PIPE HEADWALL TY 3-4 IN	42.000	EACH		
0480	01032	PERF PIPE HEADWALL TY 4-4 IN	47.000	EACH		
0490	01565	DROP BOX INLET TYPE 13GT	12.000	EACH		
0500	01740	CORED HOLE DRAINAGE BOX CON-4 IN	9.000	EACH		
0510	01982	DELINEATOR FOR GUARDRAIL-WHITE	106.000	EACH		
0520	01983	DELINEATOR FOR GUARDRAIL-YELLOW	67.000	EACH		
0530	02014	BARRICADE-TYPE III	26.000	EACH		
0540	02242	WATER	100.000	MGAL		
0550	02351	GUARDRAIL-STEEL W BEAM-S FACE	11,412.500	LF		
0560	02367	GUARDRAIL END TREATMENT TYPE 1	4.000	EACH		
0570	02369	GUARDRAIL END TREATMENT TYPE 2A	18.000	EACH		
0580	02391	GUARDRAIL END TREATMENT TYPE 4A	13.000	EACH		
0590	02562	SIGNS	887.000	SQFT		
0600	02599	FABRIC-GEOTEXTILE TYPE IV (REVISED: 3-10-11)	27,215.000	SQYD		
0610	02601	FINAL DRESSING CLASS B	26,195.000	LF		
0620	02650	MAINTAIN & CONTROL TRAFFIC	(1.00)	LS		

CONTRACT ID: 111012
 COUNTY: WARREN, DAVIESS, BUTLER, OHIO
 PROPOSAL: STP 0031(007)

PAGE: 4
 LETTING: 03/18/11
 CALL NO: 104

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
0630	02653	LANE CLOSURE	1.000	EACH		
0640	02671	PORTABLE CHANGEABLE MESSAGE SIGN	6.000	EACH		
0650	02726	STAKING	(1.00)	LS		
0660	02775	ARROW PANEL	1.000	EACH		
0670	02929	CRASH CUSHION TYPE IX	2.000	EACH		
0680	05966	TOPDRESSING FERTILIZER	5.000	TON		
0690	05985	SEEDING AND PROTECTION	96,800.000	SQYD		
0700	06417	FLEXIBLE DELINEATOR POST-W	229.000	EACH		
0710	06418	FLEXIBLE DELINEATOR POST-Y	78.000	EACH		
0720	06517	PAVE STRIPING-PERM PAINT-12 IN	3,520.000	LF		
0730	06540	PAVE STRIPING-THERMO-4 IN W	51.000	LF		
0740	06554	PAVE STRIPING-DUR TY 1-4 IN W	185.000	LF		
0750	06555	PAVE STRIPING-DUR TY 1-4 IN Y	171.000	LF		
0760	06568	PAVE MARKING-THERMO STOP BAR-24IN	134.000	LF		
0770	06574	PAVE MARKING-THERMO CURV ARROW	12.000	EACH		
0780	06589	PAVEMENT MARKER TYPE V-MW	11.000	EACH		
0790	06592	PAVEMENT MARKER TYPE V-B W/R	449.000	EACH		
0800	06593	PAVEMENT MARKER TYPE V-B Y/R	287.000	EACH		
0810	08100	CONCRETE-CLASS A	10.740	CUYD		
0820	08150	STEEL REINFORCEMENT	392.000	LB		
0830	08904	CRASH CUSHION TY VI CLASS C (REVISED: 3-16-11)	2.000	EACH		

CONTRACT ID: 111012
COUNTY: WARREN, DAVIESS, BUTLER, OHIO
PROPOSAL: STP 0031(007)

PAGE: 5
LETTING: 03/18/11
CALL NO: 104

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
0840	22854EN	PAVE STRIPE PERM-6 IN HD21-WHITE	37,847.000	LF		
0850	22855EN	PAVE STRIPE PERM-6 IN HD21-YELLOW	31,912.000	LF		
SECTION 0005 SIGNING-WARREN CO.						
0860	04903	REFERENCE MARKER	1,184.000	EACH		
0870	06405	SBM ALUMINUM PANEL SIGNS	6,245.000	SQFT		
0880	06406	SBM ALUM SHEET SIGNS .080 IN	341.300	SQFT		
0890	06407	SBM ALUM SHEET SIGNS .125 IN	1,060.000	SQFT		
0900	06410	STEEL POST TYPE 1	358.800	LF		
0910	06411	STEEL POST TYPE 2	1,729.000	LF		
0920	06412	STEEL POST MILE MARKERS	296.000	EACH		
0930	06417	FLEXIBLE DELINEATOR POST-W	100.000	EACH		
0940	06418	FLEXIBLE DELINEATOR POST-Y	50.000	EACH		
0950	06424	OSS ALUMINUM 65 FT TRUSS	1.000	EACH		
0960	06426	OSS ALUMINUM 70 FT TRUSS	2.000	EACH		
0970	06436	OSS ALUMINUM 75 FT TRUSS	3.000	EACH		
0980	06448	SIGN BRIDGE ATTACHMENT BRACKET	1.000	EACH		
0990	06449	REM OVERHEAD SIGN SUPPORT STR	1.000	EACH		
1000	06450	REM OVERHEAD STRUC CONC BASE	1.000	EACH		
1010	06451	REMOVE SIGN SUPPORT BEAM	9.000	EACH		
1020	06490	CLASS A CONCRETE FOR SIGNS	173.200	CUYD		
1030	06491	STEEL REINFORCEMENT FOR SIGNS	14,609.000	LB		

CONTRACT ID: 111012
 COUNTY: WARREN, DAVIESS, BUTLER, OHIO
 PROPOSAL: STP 0031(007)

PAGE: 6
 LETTING: 03/18/11
 CALL NO: 104

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
1040	20419ND	ROADWAY CROSS SECTION	24.000	EACH		
1050	20815ED	GMSS GALV STEEL TYPE C	5,376.000	LB		
1060	20912ND	BARRIER WALL POST	2.000	EACH		
1070	21373ND	REMOVE SIGN	10.000	EACH		
1080	21596ND	GMSS TYPE D	27.000	EACH		
1090	23603EC	REMOVE/REPLACE COPY ON PANEL SIGNS	9.600	SQFT		
1100	24089EC	REMOVE COPY ON PANEL SIGNS	108.000	SQFT		
SECTION 0006 ITS						
1110	03381	PVC PIPE-2 IN	600.000	LF		
1120	04795	CONDUIT-2 IN	120.000	LF		
1130	04820	TRENCHING AND BACKFILLING	640.000	LF		
1140	04835	WIRE-NO. 4	240.000	LF		
1150	04836	WIRE-NO. 2	1,200.000	LF		
1160	04899	ELECTRICAL SERVICE	1.000	EACH		
1170	06400	GMSS GALV STEEL TYPE A	1,136.100	LB		
1180	06490	CLASS A CONCRETE FOR SIGNS	2.550	CUYD		
1190	20419ND	ROADWAY CROSS SECTION	1.000	EACH		
1200	21065ND	MODEL 334 ENCLOSURE	1.000	EACH		
1210	21066ND	MODEL 336 ENCLOSURE	1.000	EACH		
1220	21069ND	SURGE DEVICE 120 VOLT	2.000	EACH		
1230	21071ND	DATA SURGE DEVICE	3.000	EACH		

CONTRACT ID: 111012
 COUNTY: WARREN, DAVIESS, BUTLER, OHIO
 PROPOSAL: STP 0031(007)

PAGE: 7
 LETTING: 03/18/11
 CALL NO: 104

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
1240	21076ND	FIBER TERMINATION RACK	4.000	EACH		
1250	21077ED	FIBER OPTIC CABLE	400.000	LF		
1260	21458ND	FIBER TRANSCEIVER SIGN	2.000	EACH		
1270	21489ND	RACK MOUNTED UPS	1.000	EACH		
1280	22403NN	WEB CAMERA ASSEMBLY	1.000	EACH		
1290	22408NN	VARIABLE MESSAGE SIGN-DYNAMIC SIDE MOUNT	1.000	EACH		
1300	22409NN	STEEL STRAIN POLE-40 FT	1.000	EACH		
1310	23150NN	COMMUNICATION CABLE	100.000	LF		
1320	23157EN	TRAFFIC SIGNAL POLE BASE	4.320	CUYD		
1330	23944EC	ADVANCED GROUNDING SYSTEM	2.000	EACH		
1340	24079EC	WIRELESS MODEM	1.000	EACH		
SECTION 0007 DEMOB AND MOB						
1350	02568	MOBILIZATION (NO MORE THAN 5%)		LUMP		
1360	02569	DEMOBILIZATION (AT LEAST 1.5%)		LUMP		
		TOTAL BID				