



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

July 15, 2024

CALL NO. 105
CONTRACT ID NO. 245357
ADDENDUM # 2

Subject: Jefferson County, STP BRZ 9030 (474)
Letting July 18, 2024

(1) Revised - Proposal Pages 55, 137-139 of 139

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

SPECIAL NOTE FOR CONTRACT COMPLETION DATE AND LIQUIDATED DAMAGES ON BRIDGE REPAIR CONTRACTS

I. COMPLETION DATE.

Upon Notice to Proceed, the Contractor has the option of selecting the Begin Work date. Once selected, notify the Department in writing of the date selected at least two weeks prior to beginning work and provide a proposed project schedule. All work is to be completed by the specified contract completion date. The Contractor is allotted 210 calendar days once work begins in phase 1B, where traffic is shifted and shoulders are reduced, to complete all work to safely reopen the structure in its final configuration with no lane closures. At a minimum, prior to reopening the lane to traffic, all strength requirements and curing for materials used shall be completed per Division 600 of the Standard Specifications.

The Contractor shall not shift traffic or reduce lane widths (phase 1B, 2, and 3) until after the March 1, 2025 to avoid snow and ice operations near the interchange with phased traffic.

The Engineer will begin charging calendar days for a structure on the day the Contractor begins work, with the exception of placement of signs, regardless of holidays or seasonal weather limitations.

II. LIQUIDATED DAMAGES.

Liquidated damages will be assessed to the Contractor in accordance with the Transportation Cabinet, Department of Highway's current Standard Specifications for Road and Bridge Construction, Section 112.03.15A, when the lane closures are used beyond the allotted number of calendar days. Liquidated Damages will be assessed per the Standard Specification Section 108.09 when the contract time extends beyond the contract date.

Contrary to the Standard Specifications, liquidated damages will be assessed to the Contractor during the months of December, January, February and March when the contract time has expired on any individual bridge. Contract time will be charged during these months. All construction must be completed in accordance with the weather limitations specified in Section 606 and/or Section 601 as applicable. No extension of Contract time will be granted due to inclement weather or temperature limitations that occur due to starting work on the Contract or a structure late in the construction season.

PROPOSAL BID ITEMS

245357

Page 1 of 3

Report Date 7/15/24

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00003		CRUSHED STONE BASE	3,596.00	TON		\$	
0020	00018		DRAINAGE BLANKET-TYPE II-ASPH	110.00	TON		\$	
0030	00069		CRUSHED AGGREGATE SIZE NO 3	4,735.00	TON		\$	
0040	00100		ASPHALT SEAL AGGREGATE	14.00	TON		\$	
0050	00103		ASPHALT SEAL COAT	2.00	TON		\$	
0060	00210		CL4 ASPH BASE 1.50D PG76-22	435.00	TON		\$	
0070	00217		CL4 ASPH BASE 1.00D PG64-22	1,949.00	TON		\$	
0080	00219		CL4 ASPH BASE 1.00D PG76-22	878.00	TON		\$	
0090	00342		CL4 ASPH SURF 0.38A PG76-22	478.00	TON		\$	
0100	00356		ASPHALT MATERIAL FOR TACK	8.00	TON		\$	
0110	02602		FABRIC-GEOTEXTILE CLASS 1	6,967.00	SQYD		\$	
0120	02604		FABRIC-GEOTEXTILE CLASS 1A	6,872.00	SQYD		\$	

Section: 0002 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0130	01978		CONC MEDIAN BARRIER TYPE A TL5 56 IN	135.00	LF		\$	
0140	01982		DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL WHITE	4.00	EACH		\$	
0150	01983		DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL YELLOW	11.00	EACH		\$	
0160	01984		DELINEATOR FOR BARRIER - WHITE	4.00	EACH		\$	
0170	01985		DELINEATOR FOR BARRIER - YELLOW	10.00	EACH		\$	
0180	02003		RELOCATE TEMP CONC BARRIER	5,640.00	LF		\$	
0190	02200		ROADWAY EXCAVATION	4,961.00	CUYD		\$	
0200	02262		FENCE-WOVEN WIRE TYPE 1	178.00	LF		\$	
0210	02265		REMOVE FENCE	173.00	LF		\$	
0220	02350		ADJUST GUARDRAIL	125.00	LF		\$	
0230	02351		GUARDRAIL-STEEL W BEAM-S FACE	100.00	LF		\$	
0240	02352		GUARDRAIL-STEEL W BEAM-D FACE	1,038.00	LF		\$	
0250	02359		GUARDRAIL CONNECTOR TO CONC MED BARR	4.00	EACH		\$	
0260	02367		GUARDRAIL END TREATMENT TYPE 1	1.00	EACH		\$	
0270	02381		REMOVE GUARDRAIL	1,566.00	LF		\$	
0280	02396		REMOVE GUARDRAIL END TREATMENT	1.00	EACH		\$	
0290	02484		CHANNEL LINING CLASS III	62.00	TON		\$	
0300	02545		CLEARING AND GRUBBING APPROX LESS THAN 1 ACRE	1.00	LS		\$	
0310	02562		TEMPORARY SIGNS	1,300.00	SQFT		\$	
0320	02585		EDGE KEY	71.00	LF		\$	
0330	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0340	02671		PORTABLE CHANGEABLE MESSAGE SIGN	6.00	EACH		\$	
0350	02696		SHOULDER RUMBLE STRIPS	1,670.00	LF		\$	
0360	02726		STAKING	1.00	LS		\$	
0370	02898		RELOCATE CRASH CUSHION	3.00	EACH		\$	
0380	03171		CONCRETE BARRIER WALL TYPE 9T	3,940.00	LF		\$	
0390	06542		PAVE STRIPING-THERMO-6 IN W	260.00	LF		\$	

PROPOSAL BID ITEMS

245357

Page 2 of 3

Report Date 7/15/24

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0400	06543		PAVE STRIPING-THERMO-6 IN Y	130.00	LF		\$	
0410	06549		PAVE STRIPING-TEMP REM TAPE-B	21,399.00	LF		\$	
0420	06550		PAVE STRIPING-TEMP REM TAPE-W	43,407.00	LF		\$	
0430	06551		PAVE STRIPING-TEMP REM TAPE-Y	19,058.00	LF		\$	
0440	06556		PAVE STRIPING-DUR TY 1-6 IN W	524.00	LF		\$	
0450	06557		PAVE STRIPING-DUR TY 1-6 IN Y	262.00	LF		\$	
0460	08100		CONCRETE-CLASS A	63.00	CUYD		\$	
0470	08150		STEEL REINFORCEMENT	4,302.00	LB		\$	
0480	08901		CRASH CUSHION TY VI CLASS BT TL2	3.00	EACH		\$	
0490	10020NS		FUEL ADJUSTMENT	5,821.00	DOLL	\$1.00	\$	\$5,821.00
0500	10030NS		ASPHALT ADJUSTMENT	14,622.00	DOLL	\$1.00	\$	\$14,622.00
0505	20411ED		LAW ENFORCEMENT OFFICER (ADDED: 7/15/2024)	400.00	HOUR		\$	
0510	20550ND		SAWCUT PAVEMENT	1,845.00	LF		\$	
0520	21289ED		LONGITUDINAL EDGE KEY	1,600.00	LF		\$	
0530	21415ND		EROSION CONTROL	1.00	LS		\$	
0540	23979EC		CRASH CUSHION TY VI CLASS C TL3	1.00	EACH		\$	
0550	24640ED		OBJECT MARKER TYPE 1	1.00	EACH		\$	
0560	24707ED		CABLE BARRIER SYSTEM REMOVE & RESTORE	1.00	LS		\$	
0570	25078ED		THRIE BEAM GUARDRAIL TRANSITION TL-3	4.00	EACH		\$	
0580	26233EC		MOBILIZATION FOR CONCRETE SURF TREATMENT	1.00	LS		\$	

Section: 0003 - DRAINAGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0590	00520		STORM SEWER PIPE-12 IN	83.00	LF		\$	
0600	00521		STORM SEWER PIPE-15 IN	21.00	LF		\$	
0610	00522		STORM SEWER PIPE-18 IN	61.00	LF		\$	
0620	00980		SLOTTED DRAIN PIPE-12 IN	735.00	LF		\$	
0630	01001		PERFORATED PIPE-6 IN	2,387.00	LF		\$	
0640	01011		NON-PERFORATED PIPE-6 IN	45.00	LF		\$	
0650	01021		PERF PIPE HEADWALL TY 1-6 IN	2.00	EACH		\$	
0660	01029		PERF PIPE HEADWALL TY 3-6 IN	1.00	EACH		\$	
0670	01204		PIPE CULVERT HEADWALL-18 IN	1.00	EACH		\$	
0680	01535		DROP BOX INLET TYPE 6F	1.00	EACH		\$	
0690	01568		DROP BOX INLET TYPE 13S	1.00	EACH		\$	
0700	01691		FLUME INLET TYPE 2	1.00	EACH		\$	
0710	02607		FABRIC-GEOTEXTILE CLASS 2 FOR PIPE	1,632.00	SQYD	\$2.00	\$	\$3,264.00
0720	23806EC		CONC MED BARRIER BOX INLET-TY 12B2	3.00	EACH		\$	

Section: 0004 - BRIDGE - 056B00052L-R

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0730	02231		STRUCTURE GRANULAR BACKFILL	734.00	CUYD		\$	
0740	02731		REMOVE STRUCTURE	1.00	LS		\$	
0750	03299		ARMORED EDGE FOR CONCRETE	227.00	LF		\$	

PROPOSAL BID ITEMS

245357

Page 3 of 3

Report Date 7/15/24

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0760	08002		STRUCTURE EXCAV-SOLID ROCK	62.00	CUYD		\$	
0770	08003		FOUNDATION PREPARATION	1.00	LS		\$	
0780	08019		CYCLOPEAN STONE RIP RAP	370.00	TON		\$	
0790	08033		TEST PILES	34.00	LF		\$	
0800	08039		PRE-DRILLING FOR PILES	320.00	LF		\$	
0810	08046		PILES-STEEL HP12X53	360.00	LF		\$	
0820	08094		PILE POINTS-12 IN	32.00	EACH		\$	
0830	08100		CONCRETE-CLASS A	114.20	CUYD		\$	
0840	08104		CONCRETE-CLASS AA	598.00	CUYD		\$	
0850	08140		MECHANICAL REINF COUPLER #5 EPOXY COATED	59.00	EACH		\$	
0860	08151		STEEL REINFORCEMENT-EPOXY COATED	140,787.00	LB		\$	
0870	23378EC		CONCRETE SEALING	27,460.00	SQFT		\$	
0880	24405EC		MECHANICAL REINF COUPLER-#8 EPOXY COATED	39.00	EACH		\$	
0890	24423EC		TEMPORARY SHORING	1.00	LS		\$	
0900	24463ED		PPC I-BEAM HN 54 49	1,792.00	LF		\$	
0910	25028ED		RAIL SYSTEM SINGLE SLOPE - 40 IN	261.00	LF		\$	

Section: 0005 - TRAFFIC - SIGNING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0920	06405		SBM ALUMINUM PANEL SIGNS	384.00	SQFT		\$	
0930	06406		SBM ALUM SHEET SIGNS .080 IN	14.00	SQFT		\$	
0940	06407		SBM ALUM SHEET SIGNS .125 IN	20.00	SQFT		\$	
0950	06410		STEEL POST TYPE 1	59.00	LF		\$	
0960	06412		STEEL POST MILE MARKERS	4.00	EACH		\$	
0970	06449		REM OVERHEAD SIGN SUPPORT STR	1.00	EACH		\$	
0980	06450		REM OVERHEAD STRUC CONC BASE	1.00	EACH		\$	
0990	06481		OSS GALV STEEL 90 FT TRUSS	1.00	EACH		\$	
1000	20419ND		ROADWAY CROSS SECTION	1.00	EACH		\$	
1010	24631EC		BARCODE SIGN INVENTORY	3.00	EACH		\$	

Section: 0006 - MOBILIZATION/DEMobilIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1020	02568		MOBILIZATION	1.00	LS		\$	
1030	02569		DEMobilIZATION	1.00	LS		\$	