



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Rebecca Goodman
SECRETARY

September 15, 2026

CALL NO. 105
CONTRACT ID NO. 264128
ADDENDUM # 1

Subject: Wayne County, HSIP 9010 (629)
Letting September 24, 2026

- (1) Revised - Completion Date: Cover Page & Page 4 of 262
- (2) Revised - Notes - Pages 43, 64, & 65 of 262

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures



CALL NO. 105

CONTRACT ID. 264128

WAYNE COUNTY

FED/STATE PROJECT NUMBER HSIP 9010(629)

DESCRIPTION KY HIGHWAY 90 (KY 90)

WORK TYPE ASPHALT SURFACE WITH GRADE & DRAIN

PRIMARY COMPLETION DATE 8/1/2027

LETTING DATE: September 24,2026

Sealed Bids will be received electronically through the Bid Express bidding service until 10:00 AM EASTERN DAYLIGHT TIME September 24,2026. Bids will be publicly announced at 10:00 AM EASTERN DAYLIGHT TIME.

NO PLANS ASSOCIATED WITH THIS PROJECT.

DBE CERTIFICATION REQUIRED - 0%

REQUIRED BID PROPOSAL GUARANTY: Not less than 5% of the total bid.

ADMINISTRATIVE DISTRICT - 08

CONTRACT ID - 264128
HSIP 9010(629)
COUNTY - WAYNE
PCN - 0811600902601
HSIP 9010(629)

KY HIGHWAY 90 (KY 90) (MP 10.70) SAFETY IMPROVEMENTS AT THE INTERSECTION OF KY 90 AND KY 92 (MP 11.22), A DISTANCE OF 0.52 MILES.GRADE & DRAIN WITH ASPHALT SURFACE SYP NO. 08-00956.00.
GEOGRAPHIC COORDINATES LATITUDE 36:50:36.68 LONGITUDE 84:51:59.54
ADT 13,050

COMPLETION DATE(S):
COMPLETED BY 08/01/2027 APPLIES TO ENTIRE PROJECT

Special Note for Completion Date & Liquidated Damages

I. COMPLETION DATE

The ultimate completion date for this project will be August 1, 2027. Liquidated Damages for failure to complete the project on time will be assessed following Section 108.09.

II. LIQUIDATED DAMAGES

In addition to the requirements of Section 108.09, the Department will assess Liquidated Damages in the amount of \$1,000 per hour for each hour, or fraction of an hour, for any and all lane closures that are in place beyond the time frame(s) noted in the Traffic Control Plan and approved by the Engineer

Contrary to Section 108.09, Liquidated Damages will be assessed regardless of whether seasonal limitations prohibit the Contractor from performing work on the controlling operation.

Contrary to Section 108.09, all Liquidated Damages will be assessed for the months of December through March.

All liquidated damages will be applied accumulatively.

All other applicable portions of Section 108 apply.

Traffic Control Plan
Page 6 of 15

- 1.) RT of KY 90 Stations 108+85—113+00: Remove/mill the existing shoulder asphalt pavement outside of the proposed paved shoulder line and refill with CSB.
- 2.) Construct all remaining proposed drainage pipes and structures.
- 3.) Construct all outside curb & gutter, header curb, and outside truck apron throughout project. Construct embankments and berm behind curbs as shown on cross sections.
- 4.) LT of KY 90 STATIONS 118+50 – 122+00: Construct any required embankment widening & CSB shoulder wedge.
- 5.) LT of KY 90 STATIONS 118+50 – 125+18: Remove and replace existing guardrail.
- 6.) RT of KY 90 STATIONS 118+00 – 122+00: Construct any required embankment widening & CSB shoulder wedge.
- 7.) RT of KY 90 STATIONS 118+00 – 125+33: Remove and replace existing guardrail.
- 8.) Complete installation of proposed intersection lighting.
- 9.) Install any remaining permanent signing.

PHASE VIIC

- Utilize flaggers and lane shifts as needed to complete work to perform paving work this phase.
- 1.) KY 90 Stations 115+00 - 117+05 and KY 92 Stations 48+74 - 51+50: Place proposed asphalt base layers in the curb & gutter / roundabout area where applicable.

PHASE VIII

- Perform work in this phase under traffic utilizing flaggers as needed.
- 1.) Complete any remaining grade & drain work, CSB shoulder wedge, project cleanup, landscaping, and final seeding/protection.
 - 2.) Perform any pavement milling & texturing and/or leveling/wedging necessary for placement of final 1.5" surface. Place final asphalt surface course.
 - 3.) Place pavement markings, striping, and rumble strips throughout project.
 - 4.) Remove all temporary construction signs.

The Department will allow night work on this project. Obtain the Engineer's approval of the method of lighting prior to performing night work.

Take these restrictions into account in submitting bid. The Department will not consider any claims for money or grant contract time extensions for any delays to the Contractor as a result of these restrictions.

Traffic Control Plan
Page 7 of 15

Unless otherwise approved by the Engineer, except for the left turn lane closures required for specific phases, no other lane closures will be allowed during the following times:

Labor Day Weekend	3 pm Friday, September 4, 2026 – 8 pm Monday, September 7, 2026
Thanksgiving Holiday	3 pm Wednesday, November 25, 2026 – 8 pm Sunday, November 29, 2026
Christmas Holiday	7 am Thursday, December 24, 2026 – 8 pm Sunday, December 27, 2026
New Year’s Day Holiday	7 am Thursday, December 31, 2026 – 8 pm Friday, January 1, 2027
Easter Weekend	3 pm Friday, March 26, 2027 – 8 pm Sunday, March 28, 2027
Memorial Day Weekend	3 pm Friday, May 28, 2027 – 8 pm Monday, May 31, 2027
Independence Day	7 am Friday, July 2, 2027 – 11 pm Sunday, July 4, 2027

At the discretion of the Engineer, additional days and hours may be specified when lane closures will not be allowed.

The Contractor shall submit proposed lane closure days and times to the Engineer at least 14 calendar days in advance for approval. Liquidated Damages will be assessed for each hour or fraction of an hour that a lane closure is in place outside of an approved time period. See the Special Notes for Completion Dates & Liquidated Damages for details on the Liquidated Damages amount.

LANE CLOSURES

Except for the left turn lane closures noted in the phasing notes, do not leave lane closures in place during prohibited periods. Except for the noted left turn lane closures, do not leave lane closures in place during non-working hours, unless otherwise approved by the Engineer. Contrary to Section 112.04.17, long-term lane closures will not be measured for payment but shall be incidental to Maintain and Control Traffic.

No temporary lane closures will be permitted on weekdays between the hours of 6:30 AM to 8:30 AM and 2:30 PM to 4:00 PM while school is in session. School in session is defined as any day when Wayne County Public Schools are in session with students present. NOTE: most school calendars are published online but may change due to certain circumstances. The Contractor and Engineer should work together to determine the dates when school will be and will not be in session.

TEMPORARY SIGNS

Temporary signposts and splices shall be compliant with NCHRP 350 or MASH. Manufacturer’s documentation validating this compliance shall be provided to the Engineer prior to installation. Temporary signs, including any splices, shall be installed according to manufacturer’s specifications and installation recommendations. Contrary to section 112.04.02, only long-term temporary signs (temporary signs intended to be continuously in place for more than 3 days) will be measured for payment. Short-term temporary signs (temporary signs intended to be left in place for 3 days or less) will not be measured for payment but will be incidental to Maintain and Control Traffic.