



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

September 23, 2025

CALL NO. 106
CONTRACT ID NO. 255389
ADDENDUM # 2

Subject: Pendleton County, STP BRZ 9030 (508)
Letting September 25, 2025

(1) Revised - Proposal Bid Items - Pages 130-131 of 131

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills". The signature is written in a cursive style with a large, stylized "R" and "M".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

PENDLETON COUNTY
 STP BRZ 9030 (508)
 255389

PROPOSAL BID ITEMS

Report Date 9/23/25

Page 1 of 2

255389

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00001		DGA BASE	417.00	TON		\$	
0020	00100		ASPHALT SEAL AGGREGATE	5.00	TON		\$	
0030	00103		ASPHALT SEAL COAT	1.00	TON		\$	
0040	00212		CL2 ASPH BASE 1.00D PG64-22	228.00	TON		\$	
0050	00301		CL2 ASPH SURF 0.38D PG64-22	36.00	TON		\$	
0060	00356		ASPHALT MATERIAL FOR TACK	1.00	TON		\$	

Section: 0002 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0070	00441		ENTRANCE PIPE-18 IN	36.00	LF		\$	
0080	02014		BARRICADE-TYPE III	8.00	EACH		\$	
0090	02200		ROADWAY EXCAVATION	463.00	CUYD		\$	
0100	02223		GRANULAR EMBANKMENT	75.00	CUYD		\$	
0110	02429		RIGHT-OF-WAY MONUMENT TYPE 1	11.00	EACH		\$	
0120	02432		WITNESS POST	11.00	EACH		\$	
0130	02483		CHANNEL LINING CLASS II	345.00	TON		\$	
0140	02545		CLEARING AND GRUBBING APPROX LESS THAN 1 ACRE	1.00	LS		\$	
0150	02562		TEMPORARY SIGNS	216.00	SQFT		\$	
0160	02585		EDGE KEY	24.00	LF		\$	
0170	02602		FABRIC-GEOTEXTILE CLASS 1	550.00	SQYD		\$	
0180	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0190	02671		PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH		\$	
0200	02726		STAKING	1.00	LS		\$	
0210	02731		REMOVE STRUCTURE	1.00	LS		\$	
0215	08002		STRUCTURE EXCAV-SOLID ROCK (ADDED 9-23-25)	200.00	CUYD		\$	
0220	06406		SBM ALUM SHEET SIGNS .080 IN	12.00	SQFT		\$	
0230	06410		STEEL POST TYPE 1	40.00	LF		\$	
0240	21415ND		EROSION CONTROL Includes all items necessary for erosion control including but not limited to si	1.00	LS		\$	
0250	24631EC		BARCODE SIGN INVENTORY	4.00	EACH		\$	
0260	26248EC		ELECTRONIC DELIVERY MGMT SYSTEM - AGG	1.00	LS		\$	

Section: 0003 - BRIDGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0270	02231		STRUCTURE GRANULAR BACKFILL	364.00	CUYD		\$	
0280	03299		ARMORED EDGE FOR CONCRETE	46.00	LF		\$	
0290	08003		FOUNDATION PREPARATION	1.00	LS		\$	
0300	08019		CYCLOPEAN STONE RIP RAP	525.00	TON		\$	

PROPOSAL BID ITEMS

Report Date 9/23/25

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0310	08100		CONCRETE-CLASS A	174.00	CUYD		\$	
0320	08104		CONCRETE-CLASS AA	16.00	CUYD		\$	
0330	08150		STEEL REINFORCEMENT	14,586.00	LB		\$	
0340	08151		STEEL REINFORCEMENT-EPOXY COATED	1,275.00	LB		\$	
0350	08661		PRECAST PC BOX BEAM CB12-48	128.00	LF		\$	
0360	23378EC		CONCRETE SEALING	1,991.00	SQFT		\$	
0370	26233EC		MOBILIZATION FOR CONCRETE SURF TREATMENT	1.00	LS		\$	

Section: 0004 - DEMOBILIZATION &/OR MOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0380	02568		MOBILIZATION	1.00	LS		\$	
0390	02569		DEMOBILIZATION	1.00	LS		\$	