



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

September 16, 2025

CALL NO. 109
CONTRACT ID NO. 254115
ADDENDUM # 1

Subject: Carter County, HSIP 9010(547)
Letting September 25, 2025

- (1) Revised - Summary Sheets - Pages 48-52 of 95
- (2) Revised - Proposal Bid Items - Page 95 of 95

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

COMMONWEALTH OF KENTUCKY
DEPARTMENT OF HIGHWAYS

COUNTY OF	ITEM NO.
Carter	9-951.00

Carter County
KY 7
9-951.00

GENERAL SUMMARY

BID CODE	DESCRIPTION	UNIT	QTY
1	DGA BASE	TON	440
190	LEVELING & WEDGING PG64-22	TON	50
212	CL2 ASPH SURF 1.00D PG64-22	TON	800
307	CL2 ASPH SURF 0.38B PG64-22	TON	350
356	ASPHALT MATERIAL FOR TACK	TON	1.71
2562	TEMPORARY SIGNS	SQFT	125.00
2650	MAINTAIN & CONTROL TRAFFIC	LS	1.00
2676	MOBILIZATION FOR MILL & TEXT	LS	1.00
2677	ASPHALT PAVE MILLING & TEXTURING	TON	39.20
2697	EDGE LINE RUMBLE STRIPS	LF	3,156.00
2726	STAKING	LS	1.00
6510	PAVE STRIPING-TEMP PAINT-4 IN	LF	7,220.00
6542	PAVE STRIPING-THERMO-6 IN W	LF	3,156.00
6543	PAVE STRIPING-THERMO-6 IN Y	LF	4,064.00
6568	PAVE MARKING-THERMO STOP BAR-24 IN	LF	30.00
6569	PAVE MARKING-THERMO CROSS HATCH	SQFT	924.00
6574	PAVE MARKING-THERMO CURV ARROW	EACH	6.00
21417ES717	PAVE MARK THERMO CONE CAP-SOLID YELLOW	SQFT	77.00
10020NS	FUEL ADJUSTMENT	DOLL	576.00
10030NS	ASPHALT ADJUSTMENT	DOLL	1,447.00
20748ED	SHOULDER MILLING/TRENCHING	SQYD	1,815.00
20458ES403	CENTERLINE RUMBLE STRIPS	LF	4,064.00
22664EN	WATER BLASTING EXISTING STRIPE	LF	1,200
2569	DEMOBILIZATION	LS	1

Project: HSIP 9010
(547)

County: Carter

District: D9 - Flemingsburg

Start MP	End MP	Inside Shoulder DGA	Inside Shoulder ASPH	Mainline Width (FT)	Outside Shoulder ASPH	Outside Shoulder DGA	Mainline Area (SY)	Shoulder ASPH Area (SY)	Shoulder DGA Area (SY)
9.550	9.743	1	3	36	3	1	114	680	227

Mainline Area (SY)	4,483.78	Shoulder DGA Area (SY)	227
Shoulder ASPH Area (SY)	680		

Description	Unit	Quantity
CL2 ASPH SURF 0.38B PG64-22	TON	350
DGA BASE	TON	440

Bridge No	Milepoint	W (FT)	T (IN)	L (FT)	L1 (FT)	L2 (FT)	PR (IN)	TR (IN)	Milling and Texturing (in tons)
B00112N	9.490	44	0	305	100	100	1	0	30

Project: HSIP 9010
(547)

County: Carter

District: D9 - Flemingsbur

Mile Point	Notes	Length	Width	Avg Depth	Tons
9.473	Edge Key	100	30	0.5	9.2
	Bridge Milling				30
				Total:	39.2

Milepoint	Location	Notes	PAVE MARKIN G- THERMO CROSS- HATCH	PAVE MARKIN G- THERMO CURV ARROW	PAVE MARKIN G- THERMO STOP BAR-24IN	PAVE MARK THERMO CONE CAP- SOLID YELLOW
9.528			924			
9.587	KY 773			6	15	
9.587	LAKEWAY PLZ				15	
9.623						77
Total:			924	6	30	77

254115

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00001		DGA BASE	440.00	TON		\$	
0020	00190		LEVELING & WEDGING PG64-22	50.00	TON		\$	
0030	00212		CL2 ASPH BASE 1.00D PG64-22	800.00	TON		\$	
0040	00307		CL2 ASPH SURF 0.38B PG64-22	350.00	TON		\$	
0050	00356		ASPHALT MATERIAL FOR TACK	1.71	TON		\$	
0060	02676		MOBILIZATION FOR MILL & TEXT (CARTER KY 7 HSIP)	1.00	LS		\$	
0070	02677		ASPHALT PAVE MILLING & TEXTURING (REVISED 9-16-25)	39.20	TON		\$	

Section: 0002 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0080	02562		TEMPORARY SIGNS	125.00	SQFT		\$	
0090	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0100	02697		EDGE LINE RUMBLE STRIPS	3,156.00	LF		\$	
0110	02726		STAKING (CARTER KY 7 HSIP)	1.00	LS		\$	
0120	06510		PAVE STRIPING-TEMP PAINT-4 IN	7,220.00	LF		\$	
0130	06542		PAVE STRIPING-THERMO-6 IN W	3,156.00	LF		\$	
0140	06543		PAVE STRIPING-THERMO-6 IN Y	4,064.00	LF		\$	
0150	06568		PAVE MARKING-THERMO STOP BAR-24IN	30.00	LF		\$	
0160	06569		PAVE MARKING-THERMO CROSS-HATCH	924.00	SQFT		\$	
0170	06574		PAVE MARKING-THERMO CURV ARROW	6.00	EACH		\$	
0180	10020NS		FUEL ADJUSTMENT	576.00	DOLL	\$1.00	\$	\$576.00
0190	10030NS		ASPHALT ADJUSTMENT	1,447.00	DOLL	\$1.00	\$	\$1,447.00
0200	20458ES403		CENTERLINE RUMBLE STRIPS	4,064.00	LF		\$	
0210	20748ED		SHOULDER MILLING/TRENCHING	1,815.00	SQYD		\$	
0220	21417ES717		PAVE MARK THERMO CONE CAP-SOLID YELLOW	77.00	SQFT		\$	
0230	22664EN		WATER BLASTING EXISTING STRIPE	1,200.00	LF		\$	
0240	26248EC		ELECTRONIC DELIVERY MGMT SYSTEM - AGG	1.00	LS		\$	

Section: 0003 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0250	02569		DEMOBILIZATION	1.00	LS		\$	