



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Rebecca Goodman
SECRETARY

May 20, 2026

CALL NO. 110
CONTRACT ID NO. 261509
ADDENDUM # 2

Subject: Floyd County, FD06 036 0979 011-013
Letting May 21, 2026

- (1) Revised - Proposal Bid Items - Pages 202-205 of 205
- (2) Revised - Plan Sheet R2B

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

PROPOSAL BID ITEMS

261509

Page 1 of 4

Report Date 5/20/26

261509

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00003		CRUSHED STONE BASE	4,030.00	TON		\$	
0020	00020		TRAFFIC BOUND BASE	182.00	TON		\$	
0030	00100		ASPHALT SEAL AGGREGATE	107.00	TON		\$	
0040	00103		ASPHALT SEAL COAT	32.00	TON		\$	
0050	00212		CL2 ASPH BASE 1.00D PG64-22	3,995.00	TON		\$	
0060	00301		CL2 ASPH SURF 0.38D PG64-22	1,070.00	TON		\$	
0070	02084		JPC PAVEMENT-8 IN	475.00	SQYD		\$	
0080	02602		FABRIC-GEOTEXTILE CLASS 1	12,056.00	SQYD		\$	
0090	02608		FABRIC-GEOTEXTILE CLASS 4A	13,433.00	SQYD		\$	
0100	20071EC		JOINT ADHESIVE	9,300.00	LF		\$	
0110	24970EC		ASPHALT MATERIAL FOR TACK NON-TRACKING	8.00	TON		\$	
0120	26248EC		ELECTRONIC DELIVERY MGMT SYSTEM - AGG	1.00	LS		\$	

Section: 0002 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0130	00078		CRUSHED AGGREGATE SIZE NO 2	706.00	TON		\$	
0140	01000		PERFORATED PIPE-4 IN	530.00	LF		\$	
0150	01010		NON-PERFORATED PIPE-4 IN	109.00	LF		\$	
0160	01024		PERF PIPE HEADWALL TY 2-4 IN	1.00	EACH		\$	
0170	01028		PERF PIPE HEADWALL TY 3-4 IN	5.00	EACH		\$	
0180	01740		CORED HOLE DRAINAGE BOX CON-4 IN	2.00	EACH		\$	
0190	01890		ISLAND HEADER CURB TYPE 1	972.00	LF		\$	
0200	01987		DELINEATOR FOR G/R BI DIRECTIONAL WHITE	7.00	EACH		\$	
0210	02003		RELOCATE TEMP CONC BARRIER	640.00	LF		\$	
0220	02014		BARRICADE-TYPE III	4.00	EACH		\$	
0230	02159		TEMP DITCH	1,550.00	LF		\$	
0240	02160		CLEAN TEMP DITCH	775.00	LF		\$	
0245	02191		STRUCTURE DEMOLITION (OLD GARAGE @ STA 119+00) (ADDED 5-6-26)	1.00	EACH		\$	
0250	02200		ROADWAY EXCAVATION	48,269.00	CUYD		\$	
0260	02203		STRUCTURE EXCAV-UNCLASSIFIED	215.00	CUYD		\$	
0270	02223		GRANULAR EMBANKMENT (REVISED 5-20-26)	6,094.00	CUYD		\$	
0280	02242		WATER	117.00	MGAL		\$	
0290	02360		G/R TERMINAL SECTION NO 1	8.00	EACH		\$	
0300	02371		G/R END TREATMENT TYPE 7	2.00	EACH		\$	
0310	02381		REMOVE G/R	1,077.00	LF		\$	
0320	02397		TEMP G/R	612.50	LF		\$	
0330	02429		RIGHT-OF-WAY MONUMENT TYPE 1	61.00	EACH		\$	
0340	02430		RIGHT-OF-WAY MONUMENT TYPE 1A	3.00	EACH		\$	

PROPOSAL BID ITEMS

261509

Page 2 of 4

Report Date 5/20/26

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0350	02431		WITNESS R/W MONUMENT TYPE 2	3.00	EACH		\$	
0360	02432		WITNESS POST	3.00	EACH		\$	
0370	02483		CHANNEL LINING CLASS II	115.00	TON		\$	
0380	02484		CHANNEL LINING CLASS III	83.00	TON		\$	
0390	02545		CLEARING AND GRUBBING APPROX. 15.4 ACRES	1.00	LS		\$	
0400	02555		CONCRETE-CLASS B	100.00	CUYD		\$	
0410	02562		TEMPORARY SIGNS	500.00	SQFT		\$	
0420	02585		EDGE KEY	68.00	LF		\$	
0430	02603		FABRIC-GEOTEXTILE CLASS 2	66.00	SQYD		\$	
0440	02607		FABRIC-GEOTEXTILE CLASS 2 FOR PIPE	1,997.00	SQYD	\$2.00	\$	\$3,994.00
0450	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0460	02651		DIVERSIONS (BY-PASS DETOURS)	1.00	LS		\$	
0470	02653		LANE CLOSURE	2.00	EACH		\$	
0480	02671		PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH		\$	
0490	02690		SAFELOADING	4.00	CUYD		\$	
0500	02697		EDGELINE RUMBLE STRIPS	5,705.00	LF		\$	
0510	02701		TEMP SILT FENCE	1,550.00	LF		\$	
0520	02703		SILT TRAP TYPE A	16.00	EACH		\$	
0530	02704		SILT TRAP TYPE B	16.00	EACH		\$	
0540	02705		SILT TRAP TYPE C	16.00	EACH		\$	
0550	02706		CLEAN SILT TRAP TYPE A	16.00	EACH		\$	
0560	02707		CLEAN SILT TRAP TYPE B	16.00	EACH		\$	
0570	02708		CLEAN SILT TRAP TYPE C	16.00	EACH		\$	
0580	02726		STAKING	1.00	LS		\$	
0590	02731		REMOVE STRUCTURE	1.00	LS		\$	
0600	03171		CONC BARRIER WALL TYPE 9T	640.00	LF		\$	
0610	04933		TEMP SIGNAL 2 PHASE	2.00	EACH		\$	
0620	05950		EROSION CONTROL BLANKET	3,292.00	SQYD		\$	
0630	05952		TEMP MULCH	49,713.00	SQYD		\$	
0640	05953		TEMP SEEDING AND PROTECTION	37,285.00	SQYD		\$	
0650	05963		INITIAL FERTILIZER	1.80	TON		\$	
0660	05964		MAINTENANCE FERTILIZER	3.00	TON		\$	
0670	05985		SEEDING AND PROTECTION	54,887.00	SQYD		\$	
0680	05992		AGRICULTURAL LIMESTONE	34.00	TON		\$	
0690	06510		PAVE STRIPING-TEMP PAINT-4 IN	3,700.00	LF		\$	
0700	06514		PAVE STRIPING-PERM PAINT-4 IN	490.00	LF		\$	
0710	06515		PAVE STRIPING-PERM PAINT-6 IN	14,376.00	LF		\$	
0720	06568		PAVE MARKING-THERMO STOP BAR-24IN	36.00	LF		\$	
0730	06574		PAVE MARKING-THERMO CURV ARROW	8.00	EACH		\$	
0740	06576		PAVE MARKING-THERMO ONLY	1.00	EACH		\$	
0750	08911		CRASH CUSHION TY 6 CLASS T TL2	2.00	EACH		\$	
0760	10020NS		FUEL ADJUSTMENT	20,939.00	DOLL	\$1.00	\$	\$20,939.00
0770	10030NS		ASPHALT ADJUSTMENT	21,284.00	DOLL	\$1.00	\$	\$21,284.00
0780	20099ES842		PAVE MARK TEMP PAINT STOP BAR	23.00	LF		\$	
0790	21802EN		G/R STEEL W BEAM-S FACE (7 FT POST)	812.50	LF		\$	
0800	22664EN		WATER BLASTING EXISTING STRIPE	1,000.00	LF		\$	
0810	23274EN11F		TURF REINFORCEMENT MAT 1	1,094.00	SQYD		\$	
0820	23791EC		PAVE STRIPING-CHEVRON MARKINGS	644.00	SQFT		\$	

PROPOSAL BID ITEMS

261509

Page 3 of 4

Report Date 5/20/26

Section: 0003 - DRAINAGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0830	00441		ENTRANCE PIPE-18 IN	36.00	LF		\$	
0840	00443		ENTRANCE PIPE-24 IN	60.00	LF		\$	
0850	00450		ENTRANCE PIPE-15 IN EQUIV	134.00	LF		\$	
0860	00468		CULVERT PIPE-36 IN	170.00	LF		\$	
0870	00521		STORM SEWER PIPE-15 IN	272.00	LF		\$	
0880	00522		STORM SEWER PIPE-18 IN	60.00	LF		\$	
0890	00554		STORM SEWER PIPE-24 IN EQUIV	157.00	LF		\$	
0900	00556		STORM SEWER PIPE-30 IN EQUIV	174.00	LF		\$	
0910	01211		PIPE CULVERT HEADWALL-30 IN EQUIV	1.00	EACH		\$	
0920	01212		PIPE CULVERT HEADWALL-36 IN	2.00	EACH		\$	
0930	01453		S & F BOX INLET-OUTLET-36 IN	2.00	EACH		\$	
0940	01496		DROP BOX INLET TYPE 3	1.00	EACH		\$	
0950	01529		DROP BOX INLET TYPE 6D	7.00	EACH		\$	
0960	01538		DROP BOX INLET TYPE 7	1.00	EACH		\$	
0970	23952EC		DRAINAGE JUNCTION BOX TY B	1.00	EACH		\$	
0980	24814EC		PIPELINE INSPECTION	561.00	LF		\$	

Section: 0004 - STRUCTURE 28957

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0990	08003		FOUNDATION PREPARATION	1.00	LS		\$	
1000	08100		CONCRETE-CLASS A	125.90	CUYD		\$	
1010	08150		STEEL REINFORCEMENT	17,681.00	LB		\$	
1020	08410		LOW FLOW DIVERSION CURB	1.00	LS		\$	

Section: 0005 - WATERLINE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1030	14007		W ENCASMENT STEEL BORED RANGE 2	110.00	LF		\$	
1040	14009		W ENCASMENT STEEL BORED RANGE 4	115.00	LF		\$	
1050	14022		W FLUSH HYDRANT ASSEMBLY	5.00	EACH		\$	
1060	14035		W PIPE DUCTILE IRON 04 INCH	329.00	LF		\$	
1070	14037		W PIPE DUCTILE IRON 08 INCH	1,465.00	LF		\$	
1080	14058		W PIPE PVC 04 INCH	500.00	LF		\$	
1090	14060		W PIPE PVC 08 INCH	2,600.00	LF		\$	
1100	14080		W SERV PE/PLST LONG SIDE 3/4 IN	25.00	EACH		\$	
1110	14095		W TIE-IN 08 INCH	3.00	EACH		\$	
1120	14104		W VALVE 04 INCH	4.00	EACH		\$	
1130	14106		W VALVE 08 INCH	11.00	EACH		\$	

Section: 0006 - DEMOBILIZATION &/OR MOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
------	----------	-----	-------------	----------	------	-----------	----	--------

261509

PROPOSAL BID ITEMS

Page 4 of 4

Report Date 5/20/26

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1140	02568		MOBILIZATION	1.00	LS		\$	
1150	02569		DEMOBILIZATION	1.00	LS		\$	

GENERAL SUMMARY

ITEM CODE	ITEM	UNIT	PROJECT TOTAL
78	CRUSHED AGGREGATE SIZE NO. 2	TON	706
1000	PERFORATED PIPE-4 IN	LF	530
1010	NON-PERFORATED PIPE-4 IN	LF	109
1024	PERFORATED PIPE HEADWALL TYPE 2-4 IN	EACH	1
1028	PERFORATED PIPE HEADWALL TYPE 3-4 IN	EACH	5
1740	CORED HOLE DRAINAGE BOX CON-4 IN	EACH	2
1890	ISLAND HEADER CURB TYPE 1	LF	972
1987	DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	EACH	7
2003	RELOCATE TEMP CONC BARRIER	LF	640
2014	BARRICADE-TYPE III	EACH	4
2159	TEMP DITCH	LF	1550
2160	CLEAN TEMP DITCH	LF	775
2191	STRUCTURE DEMOLITION (OLD GARAGE AT STA. 119+00)	EACH	1
2200	ROADWAY EXCAVATION	CUYD	48269
2203	STRUCTURE EXCAVATION UNCLASSIFIED	CUYD	215
2223	GRANULAR EMBANKMENT	CUYD	6094
2242	WATER	M GAL	117
2360	GUARDRAIL TERMINAL SECTION NO 1	EACH	8
2371	GUARDRAIL END TREATMENT TYPE 7	EACH	2
2381	REMOVE GUARDRAIL	LF	1077
2397	TEMP GUARDRAIL	LF	612.5
2429	RIGHT-OF-WAY MONUMENT TYPE 1	EACH	61
2430	RIGHT-OF-WAY MONUMENT TYPE 1A	EACH	3
2431	WITNESS R/W MONUMENT TYPE 2	EACH	3
2432	WITNESS POST	EACH	3
2483	CHANNEL LINING CLASS II	TON	115
2484	CHANNEL LINING CLASS III	TON	83
2545	CLEARING AND GRUBBING	LS	1
2555	CONCRETE-CLASS B	CUYD	100
2562	TEMPORARY SIGNS	SOFT	500
2568	MOBILIZATION	LS	1
2569	DEMOLITIZATION	LS	1
2585	EDGE KEY	LF	68
2603	FABRIC-GEOTEXTILE CLASS 2	SOYD	66
2607	FABRIC-GEOTEXTILE CLASS 2 FOR PIPE	SOYD	1997
2650	MAINTAIN & CONTROL TRAFFIC	LS	1
2651	DIVERSIONS (BY-PASS DETOURS)	LS	1
2653	LANE CLOSURE	EACH	2
2671	PORTABLE CHANGEABLE MESSAGE SIGN	EACH	2
2690	SAFELOADING	CUYD	4
2697	EDGE/LINE RUMBLE STRIPS	LF	5705
2701	TEMP SILT FENCE	LF	1550
2703	SILT TRAP TYPE A	EACH	16
2704	SILT TRAP TYPE B	EACH	16
2705	SILT TRAP TYPE C	EACH	16
2706	CLEAN SILT TRAP TYPE A	EACH	16
2707	CLEAN SILT TRAP TYPE B	EACH	16
2708	CLEAN SILT TRAP TYPE C	EACH	16
2726	STAKING	LS	1
2731	REMOVE STRUCTURE	LS	1
3171	CONCRETE BARRIER WALL TYPE 9T	LF	640
4933	TEMP SIGNAL 2 PHASE	EACH	2
5950	EROSION CONTROL BLANKET	SOYD	3292
5952	TEMP MULCH	SOYD	49713
5953	TEMP SEEDING AND PROTECTION	SOYD	37285
5963	INITIAL FERTILIZER	TON	1.8
5964	MAINTENANCE FERTILIZER	TON	3
5985	SEEDING AND PROTECTION	SOYD	54887
5992	AGRICULTURAL LIMESTONE	TON	34
6510	PAVE STRIPING-TEMP PAINT-4 IN	LF	3700

GENERAL SUMMARY

ITEM CODE	ITEM	UNIT	PROJECT TOTAL
6514	PAVE STRIPING-PERM PAINT-4 IN	LF	490
6515	PAVE STRIPING-PERM PAINT-6 IN	LF	14376
6568	PAVE MARKING-THERMO STOP BAR-24IN	LF	36
6574	PAVE MARKING-THERMO CURVE ARROW	EACH	8
6576	PAVE MARKING-THERMO ONLY	EACH	1
8911	CRASH CUSHION TY 6 CLASS T TL2	EACH	2
10030NS	FUEL ADJUSTMENT	DOLL	20939
10030NS	ASPHALT ADJUSTMENT	DOLL	21284
20071EC	JOINT ADHESIVE	LF	9300
20099ES842	PAVE MARK TEMP PAINT STOP BAR	LF	23
21802EN	G/R STEEL W BEAM-S FACE (7 FT POST)	LF	812.5
22664EN	WATER BLASTING EXISTING STRIPE	LF	1000
23274EN1F	TURF REINFORCEMENT MAT 1	SOYD	1094
24679ED	PAVE MARK THERMO CHEYRON	SOFT	644

PAVING AREAS

ITEM	MAINLINE	BRANCH RD.	AVERY RD.	ENTRANCE	DIVERSION	S Q U A R E Y A R D S			PROJECT TOTAL
1-5' CL2 ASPHALT SURFACE 0.38D PG64-22	11229	282	230	625	581				12947
3' CL2 ASPHALT BASE 1.00D PG64-22	22630	284	232	683	585				23731
4' CRUSHED STONE BASE	11444								12127
6' CRUSHED STONE BASE									1011
8' CRUSHED STONE BASE									523
8' JPC PAVEMENT									475
4' TRAFFIC BOUND BASE									825
FABRIC-GEOTEXTILE CLASS 1	12056								12056
FABRIC-GEOTEXTILE CLASS 4A	13433								13433
ASPHALT MATERIAL FOR TACK NON-TRACKING	22457								22457
ASPHALT SEAL COAT	2889	31	57						2977
ASPHALT SEAL AGGREGATE	2889	31	57						2977

PAVING SUMMARY

ITEM CODE	ITEM	UNIT	MAINLINE	BRANCH RD.	AVERY RD.	ENTRANCE	DIVERSION	PROJECT TOTAL
3	CRUSHED STONE BASE	TON	2633	132	109	301	205	4030
20	TRAFFIC BOUND BASE	TON				182		182
100	ASPHALT SEAL AGGREGATE	TON	58	47	2			107
103	ASPHALT SEAL COAT	TON	7	24	1			32
212	CLASS 2 ASPHALT BASE 1.00D PG64-22	TON	3734	47	39	78	97	3995
301	CLASS 2 ASPHALT SURFACE 0.38D PG64-22	TON	927	24	19	52	48	1070
2084	JPC PAVEMENT-8 IN	SOYD				475		475
2602	FABRIC-GEOTEXTILE CLASS 1	SOYD	12056					12056
2608	FABRIC-GEOTEXTILE CLASS 4A	SOYD	13433					13433
24970EC	ASPHALT MATERIAL FOR TACK NON-TRACKING	TON	8					8
26248EC	ELECTRONIC DELIVERY MGMT SYSTEM-AGG	LS	1					1

COUNTY OF	ITEM NO.	SHEET NO.
FLOYD	12-195.10	R2B

- INCLUDES 700 TONS FOR MOT AND STABILIZING CONSTRUCTION STAGING AREA, 6 TONS FROM PERFORATED PIPE HDWL
- INCLUDES THE FOLLOWING FROM GEOTECH NOTES: #11-250 LF, #12-190 LF, #13-90 LF
- INCLUDES THE FOLLOWING FROM GEOTECH NOTES: #11-25 LF, #12-48 LF, #13-36 LF
- INCLUDES THE FOLLOWING FROM GEOTECH NOTES: #13-1 EACH
- INCLUDES THE FOLLOWING FROM GEOTECH NOTES: #11-EACH, #12-4 EACH
- INCLUDES 1094 CUYD FROM PIPE DRAINAGE SUMMARY
- INCLUDES 18 CUYD FROM PIPE DRAINAGE SUMMARY
- FOR CONTROLLING DUST CAUSED BY MAINTAINING TRAFFIC ONLY
- GUARDRAIL REMOVED SHALL BE TRANSPORTED TO THE BAILEY BRIDGE LOT @ 1224 WILKINSON BLVD. IN FRANKFORT, KENTUCKY. PAYMENT SHALL BE INCIDENTAL TO BID ITEM 2381 (REMOVE GUARDRAIL)
- INCLUDES 55 TONS FROM DRAINAGE SUMMARY
- APPROXIMATELY 15.4 ACRES
- FOR RETAINING WALL CONST.

NOTES
 ALL ASPHALT MIXTURES SHALL BE ESTIMATED AT 110 LBS PER SOYD PER INCH OF DEPTH, UNLESS NOTED OTHERWISE.

- ASPHALT MATERIAL FOR TACK NON-TRACKING AT APPLICATION RATE OF 0.7 LBS. PER SQ. YD.
- INCLUDES 650 TONS FOR MOT
- ESTIMATED AT 115 LBS PER SOYD PER INCH OF DEPTH
- INCLUDES AN ADDITIONAL 10% MATERIAL IN THE BOTTOM 4" OF THE PAVEMENT DESIGN AS A CONSTRUCTION TOLERANCE ON ROCK SUBGRADE.
- ESTIMATED AT 110 LBS PER SOYD PER INCH OF DEPTH

- TOTAL EARTHWORK
- 33113 CUYD COMMON
 - 12040 CUYD ROCK CUT
 - 1094 CUYD INLET/OUTLET DT
 - 1314 CUYD EMBANKMENT BENCHING
 - 708 CUYD PROFILE BENCHING
 - 48269 CUYD TOTAL EXCAVATION
 - 15630 CUYD EMBANKMENT
 - 10095 CUYD ROCK ROADBED
 - 10095 CUYD INLET/OUTLET DT
 - 25713 CUYD TOTAL EMBANKMENT

NOTE: THE CONTRACTOR IS ADVISED THAT THE EARTHWORK CALCULATIONS SHOWN ARE FOR DESIGN AND INFORMATION ONLY. ASSUMPTIONS FOR SHRINKAGE AND SWELL FACTORS ARE THE RESPONSIBILITY OF THE CONTRACTOR.

- FOR WRAPPING PIPE TRENCH BACKFILL
- PORTABLE CHANGEABLE MESSAGE SIGN SHALL BECOME THE PROPERTY OF THE CONTRACTOR
- EXISTING DOUBLE 8'X4' MASONRY BOX CULVERT 110+25, R3
- EXISTING GARAGE 119+00 RT., R5
- CONCRETE BARRIER WALL TYPE 9T SHALL BECOME PROPERTY OF THE CONTRACTOR

INCLUDES 226 CUYD FROM RETAINING WALL CONST. AND 5868 CUYD FOR ROCK ROADBED CONST. DURING PHASE I AND II OF THE MOT.
 INCLUDES 5868 CUYD OF GRANULAR EMBANKMENT FOR ROCK ROAD BED CONST. DURING PHASE I AND II OF THE MOT.

GENERAL SUMMARY