



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

March 23, 2026

CALL NO. 110
CONTRACT ID NO. 264100
ADDENDUM # 1

Subject: Lewis County, HSIP 9010 (558)
Letting March 26, 2026

- (1) Revised - Summary Sheets - Pages 94-96 & 98 of 194
- (2) Revised - Notes - Page 100 of 194
- (3) Revised - Proposal Bid Items - Pages 193-194 of 194

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

ITEM	DESCRIPTION	UNIT	MAINLINE	APPROACH	ENTRANCE	TOTAL PROJECT
00001	DGA	TON	1165			1165
00100	ASPHALT SEAL AGGREGATE	TON	491			491
00103	ASPHALT SEAL COAT	TON	59			59
00190	LEVELING & WEDGING PG64-22	TON	2			2
00301	CL2 ASPH SURF 0.38D PG64-22	TON	3275			3275
00356	ASPHALT MATERIAL FOR TACK	TON	16			16
01987	DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	EACH	34			34
02230	EMBANKMENT IN PLACE	CUYD	774			774
02367	GUARDRAIL END TREATMENT TYPE 1	EACH	3			3
02371	GUARDRAIL END TREATMENT TYPE 7	EACH	1			1
02381	REMOVE GUARDRAIL	LF	1713			1713
02483	CHANNEL LINING CLASS II	TON	3784			3784
02545	CLEARING AND GRUBBING (1.1 AC)	LS	1			1
02562	TEMPORARY SIGN	SQFT	1500			1500
02569	DEMOBILIZATION	LS	1			1
02585	EDGE KEY	LF	46			46
02602	GEOTEXTILE FABRIC CLASS 1	SQYD	558			558
02650	MAINTAIN & CONTROL TRAFFIC	LS	1			1

ITEM	DESCRIPTION	UNIT	MAINLINE	APPROACH	ENTRANCE	TOTAL PROJECT
02671	PORTABLE CHANGEABLE MESSAGE SIGN	EACH	2			2
02697	EDGE LINE RUMBLE STRIPS	LF	31000			31000
02701	TEMP SILT FENCE	LF	13755			13755
02703	SILT TRAP TYPE A	EACH	5			5
02704	SILT TRAP TYPE B	EACH	5			5
02705	SILT TRAP TYPE C	EACH	5			5
02706	CLEAN SILT TRAP TYPE A	EACH	5			5
02707	CLEAN SILT TRAP TYPE B	EACH	5			5
02708	CLEAN SILT TRAP TYPE C	EACH	5			5
02726	STAKING	LS	1			1
05952	TEMP MULCH	SQYD	3499			3499
05953	TEMP SEEDING AND PROTECTION	SQYD	2624			2624
05963	INITIAL FERTILIZER	TON	0.25			0.25
05985	SEEDING AND PROTECTION	SQYD	5248			5248
06406	SBM ALUM SHEET SIGNS .080 IN	SQFT	102			102
06407	SBM ALUM SHEET SIGNS .125 IN	SQFT	6			6
06410	STEEL POST TYPE 1	LF	115			115

ITEM	DESCRIPTION	UNIT	MAINLINE	APPROACH	ENTRANCE	TOTAL PROJECT
06542	PAVE STRIPING-THERMO-6 IN W	LF	37080			37080
06543	PAVE STRIPING-THERMO-6 IN Y	LF	29163			29163
06568	PAVE MARKING-THERMO STOP BAR-24IN	LF	10			10
10020NS	FUEL ADJUSTMENT	DOLL	5006			5006
10030NS	ASPHALT ADJUSTMENT	DOLL	12573			12573
20071EC	JOINT ADHESIVE	LF	16015			16015
21373ND	REMOVE SIGN (STOP SIGN AT MP 24.02)	EACH	1			1
21802EN	G/R STEEL W BEAM-S FACE (7 FT POST)	LF	1650			1650
22692NS714	PAVEMENT MARKING-THERMO LETTERS	EACH	108			108
23020EN	TRIM AND REMOVE TREES AND BRUSH	ACRE	0.18			0.18
24265EC	INSTALL SIGN POST REFLECTORS	EACH	14			14
24631EC	BARCODE SIGN INVENTORY	EACH	27			27

ITEM NO. 9-9036	COUNTY OF LEWIS
SHEET NO. 000	

DIVISION 600 - STRUCTURES AND CONCRETE

650 STANDARD DRAWINGS

STANDARD DRAWINGS ARE NOT ATTACHED TO THESE PLANS. A STANDARD DRAWING BOOK AND THE HEADWALL SUPPLEMENTAL BOOK MAY BE OBTAINED FROM THE POLICY SUPPORT BRANCH OF THE DEPARTMENT OF ADMINISTRATIVE SERVICES IN FRANKFORT, KY. AT (502) 564-4610.

GENERAL NOTES AND SPECIAL PROVISIONS

DIVISION 100 - GENERAL PROVISIONS

160 N.G.S. (U.S.G.S.) BENCH MARKS

DO NOT DISTURB N.G.S. (U.S.G.S.) BENCH MARKS IN ANY MANNER UNLESS DIRECTED BY THE ENGINEER.

165 BEFORE YOU DIG

THE CONTRACTOR IS INSTRUCTED TO CALL 1-800-752-6007 TO REACH KY 811. THE ONE-CALL SYSTEM FOR INFORMATION ON THE LOCATION OF EXISTING UNDERGROUND UTILITIES. THE CALL IS TO BE PLACED A MINIMUM OF TWO (2) AND NO MORE THAN TEN (10) BUSINESS DAYS PRIOR TO EXCAVATION. THE CONTRACTOR SHOULD BE AWARE THAT OWNERS OF UNDERGROUND FACILITIES ARE NOT REQUIRED TO BE MEMBERS OF THE KY 811 ONE-CALL BEFORE-U-DIG (BUD) SERVICE. THE CONTRACTOR MUST COORDINATE EXCAVATION WITH THE UTILITY OWNERS, INCLUDING THOSE WHOM DO NOT SUBSCRIBE TO KY 811. IT MAY BE NECESSARY FOR THE CONTRACTOR TO CONTACT THE COUNTY COURT CLERK TO DETERMINE WHAT UTILITY COMPANIES HAVE FACILITIES IN THE AREA.

190 DEPARTMENT OF THE ARMY PERMIT AND WATER QUALITY CERTIFICATION APPROVALS

A DEPARTMENT OF THE ARMY (DA) PERMIT, WHICH MAY REQUIRE APPROVAL OF A STATE WATER QUALITY CERTIFICATION FROM THE KENTUCKY DIVISION OF WATER, REGULATES THIS PROJECT AT ONE OR MORE LOCATIONS. PERFORM ALL APPLICABLE WORK IN COMPLIANCE WITH THE CONDITIONS STATED IN THE DA PERMIT AND THE APPROVED WATER QUALITY CERTIFICATION. POST A COPY OF THE DA PERMIT AND THE WATER QUALITY CERTIFICATION IN A CONSPICUOUS PLACE AT THE PROJECT SITE. IF A DA PERMIT OR WATER QUALITY CERTIFICATION APPROVAL IS PENDING, DO NOT WORK IN OR DISTURB THE DESIGNATED AREA(S) UNTIL OBTAINING THE APPROPRIATE APPROVAL(S). REFER TO NOTICE(S) CONTAINED IN THE CONTRACT BID PROPOSAL FOR DESIGNATED AREA(S) WHERE WORK IS PROHIBITED BY THE ABSENCE OF APPROVAL.

DIVISION 400 - ASPHALT PAVEMENTS

444 ASPHALT PAVEMENT RIDE QUALITY

PAVEMENT RIDEABILITY REQUIREMENTS, IN ACCORDANCE WITH SECTION 410 OF THE STANDARD SPECIFICATIONS, SHALL APPLY ON THIS PROJECT. CATEGORY B SHALL APPLY.

447 COMPACTION OF ASPHALT MIXTURES

WILL ACCEPT THE COMPACTION OF ASPHALT MIXTURES FURNISHED FOR DRIVING LANES AND RAMPS AT ONE INCH OR GREATER ON THIS PROJECT BY OPTION A ACCORDING TO SUBSECTIONS 402 AND 403 OF THE CURRENT STANDARD SPECIFICATIONS. USE JOINT CORES AS DESCRIBED IN SUBSECTION 402.03.02 FOR SURFACE MIXTURES ONLY. WILL ACCEPT THE COMPACTION OF ALL OTHER ASPHALT MIXTURES BY OPTION B.

455 EDGE KEY

THIS WORK INCLUDES CUTTING OUT THE EXISTING ASPHALT SURFACE TO A MINIMUM DEPTH AND WIDTH AS DETAILED ELSEWHERE IN THE PLANS SO THAT THE NEW SURFACE MAY HEEL INTO THE EXISTING SURFACE. THE CONTRACT UNIT PRICE BID LINEAR FOOT FOR "EDGE KEY" INCLUDES ALL NECESSARY MATERIALS, LABOR AND EQUIPMENT NECESSARY TO PERFORM THE WORK AND DISPOSE OF THE REMOVED ASPHALT MATERIAL.

DRAWING TITLE: GENERAL NOTES



PROPOSAL BID ITEMS

264100

Page 1 of 2

Report Date 3/23/26

264100

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00001		DGA BASE	1,165.00	TON		\$	
0020	00100		ASPHALT SEAL AGGREGATE (REVISED 3-23-26)	491.00	TON		\$	
0030	00103		ASPHALT SEAL COAT (REVISED 3-23-26)	59.00	TON		\$	
0040	00190		LEVELING & WEDGING PG64-22	2.00	TON		\$	
0050	00301		CL2 ASPH SURF 0.38D PG64-22	3,275.00	TON		\$	
0060	00356		ASPHALT MATERIAL FOR TACK	16.00	TON		\$	
0070	02585		EDGE KEY	46.00	LF		\$	
0080	20071EC		JOINT ADHESIVE	16,015.00	LF		\$	

Section: 0002 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0090	02230		EMBANKMENT IN PLACE	964.00	CUYD		\$	
0100	02483		CHANNEL LINING CLASS II (REVISED 3-23-26)	3,275.00	TON		\$	
0110	02545		CLEARING AND GRUBBING (1.1 ACRES HSIP)	1.00	LS		\$	
0120	02562		TEMPORARY SIGNS	1,500.00	SQFT		\$	
0130	02602		FABRIC-GEOTEXTILE CLASS 1	166.00	SQYD		\$	
0140	02650		MAINTAIN & CONTROL TRAFFIC (LEWIS KY 8 HSIP)	1.00	LS		\$	
0150	02671		PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH		\$	
0160	02697		EDGELINE RUMBLE STRIPS	31,000.00	LF		\$	
0170	02701		TEMP SILT FENCE	13,755.00	LF		\$	
0180	02703		SILT TRAP TYPE A	5.00	EACH		\$	
0190	02704		SILT TRAP TYPE B	5.00	EACH		\$	
0200	02705		SILT TRAP TYPE C	5.00	EACH		\$	
0210	02706		CLEAN SILT TRAP TYPE A	5.00	EACH		\$	
0220	02707		CLEAN SILT TRAP TYPE B	5.00	EACH		\$	
0230	02708		CLEAN SILT TRAP TYPE C	5.00	EACH		\$	
0240	02726		STAKING (LEWIS KY 8 HSIP)	1.00	LS		\$	
0250	05952		TEMP MULCH	3,499.00	SQYD		\$	
0260	05953		TEMP SEEDING AND PROTECTION	2,624.00	SQYD		\$	
0270	05963		INITIAL FERTILIZER	0.25	TON		\$	
0280	05985		SEEDING AND PROTECTION	5,248.00	SQYD		\$	
0290	06542		PAVE STRIPING-THERMO-6 IN W	37,080.00	LF		\$	
0300	06543		PAVE STRIPING-THERMO-6 IN Y	29,163.00	LF		\$	
0310	06568		PAVE MARKING-THERMO STOP BAR-24IN	10.00	LF		\$	
0320	10020NS		FUEL ADJUSTMENT	5,006.00	DOLL	\$1.00	\$	\$5,006.00
0330	10030NS		ASPHALT ADJUSTMENT	12,573.00	DOLL	\$1.00	\$	\$12,573.00
0340	22692NS714		PAVEMENT MARKING-THERMO LETTERS	108.00	EACH		\$	
0350	23020EN		TRIM AND REMOVE TREES AND BRUSH	0.18	ACRE		\$	

PROPOSAL BID ITEMS

264100

Report Date 3/23/26

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0360	26248EC		ELECTRONIC DELIVERY MGMT SYSTEM - AGG (LEWIS KY 8 HSIP)	1.00	LS		\$	

Section: 0003 - SIGNING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0370	06406		SBM ALUM SHEET SIGNS .080 IN	102.00	SQFT		\$	
0380	06407		SBM ALUM SHEET SIGNS .125 IN	6.00	SQFT		\$	
0390	06410		STEEL POST TYPE 1	115.00	LF		\$	
0400	21373ND		REMOVE SIGN	1.00	EACH		\$	
0410	24265EC		INSTALL SIGN POST REFLECTORS	13.00	EACH		\$	
0420	24631EC		BARCODE SIGN INVENTORY	27.00	EACH		\$	

Section: 0004 - GUARDRAIL

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0430	01987		DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	34.00	EACH		\$	
0440	02351		GUARDRAIL-STEEL W BEAM-S FACE	1,650.00	LF		\$	
0450	02367		GUARDRAIL END TREATMENT TYPE 1	3.00	EACH		\$	
0460	02371		GUARDRAIL END TREATMENT TYPE 7	1.00	EACH		\$	
0470	02381		REMOVE GUARDRAIL	1,713.00	LF		\$	

Section: 0005 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0480	02569		DEMOBILIZATION	1.00	LS		\$	