



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

January 27, 2026

CALL NO. 113
CONTRACT ID NO. 264201
ADDENDUM # 2

Subject: Campbell County, HSIP 0272(124)
Letting January 29, 2026

- (1) Revised - Plan Sheet - Page 33 of 80
- (2) Revised - Proposal Bid Items - Page 80 of 80

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

CONSTRUCTION AND MEASUREMENT NOTES THAT ARE CONTRARY TO SECTION 723

SUBSECTION 03.02 POLES AND BASES INSTALLATION. B) REVISION/REPLACE ENTIRE TABLE WITH THE FOLLOWING:

MAXIMUM SERVICE FORCES		DRILLED SHAFT DATA				VERTICAL BARS		TIES OR SPIRAL	
MAX SERVICE MOMENT (FT-KIPS)	DIAMETER (IN.)	< 2:1 GROUND SLOPE SOIL	ROCK	DEPTH (FEET)	2:1 GROUND SLOPE SOIL	ROCK	SIZE	BAR SIZE	SPACING OR PITCH (IN.)
0-49.9	36	9	6	6.5	6.5	6.5	13	#8	12
50-99.9	36	9	6	6.5	6.5	6.5	13	#8	12
100-149.9	36	9	6	6.5	6.5	6.5	13	#8	12
150-199.9	36	9	6	6.5	6.5	6.5	13	#8	12
200-249.9	36	9	6	6.5	6.5	6.5	13	#8	12
250-299.9	36	9	6	6.5	6.5	6.5	13	#8	12
300-349.9	36	9	6	6.5	6.5	6.5	13	#8	12
350-399.9	36	9	6	6.5	6.5	6.5	13	#8	12
400-499.9	42	21.5	7.5	7.5	21.5	7.5	18	#8	12
500-599.9	48	22.5	7.5	7.5	22.5	7.5	18	#8	12

SUBSECTION: 03.12 WIRING INSTALLATION, SEE TRAFFIC OPERATIONS WEBSITE FOR WORD DOCUMENT TO REPLACE ALL CHARTS FOR WIRING TO SHOW CHANGES FOR EQUIPMENT GROUNDING.

ALL MATERIALS REMOVED AND NOT REUSED, SUCH AS SIGNS, SIGN LIGHTS, SIGN SUPPORTS, ETC, SHALL BECOME THE PROPERTY OF THE CONTRACTOR.

ADD SENTENCE TO SECTION 835.17: ALL WIRE SHALL HAVE WORDING ADDED TO THE OUTER JACKET THAT STATES : " PROPERTY OF KENTUCKY TRANSPORTATION CABINET 502 564 0901".

MEASUREMENT NOTES THAT ARE IN ADDITION TO SECTION 723

ADVANCE WARNING FLASHER - DEPARTMENT WILL MEASURE THE QUANTITY AS EACH INDIVIDUAL UNIT FURNISHED AND INSTALLED. THE DEPARTMENT WILL NOT MEASURE 48X48 INCH SIGN WITH CHANNEL POSTS, 72X44 INCH SPAN MOUNTED SIGN, CONDUIT FROM STEEL STRAIN POLE TO SIGNAL HEADS ON SIDE MOUNTED SIGN, CONDUIT FITTINGS AND STRAPS, OR ANY ASSOCIATED SIGN MOUNTING HARDWARE AND WILL CONSIDER THESE INCIDENTAL TO THIS ITEM OF WORK.

INSTALL SIGNAL CONTROLLER TYPE ATC. THE DEPARTMENT WILL MEASURE THE QUANTITY AS EACH INDIVIDUAL UNIT INSTALLED. THE DEPARTMENT WILL NOT MEASURE THE CONCRETE BASE, MOUNTING THE CABINET, CONNECTING THE SIGNAL AND DETECTORS, EXCAVATION, BACKFILLING, RESTORATION, ANY NECESSARY POLE MOUNTING HARDWARE, ELECTRIC SERVICE, ELECTRICAL INSPECTION FEES, AND REQUIRED BUILDING FEES INVOLVING UTILITY SECONDARY/PRIMARY SERVICE FOR PAYMENT AND WILL CONSIDER THEM INCIDENTAL TO THIS ITEM OF WORK. THE DEPARTMENT WILL ALSO NOT MEASURE CONNECTING THE INDUCTION LOOP AMPLIFIERS, PEDESTRIAN ISOLATORS, LOAD SWITCHES, MODEL 400 MODEM CARD FOR PAYMENT AND WILL CONSIDER THEM INCIDENTAL TO THIS ITEM OF WORK. THE DEPARTMENT WILL ALSO NOT MEASURE FURNISHING AND INSTALLING ELECTRICAL SERVICE CONDUCTORS, CONDUITS, ANCHORS, METER BASE, FUSED CUTOFF, FUSES, GROUND RODS, GROUND LUGS, AND GROUND WIRES FOR PAYMENT AND WILL CONSIDER THEM INCIDENTAL TO THIS ITEM OF WORK.

INSTALL RADAR PRESENCE DETECTOR TYPE A SHALL CONSIST OF INSTALLATION OF A POLE MOUNTED RADAR PRESENCE SENSOR, SENSOR MOUNTING BRACKET, SENSOR CABLES, INTERFACE BOXES, LEAD-IN CABLE, CONNECTORS (FURNISHED BY CONTRACTOR), AND CONTROLLER INTERFACE ASSEMBLY. RADAR PRESENCE DETECTOR TYPE A BID ITEM SHALL INCLUDE ALL LABOR REQUIRED TO PROVIDE A FUNCTIONAL DETECTION SYSTEM. RADAR PRESENCE DETECTOR TYPE A SHALL BE INSTALLED AND WIRED IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS. AFTER THE DETECTOR IS INSTALLED AND BEFORE THE DETECTOR IS POWERED ON, THE CONTRACTOR SHALL COORDINATE WITH DISTRICT TRAFFIC DIVISION'S REPRESENTATIVES TO SCHEDULE A TIME TO PERFORM THE DETECTOR SETUP. THE CONTRACTOR SHALL DOUBLE CHECK TO VERIFY THAT ALL WIRING IS CORRECTLY INSTALLED AND CONNECTED BEFORE SCHEDULING THE SETUP WORK. REPRESENTATIVES FROM KYTC AND/OR THE MANUFACTURER OR SALES REPRESENTATIVE WILL ASSIST WITH SETUP AND CALIBRATION. THE CONTRACTOR SHALL PROVIDE A BUCKET TRUCK AND OPERATORS AT THIS TIME FOR FINAL AIMING OF THE SENSORS. THE CONTRACTOR SHALL PROVIDE INDIVIDUALS CAPABLE OF OPERATING THE SETUP SOFTWARE AND LEARNING THE SETUP PROCESS SO THAT FUTURE INSTALLATIONS MAY BE COMPLETED WITHOUT ASSISTANCE FROM OTHERS.

INSTALL RADAR ADVANCE DETECTOR TYPE B SHALL CONSIST OF INSTALLATION OF A POLE MOUNTED RADAR PRESENCE SENSOR, SENSOR MOUNTING BRACKET, SENSOR CABLES, INTERFACE BOXES, LEAD-IN CABLE, CONNECTORS (FURNISHED BY CONTRACTOR), AND CONTROLLER INTERFACE ASSEMBLY. RADAR ADVANCE DETECTOR TYPE B BID ITEM SHALL INCLUDE ALL LABOR REQUIRED TO PROVIDE A FUNCTIONAL DETECTION SYSTEM. RADAR ADVANCE DETECTOR TYPE B SHALL BE INSTALLED AND WIRED IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS. AFTER THE DETECTOR IS INSTALLED AND BEFORE THE DETECTOR IS POWERED ON, THE CONTRACTOR SHALL COORDINATE WITH DISTRICT TRAFFIC DIVISION'S REPRESENTATIVES TO SCHEDULE A TIME TO PERFORM THE DETECTOR SETUP. THE CONTRACTOR SHALL DOUBLE CHECK TO VERIFY THAT ALL WIRING IS CORRECTLY INSTALLED AND CONNECTED BEFORE SCHEDULING THE SETUP WORK. REPRESENTATIVES FROM KYTC AND/OR THE MANUFACTURER OR SALES REPRESENTATIVE.

TRAFFIC SIGNAL ESTIMATE OF QUANTITIES

TOTAL	UNITS	CODE	ITEM DESCRIPTION
400	SOFT	2562	TEMPORARY SIGNS
1	LP SUM	2569	DEMOLITION
1	LP SUM	2650	MAINTAIN & CONTROL TRAFFIC
4	LP SUM	2654	TRUCK MOUNTED ATTENUATOR
4	EACH	2775	ARROW PANEL
282	LN FT	4795	CONDUIT - 2 IN.
1435	LN FT	4820	TRENCHING AND BACKFILLING
5240	LN FT	4844	CABLE - NO. 14/SC
545	LN FT	4885	MESSNGER-10800 LB
4	EACH	4932	INSTALL STEEL STRAIN POLE
10	EACH	2039NSB35	ELECTRICAL JUNCTION BOX TYPE A
8	EACH	2040RESB35	INSTALL LED BEACON - 12 IN.
1	EACH	21373ND	REMOVE SIGN
507	LN FT	21543EN	BORE AND JACK CONDUIT
15.7	CU YD	23157EN	TRAFFIC SIGNAL POLE BASE
2	EACH	2452SEC	ADVANCE WARNING FLASHER
8	EACH	24631EC	BARCODE SIGN INVENTORY
1680	LN FT	2490DEC	PVC CONDUIT - 1 1/4 INCH - SCHEDULE 80
1	EACH	24855ED	REMOVE SIGNAL EQUIPMENT
4	EACH	26119EC	INSTALL RADAR PRESENCE DETECTOR TYPE A
2	EACH	26120EC	INSTALL RADAR ADVANCE DETECTOR TYPE B

THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, CURRENT EDITION, AND OTHER SPECIAL NOTES AND SPECIFICATIONS WILL APPLY ON THIS PROJECT. SEE SECTION 706, 723, AND 112 FOR MEASUREMENT AND OTHER DETAILS. SEE SECTION 602 FOR SPIRAL REINFORCEMENT SPLICING.

THE CONTRACTOR SHALL MAKE AN INSPECTION OF THE PROJECT SITE PRIOR TO SUBMITTING A BID AND SHALL BE THOROUGHLY FAMILIARIZED WITH EXISTING CONDITIONS. SUBMISSIONS OF A BID WILL BE CONSIDERED AN AFFIRMATION OF THIS INSPECTION HAVING BEEN COMPLETED.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PICKING UP MATERIALS FOR INSTALL ITEMS AT KYTC'S DIVISION OF EQUIPMENT WAREHOUSE (1239 WILKINSON BOULEVARD, FRANKFORT, KY 40622). THE FOLLOWING PROCEDURES SHALL BE FOLLOWED FOR MATERIAL RELEASE. FAILURE TO FOLLOW THESE PROCEDURES MAY RESULT IN LONG DELAYS OR REFUSAL TO DISTRIBUTE MATERIALS UPON ARRIVAL.

- CONTRACTOR SHALL SECURE THE SIGNATURES OF KYTC'S PROJECT ENGINEER AND THE ELECTRICAL CONTRACTOR'S FOREMAN ON THE PROJECT MATERIALS RELEASE FORM. IF THE RELEASE FORM IS NOT IN THE PROPOSAL, CONTACT KIM STAMPER OR KERRY DECKER WITH THE DIVISION OF TRAFFIC OPERATIONS BY PHONE (502-762-6594/502-762-5536) OR EMAIL (KIM.STAMPER@KY.GOV/KERRY.DECKER@KY.GOV).
- CONTRACTOR SHALL CONTACT THE WAREHOUSE TO PREARRANGE PICK UP OF MATERIALS. SIGNATURES TO THE WAREHOUSE AT KIM.STAMPER@KY.GOV AND SHALL NOTIFY THE WAREHOUSE BY PHONE (502-762-6594/502-530-67553) OR EMAIL KIM.STAMPER@KY.GOV AT LEAST TWO (2) WORKING DAYS PRIOR TO ARRIVAL.
- CONTRACTOR SHALL ALSO CONTACT THE SYSTEM OPERATIONS BRANCH OF THE DIVISION OF TRAFFIC OPERATIONS BY PHONE (502-762-5543/502-762-5547) OR EMAIL (JOE.THOMPSON@KY.GOV/LARRY.INSH@KY.GOV) AT LEAST TWO (2) WORKING DAYS PRIOR TO ARRIVAL TO FACILITATE PROGRAMMING OF ROUTERS.
- CONTRACTOR SHALL ARRIVE AT THE KYTC'S DIVISION OF EQUIPMENT WAREHOUSE (1239 WILKINSON BOULEVARD, FRANKFORT, KY 40622) AT THE PREARRANGED DATE/TIME FOR MATERIAL PICK UP. TO FACILITATE THIS PROCESS, ENSURE CONTRACTOR'S DELIVERY DRIVER HAS A COPY OF THE PROJECT MATERIALS RELEASE FORM WITH THE REQUIRED SIGNATURES.



COMMONWEALTH OF KENTUCKY
DEPARTMENT OF HIGHWAYS

DRAWING TITLE: ESTIMATE OF QUANTITIES MEASUREMENT, CONSTRUCTION, AND MISC. NOTES

FILE NAME: C:\BMS\HSP-124\20160204\QUANTITIES SHEET.DGN

USER: USR06049

HORIZONTAL SCALE
SCALE: N/A

US 27 AT KY 536
ADVANCE WARNING FLASHER PLANS

ITEM NO.
C-264201
SHEET NO.
12

COUNTY OF
CAMPBELL

PROPOSAL BID ITEMS

264201

Report Date 1/27/26

Page 1 of 1

264201

Section: 0001 - SIGNING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	02562		TEMPORARY SIGNS	400.00	SQFT		\$	
0020	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0025	02654		TRUCK MOUNTED ATTENUATOR (ADDED 1-26-26)	4.00	EACH		\$	
0030	02775		ARROW PANEL	4.00	EACH		\$	
0040	21373ND		REMOVE SIGN	1.00	EACH		\$	
0045	24631EC		BARCODE SIGN INVENTORY (ADDED 1-26-26)	8.00	EACH		\$	

Section: 0002 - SIGNALIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0050	04795		CONDUIT-2 IN	282.00	LF		\$	
0060	04820		TRENCHING AND BACKFILLING (REVISED 1-27-26)	1,435.00	LF		\$	
0070	04844		CABLE-NO. 14/5C	5,240.00	LF		\$	
0080	04885		MESSENGER-10800 LB	545.00	LF		\$	
0090	04932		INSTALL STEEL STRAIN POLE	4.00	EACH		\$	
0100	20391NS835		ELECTRICAL JUNCTION BOX TYPE A	10.00	EACH		\$	
0110	20408ES835		INSTALL LED BEACON-12 IN	8.00	EACH		\$	
0120	21543EN		BORE AND JACK CONDUIT	507.00	LF		\$	
0130	23157EN		TRAFFIC SIGNAL POLE BASE	15.70	CUYD		\$	
0140	24525EC		ADVANCE WARNING FLASHER	2.00	EACH		\$	
0150	24900EC		PVC CONDUIT-1 1/4 IN-SCHEDULE 80	1,660.00	LF		\$	
0160	24955ED		REMOVE SIGNAL EQUIPMENT	1.00	EACH		\$	
0170	26119EC		INSTALL RADAR PRESENCE DETECTOR TYPE A	4.00	EACH		\$	
0180	26120EC		INSTALL RADAR ADVANCE DETECTOR TYPE B	2.00	EACH		\$	

Section: 0003 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0190	02569		DEMOBILIZATION	1.00	LS		\$	