



**COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET**
Frankfort, Kentucky 40622
www.transportation.ky.gov/

Matthew G. Bevin
Governor

Greg Thomas
Secretary

April 26, 2017

CALL NO. 115
CONTRACT ID NO. 172980
ADDENDUM # 3

Subject: Kenton County, HPP 0758 (100)
Letting April 28, 2017

- (1) Revised - Front Sheet
- (2) Revised - Completion Date - Page 4 of 239
- (3) Revised - Note - Page 120 of 239
- (4) Revised - Bid Items - Pages 237-239 of 239

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:ks
Enclosures



An Equal Opportunity Employer M/F/D



CALL NO. 115

CONTRACT ID. 172980

KENTON COUNTY

FED/STATE PROJECT NUMBER HPP 0758(100)

DESCRIPTION BRIDGE DECK OVERLAY I 75 OVER THE OHIO RIVER 059B00046N

WORK TYPE BRIDGE DECK OVERLAY

PRIMARY COMPLETION DATE 11/15/2017

LETTING DATE: April 28,2017

Sealed Bids will be received electronically through the Bid Express bidding service until 10:00 AM EASTERN DAYLIGHT TIME April 28,2017. Bids will be publicly announced at 10:00 AM EASTERN DAYLIGHT TIME.

PLANS AVAILABLE FOR THIS PROJECT.

DBE CERTIFICATION REQUIRED - 7%

REQUIRED BID PROPOSAL GUARANTY: Not less than 5% of the total bid.

ADMINISTRATIVE DISTRICT - 06

REVISED ADDENDUM #3: 4-26-17

CONTRACT ID - 172980

HPP 0758(100)

COUNTY - KENTON

PCN - MB05900751780

HPP 0758(100)

BRIDGE DECK OVERLAY I 75 OVER THE OHIO RIVER 059B00046N BRIDGE DECK OVERLAY I 75 OVER THE OHIO RIVER 059B00046N, A DISTANCE OF 0.50 MILES. BRIDGE DECK OVERLAY SYP NO. 06-00017.04.
GEOGRAPHIC COORDINATES LATITUDE 39:05:27.62 LONGITUDE -84:31:21.43

COMPLETION DATE(S):

COMPLETED BY 11/15/2017	APPLIES TO ENTIRE CONTRACT
COMPLETED BY 09/01/2017	APPLIES WHEN I75/I71 IS OUT OF NORMAL CONFIGURATION

No extension to the number of calendar days bid, or ramp closure periods, will be granted due to over-run of contract quantities. The engineer will grant an extension of the number of calendar days bid for supplemental work not previously identified in the contract that must be performed when traffic is out of its normal configuration. The Engineer will determine the number of additional calendar days due for the additional work by dividing the value of the additional work by the value of the original Contract work and multiply this ratio by the number of calendar days from Notice to Begin work to September 1, 2017.

If supplemental work must be performed when traffic is out of its normal configuration, added calendar days will be added to the September 1, 2017, milestone completion date on a day for day basis. If supplemental work can be performed when traffic is in its normal configuration, added calendar days will be added to the November 15, 2017, fixed completion date on a day for day basis. Extensions of the completion dates may include periods of time when weather conditions may not be conducive to the work required by the contract. ALL construction operations for the project will be required to be completed by the extended completion date and in accordance with any weather limitations specified in the Kentucky 2012 Standard Specifications for Road and Bridge Construction, the contract proposal or the contract plans. No further extension of contract time will be granted due to inclement weather or temperature limitations experienced during the time extension.

PROPOSAL BID ITEMS

172980

Report Date 4/26/17

Section: 0001 - BRIDGE - OHIO RIVER BRIDGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	01984		DELINEATOR FOR BARRIER - WHITE	538.00	EACH		\$	
0020	01985		DELINEATOR FOR BARRIER - YELLOW	533.00	EACH		\$	
0030	02003		RELOCATE TEMP CONC BARRIER	15,979.00	LF		\$	
0040	02275		FENCE-8 FT CHAIN LINK	65.00	LF		\$	
0050	02281		PEDESTRIAN GATE-CHAIN LINK	1.00	EACH		\$	
0060	02403		REMOVE CONCRETE MASONRY	.42	CUYD		\$	
0070	02562		TEMPORARY SIGNS	4,390.00	SQFT		\$	
0080	02562		TEMPORARY SIGNS (OVERHEAD SIGN MODIFICATION)	2,160.00	SQFT		\$	
0090	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0100	02654		TRUCK MOUNTED ATTENUATOR	4.00	EACH		\$	
0110	02671		PORTABLE CHANGEABLE MESSAGE SIGN	10.00	EACH		\$	
0120	02775		ARROW PANEL	5.00	EACH		\$	
0130	02898		RELOCATE CRASH CUSHION	6.00	EACH		\$	
0140	03171		CONCRETE BARRIER WALL TYPE 9T	14,142.00	LF		\$	
0150	03261		CLEAN BRIDGE DRAINS	128.00	EACH		\$	
0160	04721		BRACKET 6 FT	34.00	EACH		\$	
0170	04761		LIGHTING CONTROL EQUIPMENT	1.00	EACH		\$	
0180	04780		FUSED CONNECTOR KIT	68.00	EACH		\$	
0190	04793		CONDUIT-1 1/4 IN	340.00	LF		\$	
0200	04795		CONDUIT-2 IN	775.00	LF		\$	
0210	04800		MARKER	3.00	EACH		\$	
0220	04810		ELECTRICAL JUNCTION BOX REPLACE JUNCTION BOX	3.00	EACH		\$	
0230	04810		ELECTRICAL JUNCTION BOX REPLACE JUNCTION BOX COVER	10.00	EACH		\$	
0240	04820		TRENCHING AND BACKFILLING	120.00	LF		\$	
0250	04832		WIRE-NO. 12	2,580.00	LF		\$	
0260	04833		WIRE-NO. 8	1,725.00	LF		\$	
0270	04836		WIRE-NO. 2	80.00	LF		\$	
0280	04940		REMOVE LIGHTING	1.00	LS		\$	
0290	06511		PAVE STRIPING-TEMP PAINT-6 IN	44,434.00	LF		\$	
0300	06515		PAVE STRIPING-PERM PAINT-6 IN	14,229.00	LF		\$	
0310	06531		PAVE STRIPING REMOVAL-6 IN	49,115.00	LF		\$	
0320	06550		PAVE STRIPING-TEMP REM TAPE-W	6,944.00	LF		\$	
0330	06551		PAVE STRIPING-TEMP REM TAPE-Y	6,944.00	LF		\$	
0340	06585		PAVEMENT MARKER TY IVA-MW TEMP	780.00	EACH		\$	
0350	06586		PAVEMENT MARKER TY IVA-MY TEMP	289.00	EACH		\$	
0360	06592		PAVEMENT MARKER TYPE V-B W/R	132.00	EACH		\$	
0370	06593		PAVEMENT MARKER TYPE V-B Y/R	44.00	EACH		\$	
0380	08104		CONCRETE-CLASS AA	.44	CUYD		\$	
0390	08151		STEEL REINFORCEMENT-EPOXY COATED	209.00	LB		\$	
0395	08504		EPOXY SAND SLURRY (ADDED: 4-26-17)	900.00	SQYD		\$	
0400	08510		REM EPOXY BIT FOREIGN OVERLAY	17,670.50	SQYD		\$	
0410	08526		CONC CLASS M FULL DEPTH PATCH	20.00	CUYD		\$	
0420	08534		CONCRETE OVERLAY-LATEX	859.00	CUYD		\$	
0425	08549		BLAST CLEANING (ADDED: 4-26-17)	1,013.00	SQYD		\$	

PROPOSAL BID ITEMS

REVISED ADDENDUM #3: 4-26-17

172980

Page 2 of 3

Report Date 4/26/17

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0430	08550		HYDRODEMOLITION	17,670.50	SQYD		\$	
0440	08820		DRAIN PIPE-6 IN	145.00	LF		\$	
0450	08901		CRASH CUSHION TY VI CLASS BT TL2	4.00	EACH		\$	
0460	10202ND		TIME COMPONENT (APPLIES TO ENTIRE PROJECT)	200,000.00	DOLL		\$	
0470	20391NS835		ELECTRICAL JUNCTION BOX TYPE A	2.00	EACH		\$	
0480	20411ED		LAW ENFORCEMENT OFFICER	2,880.00	HOURL		\$	
0490	21543EN		BORE AND JACK CONDUIT	75.00	LF		\$	
0500	21563NN		SPLICE BOX REPLACE SPLICE BOX COVER	2.00	EACH		\$	
0510	21579EN		FLEX CONDUIT-1 1/4 IN	170.00	LF		\$	
0520	24094EC		PARTIAL DEPTH PATCHING	130.00	CUYD		\$	
0530	24525EC		ADVANCE WARNING FLASHER (TYPE B FOR TEMPORARY SIGNS)	68.00	EACH		\$	
0540	24589ED		LED LUMINAIRE	34.00	EACH		\$	
0550	24879EC		STEEL REPAIR DIAPHRAGM WELD REPAIR	10.00	EACH		\$	
0560	24879EC		STEEL REPAIR FINGER JOINT BOLT REPLACE	12.00	EACH		\$	
0570	24879EC		STEEL REPAIR FLOORBEAM T-CONNECTION REPAIR	15.00	EACH		\$	
0580	24879EC		STEEL REPAIR FLOORBEAM TOP FLANGE REPAIR	2.00	EACH		\$	
0590	24879EC		STEEL REPAIR INSPECTION WALK REPAIR	1.00	EACH		\$	
0600	24879EC		STEEL REPAIR PIN GUIDE ANGLE REPLACEMENT	32.00	EACH		\$	
0610	24897EC		EXPAN JOINT REPLACE 3/4 IN 3/4 IN	686.90	LF		\$	
0620	24899EC		PAVE MARKING-THERMO ELONG ROUTE SHIELD	16.00	EACH		\$	

Section: 0002 - BRIDGE - KENTUCKY APPROACH

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0630	00071		CRUSHED AGGREGATE SIZE NO 57	49.80	TON		\$	
0640	01690		FLUME INLET TYPE 1	1.00	EACH		\$	
0650	02157		PAVED DITCH TYPE 1	35.80	SQYD		\$	
0660	02599		FABRIC-GEOTEXTILE TYPE IV	21.30	SQYD		\$	
0670	03261		CLEAN BRIDGE DRAINS	25.00	EACH		\$	
0680	08104		CONCRETE-CLASS AA	.45	CUYD		\$	
0690	08150		STEEL REINFORCEMENT	273.00	LB		\$	
0700	08435		JACK & SUPPORT BRIDGE SPAN	1.00	LS		\$	
0710	08820		DRAIN PIPE-6 IN	40.00	LF		\$	
0720	21969NN		BEARING REPLACEMENT INSTALL SHIM	72.00	EACH		\$	
0730	21969NN		BEARING REPLACEMENT PIN REPLACEMENT	39.00	EACH		\$	
0740	21969NN		BEARING REPLACEMENT REPLACE, BEARING PAD, MASONRY PLATE, AND ANCHOR BOLTS	116.00	EACH		\$	
0750	21969NN		BEARING REPLACEMENT ROCKER REPLACEMENT	42.00	EACH		\$	

PROPOSAL BID ITEMS

REVISED ADDENDUM #3: 4-26-17

172980

Page 3 of 3

Report Date 4/26/17

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0760	21969NN		BEARING REPLACEMENT TOP PLATE REPLACEMENT	13.00	EACH		\$	
0770	22146EN		CONCRETE PATCHING REPAIR	575.00	SQFT		\$	
0780	23055N		REMOVE REMOVE VEGETATION	1.00	LS		\$	
0790	23853EC		BEARING REPAIR CLEAN AND PAINT	116.00	EACH		\$	
0800	23911EC		GROUT	.10	CUYD		\$	
0810	24662EC		CLEAN CLEAN CATCH BASIN	2.00	EACH		\$	
0820	24879EC		STEEL REPAIR DIAPHRAGM CRACK REPAIR	43.00	EACH		\$	
0830	24898EC		ALIGN CRIB WALL HEADER	3.00	EACH		\$	

Section: 0003 - BRIDGE - OHIO APPROACH

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0840	03297		EXPAN JOINT REPLACE 3 IN	316.00	LF		\$	
0850	03298		EXPAN JOINT REPLACE 4 IN	315.10	LF		\$	
0860	23034EN		EXPANSION JOINT REPLACE-5 IN	156.30	LF		\$	
0870	24879EC		STEEL REPAIR BEARING STIFFENER RETROFIT	1.00	EACH		\$	
0880	24879EC		STEEL REPAIR CROSSFRAME STIFFENER WELDING	216.00	EACH		\$	
0890	24879EC		STEEL REPAIR STEEL WEB CRACK RETROFIT	5.00	EACH		\$	

Section: 0004 - TRAFFIC LOOPS

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0900	04793		CONDUIT-1 1/4 IN	210.00	LF		\$	
0910	04795		CONDUIT-2 IN	20.00	LF		\$	
0920	04811		ELECTRICAL JUNCTION BOX TYPE B	3.00	EACH		\$	
0930	04820		TRENCHING AND BACKFILLING	220.00	LF		\$	
0940	04829		PIEZOELECTRIC SENSOR	22.00	EACH		\$	
0950	04830		LOOP WIRE	2,400.00	LF		\$	
0960	04895		LOOP SAW SLOT AND FILL	820.00	LF		\$	
0970	20359NN		GALVANIZED STEEL CABINET	1.00	EACH		\$	
0980	20360ES818		WOOD POST	6.00	EACH		\$	
0990	20468EC		ELECTRICAL JUNCTION BOX-10 X 8 X 4	2.00	EACH		\$	

Section: 0005 - MOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1000	02568		MOBILIZATION	1.00	LS		\$	
1010	02569		DEMOBILIZATION	1.00	LS		\$	