



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

May 21, 2024

CALL NO. 200
CONTRACT ID NO. 245348
ADDENDUM # 1

Subject: CARLISLE - CRITTENDEN COUNTIES, 121GR24D048-STP BRZ
Letting May 23, 2024

- (1) Revised - Material Summary - Pages 227-230 of 280
- (2) Revised - Proposal Bid Items - Pages 277-280 of 280

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

MATERIAL SUMMARY

CONTRACT ID: 245348

121GR24D048-STP BRZ

BR02000512400

US 51 ADDRESS DEFICIENCIES OF US 51 OVER LITTLE MAYFIELD CREEK (020B00004N) BRIDGE WITH GRADE & DRAIN, A DISTANCE OF .21 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	00001	DGA BASE	1,144.00	TON
0010	00100	ASPHALT SEAL AGGREGATE	4.00	TON
0015	00103	ASPHALT SEAL COAT	2.00	TON
0020	00212	CL2 ASPH BASE 1.00D PG64-22	2,372.00	TON
0025	00301	CL2 ASPH SURF 0.38D PG64-22	255.00	TON
0030	00441	ENTRANCE PIPE-18 IN	69.00	LF
0035	00462	CULVERT PIPE-18 IN	60.00	LF
0040	01433	SLOPED BOX OUTLET TYPE 1-18 IN	3.00	EACH
0045	02200	ROADWAY EXCAVATION	2,618.00	CUYD
0050	02351	GUARDRAIL-STEEL W BEAM-S FACE	487.50	LF
0055	02360	GUARDRAIL TERMINAL SECTION NO 1	1.00	EACH
0060	02367	GUARDRAIL END TREATMENT TYPE 1	3.00	EACH
0065	02381	REMOVE GUARDRAIL	328.00	LF
0070	02399	EXTRA LENGTH GUARDRAIL POST	37.00	EACH
0075	02429	RIGHT-OF-WAY MONUMENT TYPE 1	11.00	EACH
0080	02432	WITNESS POST	11.00	EACH
0085	02483	CHANNEL LINING CLASS II	453.00	TON
0090	02484	CHANNEL LINING CLASS III	50.00	TON
0095	02545	CLEARING AND GRUBBING - APPROX LESS THAN 1 ACRE	1.00	LS
0100	02565	OBJECT MARKER TYPE 2	6.00	EACH
0105	02585	EDGE KEY	48.00	LF
0110	02650	MAINTAIN & CONTROL TRAFFIC	1.00	LS
0115	02726	STAKING	1.00	LS
0120	02731	REMOVE STRUCTURE	1.00	LS
0125	03171	CONCRETE BARRIER WALL TYPE 9T	1,000.00	LF
0130	03299	ARMORED EDGE FOR CONCRETE	73.80	LF
0135	06514	PAVE STRIPING-PERM PAINT-4 IN	1,698.00	LF
0140	08003	FOUNDATION PREPARATION	1.00	LS
0145	08019	CYCLOPEAN STONE RIP RAP	435.00	TON
0150	08033	TEST PILES - (REVISED 5-21-24)	150.00	LF
0155	08046	PILES-STEEL HP12X53 - (REVISED 5-21-24)	980.00	LF
0160	08100	CONCRETE-CLASS A	45.00	CUYD
0165	08104	CONCRETE-CLASS AA	35.00	CUYD
0170	08140	MECHANICAL REINF COUPLER #5 EPOXY COATED	14.00	EACH
0175	08151	STEEL REINFORCEMENT-EPOXY COATED	9,202.00	LB
0180	08664	PRECAST PC BOX BEAM CB27-48	526.50	LF
0185	20191ED	OBJECT MARKER TY 3	3.00	EACH
0190	20738NS112	TEMP CRASH CUSHION	2.00	EACH
0195	21415ND	EROSION CONTROL	1.00	LS
0200	22883EN	CONCRETE WEDGE CURB	558.00	LF
0205	23274EN11F	TURF REINFORCEMENT MAT 1	240.00	SQYD
0210	23378EC	CONCRETE SEALING	3,255.00	SQFT

MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0215	24405EC	MECHANICAL REINF COUPLER-#8 EPOXY COATED	18.00	EACH
0220	24970EC	ASPHALT MATERIAL FOR TACK NON-TRACKING	1.00	TON
0225	25028ED	RAIL SYSTEM SINGLE SLOPE - 40 IN	117.00	LF
0230	25078ED	THRIE BEAM GUARDRAIL TRANSITION TL-3	4.00	EACH
0235	26233EC	MOBILIZATION FOR CONCRETE SURF TREATMENT	1.00	LS
0240	02568	MOBILIZATION	1.00	LS
0245	02569	DEMOBILIZATION	1.00	LS

CONTRACT ID: 245348

121GR24D048-STP BRZ

BR02000512401

US 51 ADDRESS DEFICIENCIES OF US 51 OVER GADDIE CREEK (020B00002N) BRIDGE REPLACEMENT, A DISTANCE OF .1 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0250	00001	DGA BASE	368.00	TON
0255	00100	ASPHALT SEAL AGGREGATE	1.50	TON
0260	00103	ASPHALT SEAL COAT	1.00	TON
0265	00212	CL2 ASPH BASE 1.00D PG64-22	326.00	TON
0270	00301	CL2 ASPH SURF 0.38D PG64-22	250.00	TON
0275	00521	STORM SEWER PIPE-15 IN	15.00	LF
0280	01643	JUNCTION BOX-24 IN	1.00	EACH
0285	02230	EMBANKMENT IN PLACE	443.00	CUYD
0290	02351	GUARDRAIL-STEEL W BEAM-S FACE	212.50	LF
0295	02360	GUARDRAIL TERMINAL SECTION NO 1	3.00	EACH
0300	02367	GUARDRAIL END TREATMENT TYPE 1	1.00	EACH
0305	02381	REMOVE GUARDRAIL	106.00	LF
0310	02399	EXTRA LENGTH GUARDRAIL POST	30.00	EACH
0315	02484	CHANNEL LINING CLASS III	16.00	TON
0320	02484	CHANNEL LINING CLASS III	200.00	TON
0325	02545	CLEARING AND GRUBBING - APPROX LESS THAN 1 ACRE	1.00	LS
0330	02565	OBJECT MARKER TYPE 2	4.00	EACH
0335	02585	EDGE KEY	48.00	LF
0340	02650	MAINTAIN & CONTROL TRAFFIC	1.00	LS
0345	02726	STAKING	1.00	LS
0350	02731	REMOVE STRUCTURE	1.00	LS
0355	03171	CONCRETE BARRIER WALL TYPE 9T	1,000.00	LF
0360	03299	ARMORED EDGE FOR CONCRETE	79.70	LF
0365	06514	PAVE STRIPING-PERM PAINT-4 IN	3,600.00	LF
0370	08003	FOUNDATION PREPARATION	1.00	LS
0375	08019	CYCLOPEAN STONE RIP RAP	547.00	TON
0380	08033	TEST PILES	170.00	LF
0385	08046	PILES-STEEL HP12X53	1,440.00	LF
0390	08100	CONCRETE-CLASS A	44.00	CUYD
0395	08104	CONCRETE-CLASS AA	49.00	CUYD
0400	08140	MECHANICAL REINF COUPLER #5 EPOXY COATED	8.00	EACH
0405	08151	STEEL REINFORCEMENT-EPOXY COATED	10,982.00	LB

MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0410	08664	PRECAST PC BOX BEAM CB27-48	735.00	LF
0415	20191ED	OBJECT MARKER TY 3	1.00	EACH
0420	20738NS112	TEMP CRASH CUSHION	2.00	EACH
0425	21415ND	EROSION CONTROL	1.00	LS
0430	22883EN	CONCRETE WEDGE CURB	250.00	LF
0435	23378EC	CONCRETE SEALING	4,382.00	SQFT
0440	24405EC	MECHANICAL REINF COUPLER-#8 EPOXY COATED	18.00	EACH
0445	24970EC	ASPHALT MATERIAL FOR TACK NON-TRACKING	1.00	TON
0450	25028ED	RAIL SYSTEM SINGLE SLOPE - 40 IN	147.00	LF
0455	25078ED	THRIE BEAM GUARDRAIL TRANSITION TL-3	4.00	EACH
0460	26233EC	MOBILIZATION FOR CONCRETE SURF TREATMENT	1.00	LS
0465	02568	MOBILIZATION	1.00	LS
0470	02569	DEMOBILIZATION	1.00	LS

MATERIAL SUMMARY

CONTRACT ID: 245348

121GR24D048-STP BRZ

BR02805062400

KY 506 ADDRESS DEFICIENCIES OF KY 506 OVER PINEY CREEK (028B00030N) BRIDGE WITH GRADE, DRAIN & SURFACE, A DISTANCE OF .18 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0475	00001	DGA BASE	664.00	TON
0480	00020	TRAFFIC BOUND BASE	36.00	TON
0485	00100	ASPHALT SEAL AGGREGATE	2.00	TON
0490	00103	ASPHALT SEAL COAT	1.00	TON
0495	00212	CL2 ASPH BASE 1.00D PG64-22	594.00	TON
0500	00301	CL2 ASPH SURF 0.38D PG64-22	165.00	TON
0505	00443	ENTRANCE PIPE-24 IN	64.00	LF
0510	01987	DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	20.00	EACH
0515	02223	GRANULAR EMBANKMENT	805.00	CUYD
0520	02231	STRUCTURE GRANULAR BACKFILL	212.00	CUYD
0525	02371	GUARDRAIL END TREATMENT TYPE 7	4.00	EACH
0530	02483	CHANNEL LINING CLASS II	891.00	TON
0535	02545	CLEARING AND GRUBBING - APPROX LESS THAN 1 ACRE	1.00	LS
0540	02585	EDGE KEY	40.00	LF
0545	02602	FABRIC-GEOTEXTILE CLASS 1	1,423.00	SQYD
0550	02650	MAINTAIN & CONTROL TRAFFIC	1.00	LS
0555	02671	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0560	02726	STAKING	1.00	LS
0565	02731	REMOVE STRUCTURE	1.00	LS
0570	03299	ARMORED EDGE FOR CONCRETE	54.00	LF
0575	06515	PAVE STRIPING-PERM PAINT-6 IN	2,000.00	LF
0580	08003	FOUNDATION PREPARATION	1.00	LS
0585	08019	CYCLOPEAN STONE RIP RAP	367.00	TON
0590	08033	TEST PILES	89.00	LF
0595	08046	PILES-STEEL HP12X53	395.00	LF
0600	08094	PILE POINTS-12 IN	12.00	EACH
0605	08100	CONCRETE-CLASS A	53.60	CUYD
0610	08104	CONCRETE-CLASS AA	101.20	CUYD
0615	08151	STEEL REINFORCEMENT-EPOXY COATED	24,690.00	LB
0620	21415ND	EROSION CONTROL	1.00	LS
0625	21802EN	G/R STEEL W BEAM-S FACE (7 FT POST)	100.00	LF
0630	23378EC	CONCRETE SEALING	6,847.00	SQFT
0635	23981EC	PPC I-BEAM TYPE HN 42-49	390.00	LF
0640	24970EC	ASPHALT MATERIAL FOR TACK NON-TRACKING	1.00	TON
0645	25028ED	RAIL SYSTEM SINGLE SLOPE - 40 IN	198.00	LF
0650	25078ED	THRIE BEAM GUARDRAIL TRANSITION TL-3	4.00	EACH
0655	26233EC	MOBILIZATION FOR CONCRETE SURF TREATMENT	1.00	LS
0660	02569	DEMOBILIZATION	1.00	LS

PROPOSAL BID ITEMS

Report Date 5/21/24

Section: 0001 - BRIDGE - 028B00030N

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00001		DGA BASE	664.00	TON		\$	
0020	00020		TRAFFIC BOUND BASE	36.00	TON		\$	
0030	00100		ASPHALT SEAL AGGREGATE	2.00	TON		\$	
0040	00103		ASPHALT SEAL COAT	1.00	TON		\$	
0050	00212		CL2 ASPH BASE 1.00D PG64-22	594.00	TON		\$	
0060	00301		CL2 ASPH SURF 0.38D PG64-22	165.00	TON		\$	
0070	00443		ENTRANCE PIPE-24 IN	64.00	LF		\$	
0080	01987		DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	20.00	EACH		\$	
0090	02223		GRANULAR EMBANKMENT	805.00	CUYD		\$	
0100	02231		STRUCTURE GRANULAR BACKFILL	212.00	CUYD		\$	
0110	02371		GUARDRAIL END TREATMENT TYPE 7	4.00	EACH		\$	
0120	02483		CHANNEL LINING CLASS II	891.00	TON		\$	
0130	02545		CLEARING AND GRUBBING APPROX LESS THAN 1 ACRE	1.00	LS		\$	
0140	02585		EDGE KEY	40.00	LF		\$	
0150	02602		FABRIC-GEOTEXTILE CLASS 1	1,423.00	SQYD		\$	
0160	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0170	02671		PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH		\$	
0180	02726		STAKING	1.00	LS		\$	
0190	02731		REMOVE STRUCTURE	1.00	LS		\$	
0200	03299		ARMORED EDGE FOR CONCRETE	54.00	LF		\$	
0210	06515		PAVE STRIPING-PERM PAINT-6 IN	2,000.00	LF		\$	
0220	08003		FOUNDATION PREPARATION	1.00	LS		\$	
0230	08019		CYCLOPEAN STONE RIP RAP	367.00	TON		\$	
0240	08033		TEST PILES	89.00	LF		\$	
0250	08046		PILES-STEEL HP12X53	395.00	LF		\$	
0260	08094		PILE POINTS-12 IN	12.00	EACH		\$	
0270	08100		CONCRETE-CLASS A	53.60	CUYD		\$	
0280	08104		CONCRETE-CLASS AA	101.20	CUYD		\$	
0290	08151		STEEL REINFORCEMENT-EPOXY COATED	24,690.00	LB		\$	
0300	21415ND		EROSION CONTROL	1.00	LS		\$	
0310	21802EN		G/R STEEL W BEAM-S FACE (7 FT POST)	100.00	LF		\$	
0320	23378EC		CONCRETE SEALING	6,847.00	SQFT		\$	
0330	23981EC		PPC I-BEAM TYPE HN 42-49	390.00	LF		\$	
0340	24970EC		ASPHALT MATERIAL FOR TACK NON- TRACKING	1.00	TON		\$	
0350	25028ED		RAIL SYSTEM SINGLE SLOPE - 40 IN	198.00	LF		\$	
0360	25078ED		THRIE BEAM GUARDRAIL TRANSITION TL-3	4.00	EACH		\$	
0370	26233EC		MOBILIZATION FOR CONCRETE SURF TREATMENT	1.00	LS		\$	

Section: 0002 - BRIDGE - 020B00004N

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0380	00001		DGA BASE	1,144.00	TON		\$	
0390	00100		ASPHALT SEAL AGGREGATE	4.00	TON		\$	

PROPOSAL BID ITEMS

Report Date 5/21/24

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0400	00103		ASPHALT SEAL COAT	2.00	TON		\$	
0410	00212		CL2 ASPH BASE 1.00D PG64-22	2,372.00	TON		\$	
0420	00301		CL2 ASPH SURF 0.38D PG64-22	255.00	TON		\$	
0430	00441		ENTRANCE PIPE-18 IN	69.00	LF		\$	
0440	00462		CULVERT PIPE-18 IN	60.00	LF		\$	
0450	01433		SLOPED BOX OUTLET TYPE 1-18 IN	3.00	EACH		\$	
0460	02200		ROADWAY EXCAVATION	2,618.00	CUYD		\$	
0470	02351		GUARDRAIL-STEEL W BEAM-S FACE	487.50	LF		\$	
0480	02360		GUARDRAIL TERMINAL SECTION NO 1	1.00	EACH		\$	
0490	02367		GUARDRAIL END TREATMENT TYPE 1	3.00	EACH		\$	
0500	02381		REMOVE GUARDRAIL	328.00	LF		\$	
0510	02399		EXTRA LENGTH GUARDRAIL POST	37.00	EACH		\$	
0520	02429		RIGHT-OF-WAY MONUMENT TYPE 1	11.00	EACH		\$	
0530	02432		WITNESS POST	11.00	EACH		\$	
0540	02483		CHANNEL LINING CLASS II	453.00	TON		\$	
0550	02484		CHANNEL LINING CLASS III	50.00	TON		\$	
0560	02545		CLEARING AND GRUBBING APPROX LESS THAN 1 ACRE	1.00	LS		\$	
0570	02565		OBJECT MARKER TYPE 2	6.00	EACH		\$	
0580	02585		EDGE KEY	48.00	LF		\$	
0590	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0600	02726		STAKING	1.00	LS		\$	
0610	02731		REMOVE STRUCTURE	1.00	LS		\$	
0620	03171		CONCRETE BARRIER WALL TYPE 9T	1,000.00	LF		\$	
0630	03299		ARMORED EDGE FOR CONCRETE	73.80	LF		\$	
0640	06514		PAVE STRIPING-PERM PAINT-4 IN	1,698.00	LF		\$	
0650	08003		FOUNDATION PREPARATION	1.00	LS		\$	
0660	08019		CYCLOPEAN STONE RIP RAP	435.00	TON		\$	
0670	08033		TEST PILES (REVISED 5-21-24)	150.00	LF		\$	
0680	08046		PILES-STEEL HP12X53 (REVISED 5-21-24)	980.00	LF		\$	
0690	08100		CONCRETE-CLASS A	45.00	CUYD		\$	
0700	08104		CONCRETE-CLASS AA	35.00	CUYD		\$	
0710	08140		MECHANICAL REINF COUPLER #5 EPOXY COATED	14.00	EACH		\$	
0720	08151		STEEL REINFORCEMENT-EPOXY COATED	9,202.00	LB		\$	
0730	08664		PRECAST PC BOX BEAM CB27-48	526.50	LF		\$	
0740	20191ED		OBJECT MARKER TY 3	3.00	EACH		\$	
0750	20738NS112		TEMP CRASH CUSHION	2.00	EACH		\$	
0760	21415ND		EROSION CONTROL	1.00	LS		\$	
0770	22883EN		CONCRETE WEDGE CURB	558.00	LF		\$	
0780	23274EN11F		TURF REINFORCEMENT MAT 1	240.00	SQYD		\$	
0790	23378EC		CONCRETE SEALING	3,255.00	SQFT		\$	
0800	24405EC		MECHANICAL REINF COUPLER-#8 EPOXY COATED	18.00	EACH		\$	
0810	24970EC		ASPHALT MATERIAL FOR TACK NON- TRACKING	1.00	TON		\$	
0820	25028ED		RAIL SYSTEM SINGLE SLOPE - 40 IN	117.00	LF		\$	
0830	25078ED		THRIE BEAM GUARDRAIL TRANSITION TL-3	4.00	EACH		\$	

PROPOSAL BID ITEMS

Report Date 5/21/24

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0840	26233EC		MOBILIZATION FOR CONCRETE SURF TREATMENT	1.00	LS		\$	

Section: 0003 - BRIDGE - 020B00002N

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0850	00001		DGA BASE	368.00	TON		\$	
0860	00100		ASPHALT SEAL AGGREGATE	1.50	TON		\$	
0870	00103		ASPHALT SEAL COAT	1.00	TON		\$	
0880	00212		CL2 ASPH BASE 1.00D PG64-22	326.00	TON		\$	
0890	00301		CL2 ASPH SURF 0.38D PG64-22	250.00	TON		\$	
0900	00521		STORM SEWER PIPE-15 IN	15.00	LF		\$	
0910	01643		JUNCTION BOX-24 IN	1.00	EACH		\$	
0920	02230		EMBANKMENT IN PLACE	443.00	CUYD		\$	
0930	02351		GUARDRAIL-STEEL W BEAM-S FACE	212.50	LF		\$	
0940	02360		GUARDRAIL TERMINAL SECTION NO 1	3.00	EACH		\$	
0950	02367		GUARDRAIL END TREATMENT TYPE 1	1.00	EACH		\$	
0960	02381		REMOVE GUARDRAIL	106.00	LF		\$	
0970	02399		EXTRA LENGTH GUARDRAIL POST	30.00	EACH		\$	
0980	02484		CHANNEL LINING CLASS III	216.00	TON		\$	
0990	02545		CLEARING AND GRUBBING APPROX LESS THAN 1 ACRE	1.00	LS		\$	
1000	02565		OBJECT MARKER TYPE 2	4.00	EACH		\$	
1010	02585		EDGE KEY	48.00	LF		\$	
1020	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
1030	02726		STAKING	1.00	LS		\$	
1040	02731		REMOVE STRUCTURE	1.00	LS		\$	
1050	03171		CONCRETE BARRIER WALL TYPE 9T	1,000.00	LF		\$	
1060	03299		ARMORED EDGE FOR CONCRETE	79.70	LF		\$	
1070	06514		PAVE STRIPING-PERM PAINT-4 IN	3,600.00	LF		\$	
1080	08003		FOUNDATION PREPARATION	1.00	LS		\$	
1090	08019		CYCLOPEAN STONE RIP RAP	547.00	TON		\$	
1100	08033		TEST PILES	170.00	LF		\$	
1110	08046		PILES-STEEL HP12X53	1,440.00	LF		\$	
1120	08100		CONCRETE-CLASS A	44.00	CUYD		\$	
1130	08104		CONCRETE-CLASS AA	49.00	CUYD		\$	
1140	08140		MECHANICAL REINF COUPLER #5 EPOXY COATED	8.00	EACH		\$	
1150	08151		STEEL REINFORCEMENT-EPOXY COATED	10,982.00	LB		\$	
1160	08664		PRECAST PC BOX BEAM CB27-48	735.00	LF		\$	
1170	20191ED		OBJECT MARKER TY 3	1.00	EACH		\$	
1180	20738NS112		TEMP CRASH CUSHION	2.00	EACH		\$	
1190	21415ND		EROSION CONTROL	1.00	LS		\$	
1200	22883EN		CONCRETE WEDGE CURB	250.00	LF		\$	
1210	23378EC		CONCRETE SEALING	4,382.00	SQFT		\$	
1220	24405EC		MECHANICAL REINF COUPLER-#8 EPOXY COATED	18.00	EACH		\$	
1230	24970EC		ASPHALT MATERIAL FOR TACK NON-TRACKING	1.00	TON		\$	
1240	25028ED		RAIL SYSTEM SINGLE SLOPE - 40 IN	147.00	LF		\$	

PROPOSAL BID ITEMS

Report Date 5/21/24

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1250	25078ED		THRIE BEAM GUARDRAIL TRANSITION TL-3	4.00	EACH		\$	
1260	26233EC		MOBILIZATION FOR CONCRETE SURF TREATMENT	1.00	LS		\$	

Section: 0004 - DEMOBILIZATION &/OR MOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1270	02568		MOBILIZATION	1.00	LS		\$	
1280	02569		DEMOBILIZATION	1.00	LS		\$	