



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

October 15, 2025

CALL NO. 200
CONTRACT ID NO. 251029
ADDENDUM #1

Subject: Lyon - Caldwell Counties, NHPP 0242 (080)
Letting October 23, 2025

Revised - General Summary Sheets P. 29-33 & 36-40 of 225
Revised - Special Notes P. 67 of 225
Revised - Material Summary P. 148-155 of 225
Revised - Proposal Bid Items P. 220-225 of 225

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills,

A handwritten signature in black ink that reads "Rachel Mills". The signature is written in a cursive, flowing style.

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:ce
Enclosures

GENERAL SUMMARY - ASPHALT ALTERNATE						
I-24 - LYON/CALDWELL COUNTY - ITEM NO. 01-20010.00/02-20062.00						
BID CODE	ITEM	UNIT	NOTES	QUANTITIES		
				CALDWELL COUNTY	LYON COUNTY	TOTALS
00003	CRUSHED STONE BASE	TON	16	10,153	146,994	157,147
00008	CEMENT STABILIZED ROADBED	SQYD		15,843	228,018	243,861
00071	CRUSHED AGGREGATE SIZE NO. 57	TON	3		100	100
00078	CRUSHED AGGREGATE SIZE NO. 2	TON	2	24	326	350
00100	ASPHALT SEAL AGGREGATE	TON		125	1,793	1,918
00103	ASPHALT SEAL COAT	TON		15	215	230
00190	LEVELING & WEDGING PG64-22	TON	5	6	80	86
00214	CL3 ASPH BASE 1.00D PG64-22	TON	14	1,374	19,776	21,150
00217	CL4 ASPH BASE 1.00D PG64-22	TON		4,140	59,590	63,730
00219	CL4 ASPH BASE 1.00D PG76-22	TON		1,885	27,132	29,017
00312	CL3 ASPH SURF 0.50D PG64-22	TON	15	335	4,823	5,158
00335	CL4 ASPH SURF 0.50A PG76-22	TON		1,043	13,783	14,826
00356	ASPHALT MATERIAL FOR TACK	TON	17	27	380	407
00358	ASPHALT CURING SEAL	TON		32	456	488
01006	PERFORATED PIPE EDGE DRAIN-6 IN	LF		6,732	98,421	105,153
01011	NON-PERFORATED PIPE - 6 IN	LF		264	3,524	3,788
01015	INSPECT AND CERTIFY EDGE DRAIN SYSTEM	LS		1	1	1
01021	PERF PIPE HEADWALL TY 1 - 6 IN	EACH			16	16
01025	PERF PIPE HEADWALL TY 2 - 6 IN	EACH			6	6
01029	PERF PIPE HEADWALL TY 3 - 6 IN	EACH			10	10
01033	PERF PIPE HEADWALL TY 4 - 6 IN	EACH		24	294	318
01982	DELINEATOR FOR GUARDRAIL M/W	EACH			168	168
01983	DELINEATOR FOR GUARDRAIL M/Y	EACH			24	24
02003	RELOCATE TEMP CONC BARRIER	LF	5		22,500	22,500
02014	BARRICADE-TYPE III	EACH	5	16	10	26
02058	REMOVE PCC PAVEMENT	SQYD		15,437	222,171	237,608
02351	GUARDRAIL-STEEL W BEAM-S FACE	LF			8,963	8,963
02367	GUARDRAIL END TREATMENT TYPE 1	EACH			1	1
02370	GUARDRAIL END TREATMENT TYPE 2M	EACH			9	9

GENERAL SUMMARY - ASPHALT ALTERNATE						
I-24 - LYON/CALDWELL COUNTY - ITEM NO. 01-20010.00/02-20062.00						
BID CODE	ITEM	UNIT	NOTES	QUANTITIES		
				CALDWELL COUNTY	LYON COUNTY	TOTALS
02372	REMOVE GUARDRAIL CON TO BR END	EACH			11	11
02373	GUARDRAIL END TREATMENT TYPE 3	EACH			6	6
02381	REMOVE GUARDRAIL	LF			9,030	9,030
02403	REMOVE CONCRETE MASONRY	CUYD	7		15	15
02403	REMOVE CONCRETE MASONRY	CUYD	8		15	15
02542	CEMENT	TON		308	4,433	4,741
02562	TEMPORARY SIGNS	SQFT	5	625	1,875	2,500
02568	MOBILIZATION	LS		1	1	1
02569	DEMOBILIZATION	LS		1	1	1
02650	MAINTAIN & CONTROL TRAFFIC	LS		1	1	1
02654	TRUCK MOUNTED ATTENUATOR	EACH	5	1	1	2
02655	CROSSOVER (#1)	LS	5		1	1
02655	CROSSOVER (#2)	LS	5		1	1
02655	CROSSOVER (#3)	LS	5		1	1
02655	CROSSOVER (#4)	LS	5	1		1
02671	PORTABLE CHANGEABLE MESSAGE SIGN	EACH	5	2	2	4
02677	ASPHALT PAVE MILLING & TEXTURING	TON	11		707	707
02697	EDGE LINE RUMBLE STRIPS	LF		7,312	153,363	160,675
02701	TEMP SILT FENCE	LF	6	1,000	1,000	2,000
02702	SAND FOR BLOTTER	TON		63	912	975
02705	SILT TRAP TYPE C	EACH	6	2	6	8
02708	CLEAN SILT TRAP TYPE C	EACH	6	2	6	8
02726	STAKING	LS		1	1	1
02898	RELOCATE CRASH CUSHION	EACH	5	1	3	4
03171	CONCRETE BARRIER WALL TY 9T	LF	5	1,750	29,100	30,850
04793	CONDUIT 1 1/4 INCH	LF	12		30	30
04795	CONDUIT 2 INCH	LF	12		10	10
04820	TRENCHING AND BACKFILLING	LF	12		35	35
04830	LOOP WIRE	LF	12		800	800

GENERAL SUMMARY - ASPHALT ALTERNATE						
I-24 - LYON/CALDWELL COUNTY - ITEM NO. 01-20010.00/02-20062.00						
BID CODE	ITEM	UNIT	NOTES	QUANTITIES		
				CALDWELL COUNTY	LYON COUNTY	TOTALS
04895	LOOP SAW SLOT AND FILL	LF	12		150	150
05953	TEMP SEEDING AND PROTECTION	SQYD	6	500	1,500	2,000
05963	INITIAL FERTILIZER	TON	6	0.1	0.1	0.2
05964	MAINTENANCE FERTILIZER	TON	6	0.1	0.1	0.2
05985	SEEDING AND PROTECTION	SQYD		500	1,500	2,000
05992	AGRICULTURAL LIMESTONE	TON		0.4	1.0	1.4
06511	PAVE STRIPING-TEMP PAINT-6 IN	LF	5	16,818	242,050	258,868
06542	PAVE STRIPING-THERMO-6 IN W	LF		5,486	106,148	111,634
06543	PAVE STRIPING-THERMO-6 IN Y	LF		3,657	93,560	97,217
06546	PAVE STRIPING-THERMO-12 IN W	LF		150		150
06556	PAVE STRIPING-DUR TY 1-6 IN W	LF	10	4,571	30,169	34,740
06557	PAVE STRIPING-DUR TY 1-6 IN Y	LF	10	3,657	15,493	19,150
06585	PAVEMENT MARKER TY IVA-MW TEMP	EACH	4,5	65	108	173
06586	PAVEMENT MARKER TY IVA-MY TEMP	EACH	4,5	65	108	173
06613	INLAID PAVEMENT MARKER-B W/R	EACH		46	658	704
08001	STRUCTURE EXCAVATION - COMMON	CY	7		17	17
08001	STRUCTURE EXCAVATION - COMMON	CY	8		16	16
08100	CONCRETE CLASS "A"	CY	7		27	27
08100	CONCRETE CLASS "A"	CY	8		27	27
08150	STEEL REINFORCEMENT	LBS	7		1,583	1,583
08150	STEEL REINFORCEMENT	LBS	8		1,583	1,583
08912	CRASH CUSHION TY VI CLASS T TL3	EACH	5	1	3	4
10203ND	PAVEMENT ADJUSTMENT	LS		1	1	1
20071EC	JOINT ADHESIVE	LF		3,656	52,619	56,276
20191ED	OBJECT MARKER TY 3	EACH			1	1
20359NN	GLAVANIZED STEEL CABINET	EACH	12		1	1
20360ES818	WOOD POST	EACH	12		2	2
20391NS835	ELECTRICAL JUNCTION BOX TYPE A	EACH	12		1	1
20411ED	LAW ENFORCEMENT OFFICER	HOURL	5	200	1,000	1,200

GENERAL SUMMARY - ASPHALT ALTERNATE						
I-24 - LYON/CALDWELL COUNTY - ITEM NO. 01-20010.00/02-20062.00						
BID CODE	ITEM	UNIT	NOTES	QUANTITIES		
				CALDWELL COUNTY	LYON COUNTY	TOTALS
21380ES719	THRIE BEAM GUARDRAIL	LF			625	625
22664EN	WATER BLASTING EXISTING STRIPE	LF		16,818	242,050	258,868
23147EN	HIGH TENSION CABLE-ROPE	LF	13	600		600
23148EN	END ANCHORS	EACH	9	2	2	4
23378EC	CONCRETE SEALING	SQFT	7		1,488	1,488
23378EC	CONCRETE SEALING	SQFT	8		1,474	1,474
24255EC	REMOVE CABLE GUARDRAIL BARRIER SYSTEM	LF		600	337	937
24891EC	PAVE MOUNT INFRARED TEMP EQUIPMENT	SF		150,385	2,029,751	2,180,136
25078ED	THRIE BEAM GUARDRAIL TRANSITION TL-3	EACH			7	7
26136EC	PORTABLE QUEUE WARNING ALERT SYSTEM	MONT	5	90	90	180
26137EC	QUEUE WARNING PCMS	MONT	5	90	90	180
26138EC	QUEUE WARNING PORTABLE RADAR SENSORS	MONT	5	90	90	180
26233EC	MOBILIZATION - FOR CONCRETE SURFACE TREAT	LS			1	1
26236EC	THRIE BEAM BULLNOSE TERMINAL	EACH			6	6
26237EC	CONNECTED ARROW PANEL	MONT	5	9	36	45
26248EC	ELECTRONIC DELIVERY MGMT SYSTEM-AGG	LS		1	1	1

GENERAL SUMMARY - ASPHALT ALTERNATE						
I-24 - LYON/CALDWELL COUNTY - ITEM NO. 01-20010.00/02-20062.00						
BID CODE	ITEM	UNIT	NOTES	QUANTITIES		
				CALDWELL COUNTY	LYON COUNTY	TOTALS

NOTES:

1. Quantities from all other summary sheets have been included in this General Summary Sheet
2. For perforated pipe headwalls.
3. For sinkhole remediation. To be used as directed by The Engineer.
4. Install temporary pavement markers at 40' intervals for temporary crossovers.
5. For maintenance of traffic.
6. For erosion control of temporary crossovers.
7. For construction of web walls at Friendship Road.
8. For construction of web walls at KY 903.
9. 1 for temporary anchor, 2 for permanent anchor.
10. For striping bridges and eastbound concrete section.
11. For filling existing rumble strips during maintenance of traffic.
12. For Permanent Traffic Data Acquisitions Stations.
13. For reinstallation following removal of temporary crossover #2.
14. Includes 974 tons (Caldwell County - 248 tons; Lyon County - 726 tons) for Crossovers.
15. Includes 244 tons (Caldwell County - 62 tons; Lyon County - 182 tons) for Crossovers and
707 tons (Lyon County) for Rumble Strip Removal
16. Includes 1,018 tons (Caldwell County - 259 tons; Lyon County - 759 tons) for Crossovers.
17. Includes 2.5 tons (Caldwell County - 0.6 tons; Lyon County - 1.9 tons) for Crossovers and
3.6 tons (Lyon County) for Rumble Strip Removal

GENERAL SUMMARY - JPC ALTERNATE						
I-24 - LYON/CALDWELL COUNTY - ITEM NO. 01-20010.00/02-20062.00						
BID CODE	ITEM	UNIT	NOTES	QUANTITIES		
				CALDWELL COUNTY	LYON COUNTY	TOTALS
00003	CRUSHED STONE BASE	TON	17	8,966	131,164	140,131
00008	CEMENT STABILIZED ROADBED	SQYD		15,843	228,018	243,861
00071	CRUSHED AGGREGATE SIZE NO. 57	TON	3		100	100
00078	CRUSHED AGGREGATE SIZE NO. 2	TON	2	24	326	350
00100	ASPHALT SEAL AGGREGATE	TON		125	1,793	1,918
00103	ASPHALT SEAL COAT	TON		15	215	230
00190	LEVELING & WEDGING PG64-22	TON	5	6	80	86
00214	CL3 ASPH BASE 1.00D PG64-22	TON	15	1,374	19,776	21,150
00312	CL3 ASPH SURF 0.50D PG64-22	TON	16	335	5,531	5,866
00356	ASPHALT MATERIAL FOR TACK	TON	18	2	26	28
00358	ASPHALT CURING SEAL	TON		32	456	488
01006	PERFORATED PIPE EDGE DRAIN-6 IN	LF		6,732	98,421	105,153
01011	NON-PERFORATED PIPE - 6 IN	LF		264	3,524	3,788
01015	INSPECT AND CERTIFY EDGE DRAIN SYSTEM	LS		1	1	1
01021	PERF PIPE HEADWALL TY 1 - 6 IN	EACH			16	16
01025	PERF PIPE HEADWALL TY 2 - 6 IN	EACH			6	6
01029	PERF PIPE HEADWALL TY 3 - 6 IN	EACH			10	10
01033	PERF PIPE HEADWALL TY 4 - 6 IN	EACH		24	294	318
01982	DELINEATOR FOR GUARDRAIL M/W	EACH			168	168
01983	DELINEATOR FOR GUARDRAIL M/Y	EACH			24	24
02003	RELOCATE TEMP CONC BARRIER	LF	5		22,500	22,500
02014	BARRICADE-TYPE III	EACH	5	16	10	26
02058	REMOVE PCC PAVEMENT	SQYD		15,437	222,171	237,608
02086	JPC PAVEMENT-13 IN	SQYD		12,647	167,062	179,709
02351	GUARDRAIL-STEEL W BEAM-S FACE	LF			8,963	8,963
02367	GUARDRAIL END TREATMENT TYPE 1	EACH			1	1

GENERAL SUMMARY - JPC ALTERNATE						
I-24 - LYON/CALDWELL COUNTY - ITEM NO. 01-20010.00/02-20062.00						
BID CODE	ITEM	UNIT	NOTES	QUANTITIES		
				CALDWELL COUNTY	LYON COUNTY	TOTALS
02370	GUARDRAIL END TREATMENT TYPE 2M	EACH			9	9
02372	REMOVE GUARDRAIL CON TO BR END	EACH			11	11
02373	GUARDRAIL END TREATMENT TYPE 3	EACH			6	6
02381	REMOVE GUARDRAIL	LF			9,030	9,030
02403	REMOVE CONCRETE MASONRY	CUYD	7		15	15
02403	REMOVE CONCRETE MASONRY	CUYD	8		15	15
02542	CEMENT	TON		308	4,433	4,741
02562	TEMPORARY SIGNS	SQFT	5	625	1,875	2,500
02568	MOBILIZATION	LS		1	1	1
02569	DEMOBILIZATION	LS		1	1	1
02650	MAINTAIN & CONTROL TRAFFIC	LS		1	1	1
02654	TRUCK MOUNTED ATTENUATOR	EACH		1	1	2
02655	CROSSOVER (#1)	LS	5		1	1
02655	CROSSOVER (#2)	LS	5		1	1
02655	CROSSOVER (#3)	LS	5		1	1
02655	CROSSOVER (#4)	LS	5	1		1
02671	PORTABLE CHANGEABLE MESSAGE SIGN	EACH	5	2	2	4
02677	ASPHALT PAVE MILLING & TEXTURING	TON	11		707	707
02696	SHOULDER RUMBLE STRIPS	LF	9	3,656	52,620	56,276
02697	EDGE LINE RUMBLE STRIPS	LF		3,656	100,743	104,399
02701	TEMP SILT FENCE	LF	6	1,000	jpc gensum	2,000
02702	SAND FOR BLOTTER	TON		63	912	975
02705	SILT TRAP TYPE C	EACH	6	2	6	8
02708	CLEAN SILT TRAP TYPE C	EACH	6	2	6	8
02726	STAKING	LS		1	1	1
02898	RELOCATE CRASH CUSHION	EACH	5	1	3	4

GENERAL SUMMARY - JPC ALTERNATE						
I-24 - LYON/CALDWELL COUNTY - ITEM NO. 01-20010.00/02-20062.00						
BID CODE	ITEM	UNIT	NOTES	QUANTITIES		
				CALDWELL COUNTY	LYON COUNTY	TOTALS
03171	CONCRETE BARRIER WALL TY 9T	LF	5	1,750	29,100	30,850
04793	CONDUIT 1 1/4 INCH	LF	13		30	30
04795	CONDUIT 2 INCH	LF	13		10	10
04820	TRENCHING AND BACKFILLING	LF	13		35	35
04830	LOOP WIRE	LF	13		800	800
04895	LOOP SAW SLOT AND FILL	LF	13		150	150
05953	TEMP SEEDING AND PROTECTION	SQYD	6	500	1,500	2,000
05963	INITIAL FERTILIZER	TON	6	0.1	0.1	0.2
05964	MAINTENANCE FERTILIZER	TON	6	0.1	0.1	0.2
05985	SEEDING AND PROTECTION	SQYD		500	1,500	2,000
05992	AGRICULTURAL LIMESTONE	TON		0.4	1.0	1.4
06511	PAVE STRIPING-TEMP PAINT-6 IN	LF		16,818	242,050	258,868
06542	PAVE STRIPING-THERMO-6 IN W	LF	12		50,604	50,604
06543	PAVE STRIPING-THERMO-6 IN Y	LF	12		40,484	40,484
06556	PAVE STRIPING-DUR TY 1-6 IN W	LF		9,143	86,393	95,536
06557	PAVE STRIPING-DUR TY 1-6 IN Y	LF		7,314	68,803	76,117
06560	PAVE STRIPING-DUR TY 1-12 IN W	LF		150		150
06585	PAVEMENT MARKER TY IVA-MW TEMP	EACH	4,5	65	108	173
06586	PAVEMENT MARKER TY IVA-MW TEMP	EACH	4,5	65	108	173
06613	INLAID PAVEMENT MARKER-B W/R	EACH		46	658	704
08001	STRUCTURE EXCAVATION - COMMON	CY	7		17	17
08001	STRUCTURE EXCAVATION - COMMON	CY	8		16	16
08100	CONCRETE CLASS "A"	CY	7		27	27
08100	CONCRETE CLASS "A"	CY	8		27	27
08150	STEEL REINFORCEMENT	LBS	7		1,583	1,583
08150	STEEL REINFORCEMENT	LBS	8		1,583	1,583

GENERAL SUMMARY - JPC ALTERNATE						
I-24 - LYON/CALDWELL COUNTY - ITEM NO. 01-20010.00/02-20062.00						
BID CODE	ITEM	UNIT	NOTES	QUANTITIES		
				CALDWELL COUNTY	LYON COUNTY	TOTALS
08912	CRASH CUSHION TY VI CLASS T TL3	EACH	5	1	3	4
10203ND	PAVEMENT ADJUSTMENT	LS		1	1	1
20191ED	OBJECT MARKER TY 3	EACH			1	1
20359NN	GLAVANIZED STEEL CABINET	EACH	13		1	1
20360ES818	WOOD POST	EACH	13		2	2
20391NS835	ELECTRICAL JUNCTION BOX TYPE A	EACH	13		1	1
20411ED	LAW ENFORCEMENT OFFICER	HOURL	5	200	1,000	1,200
21380ES719	THRIE BEAM GUARDRAIL	LF			625	625
22664EN	WATER BLASTING EXISTING STRIPE	LF		16,818	242,050	258,868
23147EN	HIGH TENSION CABLE-ROPE	LF	14	600		600
23148EN	END ANCHORS	EACH	10	2	2	4
23378EC	CONCRETE SEALING	SQFT	7		1,488	1,488
23378EC	CONCRETE SEALING	SQFT	8		1,474	1,474
24255EC	REMOVE CABLE GUARDRAIL BARRIER SYSTEM	LF		600	337	937
25078ED	THRIE BEAM GUARDRAIL TRANSITION TL-3	EACH			7	7
26136EC	PORTABLE QUEUE WARNING ALERT SYSTEM	MONT	5	90	90	180
26137EC	QUEUE WARNING PCMS	MONT	5	90	90	180
26138EC	QUEUE WARNING PORTABLE RADAR SENSORS	MONT	5	90	90	180
26233EC	MOBILIZATION - FOR CONCRETE SURFACE TREAT	LS			1	1
26236EC	THRIE BEAM BULLNOSE TERMINAL	EACH			6	6
26237EC	CONNECTED ARROW PANEL	MONT	5	9	36	45
26248EC	ELECTRONIC DELIVERY MGMT SYSTEM-AGG	LS		1	1	1

GENERAL SUMMARY - JPC ALTERNATE						
I-24 - LYON/CALDWELL COUNTY - ITEM NO. 01-20010.00/02-20062.00						
BID CODE	ITEM	UNIT	NOTES	QUANTITIES		
				CALDWELL COUNTY	LYON COUNTY	TOTALS

NOTES:

1. Quantities from all other summary sheets have been included in this General Summary Sheet.
2. For perforated pipe headwalls.
3. For sinkhole remediation. To be used as directed by The Engineer.
4. Install temporary pavement markers at 40' intervals for temporary crossovers.
5. For maintenance of traffic.
6. For erosion control of temporary crossovers.
7. For construction of web walls at Friendship Road.
8. For construction of web walls at KY 903.
9. For Westbound Inside Shoulder.
10. 1 for temporary anchor, 2 for permanent anchor.
11. For filling existing rumble strips during maintenance of traffic.
12. For Eastbound Asphalt pavement.
13. For Permanent Traffic Data Acquisitions Stations.
14. For reinstallation following removal of temporary crossover #2.
15. Includes 974 tons (Caldwell County - 248 tons; Lyon County - 726 tons) for Crossovers.
16. Includes 244 tons (Caldwell County - 62 tons; Lyon County - 182 tons) for Crossovers and 707 tons (Lyon County) for Rumble Strip Removal
17. Includes 1,018 tons (Caldwell County - 259 tons; Lyon County - 759 tons) for Crossovers.
18. Includes 2.5 tons (Caldwell County - 0.6 tons; Lyon County - 1.9 tons) for Crossovers and 3.6 tons (Lyon County) for Rumble Strip Removal

**TRAFFIC CONTROL PLAN
I-24 – LYON / CALDWELL COUNTIES
PAGE 4 OF 4**

Note: Warning signs (MUTCD - Uneven Lane, W8-11) should be placed in advance of and at 1500 feet intervals, or as directed by the Engineer, throughout the drop-off area. Dual posting on both sides of the traveled way shall be required. (MUTCD - Uneven Lane, W8-11)

- Two to four inches—plastic drums or vertical panels should be used in accordance with MUTCD and Kentucky Standard Drawings. Place Type III Barricades at the beginning of the lane or shoulder closures, and place additional Type III Barricades spaced at 2,500 feet, or as directed by the Engineer, during the time the lane closure is in place.
- Greater than four inches - Channelizing devices should be used in accordance with MUTCD, Kentucky Standard Drawings and these notes. A 5 foot buffer between the edge of the travel lane and the drop-off should be provided with channelization devices. A positive separation is needed when the buffer cannot be achieved. In lieu of positive separation, a pavement wedge may be constructed with compacted cuttings from milling, DGA, or asphalt mixtures with a 3:1 or flatter slope when workers are not present. When the drop-off is greater than 4 inches and within 10 feet of the traveled lane, positive separation should be considered. Place Type III Barricades at the beginning of the lane or shoulder closures, and place additional Type III Barricades spaced at 2,500 feet, or as directed by the Engineer, during the time the lane closure is in place, except when positive separation is in use. When concrete barriers are used, special reflective devices or steady-burn lights should be used for overnight installations.

TRAFFIC COORDINATOR

This project is designated as a Significant Project in accordance with Section 112.03.12 of the Kentucky Standard Specifications.

COORDINATION OF WORK

The Contractor is advised that other projects may be in progress within or in the near vicinity of this project. The traffic control of those projects may affect this project and the traffic control of this project may affect those projects. The Contractor will coordinate the work on this project with the work of the other Contractors. In case of conflict, the Engineer will determine the relative priority to give to work phasing on the various projects.

CONTRACTOR'S AND CONTRACTOR'S EMPLOYEES' VEHICLES

Do not use or allow employees to use median U-turns at any time, change vehicular direction of travel only at interchanges.

TEMPORARY CROSSOVERS

All Temporary Pipes, Drop Box Inlets, Grade and Drain and removal work for temporary crossover shall be incidental to Crossover bid item. Pavement, aggregate and striping shall be paid by the pertinent bid items.

Approximate Drainage Quantities:

- o Crossover #1 – 284 LF – Temporary 18" Pipe
- o Crossover #2 – 301 LF – Temporary 18" Pipe
- o Crossover #3 & #4 – 184 LF – Temporary 18" Pipe
 - DBI Type 5 – Approx. Grate Elevation = 554.68, IE = 552.10

INCIDENTAL TO MAINTENANCE OF TRAFFIC

As noted in above paragraphs the following items will not be measured but are considered incidental to "Maintain and Control Traffic."

- Lane and Shoulder Closures
- Relocation or Covering of Signs
- Barrels and Replacement of Damaged Barrels
- Replacement of Damage Signs
- Relocations of Portable Changeable Message Signs
- Removing and Replacing or Covering and Uncovering of Pavement Marker Lenses
- Relocations of Flashing Arrows

MATERIAL SUMMARY

CONTRACT ID: 251029

NHPP 0242 (080)

DE01700242518

I-24 FROM THE LYON COUNTY LINE MP 54.842 TO MP 55.498 PAVEMENT REHAB WITH PAVING ALTERNATES, A DISTANCE OF .65 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	00003	CRUSHED STONE BASE	10,153.00	TON
0010	00008	CEMENT STABILIZED ROADBED	15,843.00	SQYD
0015	00078	CRUSHED AGGREGATE SIZE NO 2	24.00	TON
0020	00100	ASPHALT SEAL AGGREGATE	125.00	TON
0025	00103	ASPHALT SEAL COAT	15.00	TON
0030	00190	LEVELING & WEDGING PG64-22	6.00	TON
0035	00214	CL3 ASPH BASE 1.00D PG64-22	1,374.00	TON
0040	00217	CL4 ASPH BASE 1.00D PG64-22	4,140.00	TON
0045	00219	CL4 ASPH BASE 1.00D PG76-22	1,885.00	TON
0050	00312	CL3 ASPH SURF 0.50D PG64-22	335.00	TON
0055	00335	CL4 ASPH SURF 0.50A PG76-22	1,043.00	TON
0060	00356	ASPHALT MATERIAL FOR TACK	27.00	TON
0065	00358	ASPHALT CURING SEAL	32.00	TON
0070	01006	PERFORATED PIPE EDGE DRAIN-6 IN	6,732.00	LF
0075	01011	NON-PERFORATED PIPE-6 IN	264.00	LF
0080	01015	INSPECT & CERTIFY EDGE DRAIN SYSTEM - CALDWELL COUNTY	1.00	LS
0085	01033	PERF PIPE HEADWALL TY 4-6 IN	24.00	EACH
0090	02014	BARRICADE-TYPE III	16.00	EACH
0095	02058	REMOVE PCC PAVEMENT	15,437.00	SQYD
0100	02542	CEMENT	308.00	TON
0105	02562	TEMPORARY SIGNS	625.00	SQFT
0110	02650	MAINTAIN & CONTROL TRAFFIC - CALDWELL COUNTY	1.00	LS
0115	02654	TRUCK MOUNTED ATTENUATOR	1.00	EACH
0120	02655	CROSSOVER - #4	1.00	LS
0125	02671	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0130	02697	EDGE LINE RUMBLE STRIPS	7,312.00	LF
0135	02701	TEMP SILT FENCE	1,000.00	LF
0140	02702	SAND FOR BLOTTER	63.00	TON
0145	02705	SILT TRAP TYPE C	2.00	EACH
0150	02708	CLEAN SILT TRAP TYPE C	2.00	EACH
0155	02726	STAKING - CALDWELL COUNTY	1.00	LS
0160	02898	RELOCATE CRASH CUSHION	1.00	EACH
0165	03171	CONC BARRIER WALL TYPE 9T	1,750.00	LF
0170	05953	TEMP SEEDING AND PROTECTION	500.00	SQYD
0175	05963	INITIAL FERTILIZER	0.10	TON
0180	05964	MAINTENANCE FERTILIZER	0.10	TON
0185	05985	SEEDING AND PROTECTION	500.00	SQYD
0190	05992	AGRICULTURAL LIMESTONE	0.40	TON
0195	06511	PAVE STRIPING-TEMP PAINT-6 IN	16,818.00	LF
0200	06542	PAVE STRIPING-THERMO-6 IN W	5,486.00	LF
0205	06543	PAVE STRIPING-THERMO-6 IN Y	3,657.00	LF
0210	06546	PAVE STRIPING-THERMO-12 IN W	150.00	LF

MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0215	06556	PAVE STRIPING-DUR TY 1-6 IN W	4,571.00	LF
0220	06557	PAVE STRIPING-DUR TY 1-6 IN Y	3,657.00	LF
0225	06585	PAVEMENT MARKER TY IVA-MW TEMP	65.00	EACH
0230	06586	PAVEMENT MARKER TY IVA-MY TEMP	65.00	EACH
0235	06613	INLAID PAVEMENT MARKER-B W/R	46.00	EACH
0240	08912	CRASH CUSHION TY 6 CLASS T TL3	1.00	EACH
0245	10203ND	PAVEMENT ADJUSTMENT - (CALDWELL COUNTY)	1.00	LS
0250	20071EC	JOINT ADHESIVE	3,656.00	LF
0255	20411ED	LAW ENFORCEMENT OFFICER	200.00	HOURL
0260	22664EN	WATER BLASTING EXISTING STRIPE	16,818.00	LF
0265	24891EC	PAVE MOUNT INFRARED TEMP EQUIPMENT	150,385.00	SF
0270	26136EC	PORTABLE QUEUE WARNING ALERT SYSTEM	90.00	MONT
0275	26137EC	QUEUE WARNING PCMS	90.00	MONT
0280	26138EC	QUEUE WARNING PORTABLE RADAR SENSORS	90.00	MONT
0285	26237EC	CONNECTED ARROW PANEL	9.00	MONT
0290	26248EC	ELECTRONIC DELIVERY MGMT SYSTEM - AGG - CALDWELL COUNTY	1.00	LS
0295	00003	CRUSHED STONE BASE	11,340.00	TON
0300	00008	CEMENT STABILIZED ROADBED	15,843.00	SQYD
0305	00078	CRUSHED AGGREGATE SIZE NO 2	24.00	TON
0310	00100	ASPHALT SEAL AGGREGATE	125.00	TON
0315	00103	ASPHALT SEAL COAT	15.00	TON
0320	00214	CL3 ASPH BASE 1.00D PG64-22	1,374.00	TON
0325	00312	CL3 ASPH SURF 0.50D PG64-22	335.00	TON
0330	00356	ASPHALT MATERIAL FOR TACK	2.00	TON
0335	00358	ASPHALT CURING SEAL	32.00	TON
0340	01006	PERFORATED PIPE EDGE DRAIN-6 IN	6,732.00	LF
0345	01011	NON-PERFORATED PIPE-6 IN	264.00	LF
0350	01015	INSPECT & CERTIFY EDGE DRAIN SYSTEM - CALDWELL COUNTY	1.00	LS
0355	01033	PERF PIPE HEADWALL TY 4-6 IN	24.00	EACH
0360	02058	REMOVE PCC PAVEMENT	15,437.00	SQYD
0365	02086	JPC PAVEMENT-13 IN	12,647.00	SQYD
0370	02542	CEMENT	308.00	TON
0375	02562	TEMPORARY SIGNS	625.00	SQFT
0380	02650	MAINTAIN & CONTROL TRAFFIC - CALDWELL COUNTY	1.00	LS
0385	02655	CROSSOVER - #4	1.00	LS
0390	02671	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0395	02695	RUMBLE STRIPS TYPE 3	3,656.00	LF
0400	02697	EDGE LINE RUMBLE STRIPS	3,656.00	LF
0405	02701	TEMP SILT FENCE	1,000.00	LF
0410	02702	SAND FOR BLOTTER	63.00	TON
0415	02705	SILT TRAP TYPE C	2.00	EACH
0420	02708	CLEAN SILT TRAP TYPE C	2.00	EACH
0425	02726	STAKING - CALDWELL COUNTY	1.00	LS
0430	02898	RELOCATE CRASH CUSHION	1.00	EACH
0435	03171	CONC BARRIER WALL TYPE 9T	1,750.00	LF
0440	05953	TEMP SEEDING AND PROTECTION	500.00	SQYD
0445	05963	INITIAL FERTILIZER	0.10	TON
0450	05964	MAINTENANCE FERTILIZER	0.10	TON
0455	05985	SEEDING AND PROTECTION	500.00	SQYD

MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0460	05992	AGRICULTURAL LIMESTONE	0.40	TON
0465	06511	PAVE STRIPING-TEMP PAINT-6 IN	16,818.00	LF
0470	06556	PAVE STRIPING-DUR TY 1-6 IN W	9,143.00	LF
0475	06557	PAVE STRIPING-DUR TY 1-6 IN Y	7,314.00	LF
0480	06560	PAVE STRIPING-DUR TY 1-12 IN W	150.00	LF
0485	06585	PAVEMENT MARKER TY IVA-MW TEMP	65.00	EACH
0490	06586	PAVEMENT MARKER TY IVA-MY TEMP	65.00	EACH
0495	06613	INLAID PAVEMENT MARKER-B W/R	46.00	EACH
0500	08912	CRASH CUSHION TY 6 CLASS T TL3	1.00	EACH
0505	10203ND	PAVEMENT ADJUSTMENT - (CALDWELL COUNTY)	1.00	LS
0510	20411ED	LAW ENFORCEMENT OFFICER	200.00	HOURL
0515	23147EN	HIGH TENSION CABLE-ROPE BARRIER	600.00	LF
0520	23148EN	END ANCHORS	2.00	EACH
0525	24255EC	REMOVE CABLE GUARDRAIL BARRIER SYSTEM	600.00	LF
0530	26136EC	PORTABLE QUEUE WARNING ALERT SYSTEM	90.00	MONT
0535	26137EC	QUEUE WARNING PCMS	90.00	MONT
0540	26138EC	QUEUE WARNING PORTABLE RADAR SENSORS	90.00	MONT
0545	26237EC	CONNECTED ARROW PANEL	9.00	MONT
0550	26248EC	ELECTRONIC DELIVERY MGMT SYSTEM - AGG - CALDWELL COUNTY	1.00	LS
0555	02568	MOBILIZATION	1.00	LS
0560	02569	DEMOBILIZATION	1.00	LS
0565	00190	LEVELING & WEDGING PG64-22 - (ADDED 10-15-25)	6.00	TON
0570	02654	TRUCK MOUNTED ATTENUATOR - (ADDED 10-15-25)	1.00	EACH
0575	22664EN	WATER BLASTING EXISTING STRIPE - (ADDED 10-15-25)	16,818.00	LF

CONTRACT ID: 251029

NHPP 0242 (080)

DE07200242518

I-24 BEGINNING AT MP 45.171 EXTENDING TO MP 54.842 PAVEMENT REHAB WITH PAVING ALTERNATES, A DISTANCE OF 9.67 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0565	00003	CRUSHED STONE BASE	146,994.00	TON
0570	00008	CEMENT STABILIZED ROADBED	228,018.00	SQYD
0575	00071	CRUSHED AGGREGATE SIZE NO 57	100.00	TON
0580	00078	CRUSHED AGGREGATE SIZE NO 2	326.00	TON
0585	00100	ASPHALT SEAL AGGREGATE	1,793.00	TON
0590	00103	ASPHALT SEAL COAT	215.00	TON
0595	00190	LEVELING & WEDGING PG64-22	80.00	TON
0600	00214	CL3 ASPH BASE 1.00D PG64-22	19,776.00	TON
0605	00217	CL4 ASPH BASE 1.00D PG64-22	59,590.00	TON
0610	00219	CL4 ASPH BASE 1.00D PG76-22	27,132.00	TON
0615	00312	CL3 ASPH SURF 0.50D PG64-22	4,823.00	TON
0620	00335	CL4 ASPH SURF 0.50A PG76-22	13,783.00	TON
0625	00356	ASPHALT MATERIAL FOR TACK	380.00	TON
0630	00358	ASPHALT CURING SEAL	456.00	TON

MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0635	01006	PERFORATED PIPE EDGE DRAIN-6 IN	98,421.00	LF
0640	01011	NON-PERFORATED PIPE-6 IN	3,524.00	LF
0645	01015	INSPECT & CERTIFY EDGE DRAIN SYSTEM - LYON COUNTY	1.00	LS
0650	01021	PERF PIPE HEADWALL TY 1-6 IN	16.00	EACH
0655	01025	PERF PIPE HEADWALL TY 2-6 IN	6.00	EACH
0660	01029	PERF PIPE HEADWALL TY 3-6 IN	10.00	EACH
0665	01033	PERF PIPE HEADWALL TY 4-6 IN	294.00	EACH
0670	01982	DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL WHITE	168.00	EACH
0675	01983	DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL YELLOW	24.00	EACH
0680	02003	RELOCATE TEMP CONC BARRIER	22,500.00	LF
0685	02014	BARRICADE-TYPE III	10.00	EACH
0690	02058	REMOVE PCC PAVEMENT	222,171.00	SQYD
0695	02351	GUARDRAIL-STEEL W BEAM-S FACE	8,963.00	LF
0700	02367	GUARDRAIL END TREATMENT TYPE 1	1.00	EACH
0705	02370	GUARDRAIL END TREATMENT TYPE 2M	9.00	EACH
0710	02372	REMOVE GUARDRAIL CON TO BR END	11.00	EACH
0715	02373	GUARDRAIL END TREATMENT TYPE 3	6.00	EACH
0720	02381	REMOVE GUARDRAIL	9,030.00	LF
0725	02542	CEMENT	4,433.00	TON
0730	02562	TEMPORARY SIGNS	1,875.00	SQFT
0735	02650	MAINTAIN & CONTROL TRAFFIC - LYON COUNTY	1.00	LS
0740	02654	TRUCK MOUNTED ATTENUATOR	1.00	EACH
0745	02655	CROSSOVER - #1	1.00	LS
0750	02655	CROSSOVER - #2	1.00	LS
0755	02655	CROSSOVER - #3	1.00	LS
0760	02671	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0765	02677	ASPHALT PAVE MILLING & TEXTURING	707.00	TON
0770	02697	EDGELINE RUMBLE STRIPS	157,860.00	LF
0775	02701	TEMP SILT FENCE	1,000.00	LF
0780	02702	SAND FOR BLOTTER	912.00	TON
0785	02705	SILT TRAP TYPE C	6.00	EACH
0790	02708	CLEAN SILT TRAP TYPE C	6.00	EACH
0795	02726	STAKING - LYON COUNTY	1.00	LS
0800	02898	RELOCATE CRASH CUSHION	3.00	EACH
0805	03171	CONC BARRIER WALL TYPE 9T	29,100.00	LF
0810	05953	TEMP SEEDING AND PROTECTION	1,500.00	SQYD
0815	05963	INITIAL FERTILIZER	0.10	TON
0820	05964	MAINTENANCE FERTILIZER	0.10	TON
0825	05985	SEEDING AND PROTECTION	1,500.00	SQYD
0830	05992	AGRICULTURAL LIMESTONE	1.00	TON
0835	06511	PAVE STRIPING-TEMP PAINT-6 IN	242,050.00	LF
0840	06542	PAVE STRIPING-THERMO-6 IN W	50,606.00	LF
0845	06543	PAVE STRIPING-THERMO-6 IN Y	40,484.00	LF
0850	06556	PAVE STRIPING-DUR TY 1-6 IN W	86,393.00	LF
0855	06557	PAVE STRIPING-DUR TY 1-6 IN Y	68,803.00	LF
0860	06585	PAVEMENT MARKER TY IVA-MW TEMP	108.00	EACH
0865	06586	PAVEMENT MARKER TY IVA-MY TEMP	108.00	EACH
0870	06613	INLAID PAVEMENT MARKER-B W/R	658.00	EACH

MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0875	08912	CRASH CUSHION TY 6 CLASS T TL3	3.00	EACH
0880	10203ND	PAVEMENT ADJUSTMENT - (LYON COUNTY)	1.00	LS
0885	20071EC	JOINT ADHESIVE	52,619.00	LF
0890	20191ED	OBJECT MARKER TY 3	1.00	EACH
0895	20411ED	LAW ENFORCEMENT OFFICER	1,000.00	HOURL
0900	21380ES719	GUARDRAIL THRIE BEAM	625.00	LF
0905	22664EN	WATER BLASTING EXISTING STRIPE	242,050.00	LF
0910	23147EN	HIGH TENSION CABLE-ROPE BARRIER	600.00	LF
0915	23148EN	END ANCHORS	2.00	EACH
0920	24255EC	REMOVE CABLE GUARDRAIL BARRIER SYSTEM	337.00	LF
0925	24891EC	PAVE MOUNT INFRARED TEMP EQUIPMENT	2,029,751.00	SF
0930	25078ED	THRIE BEAM GUARDRAIL TRANSITION TL-3	7.00	EACH
0935	26136EC	PORTABLE QUEUE WARNING ALERT SYSTEM	90.00	MONT
0940	26137EC	QUEUE WARNING PCMS	90.00	MONT
0945	26138EC	QUEUE WARNING PORTABLE RADAR SENSORS	90.00	MONT
0950	26233EC	MOBILIZATION FOR CONCRETE SURF TREATMENT - LYON COUNTY	1.00	LS
0955	26236EC	THRIE BEAM BULLNOSE TERMINAL	6.00	EACH
0960	26237EC	CONNECTED ARROW PANEL	36.00	MONT
0965	26248EC	ELECTRONIC DELIVERY MGMT SYSTEM - AGG - LYON COUNTY	1.00	LS
0970	00003	CRUSHED STONE BASE	131,164.00	TON
0975	00008	CEMENT STABILIZED ROADBED	228,018.00	SQYD
0980	00071	CRUSHED AGGREGATE SIZE NO 57	100.00	TON
0985	00078	CRUSHED AGGREGATE SIZE NO 2	326.00	TON
0990	00100	ASPHALT SEAL AGGREGATE	1,793.00	TON
0995	00103	ASPHALT SEAL COAT	215.00	TON
1000	00214	CL3 ASPH BASE 1.00D PG64-22	19,776.00	TON
1005	00312	CL3 ASPH SURF 0.50D PG64-22	5,531.00	TON
1010	00356	ASPHALT MATERIAL FOR TACK	26.00	TON
1015	00358	ASPHALT CURING SEAL	456.00	TON
1020	01006	PERFORATED PIPE EDGE DRAIN-6 IN	98,421.00	LF
1025	01011	NON-PERFORATED PIPE-6 IN	3,524.00	LF
1030	01015	INSPECT & CERTIFY EDGE DRAIN SYSTEM - LYON COUNTY	1.00	LS
1035	01021	PERF PIPE HEADWALL TY 1-6 IN	16.00	EACH
1040	01025	PERF PIPE HEADWALL TY 2-6 IN	6.00	EACH
1045	01029	PERF PIPE HEADWALL TY 3-6 IN	10.00	EACH
1050	01033	PERF PIPE HEADWALL TY 4-6 IN	294.00	EACH
1055	01982	DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL WHITE	168.00	EACH
1060	01983	DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL YELLOW	24.00	EACH
1065	02003	RELOCATE TEMP CONC BARRIER	22,500.00	LF
1070	02014	BARRICADE-TYPE III	10.00	EACH
1075	02058	REMOVE PCC PAVEMENT	222,171.00	SQYD
1080	02086	JPC PAVEMENT-13 IN	167,062.00	SQYD
1085	02351	GUARDRAIL-STEEL W BEAM-S FACE	8,963.00	LF
1090	02367	GUARDRAIL END TREATMENT TYPE 1	1.00	EACH
1095	02370	GUARDRAIL END TREATMENT TYPE 2M	9.00	EACH
1100	02372	REMOVE GUARDRAIL CON TO BR END	11.00	EACH

MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
1105	02373	GUARDRAIL END TREATMENT TYPE 3	6.00	EACH
1110	02381	REMOVE GUARDRAIL	9,030.00	LF
1115	02403	REMOVE CONCRETE MASONRY	15.00	CUYD
1120	02542	CEMENT	4,433.00	TON
1125	02562	TEMPORARY SIGNS	1,875.00	SQFT
1130	02650	MAINTAIN & CONTROL TRAFFIC - LYON COUNTY	1.00	LS
1135	02655	CROSSOVER - #1	1.00	LS
1140	02655	CROSSOVER - #2	1.00	LS
1145	02655	CROSSOVER - #3	1.00	LS
1150	02671	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
1155	02677	ASPHALT PAVE MILLING & TEXTURING	707.00	TON
1160	02695	RUMBLE STRIPS TYPE 3	52,620.00	LF
1165	02697	EDGE LINE RUMBLE STRIPS	153,363.00	LF
1170	02701	TEMP SILT FENCE	1,000.00	LF
1175	02702	SAND FOR BLOTTER	912.00	TON
1180	02705	SILT TRAP TYPE C	6.00	EACH
1185	02708	CLEAN SILT TRAP TYPE C	6.00	EACH
1190	02726	STAKING - LYON COUNTY	1.00	LS
1195	02898	RELOCATE CRASH CUSHION	3.00	EACH
1200	03171	CONC BARRIER WALL TYPE 9T	29,100.00	LF
1205	05953	TEMP SEEDING AND PROTECTION	1,500.00	SQYD
1210	05963	INITIAL FERTILIZER	0.10	TON
1215	05964	MAINTENANCE FERTILIZER	0.10	TON
1220	05985	SEEDING AND PROTECTION	1,500.00	SQYD
1225	05992	AGRICULTURAL LIMESTONE	1.00	TON
1230	06511	PAVE STRIPING-TEMP PAINT-6 IN	242,050.00	LF
1235	06542	PAVE STRIPING-THERMO-6 IN W	50,604.00	LF
1240	06543	PAVE STRIPING-THERMO-6 IN Y	40,484.00	LF
1245	06556	PAVE STRIPING-DUR TY 1-6 IN W	86,393.00	LF
1250	06557	PAVE STRIPING-DUR TY 1-6 IN Y	68,803.00	LF
1255	06585	PAVEMENT MARKER TY IVA-MW TEMP	108.00	EACH
1260	06586	PAVEMENT MARKER TY IVA-MY TEMP	108.00	EACH
1265	06613	INLAID PAVEMENT MARKER-B W/R	658.00	EACH
1270	08912	CRASH CUSHION TY 6 CLASS T TL3	3.00	EACH
1275	10203ND	PAVEMENT ADJUSTMENT - (LYON COUNTY)	1.00	LS
1280	20191ED	OBJECT MARKER TY 3	1.00	EACH
1285	20411ED	LAW ENFORCEMENT OFFICER	1,000.00	hour
1290	21380ES719	GUARDRAIL THRIE BEAM	625.00	LF
1295	23147EN	HIGH TENSION CABLE-ROPE BARRIER	600.00	LF
1300	23148EN	END ANCHORS	2.00	EACH
1305	24255EC	REMOVE CABLE GUARDRAIL BARRIER SYSTEM	337.00	LF
1310	25078ED	THRIE BEAM GUARDRAIL TRANSITION TL-3	7.00	EACH
1315	26136EC	PORTABLE QUEUE WARNING ALERT SYSTEM	90.00	MONTH
1320	26137EC	QUEUE WARNING PCMS	90.00	MONTH
1325	26138EC	QUEUE WARNING PORTABLE RADAR SENSORS	90.00	MONTH
1330	26233EC	MOBILIZATION FOR CONCRETE SURF TREATMENT - LYON COUNTY	1.00	LS
1335	26236EC	THRIE BEAM BULLNOSE TERMINAL	6.00	EACH
1340	26237EC	CONNECTED ARROW PANEL	36.00	MONTH
1345	26248EC	ELECTRONIC DELIVERY MGMT SYSTEM - AGG - LYON COUNTY	1.00	LS

MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
1350	02403	REMOVE CONCRETE MASONRY	15.00	CUYD
1355	08001	STRUCTURE EXCAVATION-COMMON	17.00	CUYD
1360	08100	CONCRETE-CLASS A	27.00	CUYD
1365	08150	STEEL REINFORCEMENT	1,583.00	LB
1370	23378EC	CONCRETE SEALING	1,488.00	SQFT
1375	02403	REMOVE CONCRETE MASONRY	15.00	CUYD
1380	08001	STRUCTURE EXCAVATION-COMMON	16.00	CUYD
1385	08100	CONCRETE-CLASS A	27.00	CUYD
1390	08150	STEEL REINFORCEMENT	1,583.00	LB
1395	23378EC	CONCRETE SEALING	1,474.00	SQFT
1400	04793	CONDUIT-1 1/4 IN	30.00	LF
1405	04795	CONDUIT-2 IN	10.00	LF
1410	04820	TRENCHING AND BACKFILLING	35.00	LF
1415	04830	LOOP WIRE	800.00	LF
1420	04895	LOOP SAW SLOT AND FILL	150.00	LF
1425	20359NN	GALVANIZED STEEL CABINET	1.00	EACH
1430	20360ES818	WOOD POST	2.00	EACH
1435	20391NS835	ELECTRICAL JUNCTION BOX TYPE A	1.00	EACH
1440	02742	TRAINEE PAYMENT REIMBURSEMENT - GROUP 2, 3, 4 OPERATOR	1,400.00	hour
1445	02568	MOBILIZATION	1.00	LS
1450	02569	DEMOBILIZATION	1.00	LS
1455	00190	LEVELING & WEDGING PG64-22 - (ADDED 10-15-25)	80.00	TON
1460	02654	TRUCK MOUNTED ATTENUATOR - (ADDED 10-15-25)	1.00	EACH
1465	22664EN	WATER BLASTING EXISTING STRIPE - (ADDED 10-15-25)	242,050.00	LF

251029

PROPOSAL BID ITEMS

Report Date 10/15/25

Page 1 of 6

251029

Section: 0001 - ROADWAY - ASPHALT ALTERNATE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00003		CRUSHED STONE BASE	157,147.00	TON		\$	
0020	00008		CEMENT STABILIZED ROADBED	243,861.00	SQYD		\$	
0030	00071		CRUSHED AGGREGATE SIZE NO 57	100.00	TON		\$	
0040	00078		CRUSHED AGGREGATE SIZE NO 2	350.00	TON		\$	
0050	00100		ASPHALT SEAL AGGREGATE	1,918.00	TON		\$	
0060	00103		ASPHALT SEAL COAT	230.00	TON		\$	
0070	00190		LEVELING & WEDGING PG64-22	86.00	TON		\$	
0080	00214		CL3 ASPH BASE 1.00D PG64-22	21,150.00	TON		\$	
0090	00217		CL4 ASPH BASE 1.00D PG64-22	63,730.00	TON		\$	
0100	00219		CL4 ASPH BASE 1.00D PG76-22	29,017.00	TON		\$	
0110	00312		CL3 ASPH SURF 0.50D PG64-22	5,158.00	TON		\$	
0120	00335		CL4 ASPH SURF 0.50A PG76-22	14,826.00	TON		\$	
0130	00356		ASPHALT MATERIAL FOR TACK	407.00	TON		\$	
0140	00358		ASPHALT CURING SEAL	488.00	TON		\$	
0150	01006		PERFORATED PIPE EDGE DRAIN-6 IN	105,153.00	LF		\$	
0160	01011		NON-PERFORATED PIPE-6 IN	3,788.00	LF		\$	
0170	01015		INSPECT & CERTIFY EDGE DRAIN SYSTEM CALDWELL COUNTY	1.00	LS		\$	
0180	01015		INSPECT & CERTIFY EDGE DRAIN SYSTEM LYON COUNTY	1.00	LS		\$	
0190	01021		PERF PIPE HEADWALL TY 1-6 IN	16.00	EACH		\$	
0200	01025		PERF PIPE HEADWALL TY 2-6 IN	6.00	EACH		\$	
0210	01029		PERF PIPE HEADWALL TY 3-6 IN	10.00	EACH		\$	
0220	01033		PERF PIPE HEADWALL TY 4-6 IN	318.00	EACH		\$	
0230	01982		DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL WHITE	168.00	EACH		\$	
0240	01983		DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL YELLOW	24.00	EACH		\$	
0250	02003		RELOCATE TEMP CONC BARRIER	22,500.00	LF		\$	
0260	02014		BARRICADE-TYPE III	26.00	EACH		\$	
0270	02058		REMOVE PCC PAVEMENT	237,608.00	SQYD		\$	
0280	02351		GUARDRAIL-STEEL W BEAM-S FACE	8,963.00	LF		\$	
0290	02367		GUARDRAIL END TREATMENT TYPE 1	1.00	EACH		\$	
0300	02370		GUARDRAIL END TREATMENT TYPE 2M	9.00	EACH		\$	
0310	02372		REMOVE GUARDRAIL CON TO BR END	11.00	EACH		\$	
0320	02373		GUARDRAIL END TREATMENT TYPE 3	6.00	EACH		\$	
0330	02381		REMOVE GUARDRAIL	9,030.00	LF		\$	
0340	02542		CEMENT	4,741.00	TON		\$	
0350	02562		TEMPORARY SIGNS	2,500.00	SQFT		\$	
0360	02650		MAINTAIN & CONTROL TRAFFIC CALDWELL COUNTY	1.00	LS		\$	
0370	02650		MAINTAIN & CONTROL TRAFFIC LYON COUNTY	1.00	LS		\$	
0380	02654		TRUCK MOUNTED ATTENUATOR	2.00	EACH		\$	
0390	02655		CROSSOVER #1	1.00	LS		\$	

Report Date 10/15/25

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0400	02655		CROSSOVER #2	1.00	LS		\$	
0410	02655		CROSSOVER #3	1.00	LS		\$	
0420	02655		CROSSOVER #4	1.00	LS		\$	
0430	02671		PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH		\$	
0440	02677		ASPHALT PAVE MILLING & TEXTURING	707.00	TON		\$	
0450	02697		EDGE LINE RUMBLE STRIPS	165,172.00	LF		\$	
0460	02701		TEMP SILT FENCE	2,000.00	LF		\$	
0470	02702		SAND FOR BLOTTER	975.00	TON		\$	
0480	02705		SILT TRAP TYPE C	8.00	EACH		\$	
0490	02708		CLEAN SILT TRAP TYPE C	8.00	EACH		\$	
0500	02726		STAKING CALDWELL COUNTY	1.00	LS		\$	
0510	02726		STAKING LYON COUNTY	1.00	LS		\$	
0520	02898		RELOCATE CRASH CUSHION	4.00	EACH		\$	
0530	03171		CONC BARRIER WALL TYPE 9T	30,850.00	LF		\$	
0540	05953		TEMP SEEDING AND PROTECTION	2,000.00	SQYD		\$	
0550	05963		INITIAL FERTILIZER	0.20	TON		\$	
0560	05964		MAINTENANCE FERTILIZER	0.20	TON		\$	
0570	05985		SEEDING AND PROTECTION	2,000.00	SQYD		\$	
0580	05992		AGRICULTURAL LIMESTONE	1.40	TON		\$	
0590	06511		PAVE STRIPING-TEMP PAINT-6 IN	258,868.00	LF		\$	
0600	06542		PAVE STRIPING-THERMO-6 IN W	56,092.00	LF		\$	
0610	06543		PAVE STRIPING-THERMO-6 IN Y	44,141.00	LF		\$	
0620	06546		PAVE STRIPING-THERMO-12 IN W	150.00	LF		\$	
0630	06556		PAVE STRIPING-DUR TY 1-6 IN W	90,964.00	LF		\$	
0640	06557		PAVE STRIPING-DUR TY 1-6 IN Y	72,460.00	LF		\$	
0650	06585		PAVEMENT MARKER TY IVA-MW TEMP	173.00	EACH		\$	
0660	06586		PAVEMENT MARKER TY IVA-MY TEMP	173.00	EACH		\$	
0670	06613		INLAID PAVEMENT MARKER-B W/R	704.00	EACH		\$	
0680	08912		CRASH CUSHION TY 6 CLASS T TL3	4.00	EACH		\$	
0690	10203ND		PAVEMENT ADJUSTMENT (CALDWELL COUNTY)	1.00	LS	\$242,703.0	\$	\$242,703.00
0700	10203ND		PAVEMENT ADJUSTMENT (LYON COUNTY)	1.00	LS	\$3,434,609.	\$	\$3,434,609.00
0710	20071EC		JOINT ADHESIVE	56,275.00	LF		\$	
0720	20191ED		OBJECT MARKER TY 3	1.00	EACH		\$	
0730	20411ED		LAW ENFORCEMENT OFFICER	1,200.00	hour		\$	
0740	21380ES719		GUARDRAIL THRIE BEAM	625.00	LF		\$	
0750	22664EN		WATER BLASTING EXISTING STRIPE	258,868.00	LF		\$	
0760	23147EN		HIGH TENSION CABLE-ROPE BARRIER	600.00	LF		\$	
0770	23148EN		END ANCHORS	2.00	EACH		\$	
0780	24255EC		REMOVE CABLE GUARDRAIL BARRIER SYSTEM	337.00	LF		\$	
0790	24891EC		PAVE MOUNT INFRARED TEMP EQUIPMENT	2,180,136.00	SF		\$	
0800	25078ED		THRIE BEAM GUARDRAIL TRANSITION TL-3	7.00	EACH		\$	
0810	26136EC		PORTABLE QUEUE WARNING ALERT SYSTEM	180.00	month		\$	
0820	26137EC		QUEUE WARNING PCMS	180.00	month		\$	

251029

PROPOSAL BID ITEMS

Page 3 of 6

Report Date 10/15/25

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0830	26138EC		QUEUE WARNING PORTABLE RADAR SENSORS	180.00	MONT		\$	
0840	26233EC		MOBILIZATION FOR CONCRETE SURF TREATMENT LYON COUNTY	1.00	LS		\$	
0850	26236EC		THRIE BEAM BULLNOSE TERMINAL	6.00	EACH		\$	
0860	26237EC		CONNECTED ARROW PANEL	45.00	MONT		\$	
0870	26248EC		ELECTRONIC DELIVERY MGMT SYSTEM - AGG CALDWELL COUNTY	1.00	LS		\$	
0880	26248EC		ELECTRONIC DELIVERY MGMT SYSTEM - AGG LYON COUNTY	1.00	LS		\$	

Section: 0002 - ROADWAY - CONCRETE ALTERNATE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0890	00003		CRUSHED STONE BASE	142,504.00	TON		\$	
0900	00008		CEMENT STABILIZED ROADBED	243,861.00	SQYD		\$	
0910	00071		CRUSHED AGGREGATE SIZE NO 57	100.00	TON		\$	
0920	00078		CRUSHED AGGREGATE SIZE NO 2	350.00	TON		\$	
0930	00100		ASPHALT SEAL AGGREGATE	1,918.00	TON		\$	
0940	00103		ASPHALT SEAL COAT	230.00	TON		\$	
0945	00190		LEVELING & WEDGING PG64-22 (ADDED 10-15-25)	86.00	TON		\$	
0950	00214		CL3 ASPH BASE 1.00D PG64-22	21,150.00	TON		\$	
0960	00312		CL3 ASPH SURF 0.50D PG64-22	5,866.00	TON		\$	
0970	00356		ASPHALT MATERIAL FOR TACK	28.00	TON		\$	
0980	00358		ASPHALT CURING SEAL	488.00	TON		\$	
0990	01006		PERFORATED PIPE EDGE DRAIN-6 IN	105,153.00	LF		\$	
1000	01011		NON-PERFORATED PIPE-6 IN	3,788.00	LF		\$	
1010	01015		INSPECT & CERTIFY EDGE DRAIN SYSTEM CALDWELL COUNTY	1.00	LS		\$	
1020	01015		INSPECT & CERTIFY EDGE DRAIN SYSTEM LYON COUNTY	1.00	LS		\$	
1030	01021		PERF PIPE HEADWALL TY 1-6 IN	16.00	EACH		\$	
1040	01025		PERF PIPE HEADWALL TY 2-6 IN	6.00	EACH		\$	
1050	01029		PERF PIPE HEADWALL TY 3-6 IN	10.00	EACH		\$	
1060	01033		PERF PIPE HEADWALL TY 4-6 IN	318.00	EACH		\$	
1070	01982		DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL WHITE	168.00	EACH		\$	
1080	01983		DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL YELLOW	24.00	EACH		\$	
1090	02003		RELOCATE TEMP CONC BARRIER	22,500.00	LF		\$	
1100	02014		BARRICADE-TYPE III	10.00	EACH		\$	
1110	02058		REMOVE PCC PAVEMENT	237,608.00	SQYD		\$	
1120	02086		JPC PAVEMENT-13 IN	179,709.00	SQYD		\$	
1130	02351		GUARDRAIL-STEEL W BEAM-S FACE	8,963.00	LF		\$	
1140	02367		GUARDRAIL END TREATMENT TYPE 1	1.00	EACH		\$	
1150	02370		GUARDRAIL END TREATMENT TYPE 2M	9.00	EACH		\$	
1160	02372		REMOVE GUARDRAIL CON TO BR END	11.00	EACH		\$	

Report Date 10/15/25

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1170	02373		GUARDRAIL END TREATMENT TYPE 3	6.00	EACH		\$	
1180	02381		REMOVE GUARDRAIL	9,030.00	LF		\$	
1190	02403		REMOVE CONCRETE MASONRY	15.00	CUYD		\$	
1200	02542		CEMENT	4,741.00	TON		\$	
1210	02562		TEMPORARY SIGNS	2,500.00	SQFT		\$	
1220	02650		MAINTAIN & CONTROL TRAFFIC CALDWELL COUNTY	1.00	LS		\$	
1230	02650		MAINTAIN & CONTROL TRAFFIC LYON COUNTY	1.00	LS		\$	
1235	02654		TRUCK MOUNTED ATTENUATOR (ADDED 10-15-25)	2.00	EACH		\$	
1240	02655		CROSSOVER #1	1.00	LS		\$	
1250	02655		CROSSOVER #2	1.00	LS		\$	
1260	02655		CROSSOVER #3	1.00	LS		\$	
1270	02655		CROSSOVER #4	1.00	LS		\$	
1280	02671		PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH		\$	
1290	02677		ASPHALT PAVE MILLING & TEXTURING	707.00	TON		\$	
1300	02695		RUMBLE STRIPS TYPE 3	56,276.00	LF		\$	
1310	02697		EDGE LINE RUMBLE STRIPS	157,019.00	LF		\$	
1320	02701		TEMP SILT FENCE	2,000.00	LF		\$	
1330	02702		SAND FOR BLOTTER	975.00	TON		\$	
1340	02705		SILT TRAP TYPE C	8.00	EACH		\$	
1350	02708		CLEAN SILT TRAP TYPE C	8.00	EACH		\$	
1360	02726		STAKING CALDWELL COUNTY	1.00	LS		\$	
1370	02726		STAKING LYON COUNTY	1.00	LS		\$	
1380	02898		RELOCATE CRASH CUSHION	4.00	EACH		\$	
1390	03171		CONC BARRIER WALL TYPE 9T	30,850.00	LF		\$	
1400	05953		TEMP SEEDING AND PROTECTION	2,000.00	SQYD		\$	
1410	05963		INITIAL FERTILIZER	0.20	TON		\$	
1420	05964		MAINTENANCE FERTILIZER	0.20	TON		\$	
1430	05985		SEEDING AND PROTECTION	2,000.00	SQYD		\$	
1440	05992		AGRICULTURAL LIMESTONE	1.40	TON		\$	
1450	06511		PAVE STRIPING-TEMP PAINT-6 IN	258,868.00	LF		\$	
1460	06542		PAVE STRIPING-THERMO-6 IN W	50,604.00	LF		\$	
1470	06543		PAVE STRIPING-THERMO-6 IN Y	40,484.00	LF		\$	
1480	06556		PAVE STRIPING-DUR TY 1-6 IN W	95,536.00	LF		\$	
1490	06557		PAVE STRIPING-DUR TY 1-6 IN Y	76,117.00	LF		\$	
1500	06560		PAVE STRIPING-DUR TY 1-12 IN W	150.00	LF		\$	
1510	06585		PAVEMENT MARKER TY IVA-MW TEMP	173.00	EACH		\$	
1520	06586		PAVEMENT MARKER TY IVA-MY TEMP	173.00	EACH		\$	
1530	06613		INLAID PAVEMENT MARKER-B W/R	704.00	EACH		\$	
1540	08912		CRASH CUSHION TY 6 CLASS T TL3	4.00	EACH		\$	
1550	10203ND		PAVEMENT ADJUSTMENT (CALDWELL COUNTY)	1.00	LS	\$224,502.0	\$	\$224,502.00
1560	10203ND		PAVEMENT ADJUSTMENT (LYON COUNTY)	1.00	LS	\$3,177,042.	\$	\$3,177,042.00

Report Date 10/15/25

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1570	20191ED		OBJECT MARKER TY 3	1.00	EACH		\$	
1580	20411ED		LAW ENFORCEMENT OFFICER	1,200.00	HOURL		\$	
1590	21380ES719		GUARDRAIL THRIE BEAM	625.00	LF		\$	
1595	22664EN		WATER BLASTING EXISTING STRIPE (ADDED 10-15-25)	258,868.00	LF		\$	
1600	23147EN		HIGH TENSION CABLE-ROPE BARRIER	1,200.00	LF		\$	
1610	23148EN		END ANCHORS	4.00	EACH		\$	
1620	24255EC		REMOVE CABLE GUARDRAIL BARRIER SYSTEM	937.00	LF		\$	
1630	25078ED		THRIE BEAM GUARDRAIL TRANSITION TL-3	7.00	EACH		\$	
1640	26136EC		PORTABLE QUEUE WARNING ALERT SYSTEM	180.00	MONT		\$	
1650	26137EC		QUEUE WARNING PCMS	180.00	MONT		\$	
1660	26138EC		QUEUE WARNING PORTABLE RADAR SENSORS	180.00	MONT		\$	
1670	26233EC		MOBILIZATION FOR CONCRETE SURF TREATMENT LYON COUNTY	1.00	LS		\$	
1680	26236EC		THRIE BEAM BULLNOSE TERMINAL	6.00	EACH		\$	
1690	26237EC		CONNECTED ARROW PANEL	45.00	MONT		\$	
1700	26248EC		ELECTRONIC DELIVERY MGMT SYSTEM - AGG CALDWELL COUNTY	1.00	LS		\$	
1710	26248EC		ELECTRONIC DELIVERY MGMT SYSTEM - AGG LYON COUNTY	1.00	LS		\$	

Section: 0003 - BRIDGE- FRIENDSHIP ROAD OVER I-24

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1720	02403		REMOVE CONCRETE MASONRY	15.00	CUYD		\$	
1730	08001		STRUCTURE EXCAVATION-COMMON	17.00	CUYD		\$	
1740	08100		CONCRETE-CLASS A	27.00	CUYD		\$	
1750	08150		STEEL REINFORCEMENT	1,583.00	LB		\$	
1760	23378EC		CONCRETE SEALING	1,488.00	SQFT		\$	

Section: 0004 - BRIDGE-KY-903 OVER I-24

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1770	02403		REMOVE CONCRETE MASONRY	15.00	CUYD		\$	
1780	08001		STRUCTURE EXCAVATION-COMMON	16.00	CUYD		\$	
1790	08100		CONCRETE-CLASS A	27.00	CUYD		\$	
1800	08150		STEEL REINFORCEMENT	1,583.00	LB		\$	
1810	23378EC		CONCRETE SEALING	1,474.00	SQFT		\$	

Section: 0005 - TRAFFIC LOOPS-LYON COUNTY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
------	----------	-----	-------------	----------	------	-----------	----	--------

251029

PROPOSAL BID ITEMS

Page 6 of 6

Report Date 10/15/25

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1820	04793		CONDUIT-1 1/4 IN	30.00	LF		\$	
1830	04795		CONDUIT-2 IN	10.00	LF		\$	
1840	04820		TRENCHING AND BACKFILLING	35.00	LF		\$	
1850	04830		LOOP WIRE	800.00	LF		\$	
1860	04895		LOOP SAW SLOT AND FILL	150.00	LF		\$	
1870	20359NN		GALVANIZED STEEL CABINET	1.00	EACH		\$	
1880	20360ES818		WOOD POST	2.00	EACH		\$	
1890	20391NS835		ELECTRICAL JUNCTION BOX TYPE A	1.00	EACH		\$	

Section: 0006 - TRAINEES

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1900	02742		TRAINEE PAYMENT REIMBURSEMENT GROUP 2, 3, 4 OPERATOR	1,400.00	HOUR		\$	

Section: 0007 - DEMOBILIZATION &/OR MOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1910	02568		MOBILIZATION	1.00	LS		\$	
1920	02569		DEMOBILIZATION	1.00	LS		\$	