



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

March 25, 2026

CALL NO. 200
CONTRACT ID NO. 264503
ADDENDUM # 4

Subject: McClean County, 075GR26T004-HSIP
Letting March 26, 2026

- (1) Revised - Material Summary - Pages 102-104 of 238
- (2) Revised - General Summary - Pages 115-117 of 238
- (3) Revised - Proposal Bid Items - Pages 236-238 of 238

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

MATERIAL SUMMARY

CONTRACT ID: 264503

075GR26T004-HSIP

0207502542601

KY 254 (KY 254) FROM KY 1155, EXTENDING EASTERLY TO KY 81. ASPHALT RESURFACING, A DISTANCE OF 2.63 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	00001	DGA BASE	300.00	TON
0010	00190	LEVELING & WEDGING PG64-22	300.00	TON
0015	00301	CL2 ASPH SURF 0.38D PG64-22	1,870.00	TON
0020	02562	TEMPORARY SIGNS	400.00	SQFT
0025	02650	MAINTAIN & CONTROL TRAFFIC - (KY 254)	1.00	LS
0030	02676	MOBILIZATION FOR MILL & TEXT - (KY 254)	1.00	LS
0035	02677	ASPHALT PAVE MILLING & TEXTURING	35.00	TON
0040	02697	EDGELINE RUMBLE STRIPS	27,775.00	LF
0045	06510	PAVE STRIPING-TEMP PAINT-4 IN	13,890.00	LF
0050	06515	PAVE STRIPING-PERM PAINT-6 IN	55,550.00	LF
0055	24970EC	ASPHALT MATERIAL FOR TACK NON-TRACKING	15.00	TON
0060	26248EC	ELECTRONIC DELIVERY MGMT SYSTEM - AGG	1.00	LS
0065	02569	DEMOBILIZATION	1.00	LS

CONTRACT ID: 264503

075GR26T004-HSIP

0207502542602

WEST 2ND ST (KY 254) FROM THE HOPKINS COUNTY LINE TO SACRAMENTO CITY LIMITS 0.312 MILES WEST OF KY 81 WIDENING, A DISTANCE OF 5 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0070	00001	DGA BASE	583.00	TON
0075	00100	ASPHALT SEAL AGGREGATE	39.06	TON
0080	00103	ASPHALT SEAL COAT	4.50	TON
0085	00190	LEVELING & WEDGING PG64-22	150.00	TON
0090	00221	CL2 ASPH BASE 0.75D PG64-22	350.00	TON
0095	00301	CL2 ASPH SURF 0.38D PG64-22	726.00	TON
0100	00003	CRUSHED STONE BASE	120.00	TON
0105	00078	CRUSHED AGGREGATE SIZE NO 2	115.00	TON
0110	01987	DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	12.00	EACH
0115	02101	CEM CONC ENT PAVEMENT-8 IN	44.00	SQYD
0120	02200	ROADWAY EXCAVATION	2,891.00	CUYD
0125	02367	GUARDRAIL END TREATMENT TYPE 1	4.00	EACH
0130	02381	REMOVE GUARDRAIL	713.00	LF
0135	02483	CHANNEL LINING CLASS II	8,196.00	TON
0140	02545	CLEARING AND GRUBBING - 0.43 AC	1.00	LS
0145	02602	FABRIC-GEOTEXTILE CLASS 1	23.00	SQYD
0150	02604	FABRIC-GEOTEXTILE CLASS 1A	360.00	SQYD
0155	02650	MAINTAIN & CONTROL TRAFFIC - MCLEAN KY 254 HSIP	1.00	LS
0160	02676	MOBILIZATION FOR MILL & TEXT - MCLEAN KY 254 HSIP	1.00	LS

MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0165	02677	ASPHALT PAVE MILLING & TEXTURING	154.00	TON
0170	02697	EDGE LINE RUMBLE STRIPS	28,322.00	LF
0175	02701	TEMP SILT FENCE	10,000.00	LF
0180	02703	SILT TRAP TYPE A	10.00	EACH
0185	02704	SILT TRAP TYPE B	20.00	EACH
0190	02705	SILT TRAP TYPE C	20.00	EACH
0195	02706	CLEAN SILT TRAP TYPE A	10.00	EACH
0200	02707	CLEAN SILT TRAP TYPE B	20.00	EACH
0205	02708	CLEAN SILT TRAP TYPE C	20.00	EACH
0210	02726	STAKING - MCLEAN KY 254 HSIP	1.00	LS
0215	03240	BASE FAILURE REPAIR - (REVISED 3-25-26)	378.00	SQYD
0220	05950	EROSION CONTROL BLANKET	15,000.00	SQYD
0225	05952	TEMP MULCH	50,000.00	SQYD
0230	05953	TEMP SEEDING AND PROTECTION	25,000.00	SQYD
0235	05963	INITIAL FERTILIZER	5.00	TON
0240	05964	MAINTENANCE FERTILIZER	3.00	TON
0245	05985	SEEDING AND PROTECTION	25,000.00	SQYD
0250	06510	PAVE STRIPING-TEMP PAINT-4 IN	56,644.00	LF
0255	06515	PAVE STRIPING-PERM PAINT-6 IN	61,244.00	LF
0260	06568	PAVE MARKING-THERMO STOP BAR-24IN	30.00	LF
0265	10020NS	FUEL ADJUSTMENT	2,756.00	DOLL
0270	10030NS	ASPHALT ADJUSTMENT	3,323.00	DOLL
0275	20191ED	OBJECT MARKER TY 3	4.00	EACH
0280	20748ED	SHOULDER MILLING/TRENCHING	420.00	SQYD
0285	21802EN	G/R STEEL W BEAM-S FACE (7 FT POST)	506.25	LF
0290	25079ED	THRIE BEAM GUARDRAIL TRANSITION TL-2	4.00	EACH
0295	26248EC	ELECTRONIC DELIVERY MGMT SYSTEM - AGG	1.00	LS
0300	00441	ENTRANCE PIPE-18 IN	135.00	LF
0305	00443	ENTRANCE PIPE-24 IN	14.00	LF
0310	00462	CULVERT PIPE-18 IN	196.00	LF
0315	00464	CULVERT PIPE-24 IN	20.00	LF
0320	00466	CULVERT PIPE-30 IN	113.00	LF
0325	00468	CULVERT PIPE-36 IN	56.00	LF
0330	00472	CULVERT PIPE-60 IN	38.00	LF
0335	01220	PIPE CULVERT HEADWALL-60 IN	2.00	EACH
0340	01310	REMOVE PIPE	280.00	LF
0345	02607	FABRIC-GEOTEXTILE CLASS 2 FOR PIPE	352.00	SQYD
0350	08003	FOUNDATION PREPARATION - 12'Wx4'H BOX CULVERT	1.00	LS
0355	08003	FOUNDATION PREPARATION - 9'Wx6'H BOX CULVERT	1.00	LS
0360	08100	CONCRETE-CLASS A	24.40	CUYD
0365	08100	CONCRETE-CLASS A - 12'Wx4'H BOX CULVERT	63.20	CUYD
0370	08100	CONCRETE-CLASS A - 9'Wx6'H BOX CULVERT	63.70	CUYD
0375	08150	STEEL REINFORCEMENT - 12'Wx4'H BOX CULVERT	9,919.00	LB
0380	08150	STEEL REINFORCEMENT - 9'Wx6'H BOX CULVERT	7,895.00	LB
0385	24025EC	PIPE CULVERT HEADWALL-72 IN	2.00	EACH
0390	26131ED	SLOPED AND MITERED HEADWALL-18 IN	4.00	EACH
0395	26132ED	SLOPED AND MITERED HEADWALL-24 IN	2.00	EACH
0400	26133ED	SLOPED AND MITERED HEADWALL-30 IN	8.00	EACH
0405	26134ED	SLOPED AND MITERED HEADWALL-36 IN	6.00	EACH
0410	02562	TEMPORARY SIGNS	400.00	SQFT

MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0415	06406	SBM ALUM SHEET SIGNS .080 IN	343.63	SQFT
0420	06407	SBM ALUM SHEET SIGNS .125 IN	102.52	SQFT
0425	06410	STEEL POST TYPE 1	872.00	LF
0430	21373ND	REMOVE SIGN	94.00	EACH
0435	24631EC	BARCODE SIGN INVENTORY	94.00	EACH
0440	02569	DEMOBILIZATION	1.00	LS
0445	02671	PORTABLE CHANGEABLE MESSAGE SIGN - (ADDED 3-23-26)	2.00	EACH

NOTES:

- 1 FOR CONTROLLING DUST CAUSED BY MAINTAINING TRAFFIC ONLY
- 2 APPROXIMATELY 0.43 ACRES
- 3 MILLINGS SHALL BECOME THE PROPERTY OF THE MCLEAN COUNTY MAINTENANCE BARN
- 4 QUANTITY CARRIED OVER FROM GUARDRAIL SUMMARY
- 5 QUANTITY CARRIED OVER FROM ROADSIDE REGRADING SUMMARY
- 6 QUANTITY CARRIED OVER FROM PIPE EXTENSION SUMMARY
- 7 QUANTITY CARRIED OVER FROM PIPE REPLACEMENT SUMMARY
- 8 QUANTITY CARRIED OVER FROM SIGN SUMMARY
- 9 QUANTITY CARRIED OVER FROM BOX CULVERT SUMMARY
- 10 QUANTITY CARRIED OVER FROM BASE FAILURE SUMMARY
- 11 PIPE SUMMARY
- 12 QUANTITY CARRIED OVER FROM SUPERELEVATION SUMMARY
- 13 QUANTITY 106 TON TO BE USED AS NEEDED BY ENGINEER IN THE FIELD

ITEM	DESCRIPTION	UNIT	KY 254	TOTALS
08003	FOUNDATION PREPARATION (9'WX6'H)	LS	1	1
08003	FOUNDATION PREPARATION (12'WX4'H)	LS	1	1
08100	CONCRETE CLASS A (9'WX6'H)	CUVD	63.7	63.7
08100	CONCRETE CLASS A (12'WX4'H)	CUVD	63.2	63.2
08100	CONCRETE CLASS A	CUVD	24.4	24.4
08150	STEEL REINFORCEMENT (9'WX6'H)	LB	7,895	7,895
08150	STEEL REINFORCEMENT (12'WX4'H)	LB	9,919	9,919
10020NS	FUEL ADJUSTMENT	DOILL	2,756	2,756
10030NS	ASPHALT ADJUSTMENT	DOILL	3,323	3,323
20191ED	OBJECT MARKER 'X' 3'	EACH	4	4
20748ED	SHOULDER MILLING/TRENCHING	SQVD	420	420
21373ND	REMOVE SIGN	EACH	94	94
21802EN	G/R STEEL W BEAM'S FACE (7 FT POST)	LF	506.25	506.25
24025EC	PIPE CULVERT HEADWALL-72 IN	EACH	2	2
24631EC	BARCODE SIGN INVENTORY	EACH	94	94
25079ED	THREE BEAM GUARDRAIL TRANSITION TL-2	EACH	4	4
26131ED	SLOPED AND MITERED HEADWALL-18 IN	EACH	4	4
26132ED	SLOPED AND MITERED HEADWALL-24 IN	EACH	2	2
26133ED	SLOPED AND MITERED HEADWALL-30 IN	EACH	8	8
26134ED	SLOPED AND MITERED HEADWALL-36 IN	EACH	6	6
			13	13
			13	13



COMMONWEALTH OF KENTUCKY
DEPARTMENT OF HIGHWAYS



HSIP - KY 254
GENERAL SUMMARY - Sheet 2

ITEM NO.
2-846.00

COUNTY OF
MCLEAN

SHEET NO.
GENERAL SUMMARY - 2 of 28

PAVEMENT REPAIR

Offset	Begin Station	End Station	Length	Width	Asphalt Surface Depth (inches)	Asphalt Base Depth (inches)	Crushed Agg Size #2 Depth (inches)
LT	220+07	223+07	300	4	1.00	6.00	6.00
LT	242+72	243+72	100	4	1.00	6.00	6.00
LT	247+22	248+72	150	4	1.00	6.00	6.00
LT	254+39	257+39	300	4	1.00	6.00	6.00
			0				
			0				

ITEM	DESCRIPTION	UNIT	QUANTITY
3240	BASE FAILURE REPAIR	SQYD	378

Note: 1) All quantities carried over to General Summary



COMMONWEALTH OF KENTUCKY
DEPARTMENT OF HIGHWAYS

HSIP - KY 254
BASE FAILURE SUMMARY



PROPOSAL BID ITEMS

264503

Page 1 of 3

Report Date 3/25/26

264503

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00001		DGA BASE	883.00	TON		\$	
0020	00100		ASPHALT SEAL AGGREGATE	39.06	TON		\$	
0030	00103		ASPHALT SEAL COAT	4.50	TON		\$	
0040	00190		LEVELING & WEDGING PG64-22	450.00	TON		\$	
0050	00221		CL2 ASPH BASE 0.75D PG64-22	350.00	TON		\$	
0060	00301		CL2 ASPH SURF 0.38D PG64-22	2,596.00	TON		\$	
0070	24970EC		ASPHALT MATERIAL FOR TACK NON-TRACKING	15.00	TON		\$	

Section: 0002 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0080	00003		CRUSHED STONE BASE	120.00	TON		\$	
0090	00078		CRUSHED AGGREGATE SIZE NO 2	115.00	TON		\$	
0100	01987		DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	12.00	EACH		\$	
0110	02101		CEM CONC ENT PAVEMENT-8 IN	44.00	SQYD		\$	
0120	02200		ROADWAY EXCAVATION	2,891.00	CUYD		\$	
0130	02367		GUARDRAIL END TREATMENT TYPE 1	4.00	EACH		\$	
0140	02381		REMOVE GUARDRAIL	713.00	LF		\$	
0150	02483		CHANNEL LINING CLASS II	8,196.00	TON		\$	
0160	02545		CLEARING AND GRUBBING 0.43 AC	1.00	LS		\$	
0170	02562		TEMPORARY SIGNS	400.00	SQFT		\$	
0180	02602		FABRIC-GEOTEXTILE CLASS 1	23.00	SQYD		\$	
0190	02604		FABRIC-GEOTEXTILE CLASS 1A	360.00	SQYD		\$	
0200	02650		MAINTAIN & CONTROL TRAFFIC (KY 254)	1.00	LS		\$	
0210	02650		MAINTAIN & CONTROL TRAFFIC MCLEAN KY 254 HSIP	1.00	LS		\$	
0215	02671		PORTABLE CHANGEABLE MESSAGE SIGN (ADDED 3-23-26)	2.00	EACH		\$	
0220	02676		MOBILIZATION FOR MILL & TEXT (KY 254)	1.00	LS		\$	
0230	02676		MOBILIZATION FOR MILL & TEXT MCLEAN KY 254 HSIP	1.00	LS		\$	
0240	02677		ASPHALT PAVE MILLING & TEXTURING	189.00	TON		\$	
0250	02697		EDGELINE RUMBLE STRIPS	56,097.00	LF		\$	
0260	02701		TEMP SILT FENCE	10,000.00	LF		\$	
0270	02703		SILT TRAP TYPE A	10.00	EACH		\$	
0280	02704		SILT TRAP TYPE B	20.00	EACH		\$	
0290	02705		SILT TRAP TYPE C	20.00	EACH		\$	
0300	02706		CLEAN SILT TRAP TYPE A	10.00	EACH		\$	
0310	02707		CLEAN SILT TRAP TYPE B	20.00	EACH		\$	
0320	02708		CLEAN SILT TRAP TYPE C	20.00	EACH		\$	

PROPOSAL BID ITEMS

264503

Page 2 of 3

Report Date 3/25/26

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0330	02726		STAKING MCLEAN KY 254 HSIP	1.00	LS		\$	
0340	03240		BASE FAILURE REPAIR (REVISED 3-25-26)	378.00	SQYD		\$	
0350	05950		EROSION CONTROL BLANKET	15,000.00	SQYD		\$	
0360	05952		TEMP MULCH	50,000.00	SQYD		\$	
0370	05953		TEMP SEEDING AND PROTECTION	25,000.00	SQYD		\$	
0380	05963		INITIAL FERTILIZER	5.00	TON		\$	
0390	05964		MAINTENANCE FERTILIZER	3.00	TON		\$	
0400	05985		SEEDING AND PROTECTION	25,000.00	SQYD		\$	
0410	06510		PAVE STRIPING-TEMP PAINT-4 IN	70,534.00	LF		\$	
0420	06515		PAVE STRIPING-PERM PAINT-6 IN	116,794.00	LF		\$	
0430	06568		PAVE MARKING-THERMO STOP BAR-24IN	30.00	LF		\$	
0440	10020NS		FUEL ADJUSTMENT	2,756.00	DOLL	\$1.00	\$	\$2,756.00
0450	10030NS		ASPHALT ADJUSTMENT	3,323.00	DOLL	\$1.00	\$	\$3,323.00
0460	20191ED		OBJECT MARKER TY 3	4.00	EACH		\$	
0470	20748ED		SHOULDER MILLING/TRENCHING	420.00	SQYD		\$	
0480	21802EN		G/R STEEL W BEAM-S FACE (7 FT POST)	506.25	LF		\$	
0490	25079ED		THRIE BEAM GUARDRAIL TRANSITION TL-2	4.00	EACH		\$	
0500	26248EC		ELECTRONIC DELIVERY MGMT SYSTEM - AGG	1.00	LS		\$	

Section: 0003 - DRAINAGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0510	00441		ENTRANCE PIPE-18 IN	135.00	LF		\$	
0520	00443		ENTRANCE PIPE-24 IN	14.00	LF		\$	
0530	00462		CULVERT PIPE-18 IN	196.00	LF		\$	
0540	00464		CULVERT PIPE-24 IN	20.00	LF		\$	
0550	00466		CULVERT PIPE-30 IN	113.00	LF		\$	
0560	00468		CULVERT PIPE-36 IN	56.00	LF		\$	
0570	00472		CULVERT PIPE-60 IN	38.00	LF		\$	
0580	01220		PIPE CULVERT HEADWALL-60 IN	2.00	EACH		\$	
0590	01310		REMOVE PIPE	280.00	LF		\$	
0600	02607		FABRIC-GEOTEXTILE CLASS 2 FOR PIPE	352.00	SQYD	\$2.00	\$	\$704.00
0610	08003		FOUNDATION PREPARATION 12'Wx4'H BOX CULVERT	1.00	LS		\$	
0620	08003		FOUNDATION PREPARATION 9'Wx6'H BOX CULVERT	1.00	LS		\$	
0630	08100		CONCRETE-CLASS A	24.40	CUYD		\$	
0640	08100		CONCRETE-CLASS A 12'Wx4'H BOX CULVERT	63.20	CUYD		\$	
0650	08100		CONCRETE-CLASS A 9'Wx6'H BOX CULVERT	63.70	CUYD		\$	
0660	08150		STEEL REINFORCEMENT 12'Wx4'H BOX CULVERT	9,919.00	LB		\$	
0670	08150		STEEL REINFORCEMENT 9'Wx6'H BOX CULVERT	7,895.00	LB		\$	
0680	24025EC		PIPE CULVERT HEADWALL-72 IN	2.00	EACH		\$	
0690	26131ED		SLOPED AND MITERED HEADWALL-18 IN	4.00	EACH		\$	
0700	26132ED		SLOPED AND MITERED HEADWALL-24 IN	2.00	EACH		\$	

PROPOSAL BID ITEMS

264503

Page 3 of 3

Report Date 3/25/26

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0710	26133ED		SLOPED AND MITERED HEADWALL-30 IN	8.00	EACH		\$	
0720	26134ED		SLOPED AND MITERED HEADWALL-36 IN	6.00	EACH		\$	

Section: 0004 - SIGNING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0730	02562		TEMPORARY SIGNS	400.00	SQFT		\$	
0740	06406		SBM ALUM SHEET SIGNS .080 IN	343.63	SQFT		\$	
0750	06407		SBM ALUM SHEET SIGNS .125 IN	102.52	SQFT		\$	
0760	06410		STEEL POST TYPE 1	872.00	LF		\$	
0770	21373ND		REMOVE SIGN	94.00	EACH		\$	
0780	24631EC		BARCODE SIGN INVENTORY	94.00	EACH		\$	

Section: 0005 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0790	02569		DEMOBILIZATION	1.00	LS		\$	