



**TRANSPORTATION CABINET**

Frankfort, Kentucky 40622  
www.transportation.ky.gov/

**Steven L. Beshear**  
Governor

**Michael W. Hancock, P.E.**  
Secretary

August 16, 2011

CALL NO. 201  
CONTRACT ID NO. 111330  
ADDENDUM # 1

Subject: Breathitt County, 0130015D030-NH  
Letting August 19, 2011

- (1) Revised - Plan Sheet - R2g
- (2) Revised - Material Summary - Pages 40-42 of 109
- (3) Revised - Bid Items - Pages 106-109 of 109

Proposal revisions are available at <http://transportation.ky.gov/contract/>.  
Plan revisions are available at <http://www.lynnimaging.com/kytransportation/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Ryan Griffith".

Ryan Griffith  
Director  
Division of Construction Procurement

RG:ks  
Enclosures



An Equal Opportunity Employer M/F/D

Cell Library: kytc.cel  
Cell Name: sp  
DD-MMM-YYYY HH:MM

PREPARED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHECKED BY \_\_\_\_\_ DATE \_\_\_\_\_  
APPROVED BY \_\_\_\_\_ DATE \_\_\_\_\_

Files: \$FILES\$  
Plotted: \$DATE\$ \$TIME\$

### PAVING AREAS

ITEM	10-270.67					10-270.77					TOTAL	
	KY 15	RAMP B	RAMP C	DIVERSION 2	ENTRANCES	TOTAL	KY 15	APPROACH LT 1251+48.70 EX KY 15	DIVERSION 1	ENTRANCES		TOTAL
		S	Q	U	A	R		E	Y	A		R
Travel Lanes												
1 1/4" CL3 ASPH SURF 0.38B PG64-22	15290	4054	3010		22354	54031					54031	76385
1 1/4" CL2 ASPH SURF 0.38D PG64-22			205		205		2322	254	2011	4587	4792	
2 1/4" CL2 ASPH BASE 0.75D PG64-22			428		428		2342	510	2043	4895	5323	
2 1/2" CL2 ASPH BASE 0.75D PG64-22							2378			2378	2378	
3" CL2 ASPH BASE 0.75D PG64-22	46956	12651	9390	463	463		4884	527		5411	5874	
3 1/4" CL3 ASPH BASE 1.00D PG64-22	15914	4344	3224	237	23719	41021	2466	266	2363	135307	204304	
4" CRUSHED STONE BASE										45853	69572	
Shoulders												
1 1/4" CL2 ASPH SURF 0.38D PG64-22	6570	2250	1615	149	10584	28386	1944	165		30495	41079	
2 1/4" CL2 ASPH BASE 0.75D PG64-22			149		149		1944	165		2109	2258	
3 1/4" CL2 ASPH BASE 1.00D PG64-22	6570	2250	1615		10435	26859				26859	37294	
ASPHALT SEAL AGGREGATE	3869	1741	1282		6892	15170	776			15946	22838	
EMULSIFIED ASPHALT RS-2	3869	1741	1282		6892	15170	776			15946	22838	
VARIABLE DEPTH CRUSHED STONE BASE ①	3267	1185	940		5392	15883	792			16675	22067	

### PAVING SUMMARY

ITEM CODE	ITEM	UNIT	10-270.67					10-270.77					TOTAL PROJECT
			KY 15	RAMP B	RAMP C	DIVERSION 2	ENTRANCES	TOTAL	KY 15	APPROACH LT 1251+48.70 EX KY 15	DIVERSION 1	ENTRANCES	
3	CRUSHED STONE BASE ② ⑤	TON	10423	3452	2688	55	17449	42313	2206	61	483	47316	64765
100	ASPHALT SEAL AGGREGATE ③	TON	77	35	26		138	303	16			319	457
212	CL2 ASPH BASE 1.00D PG64-22	TON	1174	402	289		1865	4801				4801	6666
214	CL3 ASPH BASE 1.00D PG64-22	TON	8393	2261	1678		12332	24186				24186	36518
221	CL2 ASPH BASE 0.75D PG64-22	TON				148	148		1663	170	253	2086	2234
291	EMULSIFIED ASPHALT RS-2 ④	TON	9	4	3		16	38	2			38	54
301	CL2 ASPH SURF 0.38D PG64-22	TON	452	155	111	24	742	1952	293	138	2412	3154	
388	CL3 ASPH SURF 0.38B PG64-22	TON	1051	279	207		1537	3715				3715	5252
2677	ASPH PAVE MILLING & TEXTURING	TON						353				353	353

#### NOTES

ALL ASPHALT MIXTURES SHALL BE ESTIMATED AT 110 LB PER SQ YD PER INCH OF DEPTH, UNLESS NOTED OTHERWISE.

- ① MEASURED IN CUBIC YARDS.
- ② ESTIMATED AT 115 LB PER SQ YD PER INCH OF DEPTH OR 2.07 TONS PER CU. YD
- ③ ESTIMATED AT 20 LB PER SQ YD ( 2 APPLICATIONS)
- ④ ESTIMATED AT 2.4 LB PER SQ YD (2 APPLICATIONS)
- ⑤ INCLUDES 10% INCREASE FOR ROCK ROADBED VOIDS

PAVING AREAS & PAVING SUMMARY

COUNTY OF	ITEM NO.	SHEET NO.
BREATHITT	10-270.67, 10-270.77	R29

Cell Library: kytc.cel  
Cell Name: sp  
DD-MMM-YYYY HH:MM

PREPARED BY: \_\_\_\_\_ DATE: \_\_\_\_\_  
CHECKED BY: \_\_\_\_\_ DATE: \_\_\_\_\_  
APPROVED BY: \_\_\_\_\_ DATE: \_\_\_\_\_

Files: \$FILES\$  
Plotted: \$DATE\$ \$TIME\$

## PAVING AREAS

ITEM	10-270.67					10-270.77					PROJECT TOTAL	
	KY 15	RAMP B	RAMP C	DIVERSION 2	TOTAL	KY 15	APPROACH LT 1251+48.70 EX KY 15	DIVERSION 1	ENTRANCES	TOTAL		
												S
<i>Travel Lanes</i>												
1 1/4" CL3 ASPH SURF 0.38B PG64-22	15290	4054	3010		22354	54031						
1 1/4" CL2 ASPH SURF 0.38D PG64-22				205	205		2322	254	2011	4587		76385
2 1/4" CL2 ASPH BASE 0.75D PG64-22				428	428		2342	510	2043	4895		4792
2 1/2" CL2 ASPH BASE 0.75D PG64-22							2378			2378		5323
3" CL2 ASPH BASE 0.75D PG64-22				463	463		4884	527		5411		2378
3 1/4" CL3 ASPH BASE 1.00D PG64-22	46956	12651	9390		68997	135307				135307		5874
4" CRUSHED STONE BASE	15914	4344	3224	237	23719	41021	2466	266	2363	45853		204304
												69572
<i>Shoulders</i>												
1 1/4" CL2 ASPH SURF 0.38D PG64-22	6570	2250	1615	149	10584	28386	1944	165		30495		41079
2 1/4" CL2 ASPH BASE 0.75D PG64-22				149	149		1944	165		2109		2258
3 1/4" CL2 ASPH BASE 1.00D PG64-22	6570	2250	1615		10435	26859				26859		37294
ASPHALT SEAL AGGREGATE	3869	1741	1282		6892	15170	776			15946		22838
EMULSIFIED ASPHALT RS-2	3869	1741	1282		6892	15170	776			15946		22838
VARIABLE DEPTH CRUSHED STONE BASE ①	3267	1185	940		5392	15883	792			16675		22067

## PAVING SUMMARY

ITEM CODE	ITEM	UNIT	10-270.67					10-270.77					TOTAL PROJECT
			KY 15	RAMP B	RAMP C	DIVERSION 2	ENTRANCES	TOTAL	KY 15	APPROACH LT 1251+48.70 EX KY 15	DIVERSION 1	ENTRANCES	
3	CRUSHED STONE BASE ② ⑤	TON	10423	3452	2688	55	17449	42313	2206	61	483	47316	64765
100	ASPHALT SEAL AGGREGATE ③	TON	77	35	26		138	303	16			319	457
212	CL2 ASPH BASE 1.00D PG64-22	TON	1174	402	289		1865	4801				4801	6666
214	CL3 ASPH BASE 1.00D PG64-22	TON	8393	2261	1678		12332	24186				24186	36518
221	CL2 ASPH BASE 0.75D PG64-22	TON				148	148		1663	170	253	2086	2234
291	EMULSIFIED ASPHALT RS-2 ④	TON	9	4	3		16	38	2			38	54
301	CL2 ASPH SURF 0.38D PG64-22	TON	452	155	111	24	742	1952	293	138	2412	3154	
388	CL3 ASPH SURF 0.38B PG64-22	TON	1051	279	207		1537	3715				3715	5252
2677	ASPH PAVE MILLING & TEXTURING	TON						353				353	353

### NOTES

ALL ASPHALT MIXTURES SHALL BE ESTIMATED AT 110 LB PER SQ YD PER INCH OF DEPTH, UNLESS NOTED OTHERWISE.

- ① MEASURED IN CUBIC YARDS.
- ② ESTIMATED AT 115 LB PER SQ YD PER INCH OF DEPTH OR 2.07 TONS PER CU. YD
- ③ ESTIMATED AT 20 LB PER SQ YD ( 2 APPLICATIONS)
- ④ ESTIMATED AT 2.4 LB PER SQ YD (2 APPLICATIONS)
- ⑤ INCLUDES 10% INCREASE FOR ROCK ROADBED VOIDS

PAVING AREAS &  
PAVING SUMMARY

COUNTY OF	ITEM NO.	SHEET NO.
BREATHITT	10-270.67, 10-270.77	R29

▲ REVISED 8-12-2011

MATERIAL SUMMARY

CONTRACT ID: 111330

NH 0151 (070) PES NO: DE01300151101  
JACKSON-CAMPTON ROAD (KY 15) FROM KY 15 AT JACKSON TO A POINT 0.43 MILE NORTH OF KY  
15 , A DISTANCE OF 0.690000 MILES.

LINE NO	BID CODE	DESCRIPTION	QUANTITY	UNIT
1046	01983	DELINEATOR FOR GUARDRAIL-YELLOW	8.00	EACH
1001	02014	BARRICADE-TYPE III	4.00	EACH
1004	02242	WATER	450.00	MGAL
1005	02351	GUARDRAIL-STEEL W BEAM-S FACE	1,750.00	LF
1007	02367	GUARDRAIL END TREATMENT TYPE 1	4.00	EACH
1008	02369	GUARDRAIL END TREATMENT TYPE 2A	4.00	EACH
1013	02562	SIGNS	240.00	SQFT
1015	02650	MAINTAIN & CONTROL TRAFFIC (10-270.67)	1.00	LS
1048	02651	DIVERSIONS (BY-PASS DETOURS) (CROSSOVER #2)	1.00	LS
1016	02671	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
1026	02726	STAKING (10-270.67())	1.00	LS
1027	02775	ARROW PANEL	1.00	EACH
1034	06510	PAVE STRIPING-TEMP PAINT-4 IN	13,000.00	LF
1035	06514	PAVE STRIPING-PERM PAINT-4 IN	22,841.00	LF
1036	06550	PAVE STRIPING-TEMP REM TAPE-W	300.00	LF
1037	06551	PAVE STRIPING-TEMP REM TAPE-Y	400.00	LF
1038	06565	PAVE MARKING-THERMO X-WALK-6 IN	359.00	LF
1039	06567	PAVE MARKING-THERMO STOP BAR-12IN	124.00	LF
1043	06592	PAVEMENT MARKER TYPE V-B W/R	76.00	EACH
1044	10020NS	FUEL ADJUSTMENT	29,700.00	DOLL
1045	10030NS	ASPHALT ADJUSTMENT	41,765.00	DOLL
3001	00003	CRUSHED STONE BASE (REVISED: 8-16-11)	17,449.00	TON
3002	00100	ASPHALT SEAL AGGREGATE	138.00	TON
3003	00212	CL2 ASPH BASE 1.00D PG64-22	1,865.00	TON
3004	00214	CL3 ASPH BASE 1.00D PG64-22 (REVISED: 8-16-11)	12,332.00	TON
3005	00221	CL2 ASPH BASE 0.75D PG64-22	148.00	TON
3006	00291	EMULSIFIED ASPHALT RS-2	16.00	TON
3007	00301	CL2 ASPH SURF 0.38D PG64-22	742.00	TON
3008	00388	CL3 ASPH SURF 0.38B PG64-22	1,537.00	TON
4001	02568	MOBILIZATION	1.00	LS
4002	02569	DEMOBILIZATION	1.00	LS

MATERIAL SUMMARY

CONTRACT ID: 111330

NH 0151 (071)

PES NO: DE01300151102

JACKSON-CAMPTON ROAD (KY 15) FROM 0.43 MILE NORTH OF KY 15 AT JACKSON TO 0.31 MILE SOUTH OF STILL HOUSE HOLLOW , A DISTANCE OF 1.740000 MILES.

LINE NO	BID CODE	DESCRIPTION	QUANTITY	UNIT
1001	02014	BARRICADE-TYPE III	9.00	EACH
1002	02091	REMOVE PAVEMENT	3,494.00	SQYD
1033	02159	TEMP DITCH	2,572.00	LF
1003	02200	ROADWAY EXCAVATION	52,359.00	CUYD
1004	02242	WATER	1,050.00	MGAL
1005	02351	GUARDRAIL-STEEL W BEAM-S FACE	3,625.00	LF
1006	02360	GUARDRAIL TERMINAL SECTION NO 1	3.00	EACH
1007	02367	GUARDRAIL END TREATMENT TYPE 1	4.00	EACH
1008	02369	GUARDRAIL END TREATMENT TYPE 2A	5.00	EACH
1009	02381	REMOVE GUARDRAIL	2,137.50	LF
1010	02483	CHANNEL LINING CLASS II	995.00	TON
1011	02484	CHANNEL LINING CLASS III	188.00	TON
1012	02545	CLEARING AND GRUBBING (7 ACRES)	1.00	LS
1013	02562	SIGNS	477.00	SQFT
1014	02585	EDGE KEY	121.00	LF
1015	02650	MAINTAIN & CONTROL TRAFFIC (10-270.77)	1.00	LS
1047	02651	DIVERSIONS (BY-PASS DETOURS) (CROSSOVER #1)	1.00	LS
1016	02671	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
1017	02676	MOBILIZATION FOR MILL & TEXT (10-270.77)	1.00	LS
1018	02701	TEMP SILT FENCE	2,572.00	LF
1019	02703	SILT TRAP TYPE A	46.00	EACH
1020	02704	SILT TRAP TYPE B	46.00	EACH
1021	02705	SILT TRAP TYPE C	23.00	EACH
1022	02706	CLEAN SILT TRAP TYPE A	92.00	EACH
1023	02707	CLEAN SILT TRAP TYPE B	92.00	EACH
1024	02708	CLEAN SILT TRAP TYPE C	46.00	EACH
1025	02709	CLEAN TEMP SILT FENCE	5,144.00	LF
1026	02726	STAKING (10-270.77)	1.00	LS
1027	02775	ARROW PANEL	1.00	EACH
1028	03171	CONCRETE BARRIER WALL TYPE 9T	80.00	LF
1029	05950	EROSION CONTROL BLANKET	1,238.00	SQYD
1030	05952	TEMP MULCH	111,465.00	SQYD
1031	05953	TEMP SEEDING AND PROTECTION	9,646.00	SQYD
1032	05985	SEEDING AND PROTECTION	96,461.00	SQYD
1034	06510	PAVE STRIPING-TEMP PAINT-4 IN	30,200.00	LF
1035	06514	PAVE STRIPING-PERM PAINT-4 IN	38,428.00	LF
1036	06550	PAVE STRIPING-TEMP REM TAPE-W	300.00	LF
1037	06551	PAVE STRIPING-TEMP REM TAPE-Y	400.00	LF
1039	06567	PAVE MARKING-THERMO STOP BAR-12IN	103.00	LF
1040	06573	PAVE MARKING-THERMO STR ARROW	4.00	EACH
1041	06574	PAVE MARKING-THERMO CURV ARROW	4.00	EACH
1042	06589	PAVEMENT MARKER TYPE V-MW	20.00	EACH
1043	06592	PAVEMENT MARKER TYPE V-B W/R	180.00	EACH
1044	10020NS	FUEL ADJUSTMENT	69,292.00	DOLL
1045	10030NS	ASPHALT ADJUSTMENT	97,445.00	DOLL
1049	23131ER701	PIPELINE VIDEO INSPECTION	98.00	LF
2001	00440	ENTRANCE PIPE-15 IN	74.00	LF

MATERIAL SUMMARY

CONTRACT ID: 111330

2002	00522	STORM SEWER PIPE-18 IN	188.00	LF
2003	00524	STORM SEWER PIPE-24 IN	8.00	LF
2004	01505	DROP BOX INLET TYPE 5B	1.00	EACH
2005	01511	DROP BOX INLET TYPE 5D	1.00	EACH
2006	01655	REMOVE JUNCTION BOX	1.00	EACH
3001	00003	CRUSHED STONE BASE (REVISED: 8-16-11)	47,316.00	TON
3002	00100	ASPHALT SEAL AGGREGATE (REVISED: 8-16-11)	319.00	TON
3003	00212	CL2 ASPH BASE 1.00D PG64-22 (REVISED: 8-16-11)	4,801.00	TON
3004	00214	CL3 ASPH BASE 1.00D PG64-22 (REVISED: 8-16-11)	24,186.00	TON
3005	00221	CL2 ASPH BASE 0.75D PG64-22 (REVISED: 8-16-11)	2,086.00	TON
3006	00291	EMULSIFIED ASPHALT RS-2 (REVISED: 8-16-11)	38.00	TON
3007	00301	CL2 ASPH SURF 0.38D PG64-22 (REVISED: 8-16-11)	2,412.00	TON
3008	00388	CL3 ASPH SURF 0.38B PG64-22 (REVISED: 8-16-11)	3,715.00	TON
3009	02677	ASPHALT PAVE MILLING & TEXTURING (REVISED: 8-16-11)	353.00	TON
4001	02568	MOBILIZATION	1.00	LS
4002	02569	DEMOBILIZATION	1.00	LS

---

CONTRACT ID: 111330  
COUNTY: BREATHITT  
PROPOSAL: 0130015D030-NH

PAGE: 1  
LETTING: 08/19/11  
CALL NO: 201

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
SECTION 0001 PAVING						
0010	00003	CRUSHED STONE BASE (REVISED: 8-16-11)	64,765.000	TON		
0020	00100	ASPHALT SEAL AGGREGATE (REVISED: 8-16-11)	457.000	TON		
0030	00212	CL2 ASPH BASE 1.00D PG64-22 (REVISED: 8-16-11)	6,666.000	TON		
0040	00214	CL3 ASPH BASE 1.00D PG64-22 (REVISED: 8-16-11)	36,518.000	TON		
0050	00221	CL2 ASPH BASE 0.75D PG64-22 (REVISED: 8-16-11)	2,234.000	TON		
0060	00291	EMULSIFIED ASPHALT RS-2 (REVISED: 8-16-11)	54.000	TON		
0070	00301	CL2 ASPH SURF 0.38D PG64-22 (REVISED: 8-16-11)	3,154.000	TON		
0080	00388	CL3 ASPH SURF 0.38B PG64-22 (REVISED: 8-16-11)	5,252.000	TON		
0090	02677	ASPHALT PAVE MILLING & TEXTURING (REVISED: 8-16-11)	353.000	TON		
SECTION 0002 ROADWAY						
0100	01983	DELINEATOR FOR GUARDRAIL-YELLOW	8.000	EACH		
0110	02014	BARRICADE-TYPE III	13.000	EACH		
0120	02091	REMOVE PAVEMENT	3,494.000	SQYD		
0130	02159	TEMP DITCH	2,572.000	LF		
0140	02200	ROADWAY EXCAVATION	52,359.000	CUYD		
0150	02242	WATER	1,500.000	MGAL		
0160	02351	GUARDRAIL-STEEL W BEAM-S FACE	5,375.000	LF		
0170	02360	GUARDRAIL TERMINAL SECTION NO 1	3.000	EACH		
0180	02367	GUARDRAIL END TREATMENT TYPE 1	8.000	EACH		
0190	02369	GUARDRAIL END TREATMENT TYPE 2A	9.000	EACH		

CONTRACT ID: 111330  
COUNTY: BREATHITT  
PROPOSAL: 0130015D030-NH

PAGE: 2  
LETTING: 08/19/11  
CALL NO: 201

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
0200	02381	REMOVE GUARDRAIL	2,137.500	LF		
0210	02483	CHANNEL LINING CLASS II	995.000	TON		
0220	02484	CHANNEL LINING CLASS III	188.000	TON		
0230	02545	CLEARING AND GRUBBING (7 ACRES)	( 1.00)	LS		
0240	02562	SIGNS	717.000	SQFT		
0250	02585	EDGE KEY	121.000	LF		
0260	02650	MAINTAIN & CONTROL TRAFFIC (10-270.67)	( 1.00)	LS		
0270	02650	MAINTAIN & CONTROL TRAFFIC (10-270.77)	( 1.00)	LS		
0280	02651	DIVERSIONS (BY-PASS DETOURS) (CROSSOVER #1)	( 1.00)	LS		
0290	02651	DIVERSIONS (BY-PASS DETOURS) (CROSSOVER #2)	( 1.00)	LS		
0300	02671	PORTABLE CHANGEABLE MESSAGE SIGN	4.000	EACH		
0310	02676	MOBILIZATION FOR MILL & TEXT (10-270.77)	( 1.00)	LS		
0320	02701	TEMP SILT FENCE	2,572.000	LF		
0330	02703	SILT TRAP TYPE A	46.000	EACH		
0340	02704	SILT TRAP TYPE B	46.000	EACH		
0350	02705	SILT TRAP TYPE C	23.000	EACH		
0360	02706	CLEAN SILT TRAP TYPE A	92.000	EACH		
0370	02707	CLEAN SILT TRAP TYPE B	92.000	EACH		
0380	02708	CLEAN SILT TRAP TYPE C	46.000	EACH		
0390	02709	CLEAN TEMP SILT FENCE	5,144.000	LF		
0400	02726	STAKING (10-270.67())	( 1.00)	LS		

CONTRACT ID: 111330  
COUNTY: BREATHITT  
PROPOSAL: 0130015D030-NH

PAGE: 3  
LETTING: 08/19/11  
CALL NO: 201

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
0410	02726	STAKING (10-270.77)	( 1.00)	LS		
0420	02775	ARROW PANEL	2.000	EACH		
0430	03171	CONCRETE BARRIER WALL TYPE 9T	80.000	LF		
0440	05950	EROSION CONTROL BLANKET	1,238.000	SQYD		
0450	05952	TEMP MULCH	111,465.000	SQYD		
0460	05953	TEMP SEEDING AND PROTECTION	9,646.000	SQYD		
0470	05985	SEEDING AND PROTECTION	96,461.000	SQYD		
0480	06510	PAVE STRIPING-TEMP PAINT-4 IN	43,200.000	LF		
0490	06514	PAVE STRIPING-PERM PAINT-4 IN	61,269.000	LF		
0500	06550	PAVE STRIPING-TEMP REM TAPE-W	600.000	LF		
0510	06551	PAVE STRIPING-TEMP REM TAPE-Y	800.000	LF		
0520	06565	PAVE MARKING-THERMO X-WALK-6 IN	359.000	LF		
0530	06567	PAVE MARKING-THERMO STOP BAR-12IN	227.000	LF		
0540	06573	PAVE MARKING-THERMO STR ARROW	4.000	EACH		
0550	06574	PAVE MARKING-THERMO CURV ARROW	4.000	EACH		
0560	06589	PAVEMENT MARKER TYPE V-MW	20.000	EACH		
0570	06592	PAVEMENT MARKER TYPE V-B W/R	256.000	EACH		
0580	10020NS	FUEL ADJUSTMENT	98,992.000	DOLL	1.00	98,992.00
0590	10030NS	ASPHALT ADJUSTMENT	139,210.000	DOLL	1.00	139,210.00
0600	23131ER701	PIPELINE VIDEO INSPECTION	98.000	LF		

SECTION 0003 DRAINAGE

CONTRACT ID: 111330  
COUNTY: BREATHITT  
PROPOSAL: 0130015D030-NH

PAGE: 4  
LETTING: 08/19/11  
CALL NO: 201

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
0610	00440	ENTRANCE PIPE-15 IN	74.000	LF		
0620	00522	STORM SEWER PIPE-18 IN	188.000	LF		
0630	00524	STORM SEWER PIPE-24 IN	8.000	LF		
0640	01505	DROP BOX INLET TYPE 5B	1.000	EACH		
0650	01511	DROP BOX INLET TYPE 5D	1.000	EACH		
0660	01655	REMOVE JUNCTION BOX	1.000	EACH		
SECTION 0004 MOBILIZATION / DEMOBILIZATION						
0670	02568	MOBILIZATION (NO MORE THAN 5%)		LUMP		
0680	02569	DEMOBILIZATION (AT LEAST 1.5%)		LUMP		
		TOTAL BID				