



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

October 22, 2025

CALL NO. 201
CONTRACT ID NO. 251032
ADDENDUM # 2

Subject: Jefferson County, NHPP 0711(096)
Letting October 23, 2025

- (1) Revised - Material Summary - Pages 171-178 of 245
- (2) Revised - Proposal Bid Items - Pages 236-245 of 245

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

MATERIAL SUMMARY

CONTRACT ID: 251032

NHPP 0711(096)

DE05600712513

I-71 WIDENING ADDITION OF NB AND SB AUXILIARY LANES ON I-71 NEAR KENNEDY INCLUDING OPERATIONAL IMPROVEMENTS TO THE ZORN INTERCHANGE GRADE DRAIN & SURFACE WITH BRIDGE, A DISTANCE OF 2.5 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0040	00001	DGA BASE	18,476.00	TON
0045	00008	CEMENT STABILIZED ROADBED	46,659.00	SQYD
0050	00018	DRAINAGE BLANKET-TYPE II-ASPH	14,145.00	TON
0055	00100	ASPHALT SEAL AGGREGATE	201.00	TON
0060	00103	ASPHALT SEAL COAT	24.00	TON
0065	00190	LEVELING & WEDGING PG64-22	416.00	TON
0070	00194	LEVELING & WEDGING PG76-22	2,727.00	TON
0075	00214	CL3 ASPH BASE 1.00D PG64-22	8,709.00	TON
0080	00217	CL4 ASPH BASE 1.00D PG64-22	15,068.00	TON
0085	00219	CL4 ASPH BASE 1.00D PG76-22	9,480.00	TON
0090	00339	CL3 ASPH SURF 0.38D PG64-22	2,537.00	TON
0095	00342	CL4 ASPH SURF 0.38A PG76-22	11,512.00	TON
0100	00358	ASPHALT CURING SEAL	48.00	TON
0105	02542	CEMENT	938.00	TON
0110	02676	MOBILIZATION FOR MILL & TEXT	1.00	LS
0115	02677	ASPHALT PAVE MILLING & TEXTURING	10,390.00	TON
0120	02702	SAND FOR BLOTTER	117.00	TON
0125	02720	SIDEWALK-4 IN CONCRETE	1,110.00	SQYD
0130	20071EC	JOINT ADHESIVE	106,876.00	LF
0135	21289ED	LONGITUDINAL EDGE KEY	24,912.00	LF
0140	24970EC	ASPHALT MATERIAL FOR TACK NON-TRACKING	188.00	TON
0145	00078	CRUSHED AGGREGATE SIZE NO 2	16,033.00	TON
0150	01001	PERFORATED PIPE-6 IN	11,290.00	LF
0155	01011	NON-PERFORATED PIPE-6 IN	424.00	LF
0160	01033	PERF PIPE HEADWALL TY 4-6 IN	1.00	EACH
0165	01690	FLUME INLET TYPE 1	3.00	EACH
0170	01691	FLUME INLET TYPE 2	17.00	EACH
0175	01877	SPECIAL HEADER CURB	3,276.00	LF
0180	01885	LIP HEADER CURB	165.00	LF
0185	01890	ISLAND HEADER CURB TYPE 1	547.00	LF
0190	01903	REMOVE CONCRETE ROLL CURB	66.00	LF
0195	01978	CONC MEDIAN BARRIER TYPE A TL5 56 IN	10,231.00	LF
0200	01978	CONC MEDIAN BARRIER TYPE A TL5 56 IN - MODIFIED	185.00	LF
0205	01982	DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL WHITE	405.00	EACH
0210	01983	DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL YELLOW	10.00	EACH
0215	01985	DELINEATOR FOR BARRIER - YELLOW	200.00	EACH
0220	01987	DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	4.00	EACH
0225	02003	RELOCATE TEMP CONC BARRIER	18,200.00	LF
0230	02014	BARRICADE-TYPE III	8.00	EACH
0235	02070	JPC PAVEMENT-12 IN	166.00	SQYD
0240	02076	JPC PAVEMENT-7 IN	121.00	SQYD
0245	02091	REMOVE PAVEMENT	8,556.00	SQYD

MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0250	02159	TEMP DITCH	6,944.00	LF
0255	02160	CLEAN TEMP DITCH	3,472.00	LF
0260	02200	ROADWAY EXCAVATION	40,364.00	CUYD
0265	02223	GRANULAR EMBANKMENT	978.00	CUYD
0270	02242	WATER	2,400.00	MGAL
0275	02262	FENCE-WOVEN WIRE TYPE 1	25,112.00	LF
0280	02289	DOUBLE VEHICULAR WOVEN WIRE GATE	1.00	EACH
0285	02351	GUARDRAIL-STEEL W BEAM-S FACE	28,412.50	LF
0290	02367	GUARDRAIL END TREATMENT TYPE 1	7.00	EACH
0295	02370	GUARDRAIL END TREATMENT TYPE 2M	10.00	EACH
0300	02371	GUARDRAIL END TREATMENT TYPE 7	1.00	EACH
0305	02381	REMOVE GUARDRAIL	31,898.00	LF
0310	02395	REMOVE GUARDRAIL TERMINAL SECT	2.00	EACH
0315	02396	REMOVE GUARDRAIL END TREATMENT	9.00	EACH
0320	02483	CHANNEL LINING CLASS II	644.00	TON
0325	02545	CLEARING AND GRUBBING - 47.6 ACRES	1.00	LS
0330	02555	CONCRETE-CLASS B - (REVISED 10-21-25)	52.52	CUYD
0335	02562	TEMPORARY SIGNS	1,450.00	SQFT
0340	02565	OBJECT MARKER TYPE 2	12.00	EACH
0345	02570	PROJECT CPM SCHEDULE	1.00	LS
0350	02602	FABRIC-GEOTEXTILE CLASS 1	5,372.00	SQYD
0355	02612	HANDRAIL-TYPE A-2	80.00	LF
0360	02650	MAINTAIN & CONTROL TRAFFIC - NHPP 0711(096)	1.00	LS
0365	02671	PORTABLE CHANGEABLE MESSAGE SIGN	10.00	EACH
0370	02697	EDGE LINE RUMBLE STRIPS	42,724.00	LF
0375	02701	TEMP SILT FENCE	6,944.00	LF
0380	02703	SILT TRAP TYPE A	48.00	EACH
0385	02704	SILT TRAP TYPE B	48.00	EACH
0390	02705	SILT TRAP TYPE C	48.00	EACH
0395	02706	CLEAN SILT TRAP TYPE A	48.00	EACH
0400	02707	CLEAN SILT TRAP TYPE B	48.00	EACH
0405	02708	CLEAN SILT TRAP TYPE C	48.00	EACH
0410	02726	STAKING	1.00	LS
0415	02731	REMOVE STRUCTURE - STA 547+57 NB BRIDGE OVER ABANDONED R/R	1.00	LS
0420	02731	REMOVE STRUCTURE - STA 547+57 SB BRIDGE OVER ABANDONED R/R	1.00	LS
0425	02898	RELOCATE CRASH CUSHION	7.00	EACH
0430	02998	MASONRY COATING	11,547.00	SQYD
0435	03171	CONC BARRIER WALL TYPE 9T	26,920.00	LF
0440	05950	EROSION CONTROL BLANKET	10,642.00	SQYD
0445	05952	TEMP MULCH	154,357.00	SQYD
0450	05953	TEMP SEEDING AND PROTECTION	115,265.00	SQYD
0455	05963	INITIAL FERTILIZER	4.90	TON
0460	05964	MAINTENANCE FERTILIZER	2.90	TON
0465	05985	SEEDING AND PROTECTION	95,011.00	SQYD
0470	05992	AGRICULTURAL LIMESTONE	58.90	TON
0475	06404	FLEXIBLE DELINEATOR POST-M/Y	55.00	EACH
0480	06510	PAVE STRIPING-TEMP PAINT-4 IN	1,178.00	LF
0485	06511	PAVE STRIPING-TEMP PAINT-6 IN	194,500.00	LF
0490	06530	PAVE STRIPING REMOVAL-4 IN	1,178.00	LF

MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0495	06531	PAVE STRIPING REMOVAL-6 IN	27,974.00	LF
0500	06542	PAVE STRIPING-THERMO-6 IN W	43,368.00	LF
0505	06543	PAVE STRIPING-THERMO-6 IN Y	31,024.00	LF
0510	06546	PAVE STRIPING-THERMO-12 IN W	4,018.00	LF
0515	06547	PAVE STRIPING-THERMO-12 IN Y	399.00	LF
0520	06550	PAVE STRIPING-TEMP REM TAPE-W	5,670.00	LF
0525	06551	PAVE STRIPING-TEMP REM TAPE-Y	27,613.00	LF
0530	06568	PAVE MARKING-THERMO STOP BAR-24IN	162.00	LF
0535	06569	PAVE MARKING-THERMO CROSS-HATCH	2,619.00	SQFT
0540	06573	PAVE MARKING-THERMO STR ARROW	4.00	EACH
0545	06574	PAVE MARKING-THERMO CURV ARROW	30.00	EACH
0550	06585	PAVEMENT MARKER TY IVA-MW TEMP	300.00	EACH
0555	06586	PAVEMENT MARKER TY IVA-MY TEMP	300.00	EACH
0560	06600	REMOVE PAVEMENT MARKER TYPE V	1,135.00	EACH
0565	06610	INLAID PAVEMENT MARKER-MW	636.00	EACH
0570	06611	INLAID PAVEMENT MARKER-MY	292.00	EACH
0575	06613	INLAID PAVEMENT MARKER-B W/R	78.00	EACH
0580	06614	INLAID PAVEMENT MARKER-B Y/R	48.00	EACH
0585	08003	FOUNDATION PREPARATION	1.00	LS
0590	08018	RETAINING WALL	3,600.00	SQFT
0600	08912	CRASH CUSHION TY 6 CLASS T TL3	4.00	EACH
0605	10020NS	FUEL ADJUSTMENT	102,385.00	DOLL
0610	10030NS	ASPHALT ADJUSTMENT	240,409.00	DOLL
0615	15094	S MANHOLE ADJUST TO GRADE	1.00	EACH
0625	20191ED	OBJECT MARKER TY 3	4.00	EACH
0630	20257NC	SITE PREPARATION	1.00	LS
0635	20259ED	TEMPORARY MEDIAN CROSSOVER	2.00	EACH
0640	20411ED	LAW ENFORCEMENT OFFICER	400.00	hour
0645	20432ES112	REMOVE CRASH CUSHION	11.00	EACH
0650	20521NS719	REMOVE BRIDGE END CONNECTOR	35.00	EACH
0655	20550ND	SAWCUT PAVEMENT	26,057.00	LF
0660	21590EN	SOUND BARRIER WALL	72,846.00	SQFT
0665	22045NN	FLUME INLET TY 2-MOD	1.00	EACH
0670	22520EN	PAVE MARKING-THERMO YIELD BAR-36 IN	144.00	LF
0675	22880ED	BARRIER WALL TRANSITION	73.00	LF
0680	23148EN	END ANCHORS	2.00	EACH
0685	23158ES505	DETECTABLE WARNINGS	122.00	SQFT
0690	23253ES717	PAVE MARK TY 1 TAPE CROSS-HATCH	172.00	SQFT
0695	23496EC	MEDIAN CROSSOVER REMOVAL	2.00	EACH
0700	23607EC	PAVE MARK THERMO-LANE REDUCTION ARROW	3.00	EACH
0705	23875NC	REMOVE THERMOPLASTIC ARROWS	2.00	EACH
0710	23979EC	CRASH CUSHION TY 6 CLASS C TL3	1.00	EACH
0715	24255EC	REMOVE CABLE GUARDRAIL BARRIER SYSTEM	10,217.00	LF
0720	24679ED	PAVE MARK THERMO CHEVRON	392.00	SQFT
0725	24689EC	PAVE MARK THERMO-WRONG WAY ARROW	10.00	EACH
0730	24843EC	VIBRATING WIRE PIEZOMETER	2.00	EACH
0735	24880EC	REMOVE PAVEMENT MARKER	544.00	EACH
0740	24899EC	PAVE MARKING-THERMO ELONG ROUTE SHIELD	10.00	EACH
0745	25078ED	THRIE BEAM GUARDRAIL TRANSITION TL-3	18.00	EACH

MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0750	26146ES717	PAVE MARK TY 1 TAPE LANE REDUCTION ARROW	1.00	EACH
0755	26166ES717	PAVE MARK TY 1 TAPE CHEVRON	132.00	SQFT
0760	26236EC	THRIE BEAM BULLNOSE TERMINAL	1.00	EACH
0765	26237EC	CONNECTED ARROW PANEL	8.00	MONT
0770	26240EC	PAVE STRIPE-WET REF CONT TAPE-6 IN W	2,279.00	LF
0775	26241EC	PAVE STRIPE-WET REF CONT TAPE-6 IN Y	1,650.00	LF
0780	26242EC	PAVE STRIPE-WET REF CONT TAPE-12 IN W	607.00	LF
0785	26248EC	ELECTRONIC DELIVERY MGMT SYSTEM - AGG	1.00	LS
0790	26248EC	ELECTRONIC DELIVERY MGMT SYSTEM - AGG	1.00	LS
0795	00521	STORM SEWER PIPE-15 IN	1,475.00	LF
0800	00522	STORM SEWER PIPE-18 IN	2,146.00	LF
0805	00524	STORM SEWER PIPE-24 IN	53.00	LF
0810	01204	PIPE CULVERT HEADWALL-18 IN	1.00	EACH
0815	01208	PIPE CULVERT HEADWALL-24 IN	1.00	EACH
0820	01310	REMOVE PIPE	219.00	LF
0825	01443	SLOPED AND PARALLEL HEADWALL-15 IN	1.00	EACH
0830	01480	CURB BOX INLET TYPE B	1.00	EACH
0835	01605	CONC MED BARR BOX INLET TY B1 TL5 56	3.00	EACH
0840	01623	CONC MED BARR BOX INLET TY B1 TL5 56	9.00	EACH
0845	01624	CONC MED BARR BOX INLET TY B2 TL5 56	32.00	EACH
0850	01626	CONC MED BARR BOX INLET TY A2 TL5 56	4.00	EACH
0855	01626	CONC MED BARR BOX INLET TY A2 TL5 56 - (MODIFIED)	1.00	EACH
0860	01718	REMOVE INLET	31.00	EACH
0865	02607	FABRIC-GEOTEXTILE CLASS 2 FOR PIPE	5,096.00	SQYD
0870	02625	REMOVE HEADWALL	6.00	EACH
0875	02690	SAFELOADING	35.00	CUYD
0880	08100	CONCRETE-CLASS A	25.00	CUYD
0885	21799EN	BORE AND JACK PIPE-24 IN	56.00	LF
0890	23126EN	BORE AND JACK PIPE-18 IN	71.00	LF
0895	24814EC	PIPELINE INSPECTION	1,957.00	LF
0900	01643	JUNCTION BOX-24 IN	4.00	EACH
0905	02231	STRUCTURE GRANULAR BACKFILL	158.20	CUYD
0910	03299	ARMORED EDGE FOR CONCRETE	58.50	LF
0915	04797	CONDUIT-3 IN	287.00	LF
0920	08003	FOUNDATION PREPARATION	1.00	LS
0925	08014	REINF CONC SLOPE WALL-4 IN	210.00	SQYD
0930	08033	TEST PILES	290.00	LF
0935	08052	PILES-STEEL HP14X117	1,764.00	LF
0940	08095	PILE POINTS-14 IN	32.00	EACH
0945	08100	CONCRETE-CLASS A	142.40	CUYD
0950	08104	CONCRETE-CLASS AA	221.90	CUYD
0955	08150	STEEL REINFORCEMENT	18,938.00	LB
0960	08151	STEEL REINFORCEMENT-EPOXY COATED	64,335.00	LB
0965	08301	REMOVE SUPERSTRUCTURE	1.00	LS
0970	08669	PRECAST PC BOX BEAM SB21	550.30	LF
0975	20391NS835	ELECTRICAL JUNCTION BOX TYPE A	4.00	EACH
0980	23378EC	CONCRETE SEALING	7,580.00	SQFT
0985	23744EC	EPOXY INJECTION CRACK REPAIR	4.00	LF
0990	26233EC	MOBILIZATION FOR CONCRETE SURF TREATMENT	1.00	LS

MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0995	01643	JUNCTION BOX-24 IN	6.00	EACH
1000	02231	STRUCTURE GRANULAR BACKFILL	848.00	CUYD
1005	02403	REMOVE CONCRETE MASONRY	278.00	CUYD
1010	03299	ARMORED EDGE FOR CONCRETE	221.50	LF
1015	08003	FOUNDATION PREPARATION	1.00	LS
1020	08019	CYCLOPEAN STONE RIP RAP	504.00	TON
1025	08033	TEST PILES	659.00	LF
1030	08051	PILES-STEEL HP14X89	3,822.00	LF
1035	08095	PILE POINTS-14 IN	44.00	EACH
1040	08100	CONCRETE-CLASS A	735.90	CUYD
1045	08104	CONCRETE-CLASS AA	1,215.10	CUYD
1050	08130	MECHANICAL REINF COUPLER #5	80.00	EACH
1055	08135	MECHANICAL REINF COUPLER #10	64.00	EACH
1060	08150	STEEL REINFORCEMENT	91,599.00	LB
1065	08151	STEEL REINFORCEMENT-EPOXY COATED	327,278.00	LB
1070	08301	REMOVE SUPERSTRUCTURE	1.00	LS
1075	08634	PRECAST PC I BEAM TYPE 4	2,878.00	LF
1080	20391NS835	ELECTRICAL JUNCTION BOX TYPE A - BRIDGE OVER BEARGRASS CREEK (LUMP SUM)	4.00	EACH
1085	22585NN	MICROPILE PROOF TEST	2.00	EACH
1090	23378EC	CONCRETE SEALING	73,769.00	SQFT
1095	23813EC	DECK DRAIN	40.00	EACH
1100	24006EC	MICROPILE VERIFICATION TEST	1.00	EACH
1105	24179EC	MECHANICAL REINF COUPLER #4-EPOXY COATED	1,964.00	EACH
1110	24902EC	PVC CONDUIT-3 IN-SCHEDULE 80	492.00	LF
1115	25028ED	RAIL SYSTEM SINGLE SLOPE - 40 IN	492.00	LF
1120	25034ED	MICROPILE BOND ZONE	12.00	EACH
1125	26141EC	GALVANIC ANODE	552.00	EACH
1130	26209EC	MICROPILES-9 5/8 IN-COMMON	1,544.00	LF
1135	26210EC	MICROPILES-9 5/8 IN-SOLID ROCK	60.00	LF
1140	01643	JUNCTION BOX-24 IN	6.00	EACH
1145	02231	STRUCTURE GRANULAR BACKFILL	229.60	CUYD
1150	03299	ARMORED EDGE FOR CONCRETE	69.10	LF
1155	04797	CONDUIT-3 IN	549.00	LF
1160	08003	FOUNDATION PREPARATION	1.00	LS
1165	08020	CRUSHED AGGREGATE SLOPE PROT	271.00	TON
1170	08033	TEST PILES	439.00	LF
1175	08052	PILES-STEEL HP14X117	2,684.00	LF
1180	08095	PILE POINTS-14 IN	32.00	EACH
1185	08100	CONCRETE-CLASS A	187.30	CUYD
1190	08104	CONCRETE-CLASS AA	449.20	CUYD
1195	08141	MECHANICAL REINF COUPLER #6 EPOXY COATED	1,662.00	EACH
1200	08150	STEEL REINFORCEMENT	27,812.00	LB
1205	08151	STEEL REINFORCEMENT-EPOXY COATED	160,270.00	LB
1210	08301	REMOVE SUPERSTRUCTURE	1.00	LS
1215	20391NS835	ELECTRICAL JUNCTION BOX TYPE A	4.00	EACH
1220	22585NN	MICROPILE PROOF TEST	2.00	EACH
1225	23378EC	CONCRETE SEALING	14,477.00	SQFT
1230	23744EC	EPOXY INJECTION CRACK REPAIR	30.00	LF
1235	23981EC	PPC I-BEAM TYPE HN 42-49	1,085.30	LF

MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
1240	24006EC	MICROPILE VERIFICATION TEST	1.00	EACH
1245	25034ED	MICROPILE BOND ZONE	4.00	EACH
1250	26209EC	MICROPILES-9 5/8 IN-COMMON	496.00	LF
1255	26210EC	MICROPILES-9 5/8 IN-SOLID ROCK	16.00	LF
1260	26233EC	MOBILIZATION FOR CONCRETE SURF TREATMENT	1.00	LS
1265	01643	JUNCTION BOX-24 IN	4.00	EACH
1270	02231	STRUCTURE GRANULAR BACKFILL	196.00	CUYD
1275	03299	ARMORED EDGE FOR CONCRETE	58.90	LF
1280	08003	FOUNDATION PREPARATION	1.00	LS
1285	08020	CRUSHED AGGREGATE SLOPE PROT	199.00	TON
1290	08033	TEST PILES	424.00	LF
1295	08052	PILES-STEEL HP14X117	2,656.00	LF
1300	08095	PILE POINTS-14 IN	32.00	EACH
1305	08100	CONCRETE-CLASS A	158.80	CUYD
1310	08104	CONCRETE-CLASS AA	224.90	CUYD
1315	08150	STEEL REINFORCEMENT	22,168.00	LB
1320	08151	STEEL REINFORCEMENT-EPOXY COATED	47,686.00	LB
1325	08301	REMOVE SUPERSTRUCTURE	1.00	LS
1330	08669	PRECAST PC BOX BEAM SB21	632.70	LF
1335	20391NS835	ELECTRICAL JUNCTION BOX TYPE A	4.00	EACH
1340	22146EN	CONCRETE PATCHING REPAIR	203.00	SQFT
1345	23378EC	CONCRETE SEALING	8,731.00	SQFT
1350	23744EC	EPOXY INJECTION CRACK REPAIR	16.00	LF
1355	24902EC	PVC CONDUIT-3 IN-SCHEDULE 80	318.00	LF
1360	26233EC	MOBILIZATION FOR CONCRETE SURF TREATMENT	1.00	LS
1365	04903	REFERENCE MARKER	24.00	EACH
1370	04904	BARRIER MOUNTING BRACKET	12.00	EACH
1375	06400	GMSS GALV STEEL TYPE A	3,191.00	LB
1380	06405	SBM ALUMINUM PANEL SIGNS	3,038.00	SQFT
1385	06406	SBM ALUM SHEET SIGNS .080 IN	301.80	SQFT
1390	06407	SBM ALUM SHEET SIGNS .125 IN	1,005.90	SQFT
1395	06410	STEEL POST TYPE 1	1,654.00	LF
1400	06412	STEEL POST MILE MARKERS	4.00	EACH
1405	06415	OSS GALV STEEL CANTILEVER	4.00	EACH
1410	06441	GMSS GALV STEEL TYPE C	598.00	LB
1415	06449	REM OVERHEAD SIGN SUPPORT STR	5.00	EACH
1420	06450	REM OVERHEAD STRUC CONC BASE	5.00	EACH
1425	06451	REMOVE SIGN SUPPORT BEAM	10.00	EACH
1430	06475	OSS GALV STEEL 60 FT TRUSS	2.00	EACH
1435	06490	CLASS A CONCRETE FOR SIGNS	186.30	CUYD
1440	06491	STEEL REINFORCEMENT FOR SIGNS	14,708.00	LB
1445	20418ED	REMOVE & RELOCATE SIGNS	4.00	EACH
1450	20419ND	ROADWAY CROSS SECTION	19.00	EACH
1455	20912ND	BARRIER WALL POST	5.00	EACH
1460	21373ND	REMOVE SIGN	14.00	EACH
1465	21596ND	GMSS TYPE D	29.00	EACH
1470	24631EC	BARCODE SIGN INVENTORY	148.00	EACH
1475	04820	TRENCHING AND BACKFILLING	70.00	LF
1480	04845	CABLE-NO. 14/7C	2,850.00	LF
1485	04884	ANCHOR	1.00	EACH

MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
1490	04886	MESSENGER-15400 LB	600.00	LF
1495	04932	INSTALL STEEL STRAIN POLE	4.00	EACH
1500	04953	TEMP RELOCATION OF SIGNAL HEAD	6.00	EACH
1505	20093NS835	INSTALL PEDESTRIAN HEAD-LED	4.00	EACH
1510	20188NS835	INSTALL LED SIGNAL-3 SECTION	8.00	EACH
1515	20266ES835	INSTALL LED SIGNAL- 4 SECTION	1.00	EACH
1520	21743NN	INSTALL PEDESTRIAN DETECTOR	4.00	EACH
1525	23068NN	REMOVE & REINSTALL COORDINATING UNIT	1.00	EACH
1530	23157EN	TRAFFIC SIGNAL POLE BASE	18.00	CUYD
1535	23222EC	INSTALL SIGNAL PEDESTAL	2.00	EACH
1540	23235EC	INSTALL PEDESTAL POST	2.00	EACH
1545	24528ED	TETHER WIRE - SIGNALS(LUMP SUM)	600.00	LF
1550	24900EC	PVC CONDUIT-1 1/4 IN-SCHEDULE 80	70.00	LF
1555	24908EC	INSTALL SIGNAL CONTROLLER-TY ATC	1.00	EACH
1560	24955ED	REMOVE SIGNAL EQUIPMENT	1.00	EACH
1565	26119EC	INSTALL RADAR PRESENCE DETECTOR TYPE A	3.00	EACH
1570	02187	SITE PREPARATION	1.00	EACH
1575	04740	POLE BASE	1.00	EACH
1580	04795	CONDUIT-2 IN	525.00	LF
1585	04811	ELECTRICAL JUNCTION BOX TYPE B	1.00	EACH
1590	04820	TRENCHING AND BACKFILLING	525.00	LF
1595	04835	WIRE-NO. 4	1,050.00	LF
1600	08100	CONCRETE-CLASS A	39.70	CUYD
1605	08150	STEEL REINFORCEMENT	2,779.00	LB
1610	21059ND	CCTV ASSEMBLY	2.00	EACH
1615	21066ND	MODEL 336 ENCLOSURE	2.00	EACH
1620	21069ND	SURGE DEVICE 120 VOLT	2.00	EACH
1625	21071ND	DATA SURGE DEVICE	2.00	EACH
1630	21072ND	VIDEO SURGE DEVICE	2.00	EACH
1635	23842EC	POLE 50 FT-INSTALL	1.00	EACH
1640	23945EC	INST VARIABLE MESSAGE SIGN-EXIST TRUSS	1.00	EACH
1645	04710	POLE 80 FT MTG HT HIGH MAST	4.00	EACH
1650	04780	FUSED CONNECTOR KIT	18.00	EACH
1655	04800	MARKER	10.00	EACH
1660	04820	TRENCHING AND BACKFILLING	3,575.00	LF
1665	04940	REMOVE LIGHTING	1.00	LS
1670	20391NS835	ELECTRICAL JUNCTION BOX TYPE A	11.00	EACH
1675	20392NS835	ELECTRICAL JUNCTION BOX TYPE C	2.00	EACH
1680	20410ED	MAINTAIN LIGHTING	1.00	LS
1685	21543EN	BORE AND JACK CONDUIT	1,240.00	LF
1690	23161EN	POLE BASE-HIGH MAST	20.00	CUYD
1695	23778EC	WIRE-NO. 10	2,025.00	LF
1700	24749EC	HIGH MAST LED LUMINAIRE	16.00	EACH
1705	24851EC	CABLE-NO. 10/3C DUCTED - LIGHTING - ZORN INTERCHANGE ONLY	5,415.00	LF
1710	24901EC	PVC CONDUIT-2 IN-SCHEDULE 80	610.00	LF
1715	24902EC	PVC CONDUIT-3 IN-SCHEDULE 80	1,050.00	LF
1720	02568	MOBILIZATION	1.00	LS
1725	02569	DEMOBILIZATION	1.00	LS
1730	04793	CONDUIT-1 1/4 IN	80.00	LF

MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
1735	04795	CONDUIT-2 IN	20.00	LF
1740	04811	ELECTRICAL JUNCTION BOX TYPE B	2.00	EACH
1745	04820	TRENCHING AND BACKFILLING	90.00	LF
1750	04829	PIEZOELECTRIC SENSOR	6.00	EACH
1755	04830	LOOP WIRE	2,650.00	LF
1760	04895	LOOP SAW SLOT AND FILL	600.00	LF
1765	20359NN	GALVANIZED STEEL CABINET	2.00	EACH
1770	20360ES818	WOOD POST	4.00	EACH
1775	02223	GRANULAR EMBANKMENT	469.00	CUYD
1780	08003	FOUNDATION PREPARATION	1.00	LS
1785	08100	CONCRETE-CLASS A	1,181.30	CUYD
1790	08150	STEEL REINFORCEMENT	210,141.00	LB
1795	02742	TRAINEE PAYMENT REIMBURSEMENT - CEMENT MASON	1,400.00	HOURL

CONTRACT ID: 251032

NHPP 0711(096)

DE05600712524

I-71 BRIDGE DECK OVERLAY ON THE I-64 EB RAMP 611 FROM MP 0.4 TO MP 0.571 BRIDGE DECK OVERLAY, A DISTANCE OF .17 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	02060	PCC PAVEMENT DIAMOND GRINDING	5,618.00	SQYD
0010	02650	MAINTAIN & CONTROL TRAFFIC - LBGT 056 071 000-001	1.00	LS
0015	06511	PAVE STRIPING-TEMP PAINT-6 IN	2,257.00	LF
0020	06542	PAVE STRIPING-THERMO-6 IN W	1,354.00	LF
0025	06543	PAVE STRIPING-THERMO-6 IN Y	903.00	LF
0030	23229EC	HIGH FRICTION SURFACE TREATMENT	11,236.00	SQYD
0035	02569	DEMOBILIZATION	1.00	LS

251032

Section: 0001 - SIGNALS

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	04820		TRENCHING AND BACKFILLING	70.00	LF		\$	
0020	04845		CABLE-NO. 14/7C	2,850.00	LF		\$	
0030	04884		ANCHOR	1.00	EACH		\$	
0040	04886		MESSENGER-15400 LB	600.00	LF		\$	
0050	04932		INSTALL STEEL STRAIN POLE	4.00	EACH		\$	
0060	04953		TEMP RELOCATION OF SIGNAL HEAD	6.00	EACH		\$	
0070	20093NS835		INSTALL PEDESTRIAN HEAD-LED	4.00	EACH		\$	
0080	20188NS835		INSTALL LED SIGNAL-3 SECTION	8.00	EACH		\$	
0090	20266ES835		INSTALL LED SIGNAL- 4 SECTION	1.00	EACH		\$	
0100	21743NN		INSTALL PEDESTRIAN DETECTOR	4.00	EACH		\$	
0110	23068NN		REMOVE & REINSTALL COORDINATING UNIT	1.00	EACH		\$	
0120	23157EN		TRAFFIC SIGNAL POLE BASE	18.00	CUYD		\$	
0130	23222EC		INSTALL SIGNAL PEDESTAL	2.00	EACH		\$	
0140	23235EC		INSTALL PEDESTAL POST	2.00	EACH		\$	
0150	24528ED		TETHER WIRE SIGNALS(LUMP SUM)	600.00	LF		\$	
0160	24900EC		PVC CONDUIT-1 1/4 IN-SCHEDULE 80	70.00	LF		\$	
0170	24908EC		INSTALL SIGNAL CONTROLLER-TY ATC	1.00	EACH		\$	
0180	24955ED		REMOVE SIGNAL EQUIPMENT	1.00	EACH		\$	
0190	26119EC		INSTALL RADAR PRESENCE DETECTOR TYPE A	3.00	EACH		\$	

Section: 0002 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0200	00001		DGA BASE	18,476.00	TON		\$	
0210	00008		CEMENT STABILIZED ROADBED	46,659.00	SQYD		\$	
0220	00018		DRAINAGE BLANKET-TYPE II-ASPH	14,145.00	TON		\$	
0230	00100		ASPHALT SEAL AGGREGATE	201.00	TON		\$	
0240	00103		ASPHALT SEAL COAT	24.00	TON		\$	
0250	00190		LEVELING & WEDGING PG64-22	416.00	TON		\$	
0260	00194		LEVELING & WEDGING PG76-22	2,727.00	TON		\$	
0270	00214		CL3 ASPH BASE 1.00D PG64-22	8,709.00	TON		\$	
0280	00217		CL4 ASPH BASE 1.00D PG64-22	15,068.00	TON		\$	
0290	00219		CL4 ASPH BASE 1.00D PG76-22	9,480.00	TON		\$	
0300	00339		CL3 ASPH SURF 0.38D PG64-22	2,537.00	TON		\$	
0310	00342		CL4 ASPH SURF 0.38A PG76-22	11,512.00	TON		\$	
0320	00358		ASPHALT CURING SEAL	48.00	TON		\$	
0330	02542		CEMENT	938.00	TON		\$	
0340	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0350	02677		ASPHALT PAVE MILLING & TEXTURING	10,390.00	TON		\$	
0360	02702		SAND FOR BLOTTER	117.00	TON		\$	
0370	02720		SIDEWALK-4 IN CONCRETE	1,110.00	SQYD		\$	

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0380	20071EC		JOINT ADHESIVE	106,876.00	LF		\$	
0390	21289ED		LONGITUDINAL EDGE KEY	24,912.00	LF		\$	
0400	24970EC		ASPHALT MATERIAL FOR TACK NON-TRACKING	188.00	TON		\$	

Section: 0003 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0410	00078		CRUSHED AGGREGATE SIZE NO 2	16,033.00	TON		\$	
0420	01001		PERFORATED PIPE-6 IN	11,290.00	LF		\$	
0430	01011		NON-PERFORATED PIPE-6 IN	424.00	LF		\$	
0440	01033		PERF PIPE HEADWALL TY 4-6 IN	1.00	EACH		\$	
0450	01690		FLUME INLET TYPE 1	3.00	EACH		\$	
0460	01691		FLUME INLET TYPE 2	17.00	EACH		\$	
0470	01877		SPECIAL HEADER CURB	3,276.00	LF		\$	
0480	01885		LIP HEADER CURB	165.00	LF		\$	
0490	01890		ISLAND HEADER CURB TYPE 1	547.00	LF		\$	
0500	01903		REMOVE CONCRETE ROLL CURB	66.00	LF		\$	
0510	01978		CONC MEDIAN BARRIER TYPE A TL5 56 IN	10,231.00	LF		\$	
0520	01978		CONC MEDIAN BARRIER TYPE A TL5 56 IN MODIFIED	185.00	LF		\$	
0530	01982		DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL WHITE	405.00	EACH		\$	
0540	01983		DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL YELLOW	10.00	EACH		\$	
0550	01985		DELINEATOR FOR BARRIER - YELLOW	200.00	EACH		\$	
0560	01987		DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	4.00	EACH		\$	
0570	02003		RELOCATE TEMP CONC BARRIER	18,200.00	LF		\$	
0580	02014		BARRICADE-TYPE III	8.00	EACH		\$	
0590	02060		PCC PAVEMENT DIAMOND GRINDING	5,618.00	SQYD		\$	
0600	02070		JPC PAVEMENT-12 IN	166.00	SQYD		\$	
0610	02076		JPC PAVEMENT-7 IN	121.00	SQYD		\$	
0620	02091		REMOVE PAVEMENT	8,556.00	SQYD		\$	
0630	02159		TEMP DITCH	6,944.00	LF		\$	
0640	02160		CLEAN TEMP DITCH	3,472.00	LF		\$	
0650	02200		ROADWAY EXCAVATION	40,364.00	CUYD		\$	
0660	02223		GRANULAR EMBANKMENT	978.00	CUYD		\$	
0670	02242		WATER	2,400.00	MGAL		\$	
0680	02262		FENCE-WOVEN WIRE TYPE 1	25,112.00	LF		\$	
0690	02289		DOUBLE VEHICULAR WOVEN WIRE GATE	1.00	EACH		\$	
0700	02351		GUARDRAIL-STEEL W BEAM-S FACE	28,412.50	LF		\$	
0710	02367		GUARDRAIL END TREATMENT TYPE 1	7.00	EACH		\$	
0720	02370		GUARDRAIL END TREATMENT TYPE 2M	10.00	EACH		\$	
0730	02371		GUARDRAIL END TREATMENT TYPE 7	1.00	EACH		\$	
0740	02381		REMOVE GUARDRAIL	31,898.00	LF		\$	
0750	02395		REMOVE GUARDRAIL TERMINAL SECT	2.00	EACH		\$	
0760	02396		REMOVE GUARDRAIL END TREATMENT	9.00	EACH		\$	
0770	02483		CHANNEL LINING CLASS II	644.00	TON		\$	

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0780	02545		CLEARING AND GRUBBING 47.6 ACRES	1.00	LS		\$	
0790	02555		CONCRETE-CLASS B (REVISED 10-21-25)	52.52	CUYD		\$	
0800	02562		TEMPORARY SIGNS	1,450.00	SQFT		\$	
0810	02565		OBJECT MARKER TYPE 2	12.00	EACH		\$	
0820	02570		PROJECT CPM SCHEDULE	1.00	LS		\$	
0830	02602		FABRIC-GEOTEXTILE CLASS 1	5,372.00	SQYD		\$	
0840	02612		HANDRAIL-TYPE A-2	80.00	LF		\$	
0850	02650		MAINTAIN & CONTROL TRAFFIC LBGT 056 071 000-001	1.00	LS		\$	
0860	02650		MAINTAIN & CONTROL TRAFFIC NHPP 0711(096)	1.00	LS		\$	
0870	02671		PORTABLE CHANGEABLE MESSAGE SIGN	10.00	EACH		\$	
0880	02697		EDGE LINE RUMBLE STRIPS	42,724.00	LF		\$	
0890	02701		TEMP SILT FENCE	6,944.00	LF		\$	
0900	02703		SILT TRAP TYPE A	48.00	EACH		\$	
0910	02704		SILT TRAP TYPE B	48.00	EACH		\$	
0920	02705		SILT TRAP TYPE C	48.00	EACH		\$	
0930	02706		CLEAN SILT TRAP TYPE A	48.00	EACH		\$	
0940	02707		CLEAN SILT TRAP TYPE B	48.00	EACH		\$	
0950	02708		CLEAN SILT TRAP TYPE C	48.00	EACH		\$	
0960	02726		STAKING	1.00	LS		\$	
0970	02731		REMOVE STRUCTURE STA 547+57 NB BRIDGE OVER ABANDONED R/R	1.00	LS		\$	
0980	02731		REMOVE STRUCTURE STA 547+57 SB BRIDGE OVER ABANDONED R/R	1.00	LS		\$	
0990	02898		RELOCATE CRASH CUSHION	7.00	EACH		\$	
1000	02998		MASONRY COATING	11,547.00	SQYD		\$	
1010	03171		CONC BARRIER WALL TYPE 9T	26,920.00	LF		\$	
1020	05950		EROSION CONTROL BLANKET	10,642.00	SQYD		\$	
1030	05952		TEMP MULCH	154,357.00	SQYD		\$	
1040	05953		TEMP SEEDING AND PROTECTION	115,265.00	SQYD		\$	
1050	05963		INITIAL FERTILIZER	4.90	TON		\$	
1060	05964		MAINTENANCE FERTILIZER	2.90	TON		\$	
1070	05985		SEEDING AND PROTECTION	95,011.00	SQYD		\$	
1080	05992		AGRICULTURAL LIMESTONE	58.90	TON		\$	
1090	06404		FLEXIBLE DELINEATOR POST-M/Y	55.00	EACH		\$	
1100	06510		PAVE STRIPING-TEMP PAINT-4 IN	1,178.00	LF		\$	
1110	06511		PAVE STRIPING-TEMP PAINT-6 IN	196,757.00	LF		\$	
1120	06530		PAVE STRIPING REMOVAL-4 IN	1,178.00	LF		\$	
1130	06531		PAVE STRIPING REMOVAL-6 IN	27,974.00	LF		\$	
1140	06542		PAVE STRIPING-THERMO-6 IN W	44,722.00	LF		\$	
1150	06543		PAVE STRIPING-THERMO-6 IN Y	31,927.00	LF		\$	
1160	06546		PAVE STRIPING-THERMO-12 IN W	4,018.00	LF		\$	
1170	06547		PAVE STRIPING-THERMO-12 IN Y	399.00	LF		\$	
1180	06550		PAVE STRIPING-TEMP REM TAPE-W	5,670.00	LF		\$	
1190	06551		PAVE STRIPING-TEMP REM TAPE-Y	27,613.00	LF		\$	
1200	06568		PAVE MARKING-THERMO STOP BAR-24IN	162.00	LF		\$	
1210	06569		PAVE MARKING-THERMO CROSS-HATCH	2,619.00	SQFT		\$	

Report Date 10/21/25

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1220	06573		PAVE MARKING-THERMO STR ARROW	4.00	EACH		\$	
1230	06574		PAVE MARKING-THERMO CURV ARROW	30.00	EACH		\$	
1240	06585		PAVEMENT MARKER TY IVA-MW TEMP	300.00	EACH		\$	
1250	06586		PAVEMENT MARKER TY IVA-MY TEMP	300.00	EACH		\$	
1260	06600		REMOVE PAVEMENT MARKER TYPE V	1,135.00	EACH		\$	
1270	06610		INLAID PAVEMENT MARKER-MW	636.00	EACH		\$	
1280	06611		INLAID PAVEMENT MARKER-MY	292.00	EACH		\$	
1290	06613		INLAID PAVEMENT MARKER-B W/R	78.00	EACH		\$	
1300	06614		INLAID PAVEMENT MARKER-B Y/R	48.00	EACH		\$	
1310	08003		FOUNDATION PREPARATION	1.00	LS		\$	
1320	08018		RETAINING WALL	3,600.00	SQFT		\$	
1340	08912		CRASH CUSHION TY 6 CLASS T TL3	4.00	EACH		\$	
1350	10020NS		FUEL ADJUSTMENT	102,385.00	DOLL	\$1.00	\$	\$102,385.00
1360	10030NS		ASPHALT ADJUSTMENT	240,409.00	DOLL	\$1.00	\$	\$240,409.00
1370	15094		S MANHOLE ADJUST TO GRADE	1.00	EACH		\$	
							\$	
1390	20191ED		OBJECT MARKER TY 3	4.00	EACH		\$	
1400	20257NC		SITE PREPARATION	1.00	LS		\$	
1410	20259ED		TEMPORARY MEDIAN CROSSOVER	2.00	EACH		\$	
1420	20411ED		LAW ENFORCEMENT OFFICER	400.00	HOURL		\$	
1430	20432ES112		REMOVE CRASH CUSHION	11.00	EACH		\$	
1440	20521NS719		REMOVE BRIDGE END CONNECTOR	35.00	EACH		\$	
1450	20550ND		SAWCUT PAVEMENT	26,057.00	LF		\$	
1460	21590EN		SOUND BARRIER WALL	72,846.00	SQFT		\$	
1470	22045NN		FLUME INLET TY 2-MOD	1.00	EACH		\$	
1480	22520EN		PAVE MARKING-THERMO YIELD BAR-36 IN	144.00	LF		\$	
1490	22880ED		BARRIER WALL TRANSITION	73.00	LF		\$	
1500	23148EN		END ANCHORS	2.00	EACH		\$	
1510	23158ES505		DETECTABLE WARNINGS	122.00	SQFT		\$	
1520	23229EC		HIGH FRICTION SURFACE TREATMENT	11,236.00	SQYD		\$	
1530	23253ES717		PAVE MARK TY 1 TAPE CROSS-HATCH	172.00	SQFT		\$	
1540	23496EC		MEDIAN CROSSOVER REMOVAL	2.00	EACH		\$	
			PAVE MARK THERMO-LANE REDUCTION ARROW	3.00	EACH		\$	
1550	23607EC		REMOVE THERMOPLASTIC ARROWS	2.00	EACH		\$	
1570	23979EC		CRASH CUSHION TY 6 CLASS C TL3	1.00	EACH		\$	
1580	24255EC		REMOVE CABLE GUARDRAIL BARRIER SYSTEM	10,217.00	LF		\$	
1590	24679ED		PAVE MARK THERMO CHEVRON	392.00	SQFT		\$	
1600	24689EC		PAVE MARK THERMO-WRONG WAY ARROW	10.00	EACH		\$	
1610	24843EC		VIBRATING WIRE PIEZOMETER	2.00	EACH		\$	
1620	24880EC		REMOVE PAVEMENT MARKER	544.00	EACH		\$	
1630	24899EC		PAVE MARKING-THERMO ELONG ROUTE SHIELD	10.00	EACH		\$	
1640	25078ED		THRIE BEAM GUARDRAIL TRANSITION TL-3	18.00	EACH		\$	
1650	26146ES717		PAVE MARK TY 1 TAPE LANE REDUCTION ARROW	1.00	EACH		\$	
1660	26166ES717		PAVE MARK TY 1 TAPE CHEVRON	132.00	SQFT		\$	
1670	26236EC		THRIE BEAM BULLNOSE TERMINAL	1.00	EACH		\$	
1680	26237EC		CONNECTED ARROW PANEL	8.00	MONT		\$	
1690	26240EC		PAVE STRIPE-WET REF CONT TAPE-6 IN W	2,279.00	LF		\$	

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1700	26241EC		PAVE STRIPE-WET REF CONT TAPE-6 IN Y	1,650.00	LF		\$	
1710	26242EC		PAVE STRIPE-WET REF CONT TAPE-12 IN W	607.00	LF		\$	
1720	26248EC		ELECTRONIC DELIVERY MGMT SYSTEM - AGG	1.00	LS		\$	

Section: 0004 - DRAINAGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1730	00521		STORM SEWER PIPE-15 IN	1,475.00	LF		\$	
1740	00522		STORM SEWER PIPE-18 IN	2,146.00	LF		\$	
1750	00524		STORM SEWER PIPE-24 IN	53.00	LF		\$	
1760	01204		PIPE CULVERT HEADWALL-18 IN	1.00	EACH		\$	
1770	01208		PIPE CULVERT HEADWALL-24 IN	1.00	EACH		\$	
1780	01310		REMOVE PIPE	219.00	LF		\$	
1790	01443		SLOPED AND PARALLEL HEADWALL-15 IN	1.00	EACH		\$	
1800	01480		CURB BOX INLET TYPE B	1.00	EACH		\$	
1810	01605		CONC MED BARR BOX INLET TY B1 TL5 56	3.00	EACH		\$	
1820	01623		CONC MED BARR BOX INLET TY B1 TL5 56	9.00	EACH		\$	
1830	01624		CONC MED BARR BOX INLET TY B2 TL5 56	32.00	EACH		\$	
1840	01626		CONC MED BARR BOX INLET TY A2 TL5 56	4.00	EACH		\$	
1850	01626		CONC MED BARR BOX INLET TY A2 TL5 56 (MODIFIED)	1.00	EACH		\$	
1860	01718		REMOVE INLET	31.00	EACH		\$	
1870	02607		FABRIC-GEOTEXTILE CLASS 2 FOR PIPE	5,096.00	SQYD	\$2.00	\$	\$10,192.00
1880	02625		REMOVE HEADWALL	6.00	EACH		\$	
1890	02690		SAFELOADING	35.00	CUYD		\$	
1900	08100		CONCRETE-CLASS A	25.00	CUYD		\$	
1910	21799EN		BORE AND JACK PIPE-24 IN	56.00	LF		\$	
1920	23126EN		BORE AND JACK PIPE-18 IN	71.00	LF		\$	
1930	24814EC		PIPELINE INSPECTION	1,957.00	LF		\$	

Section: 0005 - BRIDGE- CULVERT- I-71 OVER ABANDONED RR

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1940	02223		GRANULAR EMBANKMENT	469.00	CUYD		\$	
1950	08003		FOUNDATION PREPARATION	1.00	LS		\$	
1960	08100		CONCRETE-CLASS A	1,181.30	CUYD		\$	
1970	08150		STEEL REINFORCEMENT	210,141.00	LB		\$	

Section: 0006 - BRIDGE - OVER EDITH ROAD

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1980	01643		JUNCTION BOX-24 IN	4.00	EACH		\$	
1990	02231		STRUCTURE GRANULAR BACKFILL	158.20	CUYD		\$	
2000	03299		ARMORED EDGE FOR CONCRETE	58.50	LF		\$	
2010	04797		CONDUIT-3 IN	287.00	LF		\$	

Report Date 10/21/25

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
2020	08003		FOUNDATION PREPARATION	1.00	LS		\$	
2030	08014		REINF CONC SLOPE WALL-4 IN	210.00	SQYD		\$	
2040	08033		TEST PILES	290.00	LF		\$	
2050	08052		PILES-STEEL HP14X117	1,764.00	LF		\$	
2060	08095		PILE POINTS-14 IN	32.00	EACH		\$	
2070	08100		CONCRETE-CLASS A	142.40	CUYD		\$	
2080	08104		CONCRETE-CLASS AA	221.90	CUYD		\$	
2090	08150		STEEL REINFORCEMENT	18,938.00	LB		\$	
2100	08151		STEEL REINFORCEMENT-EPOXY COATED	64,335.00	LB		\$	
2110	08301		REMOVE SUPERSTRUCTURE	1.00	LS		\$	
2120	08669		PRECAST PC BOX BEAM SB21	550.30	LF		\$	
2130	20391NS835		ELECTRICAL JUNCTION BOX TYPE A	4.00	EACH		\$	
2140	23378EC		CONCRETE SEALING	7,580.00	SQFT		\$	
2150	23744EC		EPOXY INJECTION CRACK REPAIR	4.00	LF		\$	
2160	26233EC		MOBILIZATION FOR CONCRETE SURF TREATMENT	1.00	LS		\$	

Section: 0007 - BRIDGE- OVER BEARGRASS CREEK

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
2170	01643		JUNCTION BOX-24 IN	6.00	EACH		\$	
2180	02231		STRUCTURE GRANULAR BACKFILL	848.00	CUYD		\$	
2190	02403		REMOVE CONCRETE MASONRY	278.00	CUYD		\$	
2200	03299		ARMORED EDGE FOR CONCRETE	221.50	LF		\$	
2210	08003		FOUNDATION PREPARATION	1.00	LS		\$	
2220	08019		CYCLOPEAN STONE RIP RAP	504.00	TON		\$	
2230	08033		TEST PILES	659.00	LF		\$	
2240	08051		PILES-STEEL HP14X89	3,822.00	LF		\$	
2250	08095		PILE POINTS-14 IN	44.00	EACH		\$	
2260	08100		CONCRETE-CLASS A	735.90	CUYD		\$	
2270	08104		CONCRETE-CLASS AA	1,215.10	CUYD		\$	
2280	08130		MECHANICAL REINF COUPLER #5	80.00	EACH		\$	
2290	08135		MECHANICAL REINF COUPLER #10	64.00	EACH		\$	
2300	08150		STEEL REINFORCEMENT	91,599.00	LB		\$	
2310	08151		STEEL REINFORCEMENT-EPOXY COATED	327,278.00	LB		\$	
2320	08301		REMOVE SUPERSTRUCTURE	1.00	LS		\$	
2330	08634		PRECAST PC I BEAM TYPE 4	2,878.00	LF		\$	
2340	20391NS835		ELECTRICAL JUNCTION BOX TYPE A BRIDGE OVER BEARGRASS CREEK (LUMP SUM)	4.00	EACH		\$	
2350	22585NN		MICROPILE PROOF TEST	2.00	EACH		\$	
2360	23378EC		CONCRETE SEALING	73,769.00	SQFT		\$	
2370	23813EC		DECK DRAIN	40.00	EACH		\$	
2380	24006EC		MICROPILE VERIFICATION TEST	1.00	EACH		\$	
2390	24179EC		MECHANICAL REINF COUPLER #4-EPOXY COATED	1,964.00	EACH		\$	
2400	24902EC		PVC CONDUIT-3 IN-SCHEDULE 80	492.00	LF		\$	
2410	25028ED		RAIL SYSTEM SINGLE SLOPE - 40 IN	492.00	LF		\$	
2420	25034ED		MICROPILE BOND ZONE	12.00	EACH		\$	

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
2430	26141EC		GALVANIC ANODE	552.00	EACH		\$	
2440	26209EC		MICROPILES-9 5/8 IN-COMMON	1,544.00	LF		\$	
2450	26210EC		MICROPILES-9 5/8 IN-SOLID ROCK	60.00	LF		\$	

Section: 0008 - BRIDGE - OVER ZORN AVENUE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
2460	01643		JUNCTION BOX-24 IN	6.00	EACH		\$	
2470	02231		STRUCTURE GRANULAR BACKFILL	229.60	CUYD		\$	
2480	03299		ARMORED EDGE FOR CONCRETE	69.10	LF		\$	
2490	04797		CONDUIT-3 IN	549.00	LF		\$	
2500	08003		FOUNDATION PREPARATION	1.00	LS		\$	
2510	08020		CRUSHED AGGREGATE SLOPE PROT	271.00	TON		\$	
2520	08033		TEST PILES	439.00	LF		\$	
2530	08052		PILES-STEEL HP14X117	2,684.00	LF		\$	
2540	08095		PILE POINTS-14 IN	32.00	EACH		\$	
2550	08100		CONCRETE-CLASS A	187.30	CUYD		\$	
2560	08104		CONCRETE-CLASS AA	449.20	CUYD		\$	
2570	08141		MECHANICAL REINF COUPLER #6 EPOXY COATED	1,662.00	EACH		\$	
2580	08150		STEEL REINFORCEMENT	27,812.00	LB		\$	
2590	08151		STEEL REINFORCEMENT-EPOXY COATED	160,270.00	LB		\$	
2600	08301		REMOVE SUPERSTRUCTURE	1.00	LS		\$	
2610	20391NS835		ELECTRICAL JUNCTION BOX TYPE A	4.00	EACH		\$	
2620	22585NN		MICROPILE PROOF TEST	2.00	EACH		\$	
2630	23378EC		CONCRETE SEALING	14,477.00	SQFT		\$	
2640	23744EC		EPOXY INJECTION CRACK REPAIR	30.00	LF		\$	
2650	23981EC		PPC I-BEAM TYPE HN 42-49	1,085.30	LF		\$	
2660	24006EC		MICROPILE VERIFICATION TEST	1.00	EACH		\$	
2670	25034ED		MICROPILE BOND ZONE	4.00	EACH		\$	
2680	26209EC		MICROPILES-9 5/8 IN-COMMON	496.00	LF		\$	
2690	26210EC		MICROPILES-9 5/8 IN-SOLID ROCK	16.00	LF		\$	
2700	26233EC		MOBILIZATION FOR CONCRETE SURF TREATMENT	1.00	LS		\$	

Section: 0009 - BRIDGE - OVER MOCKINGBIRD VALLEY ROAD

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
2710	01643		JUNCTION BOX-24 IN	4.00	EACH		\$	
2720	02231		STRUCTURE GRANULAR BACKFILL	196.00	CUYD		\$	
2730	03299		ARMORED EDGE FOR CONCRETE	58.90	LF		\$	
2740	08003		FOUNDATION PREPARATION	1.00	LS		\$	
2750	08020		CRUSHED AGGREGATE SLOPE PROT	199.00	TON		\$	
2760	08033		TEST PILES	424.00	LF		\$	
2770	08052		PILES-STEEL HP14X117	2,656.00	LF		\$	
2780	08095		PILE POINTS-14 IN	32.00	EACH		\$	
2790	08100		CONCRETE-CLASS A	158.80	CUYD		\$	
2800	08104		CONCRETE-CLASS AA	224.90	CUYD		\$	

Report Date 10/21/25

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
2810	08150		STEEL REINFORCEMENT	22,168.00	LB		\$	
2820	08151		STEEL REINFORCEMENT-EPOXY COATED	47,686.00	LB		\$	
2830	08301		REMOVE SUPERSTRUCTURE	1.00	LS		\$	
2840	08669		PRECAST PC BOX BEAM SB21	632.70	LF		\$	
2850	20391NS835		ELECTRICAL JUNCTION BOX TYPE A	4.00	EACH		\$	
2860	22146EN		CONCRETE PATCHING REPAIR	203.00	SQFT		\$	
2870	23378EC		CONCRETE SEALING	8,731.00	SQFT		\$	
2880	23744EC		EPOXY INJECTION CRACK REPAIR	16.00	LF		\$	
2890	24902EC		PVC CONDUIT-3 IN-SCHEDULE 80	318.00	LF		\$	
2900	26233EC		MOBILIZATION FOR CONCRETE SURF TREATMENT	1.00	LS		\$	

Section: 0010 - SIGNING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
2910	04903		REFERENCE MARKER	24.00	EACH		\$	
2920	04904		BARRIER MOUNTING BRACKET	12.00	EACH		\$	
2930	06400		GMSS GALV STEEL TYPE A	3,191.00	LB		\$	
2940	06405		SBM ALUMINUM PANEL SIGNS	3,038.00	SQFT		\$	
2950	06406		SBM ALUM SHEET SIGNS .080 IN	301.80	SQFT		\$	
2960	06407		SBM ALUM SHEET SIGNS .125 IN	1,005.90	SQFT		\$	
2970	06410		STEEL POST TYPE 1	1,654.00	LF		\$	
2980	06412		STEEL POST MILE MARKERS	4.00	EACH		\$	
2990	06415		OSS GALV STEEL CANTILEVER	4.00	EACH		\$	
3000	06441		GMSS GALV STEEL TYPE C	598.00	LB		\$	
3010	06449		REM OVERHEAD SIGN SUPPORT STR	5.00	EACH		\$	
3020	06450		REM OVERHEAD STRUC CONC BASE	5.00	EACH		\$	
3030	06451		REMOVE SIGN SUPPORT BEAM	10.00	EACH		\$	
3040	06475		OSS GALV STEEL 60 FT TRUSS	2.00	EACH		\$	
3050	06490		CLASS A CONCRETE FOR SIGNS	186.30	CUYD		\$	
3060	06491		STEEL REINFORCEMENT FOR SIGNS	14,708.00	LB		\$	
3070	20418ED		REMOVE & RELOCATE SIGNS	4.00	EACH		\$	
3080	20419ND		ROADWAY CROSS SECTION	19.00	EACH		\$	
3090	20912ND		BARRIER WALL POST	5.00	EACH		\$	
3100	21373ND		REMOVE SIGN	14.00	EACH		\$	
3110	21596ND		GMSS TYPE D	29.00	EACH		\$	
3120	24631EC		BARCODE SIGN INVENTORY	148.00	EACH		\$	

Section: 0011 - LIGHTING - ZORN AVE INTERCHANGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
3130	04710		POLE 80 FT MTG HT HIGH MAST	4.00	EACH		\$	
3140	04780		FUSED CONNECTOR KIT	18.00	EACH		\$	
3150	04800		MARKER	10.00	EACH		\$	
3160	04820		TRENCHING AND BACKFILLING	3,575.00	LF		\$	
3170	04940		REMOVE LIGHTING	1.00	LS		\$	
3180	20391NS835		ELECTRICAL JUNCTION BOX TYPE A	11.00	EACH		\$	

Report Date 10/21/25

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
3190	20392NS835		ELECTRICAL JUNCTION BOX TYPE C	2.00	EACH		\$	
3200	20410ED		MAINTAIN LIGHTING	1.00	LS		\$	
3210	21543EN		BORE AND JACK CONDUIT	1,240.00	LF		\$	
3220	23161EN		POLE BASE-HIGH MAST	20.00	CUYD		\$	
3230	23778EC		WIRE-NO. 10	2,025.00	LF		\$	
3240	24749EC		HIGH MAST LED LUMINAIRE	16.00	EACH		\$	
3250	24851EC		CABLE-NO. 10/3C DUCTED LIGHTING - ZORN INTERCHANGE ONLY	5,415.00	LF		\$	
3260	24901EC		PVC CONDUIT-2 IN-SCHEDULE 80	610.00	LF		\$	
3270	24902EC		PVC CONDUIT-3 IN-SCHEDULE 80	1,050.00	LF		\$	

Section: 0012 - TRAFFIC LOOPS

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
3280	04793		CONDUIT-1 1/4 IN	80.00	LF		\$	
3290	04795		CONDUIT-2 IN	20.00	LF		\$	
3300	04811		ELECTRICAL JUNCTION BOX TYPE B	2.00	EACH		\$	
3310	04820		TRENCHING AND BACKFILLING	90.00	LF		\$	
3320	04829		PIEZOELECTRIC SENSOR	6.00	EACH		\$	
3330	04830		LOOP WIRE	2,650.00	LF		\$	
3340	04895		LOOP SAW SLOT AND FILL	600.00	LF		\$	
3350	20359NN		GALVANIZED STEEL CABINET	2.00	EACH		\$	
3360	20360ES818		WOOD POST	4.00	EACH		\$	

Section: 0013 - INTELLIGENT TRANSPORTATION SYSTEMS

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
3370	02187		SITE PREPARATION	1.00	EACH		\$	
3380	04740		POLE BASE	1.00	EACH		\$	
3390	04795		CONDUIT-2 IN	525.00	LF		\$	
3400	04811		ELECTRICAL JUNCTION BOX TYPE B	1.00	EACH		\$	
3410	04820		TRENCHING AND BACKFILLING	525.00	LF		\$	
3420	04835		WIRE-NO. 4	1,050.00	LF		\$	
3430	08100		CONCRETE-CLASS A	39.70	CUYD		\$	
3440	08150		STEEL REINFORCEMENT	2,779.00	LB		\$	
3450	21059ND		CCTV ASSEMBLY	2.00	EACH		\$	
3460	21066ND		MODEL 336 ENCLOSURE	2.00	EACH		\$	
3470	21069ND		SURGE DEVICE 120 VOLT	2.00	EACH		\$	
3480	21071ND		DATA SURGE DEVICE	2.00	EACH		\$	
3490	21072ND		VIDEO SURGE DEVICE	2.00	EACH		\$	
3500	23842EC		POLE 50 FT-INSTALL	1.00	EACH		\$	
3510	23945EC		INST VARIABLE MESSAGE SIGN-EXIST TRUSS	1.00	EACH		\$	

Section: 0014 - TRAINEES

Report Date 10/21/25

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
3520	02742		TRAINEE PAYMENT REIMBURSEMENT CEMENT MASON	1,400.00	HOUR		\$	

Section: 0015 - DEMOBILIZATION &/OR MOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
3530	02568		MOBILIZATION	1.00	LS		\$	
3540	02569		DEMOBILIZATION	1.00	LS		\$	