



**Matthew G. Bevin**  
Governor

**COMMONWEALTH OF KENTUCKY  
TRANSPORTATION CABINET**  
Frankfort, Kentucky 40622  
[www.transportation.ky.gov/](http://www.transportation.ky.gov/)

**Greg Thomas**  
Secretary

March 16, 2019

CALL NO. 300  
CONTRACT ID NO. 191023  
ADDENDUM # 1

Subject: LAUREL COUNTY, FD04 SPP 063 0363 009-010  
Letting May 24, 2019

(1) Revised - Utilities and Rail Certification Note - Pages 16-18 of 272

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.  
Director  
Division of Construction Procurement

RM:mr  
Enclosures



An Equal Opportunity Employer M/F/D

## UTILITIES AND RAIL CERTIFICATION NOTE

**LAUREL COUNTY  
FD04 063 80639 01U  
RECONSTRUCT KY363  
11-147.1**

**GENERAL PROJECT NOTE ON UTILITY PROTECTION**

Exercise care when operating near overhead lines and/or digging near underground utilities.

**NOTE: DO NOT DISTURB THE FOLLOWING UTILITIES LOCATED WITHIN THE PROJECT DISTURB LIMITS**

Delta Gas has an existing 1" plastic service line to P108 @ approx. RT STA 121+84 that will be crossed by the proposed water & sewer lines. Use extreme caution in this area & do not disturb the gas line.

**\*The Contractor is fully responsible for protection of all utilities listed above\***

**THE FOLLOWING COMPANIES ARE RELOCATING/ADJUSTING THEIR UTILITIES WITHIN THE PROJECT LIMITS AND WILL BE COMPLETE PRIOR TO CONSTRUCTION**

N/A

**THE FOLLOWING COMPANIES HAVE FACILITIES TO BE RELOCATED/ADJUSTED BY THE COMPANY OR THE COMPANY'S SUBCONTRACTOR AND IS TO BE COORDINATED WITH THE ROAD CONTRACT**

KU, Windstream, & Spectrum are relocating their overhead lines to be clear of construction. Relocation plans can be provided, however, poles as relocated in the field will supersede respective locations shown on plans.

Delta Gas is relocating their gas lines to be clear of roadwork. Relocation plans will be provided.

**The above activities will not conflict with construction of the new detention basin & may be ongoing until August 1<sup>st</sup>, 2019. The completion date of the roadwork has been set accordingly & the Contractor should plan work with this utility involvement in mind. As such, absolutely no claims for delays due to the above listed work during this time period will be accepted.**

The Department will consider submission of a bid as the Contractor's agreement to not make any claims for monetary compensation due to delays or other conditions created by the operations of the companies listed above. Working days will not be charged for those days on which work on these facilities is delayed after the above date, as provided in the current edition of the KY Standard Specifications for Road and Bridge Construction. Should a difference of opinion arise as to the rights of the Contractor and others working within the limits of, or adjacent to the project, the KYTC Resident Engineer will decide as to the respective rights of the various parties involved in order to assure the completion of the Department's work in general harmony and in a satisfactory manner, and his decision shall be final and binding upon the Contractor.

## UTILITIES AND RAIL CERTIFICATION NOTE

**LAUREL COUNTY  
FD04 063 80639 01U  
RECONSTRUCT KY363  
11-147.1**

**THE FOLLOWING COMPANIES HAVE FACILITIES TO BE RELOCATED/ADJUSTED BY THE ROAD CONTRACTOR AS INCLUDED IN THIS CONTRACT**

Relocation of the London Utility Commission’s water & sewer lines is to be performed as part of the road contract. This will include a reconnection of Lowe’s fire service line. Plans & specifications have been included as part of the contract proposal, as well as a General Utility Note specifying approved contractors. Coordinate the relocation with Mr. Steve Baker.

**THE FOLLOWING RAIL COMPANIES HAVE FACILITIES IN CONJUNCTION WITH THIS PROJECT AS NOTED**

- No Rail Involved**       **Minimal Rail Involved (See Below)**       **Rail Involved (See Below)**

**UNDERGROUND FACILITY DAMAGE PROTECTION – BEFORE YOU DIG**

The contractor shall make every effort to protect underground facilities from damage as prescribed in the Underground Facility Damage Protection Act of 1994, Kentucky Revised Statute KRS 367.4901 to 367.4917. It is the contractor’s responsibility to determine and take steps necessary to be in compliance with federal and state damage prevention directives. The contractor is instructed to contact KY 811 for the location of existing underground utilities. Contact shall be made a minimum of two (2) and no more than ten (10) business days prior to excavation.

The contractor shall submit Excavation Locate Requests to the Kentucky Contact Center (KY 811) via web ticket entry. The submission of this request does not relieve the contractor from the responsibility of contacting non-member facility owners, whom are to be contacted through their individual Protection Notification Center. It may be necessary for the contractor to contact the County Court Clerk to determine what utility companies have facilities in the area. Non-compliance with these directives can result in the enforcement of penalties.

**SPECIAL CAUTION NOTE – PROTECTION OF UTILITIES**

The contractor will be responsible for contacting all utility facility owners on the subject project to coordinate his activities. The contractor will coordinate his activities to minimize and, where possible, avoid conflicts with utility facilities. Due to the nature of the work proposed, it is unlikely to conflict with the existing utilities beyond minor facility adjustments. Where conflicts with utility facilities are unavoidable, the contractor will coordinate any necessary relocation work with the facility owner and Resident Engineer. The Kentucky Transportation Cabinet maintains the right to remove or alter portions of this contract if a utility conflict occurs.

## UTILITIES AND RAIL CERTIFICATION NOTE

**LAUREL COUNTY  
FD04 063 80639 01U  
RECONSTRUCT KY363  
11-147.1**

The utility facilities as noted in the previous section(s) have been determined using data garnered by varied means and with varying degrees of accuracy: from the facility owners, a result of S.U.E., field inspections, and/or reviews of record drawings. The facilities defined may not be inclusive of all utilities in the project scope and are not Level A quality, unless specified as such. It is the contractor's responsibility to verify all utilities and their respective locations before excavating.

*Please Note: The information presented in this Utility Note is informational in nature and the information contained herein is not guaranteed.*

### AREA UTILITIES CONTACT LIST

<u>Utility Company/Agency</u>	<u>Contact Name</u>	<u>Contact Information</u>
<b>London Utility Commission</b>	<b>Steve Baker</b>	<b>606-813-8480</b>
<b>Eclipse Engineers (for LUC)</b>	<b>Alan Robinson</b>	<b>606-451-0959</b>
<b>KU</b>	<b>David Laun</b>	<b>606-864-2821</b>
<b>Windstream</b>	<b>Bryan Reed</b>	<b>606-878-3263</b>
<b>Spectrum</b>	<b>Lee Bowlin</b>	<b>606-271-2504</b>
<b>Delta Gas</b>	<b>Brent Means</b>	<b>859-744-6171x1134</b>