



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

October 20, 2025

CALL NO. 303
CONTRACT ID NO. 252964
ADDENDUM # 1

Subject: FRANKLIN COUNTY FD04 037 0060 008-009
Letting October 23, 2025

1. Revised Special Note - Page 28-29 of 53

Proposal revisions are available at
<http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:so
Enclosures

SPECIAL NOTE FOR TRAFFIC CONTROL ON BRIDGE REPAIR CONTRACTS

1. TRAFFIC CONTROL GENERAL

Except as provided herein, traffic shall be maintained in accordance with the Standard Specifications (current edition), Section 112. Except for the roadway and traffic control bid items listed, all items of work necessary to maintain and control traffic will be paid at the lump sum bid price to "Maintain and Control Traffic". Contrary to Section 106.01, traffic control devices used on this project may be new or used in new condition, at the beginning of the work and maintained in like new condition until completion of the work.

2. TRAFFIC COORDINATOR

Furnish a Traffic Coordinator as per Section 112. The Traffic Coordinator shall inspect the project maintenance of traffic, at least three times daily, or as directed by the Engineer, during the Contractor's operations and at any time a lane closure is in place. The personnel shall have access on the project to a radio or telephone to be used in case of emergencies or accidents. The Traffic Coordinator shall report all incidents throughout the work zone to the Engineer on the project. The Contractor shall furnish the name and telephone number where the Traffic Coordinator can be contacted at all times.

3. SIGNS

Contrary to Section 112.04.02, only long-term signs (sign intended to be continuously in place for more than 3 days) will be measured for payment; short term signs (signs intended to be left in place for 3 days or less) will not be measured for payment but will be incidental to Maintain and Control Traffic.

The contractor is to install warning signs for wide loads in advance of the bridge under the direction of the Engineer. The Department will not measure installation, maintenance, or removal for payment, and will consider these incidentals to Maintain and Control Traffic.

4. STRUCTURE CLOSURE FOR BRIDGE DECK RESTORATION ITEMS.

The structure shall be closed for all bridge deck restoration items. **4 - 57 hour periods** will be allotted for the closure from **8:00 PM Friday through 5:00 AM Monday June 5-August 1, 2026**. All work must be completed and traffic restored during this time period. **A penalty of \$1,000.00 per hour will be assessed when the allotted time is exceeded.** The Contractor shall submit a detour and phasing plan for approval at the preconstruction conference. All items for the detour shall be considered incidental to the lump sum bid for Maintain and Control Traffic.

5. LANE AND SIDEWALK CLOSURES FOR CONCRETE HANDRAIL REPAIR ITEMS.

2 Ten (10) foot lanes shall be maintain for all Concrete Handrail Repair. Lane and side walk closures will be permitted **June 5-August 1, 2026** and must be removed when not working. Barricades must be in place to protect pedestrian traffic if the Concrete Handrail is left open when the sidewalk closure is removed. Concrete Handrail Repair items may be completed in the structure closure time allotments for bridge deck restoration items also. At least one sidewalk is to remain open to pedestrians at all times.

6. CONCRETE PATCHING, FRP WRAP AND PREVENTIVE MAINTENANCE ITEMS.

No lane closures will be permitted for Concrete Patching, FRP Wrap and Preventive Maintenance items. All work must be performed below the structure.

7. MEASUREMENT.

Temporary Signs:

The Cabinet will measure the quantity by “Square Feet”.

Maintain and Control Traffic:

The Cabinet will measure the quantity by “Lump Sum”.

Barricade Type III, Lane Closure and Portable Changeable Message Sign

The Cabinet will measure quantity by “Each”.

8. PAYMENT.

Temporary Signs (02562):

Payment at the contract unit price for “Square Feet” is full compensation for all items to complete this work as specified.

Maintain and Control Traffic (02650):

Payment at the contract unit price for “Lump Sum” is full compensation for all items to complete this work as specified.

Barricade Type III (02014), Lane Closure), (02653) and Portable Changeable Message Sign (02671):

Payment at the contract unit price “Each” is full compensation for all items to complete this work as specified.