



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Rebecca Goodman
SECRETARY

May 13, 2026

CALL NO. 303
CONTRACT ID NO. 261109
ADDENDUM # 1

Subject: Madison County, FD04 076 NEW ROUTE
Letting May 21, 2026

- (1) Revised - Proposal Bid Items - Pages 127-129 of 129
- (2) Revised - Plan Sheet R2B

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

PROPOSAL BID ITEMS

Report Date 5/13/26

261109

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00001		DGA BASE	5,714.00	TON		\$	
0020	00008		CEMENT STABILIZED ROADBED	16,487.00	SQYD		\$	
0030	00020		TRAFFIC BOUND BASE	81.00	TON		\$	
0040	00190		LEVELING & WEDGING PG64-22	356.00	TON		\$	
0050	00212		CL2 ASPH BASE 1.00D PG64-22	6,041.00	TON		\$	
0060	00221		CL2 ASPH BASE 0.75D PG64-22	27.00	TON		\$	
0070	00301		CL2 ASPH SURF 0.38D PG64-22	1,406.00	TON		\$	
0080	00356		ASPHALT MATERIAL FOR TACK	13.28	TON		\$	
0090	00358		ASPHALT CURING SEAL	48.40	TON		\$	
0100	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0110	02677		ASPHALT PAVE MILLING & TEXTURING	287.00	TON		\$	
0120	02702		SAND FOR BLOTTER	48.00	TON		\$	

Section: 0002 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0130	01310		REMOVE PIPE	1,309.00	LF		\$	
0140	01810		STANDARD CURB AND GUTTER	6,990.00	LF		\$	
0150	01982		DELINEATOR FOR G/R MONO DIRECTIONAL WHITE	21.00	EACH		\$	
0160	02014		BARRICADE-TYPE III	4.00	EACH		\$	
0170	02091		REMOVE PAVEMENT	1,436.00	SQYD		\$	
0180	02159		TEMP DITCH	2,166.00	LF		\$	
0190	02160		CLEAN TEMP DITCH	1,083.00	LF		\$	
0200	02230		EMBANKMENT IN PLACE	41,831.00	CUYD		\$	
0210	02242		WATER	41.00	MGAL		\$	
0220	02351		G/R-W BEAM-S FACE TL-3	1,000.00	LF		\$	
0230	02367		G/R END TREATMENT TYPE 1	5.00	EACH		\$	
0240	02370		G/R END TREATMENT TYPE 2M	5.00	EACH		\$	
0250	02429		RIGHT-OF-WAY MONUMENT TYPE 1	25.00	EACH		\$	
0260	02432		WITNESS POST	25.00	EACH		\$	
0270	02483		CHANNEL LINING CLASS II	1,623.00	TON		\$	
0280	02484		CHANNEL LINING CLASS III	65.00	TON		\$	
0285	02542		CEMENT (ADDED 5-13-26)	7,254.00	TON		\$	
0290	02545		CLEARING AND GRUBBING APPROXIMATELY 10 ACRES	1.00	LS		\$	
0300	02562		TEMPORARY SIGNS	275.00	SQFT		\$	
0310	02585		EDGE KEY	71.90	LF		\$	
0320	02625		REMOVE HEADWALL	4.00	EACH		\$	
0330	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0340	02653		LANE CLOSURE	1.00	EACH		\$	
0350	02701		TEMP SILT FENCE	2,166.00	LF		\$	
0360	02703		SILT TRAP TYPE A	10.00	EACH		\$	

PROPOSAL BID ITEMS

Report Date 5/13/26

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0370	02704		SILT TRAP TYPE B	10.00	EACH		\$	
0380	02705		SILT TRAP TYPE C	10.00	EACH		\$	
0390	02706		CLEAN SILT TRAP TYPE A	10.00	EACH		\$	
0400	02707		CLEAN SILT TRAP TYPE B	10.00	EACH		\$	
0410	02708		CLEAN SILT TRAP TYPE C	10.00	EACH		\$	
0420	02726		STAKING	1.00	LS		\$	
0430	04935		TEMP SIGNAL APPROX STA. 52+50	1.00	LS		\$	
0440	04935		TEMP SIGNAL APPROX STA. 56+00	1.00	LS		\$	
0450	05952		TEMP MULCH	33,300.00	SQYD		\$	
0460	05953		TEMP SEEDING AND PROTECTION	24,675.00	SQYD		\$	
0470	05963		INITIAL FERTILIZER	1.00	TON		\$	
0480	05964		MAINTENANCE FERTILIZER	1.60	TON		\$	
0490	05985		SEEDING AND PROTECTION	30,910.00	SQYD		\$	
0500	05992		AGRICULTURAL LIMESTONE	30.00	TON		\$	
0510	06406		SBM ALUM SHEET SIGNS .080 IN	61.00	SQFT		\$	
0520	06410		STEEL POST TYPE 1	100.00	LF		\$	
0530	06514		PAVE STRIPING-PERM PAINT-4 IN	8,102.00	LF		\$	
0540	06568		PAVE MARKING-THERMO STOP BAR-24IN	24.00	LF		\$	
0550	06574		PAVE MARKING-THERMO CURV ARROW	2.00	EACH		\$	
0560	08002		STRUCTURE EXCAV-SOLID ROCK	13.00	CUYD		\$	
0570	08003		FOUNDATION PREPARATION	1.00	LS		\$	
0580	08100		CONCRETE-CLASS A	363.50	CUYD		\$	
0590	08150		STEEL REINFORCEMENT	66,881.00	LB		\$	
0600	10020NS		FUEL ADJUSTMENT	19,784.00	DOLL	\$1.00	\$	\$19,784.00
0610	10030NS		ASPHALT ADJUSTMENT	30,270.00	DOLL	\$1.00	\$	\$30,270.00
0620	20191ED		OBJECT MARKER TY 3	5.00	EACH		\$	
0630	24631EC		BARCODE SIGN INVENTORY	8.00	EACH		\$	
0640	24814EC		PIPELINE INSPECTION	5,203.00	LF		\$	
0650	26248EC		ELECTRONIC DELIVERY MGMT SYSTEM - AGG	1.00	LS		\$	

Section: 0003 - DRAINAGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0660	00440		ENTRANCE PIPE-15 IN	93.00	LF		\$	
0670	00443		ENTRANCE PIPE-24 IN	60.00	LF		\$	
0680	00462		CULVERT PIPE-18 IN	34.00	LF		\$	
0690	00521		STORM SEWER PIPE-15 IN	3,925.00	LF		\$	
0700	00522		STORM SEWER PIPE-18 IN	602.00	LF		\$	
0710	00523		STORM SEWER PIPE-21 IN	41.00	LF		\$	
0720	00524		STORM SEWER PIPE-24 IN	248.00	LF		\$	
0730	01000		PERFORATED PIPE-4 IN	168.00	LF		\$	
0740	01010		NON-PERFORATED PIPE-4 IN	32.00	LF		\$	
0750	01024		PERF PIPE HEADWALL TY 2-4 IN	1.00	EACH		\$	
0760	01028		PERF PIPE HEADWALL TY 3-4 IN	2.00	EACH		\$	
0770	01450		S & F BOX INLET-OUTLET-18 IN	2.00	EACH		\$	
0780	01451		S & F BOX INLET-OUTLET-24 IN	5.00	EACH		\$	

MADISON COUNTY
 FD04 076 NEW ROUTE
 261109

PROPOSAL BID ITEMS

Report Date 5/13/26

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0790	01456		CURB BOX INLET TYPE A	39.00	EACH		\$	

Section: 0004 - DEMOBILIZATION &/OR MOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0800	02568		MOBILIZATION	1.00	LS		\$	
0810	02569		DEMOBILIZATION	1.00	LS		\$	

GENERAL SUMMARY

PAVING SUMMARY

ITEM	DESCRIPTION	UNIT	Mainline	Menelaus Rd	Total
1310	REMOVE PIPE	LF	1,309		1,309
1810	STANDARD CURB AND GUTTER	LF	6,990		6,990
1982	DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL WHITE	EACH	21		21
2014	BARRICADE-TYPE III (5)	EACH		4	4
2091	REMOVE PAVEMENT	SO YD	1,436		1,436
2159	TEMP DITCH	LF	2,075	91	2,166
2160	CLEAN TEMP DITCH	LF	1,038	45	1,083
2230	EMBANKMENT IN PLACE	CU YD	41,479	352	41,831
2242	WATER	MGAL	39	2	41
2351	GUARDRAIL-STEEL W BEAM-S FACE	LF	1,000		1,000
2367	GUARDRAIL END TREATMENT TYPE 1	EACH	5		5
2370	GUARDRAIL END TREATMENT TYPE 2M	EACH	5		5
2429	RIGHT OF WAY MONUMENT TYPE 1	EACH	25		25
2432	WITNESS POST	EACH	25		25
2483	CHANNEL LINING CLASS II	TON	1,596	27	1,623
2484	CHANNEL LINING CLASS III	TON	65		65
2542	CEMENT	TONS	7,134	120	7,254
2545	CLEARING AND GRUBBING	LS	1		1
2562	TEMPORARY SIGNS (5)	SO FT		275	275
2568	MOBILIZATION	LS	1		1
2569	DEMOLITION	LS	1		1
2585	EDGE KEY	LF	54.5	17.4	71.9
2625	REMOVE HEADWALL	EACH	4		4
2650	MAINTAIN AND CONTROL TRAFFIC	LS	1		1
2653	LANE CLOSURE (5)	EACH		1	1
2701	TEMP SILT FENCE	LF	2,075	91	2,166
2703	SILT TRAP TYPE A	EACH	10		10
2704	SILT TRAP TYPE B	EACH	10		10
2705	SILT TRAP TYPE C	EACH	10		10
2706	CLEAN SILT TRAP TYPE A	EACH	10		10
2707	CLEAN SILT TRAP TYPE B	EACH	10		10
2708	CLEAN SILT TRAP TYPE C	EACH	10		10
2726	STAKING	LS	1		1
4935	TEMPORARY SIGNAL (5)	EACH	2		2
5952	TEMP MULCH	SO YD	33,300		33,300
5953	TEMP SEED AND PROTECT	SO YD	24,975		24,975
5963	INITIAL FERTILIZER	TONS	1		1
5964	MAINTENANCE FERTILIZER	TONS	1.60		1.60
5985	SEEDING AND PROTECTION	SO YD	30,910		30,910
5992	AGRICULTURAL LIMESTONE	TONS	30		30
6406	SBM ALUM SHEET SIGNS .080 IN (6)	SO FT	61		61
6410	STEEL POST TYPE 1 (6)	LF	100		100
6514	PAVE STRIPING-PERM PAINT-4 IN (WHITE)	LF	90		90
6514	PAVE STRIPING-PERM PAINT-4 IN (YELLOW)	LF	7,780	232	8,012
6568	PAVE MARKING-THERMO STOP BAR-24 IN	LF		24	24
6574	PAVE MARKING-THERMO CURVE ARROW	EACH	2		2
20191ED	OBJECT MARKER TY 3	EACH	5		5
24631EC	BARCODE SIGN INVENTORY (6)	EACH	8		8
24814EC	PIPELINE INSPECTION	LF	5,169	34	5,203

ITEM CODE	ITEM	UNIT	Mainline	Menelaus Rd	Approach	Entrances	Total
00001	DGA BASE	TON	5,576	86		52	5,714
00008	CEMENT STABILIZED ROADBED	SO YD	16,214	273			16,487
00020	TRAFFIC BOUND BASE	TON				81	81
00190	LEVELING & WEDGING PG64-22 (1) (2)	TON	168	188			356
00212	CL2 ASPH BASE 1.000 PG 64-22	TON	5,960	81			6,041
00221	CL2 ASPH BASE 0.750 PG 64-22	TON				27	27
00301	CL2 ASPH SURF 0.380 PG 64-22	TON	1,348	43		15	1,406
00356	ASPHALT MATERIAL FOR TACK	TON	13	0.19		0.09	13.28
00358	ASPHALT CURING SEAL	LS	1			0.40	48.40
02676	MOBILIZATION FOR MILLING AND TEXTURING						1
02677	ASPHALT PAVE MILLING & TEXTURIZING (3) (4)	TON	236	51			287
02702	SAND FOR BLOTTER	TON	47	0.68		0.33	48

PAVING AREAS

ITEM	Mainline	Menelaus Rd	LT STA 54+00 Entrance	Total
1.25" CL2 ASPH SURF 0.380 PG 64-22			216	216
1.50" CL2 ASPH SURF 0.380 PG 64-22	16,338	524		16,862
2.25" CL2 ASPH BASE 0.75B PG 64-22			219	219
3.00" CL2 ASPH BASE 1.00B PG 64-22	15,535	220		15,755
3.50" CL2 ASPH BASE 1.000 PG 64-22	15,560	233		15,793
4.00" DGA BASE			224	224
6.00" DGA BASE	16,164	248		16,412
8" CEMENT STABILIZED ROADBED	16,214	273		16,487
ASPHALT MATERIAL FOR TACK	31,095	453	219	31,767
LEVELING & WEDGING PG64-22	815	310		1,125

Earthwork Quantities
Mainline and Menelaus Rd
Com = 27,678
Emb* = 41,831

*TOTAL INCLUDES 645 CY FROM EMBANKMENT FOUNDATION BENCHES

NOTES

ALL ASPHALT MIXTURES SHALL BE ESTIMATED AT 110 LBS. PER SQ. YD. PER INCH OF DEPTH, UNLESS NOTED OTHERWISE.

ASPHALT CURING SEAL ESTIMATED AT 2 LBS PER SQ. YD

ASPHALT MATERIAL FOR TACK ESTIMATED AT 0.84 LBS PER SQ. YD

SAND FOR BLOTTER ESTIMATED AT 3 LBS PER SQ. YD

DISTURBED LIMITS = 10 ACRES

1 MAINLINE L&W BASED ON AN AVERAGE DEPTH: 17+00)

3 IN STA. 16+50 - 17+00)

4 IN STA. 55+00 - 58+00)

2 MENELAUS L&W BASED ON AN AVERAGE DEPTH OF 11 IN

3 MAINLINE MILLING BASED ON AN AVERAGE DEPTH: 16+30 - 17+00)

6 IN (STA. 55+00 - 58+00)

4 MENELAUS MILLING BASED ON AN AVERAGE DEPTH OF 3 IN

5 ITEMS FOR MAINTENANCE OF TRAFFIC PERMINT SIGNS

6 FOR CONSTRUCTION OF PERMINT SIGNS



GENERAL SUMMARY

PAVING SUMMARY

ITEM	DESCRIPTION	UNIT	Mainline	Menelaus Rd	Total
1310	REMOVE PIPE	LF	1,309		1,309
1810	STANDARD CURB AND GUTTER	LF	6,990		6,990
1982	DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL WHITE	EACH	21		21
2014	BARRICADE-TYPE III (5)	EACH		4	4
2091	REMOVE PAVEMENT	SO YD	1,436	1,436	1,436
2159	TEMP DITCH	LF	2,075	91	2,166
2160	CLEAN TEMP DITCH	LF	1,038	45	1,083
2230	EMBANKMENT IN PLACE	CU YD	41,479	352	41,831
2242	WATER	MGAL	39	2	41
2351	GUARDRAIL-STEEL W BEAM-S FACE	LF	1,000		1,000
2367	GUARDRAIL END TREATMENT TYPE 1	EACH	5		5
2370	GUARDRAIL END TREATMENT TYPE 2M	EACH	5		5
2429	RIGHT OF WAY MONUMENT TYPE 1	EACH	25		25
2432	WITNESS POST	EACH	25		25
2483	CHANNEL LINING CLASS II	TON	1,596	27	1,623
2484	CHANNEL LINING CLASS III	TON	65		65
2542	CEMENT	TONS	7,134	120	7,254
2543	CLEARING AND GRUBBING	LS			
2562	TEMPORARY SIGNS (5)	SO FT		275	275
2568	MOBILIZATION	LS	1		1
2569	DEMOBILIZATION	LS	1		1
2585	EDGE KEY	LF	54.5	17.4	71.9
2625	REMOVE HEADWALL	EACH	4		4
2650	MAINTAIN AND CONTROL TRAFFIC	LS	1		1
2653	LANE CLOSURE (5)	EACH		1	1
2701	TEMP SILT FENCE	LF	2,075	91	2,166
2703	SILT TRAP TYPE A	EACH	10		10
2704	SILT TRAP TYPE B	EACH	10		10
2705	SILT TRAP TYPE C	EACH	10		10
2706	CLEAN SILT TRAP TYPE A	EACH	10		10
2707	CLEAN SILT TRAP TYPE B	EACH	10		10
2708	CLEAN SILT TRAP TYPE C	EACH	10		10
2726	STAKING	LS	1		1
4935	TEMPORARY SIGNAL (5)	EACH	2		2
5952	TEMP MULCH	SO YD	33,300		33,300
5953	TEMP SEED AND PROTECT	SO YD	24,975		24,975
5963	INITIAL FERTILIZER	TONS	1		1
5964	MAINTENANCE FERTILIZER	TONS	1.60		1.60
5985	SEEDING AND PROTECTION	SO YD	30,910		30,910
5992	AGRICULTURAL LIMESTONE	TONS	30		30
6406	SBM ALUM SHEET SIGNS .080 IN (6)	SO FT	61		61
6410	STEEL POST TYPE 1 (6)	LF	100		100
6514	PAVE STRIPING-PERM PAINT-4 IN (WHITE)	LF	90		90
6514	PAVE STRIPING-PERM PAINT-4 IN (YELLOW)	LF	7,780	232	8,012
6568	PAVE MARKING-THERMO STOP BAR-24 IN	LF		24	24
6574	PAVE MARKING-THERMO CURVE ARROW	EACH	2		2
20191ED	OBJECT MARKER TY 3	EACH	5		5
24631EC	BARCODE SIGN INVENTORY (6)	EACH	8		8
24814EC	PIPELINE INSPECTION	LF	5,169	34	5,203

ITEM CODE	ITEM	UNIT	Mainline	Menelaus Rd	Approach	Entrances	Total
00001	DGA BASE	TON	5,576	86		52	5,714
00008	CEMENT STABILIZED ROADBED	SO YD	16,214	273			16,487
00020	TRAFFIC BOUND BASE	TON				81	81
00190	LEVELING & WEDGING PG64-22 (1) (2)	TON	168	188			356
00212	CL2 ASPH BASE 1.000 PG 64-22	TON	5,960	81			6,041
00221	CL2 ASPH BASE 0.750 PG 64-22	TON				27	27
00301	CL2 ASPH SURF 0.380 PG 64-22	TON	1,348	43		15	1,406
00356	ASPHALT MATERIAL FOR TACK	TON	13	0.19		0.09	13.28
00358	ASPHALT CURING SEAL	LS	47	1		0.40	48.40
02676	MOBILIZATION FOR MILLING AND TEXTURING		1				1
02677	ASPHALT PAVE MILLING & TEXTURIZING (3) (4)	TON	236	51			287
02702	SAND FOR BLOTTER	TON	47	0.68		0.33	48

PAVING AREAS

ITEM	Mainline	Menelaus Rd	LT STA 54+00	Total
1.25" CL2 ASPH SURF 0.380 PG 64-22			216	216
1.50" CL2 ASPH SURF 0.380 PG 64-22	16,338	524		16,862
2.25" CL2 ASPH BASE 0.75B PG 64-22			219	219
3.00" CL2 ASPH BASE 1.00B PG 64-22	15,535	220		15,755
3.50" CL2 ASPH BASE 1.000 PG 64-22	15,560	233		15,793
4.00" DGA BASE			224	224
6.00" DGA BASE	16,164	248		16,412
8" CEMENT STABILIZED ROADBED	16,214	273		16,487
ASPHALT MATERIAL FOR TACK	31,095	453	219	31,767
LEVELING & WEDGING PG64-22	815	310		1,125

Earthwork Quantities
Mainline and Menelaus Rd
Com = 27,678
Emb* = 41,831

*TOTAL INCLUDES 645 CY FROM EMBANKMENT FOUNDATION BENCHES

NOTES

- ALL ASPHALT MIXTURES SHALL BE ESTIMATED AT 110 LBS. PER SQ. YD. PER INCH OF DEPTH, UNLESS NOTED OTHERWISE.
- ASPHALT CURING SEAL ESTIMATED AT 2 LBS PER SQ. YD
- ASPHALT MATERIAL FOR TACK ESTIMATED AT 0.84 LBS PER SQ. YD
- SAND FOR BLOTTER ESTIMATED AT 3 LBS PER SQ. YD
- DISTURBED LIMITS = 10 ACRES
- ① MAINLINE L&W BASED ON AN AVERAGE DEPTH: 17+00)
- ② MENELAUS L&W BASED ON AN AVERAGE DEPTH OF 11 IN
- ③ MAINLINE MILLING BASED ON AN AVERAGE DEPTH: 16+30 - 17+00)
- ④ MENELAUS MILLING BASED ON AN AVERAGE DEPTH OF 3 IN
- ⑤ ITEMS FOR MAINTENANCE OF TRAFFIC PERMINT SIGNS
- ⑥ FOR CONSTRUCTION OF TRAFFIC PERMINT SIGNS

