Andy Beshear
GOVERNOR

TRANSPORTATION CABINET
200 Mero Street Frankfort,
Kentucky 40601

Rebecca Goodman
SECRETARY

November 24, 2026

CALL NO. 303
CONTRACT ID NO. 263087
ADDENDUM # 1

Subject: NICHOLAS COUNTY
CB06 091 0057 000-003
Letting December 10, 2026

1. Added Summary Sheet p. 20A of 32.
2. Revised Proposal Bid Items p. 32 of 32.

Proposal revisions are available at
http://transportation.ky.gov/Construction-Procurement/.

If you have any questions, please contact us at 502-564-3500.

Sincerely,



Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mb
Enclosures

NICHOLAS COUNTY KY 57 BASE FAILURE REPAIR SUMMARY

CB06 091 0057 000-004

LANE	BEGIN MP	END MP	LENGTH (FT)	WIDTH (FT)	DEPTH (IN)	ASPHALT BASE (TONS)	MILLING (TONS)
NB	0.051	0.149	518	4	4	53	53
NB	0.475	0.495	106	6	4	17	17
NB	0.542	0.557	80	6	4	13	13
NB	0.725	0.774	259	4	4	27	27
NB	0.808	0.929	639	4	4	66	66
NB	0.951	0.971	106	4	4	11	11
NB	1.119	1.131	64	6	4	10	10
NB	1.425	1.441	85	6	4	14	14
NB	1.571	1.582	59	4	4	7	7
NB	1.607	1.616	48	4	4	5	5
NB	1.991	2.034	228	4	4	24	24
SB	0.012	0.029	90	4	4	10	10
SB	0.063	0.108	238	6	4	37	37
SB	0.124	0.245	639	6	4	98	98
SB	0.401	0.498	513	4	4	53	53
SB	0.555	0.566	59	4	4	7	7
SB	0.584	0.649	344	4	4	36	36
SB	0.761	0.928	882	4	4	91	91
SB	0.953	1.075	645	4	4	66	66
SB	1.300	1.305	27	4	4	3	3
SB	1.571	1.654	439	4	4	45	45
SB	1.724	1.733	48	4	4	5	5
SB	1.978	1.999	111	4	4	12	12
SB	2.075	2.109	180	4	4	19	19
SB	2.207	2.284	407	4	4	42	42

TOTAL ASPHALT BASE (TONS):	**771**
TOTAL MILLING (TONS):	**771**

263087

PROPOSAL BID ITEMS

Report Date 11/24/26

263087

Section: 0001 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00001		DGA BASE	315.00	TON		$	
0020	00190		LEVELING & WEDGING PG64-22	421.00	TON		$	
0030	00212		CL2 ASPH BASE 1.00D PG64-22	771.00	TON		$	
0040	00301		CL2 ASPH SURF 0.38D PG64-22	1,540.00	TON		$	
0050	00356		ASPHALT MATERIAL FOR TACK	17.00	TON		$	
0060	02562		TEMPORARY SIGNS	250.00	SQFT		$	
0070	02650		MAINTAIN & CONTROL TRAFFIC KY-57	1.00	LS		$	
0080	02676		MOBILIZATION FOR MILL & TEXT KY-57	1.00	LS		$	
0090	02677		ASPHALT PAVE MILLING & TEXTURING (REVISED 11-24-26)	803.00	TON		$	
0100	06514		PAVE STRIPING-PERM PAINT-4 IN	24,288.00	LF		$	
0110	10030NS		ASPHALT ADJUSTMENT	7,667.00	DOLL	$1.00	$	$7,667.00

Section: 0002 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0120	02569		DEMOBILIZATION	1.00	LS		$	