



COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET
www.transportation.ky.gov/

Andy Beshear
GOVERNOR

Jim Gray
SECRETARY

May 20, 2022

CALL NO. 304
CONTRACT ID NO. 222222
ADDENDUM # 1

Subject: Boone County, FD05 008 0014 003-009
Letting May 26, 2022

- (1) Revised - Loop Summary - Page 29 of 44
- (2) Revised - Proposal Bid Items - Page 44 of 44

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

**Boone County
 TRAFFIC LOOP SUMMARY
 FD05 008 0014 003-009
 LOOP SUMMARY**

MPT	INTERSECTION	SAW, SLOT AND FILL LF	LOOP WIRE LF	CONDUIT		PVC CONDUIT		CABLE NO. 14 LF	JUNCTION		Trenching and Backfilling LF	Loop Test EA	NOTES
				1 INCH LF	1 1/4 INCH LF	2 INCH LF	TYPE B EA						
8.056	KY 14												
	KY 1292	254	868	20	100	0	200	2	100			2	2 LOOPS
	Total	254	868	20	100	0	200	2	100			2	

NOTES for all intersections:
 1. Quantities are for estimating purposes only. The Contractor shall field measure and inspect items to verify quantities
 2. 2 - 1 1/4 inch conduits may be used in place of 2" conduit. Field verify conduit to match existing facilities/tie-in to poles/cabinets.
 Only replace existing conduit if damaged.

PROPOSAL BID ITEMS

222222

Page 1 of 1

Report Date 5/20/22

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00190		LEVELING & WEDGING PG64-22	122.00	TON		\$	
0020	00301		CL2 ASPH SURF 0.38D PG64-22	3,400.00	TON		\$	
0030	00356		ASPHALT MATERIAL FOR TACK	27.00	TON		\$	
0040	02562		TEMPORARY SIGNS	370.00	SQFT		\$	
0050	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0060	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0070	02677		ASPHALT PAVE MILLING & TEXTURING	3,400.00	TON		\$	
0080	02697		EDGE LINE RUMBLE STRIPS	26,675.00	LF		\$	
0090	04792		CONDUIT-1 IN	20.00	LF		\$	
0100	04811		ELECTRICAL JUNCTION BOX TYPE B	2.00	EACH		\$	
0110	04820		TRENCHING AND BACKFILLING	100.00	LF		\$	
0120	04830		LOOP WIRE	868.00	LF		\$	
0130	04850		CABLE-NO. 14/1 PAIR	200.00	LF		\$	
0140	04895		LOOP SAW SLOT AND FILL	254.00	LF		\$	
0150	06510		PAVE STRIPING-TEMP PAINT-4 IN	38,000.00	LF		\$	
0160	06515		PAVE STRIPING-PERM PAINT-6 IN	75,200.00	LF		\$	
0170	06568		PAVE MARKING-THERMO STOP BAR-24IN	40.00	LF		\$	
0180	06574		PAVE MARKING-THERMO CURV ARROW	8.00	EACH		\$	
0190	06575		PAVE MARKING-THERMO COMB ARROW	2.00	EACH		\$	
0200	06576		PAVE MARKING-THERMO ONLY	1.00	EACH		\$	
0210	10020NS		FUEL ADJUSTMENT	5,482.00	DOLL	\$1.00	\$	\$5,482.00
0220	10030NS		ASPHALT ADJUSTMENT	13,770.00	DOLL	\$1.00	\$	\$13,770.00
0230	24900EC		PVC CONDUIT-1 1/4 IN-SCHEDULE 80	100.00	LF		\$	
0250	24963ED		LOOP TEST	2.00	EACH		\$	

Section: 0002 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0260	02569		DEMOBILIZATION	1.00	LS		\$	