



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

September 26, 2023

CALL NO. 304
CONTRACT ID NO. 232426
ADDENDUM # 1

Subject: Bullitt County, FD05 015 0061 019-021
Letting September 28, 2023

- (1) Revised - Special Note - Page 10 of 56
- (2) Revised - Proposal Bid Items - Page 56 of 56

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

SURFACING AREAS

The Department estimates the mainline surfacing width to be varied 24 to 48 feet.

The Department estimates the total mainline area to be surfaced to be 28,320 square yards.

The Department estimates the shoulder width to be varied 4 to 11 feet on each side.

The Department estimates the total shoulder area to be surfaced to be 12,355 square yards.

ASPHALT MIXTURE

Unless otherwise noted, the Department estimates the rate of application for all asphalt mixtures to be 110 lbs/sy per inch of depth.

INCIDENTAL SURFACING

The Department has included in the quantities of asphalt mixtures established in the proposal estimated quantities required for resurfacing or surfacing mailbox turnouts, farm field entrances, residential and commercial entrances, curve widening, ramp gores and tapers, and road and street approaches, as applicable. Pave these areas to the limits as shown on Standard Drawing RPM-110-06 or as directed by the Engineer. In the event signal detectors are present in the intersecting streets or roads, pave the crossroads to the right of way limit or back of the signal detector, whichever is the farthest back of the mainline. Surface or resurface these areas as directed by the Engineer. The Department will not measure placing and compacting for separate payment but shall be incidental to the Contract unit price for the asphalt mixtures.

OPTION A

Be advised that the Department will accept compaction of asphalt mixtures furnished for driving lanes and ramps, at 1 inch (25mm) or greater, on this project according to OPTION A in accordance with Section 402 and Section 403 of the current Standard Specifications. The Department will require joint cores as described in Section 402.03.02 for surface mixtures only. The Department will accept compaction of all other asphalt mixtures according to OPTION B.

FUEL AND ASPHALT PAY ADJUSTMENT

The Department has included the Contract items Asphalt Adjustment and Fuel Adjustment for possible future payments at an established Contract unit price of \$1.00. The Department will calculate actual adjustment quantities after work is completed. If existing Contract amount is insufficient to pay all items on the contract with the adjustments, the Department will establish additional monies with a change order.

PROPOSAL BID ITEMS

232426

Page 1 of 1

Report Date 9/26/23

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00190		LEVELING & WEDGING PG64-22	267.00	TON		\$	
0020	00301		CL2 ASPH SURF 0.38D PG64-22	630.00	TON		\$	
0030	00388		CL3 ASPH SURF 0.38B PG64-22	2,180.00	TON		\$	
0040	02562		TEMPORARY SIGNS	230.00	SQFT		\$	
0050	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0060	02671		PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH		\$	
0070	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0080	02677		ASPHALT PAVE MILLING & TEXTURING	345.00	TON		\$	
0090	02696		SHOULDER RUMBLE STRIPS	12,750.00	LF		\$	
0100	02720		SIDEWALK-4 IN CONCRETE	56.00	SQYD		\$	
0110	02775		ARROW PANEL	2.00	EACH		\$	
0120	06510		PAVE STRIPING-TEMP PAINT-4 IN	10,000.00	LF		\$	
0130	06515		PAVE STRIPING-PERM PAINT-6 IN	600.00	LF		\$	
0140	06542		PAVE STRIPING-THERMO-6 IN W	11,600.00	LF		\$	
0150	06543		PAVE STRIPING-THERMO-6 IN Y	6,900.00	LF		\$	
0160	06547		PAVE STRIPING-THERMO-12 IN Y	430.00	LF		\$	
0170	06565		PAVE MARKING-THERMO X-WALK-6 IN	870.00	LF		\$	
0180	06568		PAVE MARKING-THERMO STOP BAR-24IN	504.00	LF		\$	
0190	06574		PAVE MARKING-THERMO CURV ARROW	43.00	EACH		\$	
0200	06575		PAVE MARKING-THERMO COMB ARROW	2.00	EACH		\$	
0202	10030NS		ASPHALT ADJUSTMENT (ADDED 9-26-23)	12,030.00	DOLL		\$	
0204	10020NS		FUEL ADJUSTMENT (ADDED 9-26-23)	4,790.00	DOLL		\$	
0210	20071EC		JOINT ADHESIVE	1,624.00	LF		\$	
0220	23158ES505		DETECTABLE WARNINGS (NEW)	122.00	SQFT		\$	
0230	24683ED		PAVE MARKING-THERMO DOTTED LANE EXTEN	320.00	LF		\$	
0240	24880EC		REMOVE PAVEMENT MARKER	125.00	EACH		\$	
0250	24970EC		ASPHALT MATERIAL FOR TACK NON- TRACKING	18.00	TON		\$	
0260	26119EC		INSTALL RADAR PRESENCE DETECTOR TYPE A	4.00	EACH		\$	

Section: 0002 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0270	02569		DEMOBILIZATION	1.00	LS		\$	