



TRANSPORTATION CABINET

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Steven L. Beshear
Governor

Michael W. Hancock, P.E.
Secretary

May 15, 2012

CALL NO. 304
CONTRACT ID NO. 122413
ADDENDUM # 3

Subject: Hardin County, FE01 047 8111
Letting May 18, 2012

- (1) Revised - Surfacing Areas - Pages 11-12 of 89
- (2) Revised - Bid Items - Page 89 of 89

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Ryan Griffith".

Ryan Griffith
Director
Division of Construction Procurement

RG:ks
Enclosures



An Equal Opportunity Employer M/F/D

EXPEDITE PROJECT WORK ORDER

The Contractor may request that the Department expedite the work order for this project to allow for maximization of time to complete the work. In order for the Department to accomplish this task, the Contractor may be required to “hand carry” all required project documentation to facilitate the process. Immediately UPON NOTIFICATION OF AWARD OF THE CONTRACT, deliver required project documentation to:

Division of Construction Procurement
200 Mero St.
Frankfort, KY 40602

SURFACING AREAS (ECTC PARKING LOT A1)

Parking lot surfacing width is estimated to be 111 feet.

(This includes approach to parking lot)

Total mainline area to be surfaced is estimated to be 4,988 square yards.

SURFACING AREAS (ECTC PARKING LOT A2)

Parking lot surfacing width is estimated to be 139 feet.

Total mainline area to be surfaced is estimated to be 5,243 square yards.

SURFACING AREAS (ECTC PARKING LOT A3)

Parking lot surfacing width is estimated to be 121 feet.

Total mainline area to be surfaced is estimated to be 1,721 square yards.

SURFACING AREAS (ECTC PARKING LOT A3 extension)

Parking lot surfacing width is estimated to be 121 feet.

Total mainline area to be surfaced is estimated to be 934 square yards.

SURFACING AREAS (ECTC PARKING LOT B)

Parking lot surfacing width is estimated to be 265 feet.

Total mainline area to be surfaced is estimated to be 5,683 square yards.

SURFACING AREAS (ECTC PARKING LOT C)

Mainline surfacing width is estimated to be 22 – 121 feet.

Total mainline area to be surfaced is estimated to be 3,234 square yards.

SURFACING AREAS (ECTC PARKING LOT K)

Mainline surfacing width is estimated to be 59 feet.

Total mainline area to be surfaced is estimated to be 1,296 square yards.

SURFACING AREAS (ECTC PARKING LOT J)

Mainline surfacing width is estimated to be 68 feet.

Total mainline area to be surfaced is estimated to be 1,082 square yards.

(This includes approach to parking lot)

SURFACING AREAS (ECTC PARKING LOT D)

Mainline surfacing width is estimated to be 120 feet.

Total mainline surface area to be surfaced is estimated to be 6,667 square yards.

SEALING AREA (ECTC PARKING LOT E)

Mainline sealing width is estimated to be 210 feet.

Total mainline sealing area is estimated to be 12,883 square yards.

SEALING AREA (ECTC PARKING LOT F)

Mainline sealing width is estimated to be 210 feet.

Total mainline sealing area is estimated to be 9,800 square yards.

SEALING AREA (ECTC PARKING LOT G)

Mainline sealing width is estimated to be 96 feet.

Total mainline sealing area is estimated to be 21,333 square yards.

ASPHALT MIXTURE

Unless otherwise noted, the Department estimates the rate of application for all asphalt mixtures to be 110 lbs/sy per inch of depth.

OPTION B

Be advised that the Department will control and accept compaction of asphalt mixtures furnished on this project under OPTION B in accordance with Sections 402 and 403.

CONTRACT ID: 122413
COUNTY: HARDIN
PROPOSAL: FE01 047 8111

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
SECTION 0001 ROADWAY						
0010	00003	CRUSHED STONE BASE	557.000	TON		
0020	00078	CRUSHED AGGREGATE SIZE NO 2	433.000	TON		
0030	00221	CL2 ASPH BASE 0.75D PG64-22	633.000	TON		
0040	00301	CL2 ASPH SURF 0.38D PG64-22 (REVISED: 5-15-12)	1,700.000	TON		
0050	02187	SITE PREPARATION	1.000	EACH		
0060	02562	SIGNS	150.000	SQFT		
0070	02650	MAINTAIN & CONTROL TRAFFIC	(1.00)	LS		
0080	06514	PAVE STRIPING-PERM PAINT-4 IN	24,586.000	LF		
0090	08540	JOINT SEALING	10,991.000	LF		
0091	20206EC	PAVE MARK HANDICAP SYMBOL (ADDED: 5-9-12)	14.000	EACH		
0100	23802EC	PRECAST VEHICLE STOP (REVISED: 5-14-12)	21.000	EACH		
0110	23957EX	SEAL COATING	43,966.000	SQYD		
SECTION 0002 DEMOBILIZATION						
0120	02569	DEMOBILIZATION (AT LEAST 1.5%)		LUMP		
		TOTAL BID				