



TRANSPORTATION CABINET

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Steven L. Beshear
Governor

Michael W. Hancock, P.E.
Secretary

August 15, 2012

CALL NO. 304
CONTRACT ID NO. 121028
Addendum # 2

**Subject: Rockcastle County, FD04 SPP 102 0078 055-059
Letting August 17, 2012**

- (1) Revised - Pipe and Drainage Summary - Page 34 of 92
- (2) Revised - Bid Items - Pages 89-92 of 92

Proposal revisions are available at
<http://transportation.ky.gov/Construction-Procurement>

Plan Revisions are available at: <http://www.lynnimaging.com/kytransportation/>

If you have any questions, please contact us at (502) 564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Ryan Griffith".

Ryan Griffith
Director
Division of Construction Procurement

RG:jj

Enclosures



An Equal Opportunity Employer M/F/D

I-75
ROCKCASTLE COUNTY
PAVEMENT REHABILITATION, MILEPOST 55.74 TO 58.95
Item No. 8-2009.00

NORTHBOUND I-75 - PIPE AND DRAINAGE SUMMARY

Location	Milepost	COMMENTS																
		S.S. Pipe - 18 IN	Curb Box Inlet Type B	Curb Box Inlet Type B (T)	Spring Box Inlet Type A	Flume Inlet Type 2 (1)	Adjust Inlet	Manhole Type A	Island Header Curb Type 1	Remove Curb	Flowable Fill	Channel Lining CL II	Channel Lining CL III	Clean Pipe Structure	Concrete - Class A	Steel Reinforcement	Special Concrete Header Curb	
Units	Lin. Ft.	Each	Each	Each	Each	Each	Each	Lin. Ft.	Lin. Ft	Cu. Yd.	Ton	Ton	Each	Cu. Yd.	Lb.	Lin. Ft.		
Item Number	522	1480	1484	1660	1691	1719	1756	1890	1904	2220	2483	2484	3262	8100	8150	----		
RT	56.39									4	50						CONST. FLOWABLE FILL BENEATH HDWL OUTLET, CONST. CHANNEL LINING AT OUTLET AND ALONG ADJACENT DITCHES	
RT	56.95	235			1												CONST. SPRING BOX INLET TYPE A; DRAIN TO EXIST MEDIAN BOX AT MP 57.00; REGRADE MEDIAN TO DRAIN TO MEDIAN BOX	
RT	57.00										10						REMOVE PAVED DITCH BENEATH HDWL OUTLET AND CONST. CHANNEL LINING CL. II	
RT	56.84					1											ADJUST DITCH INLET TO GRADE (G)	
RT	57.29 - 57.44											267					REMOVE PAVED DITCH AND CONST. CHANNEL LINING CL. III	
RT	57.65						1										ADJUST DITCH INLET TO GRADE (G)	
RT	58.65					1					8					250	CONST. CHANNEL LINING AT FLUME OUTLET	
RT	58.70					1						8				250	CONST. CHANNEL LINING AT FLUME OUTLET	
RT	58.79	46					1							0.93	8		CONST. MANHOLE (T/R, ELEV. 1183.1, F.L. ELEV. 1189.6) WITH FRAME AND LID TYPE 2, 46 OF 18" PIPE AND ONE (1) 18" SLOPED AND FLARED HEADWALL OUTLET. (O.E. 1188.3) (2)	
RT	58.81	136	1													230	CONSTRUCT CBI AT APPROX. F.L. ELEV. 1192.7 AND APPROX. G.L. ELEV. 1196.7; CONSTRUCT CBI AND CURB AT 64' RT. OF CENTERLINE. (2)	
RT	58.86	240	1													231	CONSTRUCT CBI AT APPROX. F.L. ELEV. 1199.4 AND APPROX. G.L. ELEV. 1203.4 CONSTRUCT CBI AND CURB AT 64' RT. OF CENTERLINE. (2)	
RT	58.91	255	1													220	CONSTRUCT CBI AT APPROX. F.L. ELEV. 1206.3 AND APPROX. G.L. ELEV. 1210.3; CONSTRUCT CBI AND CURB AT 64' RT. OF CENTERLINE. (2)	
RT	58.94												1				CLEAN 60" PIPE	
RT	58.95			1				20	20								CONST. CURB AT BRIDGE APPROACH AND CONST. TOP PHASE ONLY OF CBI	
PROJECT TOTAL		912	3	1	1	2	2	1	20	20	4	76	267	1	1	8	1,181	

The Milepost references listed above are given as distances measured from the nearest mile post sign
(1) Removal of existing flume is incidental to Bid Item "Flume Inlet Type 2"
(2) Elevations are shown for information purposes only, all drainage should be verified by field engineer to drain properly.

CONTRACT ID: 121028
COUNTY: ROCKCASTLE
PROPOSAL: FD04 SPP 102 0075 055-059

PAGE: 1
LETTING: 08/17/12
CALL NO: 304

LINE NO	ITEM	DESCRIPTION	APPROXIMATE UNIT QUANTITY	UNIT PRICE	AMOUNT
SECTION 0001 ROADWAY					
0010	00001	DGA BASE (REVISED: 8-15-12)	617.000 TON		
0020	00018	DRAINAGE BLANKET-TYPE II-ASPH	573.000 TON		
0030	00078	CRUSHED AGGREGATE SIZE NO 2 (REVISED: 8-15-12)	2,448.000 TON		
0040	00100	ASPHALT SEAL AGGREGATE (REVISED: 8-15-12)	349.000 TON		
0050	00194	LEVELING & WEDGING PG76-22	85.000 TON		
0060	00214	CL3 ASPH BASE 1.00D PG64-22 (REVISED: 8-14-12)	4,519.000 TON		
0070	00214	CL3 ASPH BASE 1.00D PG64-22 FOR EDGE DRAIN	526.000 TON		
0080	00219	CL4 ASPH BASE 1.00D PG76-22	10,690.000 TON		
0090	00291	EMULSIFIED ASPHALT RS-2 (REVISED: 8-15-12)	42.000 TON		
0100	00339	CL3 ASPH SURF 0.38D PG64-22	1,389.000 TON		
0110	00342	CL4 ASPH SURF 0.38A PG76-22	3,548.000 TON		
0120	00522	STORM SEWER PIPE-18 IN	912.000 LF		
0130	01000	PERFORATED PIPE-4 IN (REVISED: 8-15-12)	12,330.000 LF		
0131	01001	PERFORATED PIPE-6 IN (ADDED: 8-15-12)	4,995.000 LF		
0132	01002	PERFORATED PIPE-8 IN (ADDED: 8-15-12)	8,485.000 LF		
0140	01010	NON-PERFORATED PIPE-4 IN (REVISED: 8-15-12)	152.000 LF		
0141	01011	NON-PERFORATED PIPE-6 IN (ADDED: 8-15-12)	92.000 LF		
0142	01012	NON-PERFORATED PIPE-8 IN (ADDED: 8-15-12)	100.000 LF		
0150	01015	INSPECT & CERTIFY EDGE DRAIN SYSTEM	(1.00) LS		
0160	01020	PERF PIPE HEADWALL TY 1-4 IN (REVISED: 8-15-12)	11.000 EACH		

CONTRACT ID: 121028
COUNTY: ROCKCASTLE
PROPOSAL: FD04 SPP 102 0075 055-059

PAGE: 2
LETTING: 08/17/12
CALL NO: 304

LINE NO	ITEM	DESCRIPTION	APPROXIMATE UNIT QUANTITY	UNIT PRICE	AMOUNT
0161	01021	PERF PIPE HEADWALL TY 1-6 IN (ADDED: 8-15-12)	17.000 EACH		
0162	01022	PERF PIPE HEADWALL TY 1-8 IN (ADDED: 8-15-12)	8.000 EACH		
0170	01028	PERF PIPE HEADWALL TY 3-4 IN	10.000 EACH		
0171	01029	PERF PIPE HEADWALL TY 3-6 IN (ADDED: 8-15-12)	1.000 EACH		
0180	01480	CURB BOX INLET TYPE B	3.000 EACH		
0190	01484	CURB BOX INLET TYPE B-T	1.000 EACH		
0210	01660	SPRING BOX INLET TYPE A	1.000 EACH		
0220	01691	FLUME INLET TYPE 2	2.000 EACH		
0221	01719	ADJUST INLET (ADDED: 8-15-12)	2.000 EACH		
0230	01756	MANHOLE TYPE A	1.000 EACH		
0240	01877	SPECIAL HEADER CURB	1,181.000 LF		
0250	01890	ISLAND HEADER CURB TYPE 1	320.000 LF		
0260	01904	REMOVE CURB	20.000 LF		
0270	01982	DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL (REVISED: 8-15-12)	WHITE 91.000 EACH		
0280	01983	DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL (REVISED: 8-15-12)	YELLOW 4.000 EACH		
0290	02014	BARRICADE-TYPE III	6.000 EACH		
0300	02220	FLOWABLE FILL	4.000 CUYD		
0320	02237	DITCHING (REVISED: 8-15-12)	12,000.000 LF		
0330	02352	GUARDRAIL-STEEL W BEAM-D FACE	275.000 LF		
0340	02360	GUARDRAIL TERMINAL SECTION NO 1	2.000 EACH		
0350	02363	GUARDRAIL CONNECTOR TO BRIDGE END TY A	2.000 EACH		

CONTRACT ID: 121028
COUNTY: ROCKCASTLE
PROPOSAL: FD04 SPP 102 0075 055-059

PAGE: 3
LETTING: 08/17/12
CALL NO: 304

LINE NO	ITEM	DESCRIPTION	APPROXIMATE UNIT QUANTITY	UNIT PRICE	AMOUNT
0360	02365	CRASH CUSHION TYPE IX-A	2.000 EACH		
0370	02367	GUARDRAIL END TREATMENT TYPE 1	3.000 EACH		
0380	02369	GUARDRAIL END TREATMENT TYPE 2A	6.000 EACH		
0390	02373	GUARDRAIL END TREATMENT TYPE 3	1.000 EACH		
0400	02381	REMOVE GUARDRAIL	8,712.500 LF		
0401	02482	CHANNEL LINING CLASS IA (ADDED: 8-15-12)	3,400.000 TON		
0410	02483	CHANNEL LINING CLASS II (REVISED: 8-15-12)	76.000 TON		
0420	02484	CHANNEL LINING CLASS III	267.000 TON		
0430	02562	SIGNS	500.000 SQFT		
0440	02565	OBJECT MARKER TYPE 2	2.000 EACH		
0450	02650	MAINTAIN & CONTROL TRAFFIC	(1.00) LS		
0460	02671	PORTABLE CHANGEABLE MESSAGE SIGN	2.000 EACH		
0470	02676	MOBILIZATION FOR MILL & TEXT	(1.00) LS		
0480	02677	ASPHALT PAVE MILLING & TEXTURING	7,122.000 TON		
0490	02696	SHOULDER RUMBLE STRIPS-SAWED	34,400.000 LF		
0500	02775	ARROW PANEL	2.000 EACH		
0510	03262	CLEAN PIPE STRUCTURE	1.000 EACH		
0520	05950	EROSION CONTROL BLANKET	11,200.000 SQYD		
0530	06412	STEEL POST MILE MARKERS	3.000 EACH		
0540	06417	FLEXIBLE DELINEATOR POST-W	172.000 EACH		
0550	06418	FLEXIBLE DELINEATOR POST-Y	12.000 EACH		

CONTRACT ID: 121028
COUNTY: ROCKCASTLE
PROPOSAL: FD04 SPP 102 0075 055-059

PAGE: 4
LETTING: 08/17/12
CALL NO: 304

LINE NO	ITEM	DESCRIPTION	APPROXIMATE UNIT QUANTITY	UNIT PRICE	AMOUNT
0560	06511	PAVE STRIPING-TEMP PAINT-6 IN	43,000.000 LF		
0570	06568	PAVE MARKING-THERMO STOP BAR-24IN	52.000 LF		
0580	06592	PAVEMENT MARKER TYPE V-B W/R	257.000 EACH		
0590	06593	PAVEMENT MARKER TYPE V-B Y/R	28.000 EACH		
0600	06600	REMOVE PAVEMENT MARKER TYPE V	257.000 EACH		
0610	08100	CONCRETE-CLASS A	1.000 CUYD		
0620	08150	STEEL REINFORCEMENT	8.000 LB		
0630	10020NS	FUEL ADJUSTMENT (REVISED: 8-15-12)	28,441.000 DOLL	1.00	28,441.00
0640	10030NS	ASPHALT ADJUSTMENT (REVISED: 8-15-12)	50,118.000 DOLL	1.00	50,118.00
0650	20757ED	PAVEMENT REPAIR (REVISED: 8-15-12)	2,291.000 SQYD		
0660	21802EN	G/R STEEL W BEAM-S FACE (7 FT POST)	8,687.500 LF		
0670	23143ED	KPDES PERMIT AND TEMP EROSION CONTROL	(1.00) LS		
0680	23237EN10W	WATERBLAST STRIPE REMOVAL	17,200.000 LF		
0690	24189ER	DURABLE WATERBORNE MARKING-6 IN W	21,080.000 LF		
0700	24190ER	DURABLE WATERBORNE MARKING-6 IN Y	18,303.000 LF		
0710	24191ER	DURABLE WATERBORNE MARKING-12 IN W	840.000 LF		
SECTION 0002 MOB AND DEMOB					
0720	02568	MOBILIZATION (NO MORE THAN 5%)	LUMP		
0730	02569	DEMOBILIZATION (AT LEAST 1.5%)	LUMP		
		TOTAL BID			