



TRANSPORTATION CABINET

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Steven L. Beshear
Governor

Michael W. Hancock, P.E.
Secretary

November 2, 2012

CALL NO. 311
CONTRACT ID NO. 121056
ADDENDUM # 1

Subject: McCracken County, FD04 SPP 073 0024 003-017
Letting November 16, 2012

(1) Revised - General Summary - Page 52 of 234

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Ryan Griffith".

Ryan Griffith
Director
Division of Construction Procurement

RG:ks
Enclosures



An Equal Opportunity Employer M/F/D

I-24 PAVEMENT REHABILITATION MCCRACKEN COUNTY MILEPOST 2.989 TO 16.171 ITEM NUMBER: 1-2033.00 GENERAL SUMMARY			
ITEM NUMBER	ITEM	QUANTITY	UNIT
6549	PAVE STRIPING-TEMP REM TAPE-B	189250	LIN FT
6550	PAVE STRIPING-TEMP REM TAPE-W	378500	LIN FT
6551	PAVE STRIPING-TEMP REM TAPE-Y	378500	LIN FT
6568	PAVE MARKING-THERMO STOP BAR-24IN	310	LF
6574	PAVE MARKING-THERMO CURV ARROW	22	EACH
6575	PAVE MARKING-THERMO COMB ARROW	2	EACH
6592	PAVEMENT MARKER TYPE V-B W/R	2081	EACH
6593	PAVEMENT MARKER TYPE V-B Y/R	437	EACH
6600	REMOVE PAVEMENT MARKER TYPE V	2518	EACH
8100	CLASS A CONCRETE (6)	1.86	CU YD
8150	STEEL REINFORCEMENT (6)	16.00	LBS
10020NS	FUEL ADJUSTMENT	64959	DOLLAR
10030NS	ASPHALT ADJUSTMENT	114470	DOLLAR
20071EC	JOINT ADHESIVE (11)	241245	LIN FT
20191ED	OBJECT MARKER TYPE 3	48	EACH
20366NN	REPLACE GRATE	38	EACH
20411ED	LAW ENFORCEMENT OFFICER	2000	HOUR
20432ES112	REMOVE CRASH CUSHION	12	EACH
20757ED	PAVEMENT REPAIR (MAJOR) (12)	72	SQ YD
20757ED	PAVEMENT REPAIR (MINOR) (12)	350	SQ YD
21533EN	EMBANKMENT (7)	355	CU YD
23143ED	KPDES PERMIT AND TEMPORARY EROSION CONTROL	1	LUMP SUM
24189ER	DURABLE WATERBORNE MARKING-6 IN W	180195	LIN FT
24190ER	DURABLE WATERBORNE MARKING-6 IN Y	142311	LIN FT
24191ER	DURABLE WATERBORNE MARKING-12 IN W	5008	LIN FT
	SPECIAL CONCRETE HEADER CURB	35271	LIN FT

- (1) Ditching is intended for repair to the eroded and/or poorly draining areas throughout the project as directed by the engineer. Any embankment required is incidental to ditching.
 - (2) Any excavation and Fabric-Geotextile Type I required to place the Channel Lining Class II or III is incidental to the lining.
 - (3) The quantity for these items includes initial placement. Any relocation required will not be paid for directly, but will be considered incidental to maintain and control traffic.
 - (4) To be used as directed by the Engineer
 - (5) The drainage summary includes flowable fill to repair voids near drainage structures.
 - (6) Removal of existing structure or pipe is incidental.
 - (7) Contrary to the Standard Specifications, payment will be based on measured quantity **NOT** plan quantity.
 - (8) Shouldering quantity for shaping the DGA shoulder along guardrail replacement areas and other project areas as directed by the Engineer.
 - (9) Flashing Arrows and Portable Changeable Message Signs to become the property of the Department.
 - (10) DGA Base for shoulder wedge throughout the project as directed by the Engineer.
 - (11) Longitudinal Pavement Joint Adhesive for Centerline and Outside shoulder joints.
 - (12) Includes an additional 20% for continuing pavement deterioration.
 - (13) For replacing the inside and outside concrete shoulders on both ends of the westbound bridge over Poole Rd.
- NOTE: Quantities from all summaries have been carried over and included in this General Summary